

BHARAT COKING COAL LTD.

Chanch Victoria Area

Ref. no. E &M/XII/BCCL/NIT/09-10/357-373

Dated: 22/23.02.10

Notice Inviting Tender

Sealed tenders are invited from experienced and bonafide contractor / Agency for the under noted work. The tender should be submitted in two part, that is, Part I containing Tech – Commercial bid and Part – II Containing Price Bid, Part I – and Part II envelope must be superscribed and sealed. Sealed part I & Part II envelope must be sealed in a third envelope.

Tenders must reach the office of the undersigned latest by 16.03.10 up to 1.00 P.M. and Tech-Commercial bid will be opened on the same day at 3.00 P.M.

Sl. No.	Description of Work	Tender Cost (Rs)	Estimated Cost (Rs)	Earnest Money (Rs)	Time of Completion
1.	Renovation of 220v O/H line Sub-Stn. to Area Gust House at Bugunia Colliery.	Rs. 100/- + Tax (Non-refundable)	Rs. 2,07,969/-	Rs. 2,080/- (Refundable)	15 Days
Tender issued upto 15.03.10					

Terms & Conditions:-

1. Tender paper can be obtained from the office of the undersigned on any working day on production of money Receipt for the Cost of Tender paper (Non-refundable).
2. Earnest money as mentioned above should be deposited either in the form of Bank Draft drawn in favour of BCCL, A-XII, payable at Barakar or may be deposited in Cash with Finance Dept. up to 1.00 P.M. on week days and money receipt in original is to be submitted along with the offer. Without E. Money no tender will be accepted.

3. Other Requirements:-

(a) PAN CARD (ZEROX) (b) VAT (Upto date) (c) E, Money Receipt (in original) (d) Time of completion (e) Validity of Tender should be 120 days from the date of opening of price bid (f) Guarantee period minimum six months after installation (g) Valid Contractor License with Supervisory Certificates for power line jobs applicable, (H.T./L.T. as applicable). (h) Service Tax Registration copy (i) Deed of Partnership, Residential proof and proof of commencement of business. (j) All documents should be self attested with date & seals.

(k) Desirable Experience Credential.

The intending tenders must have in his name and experience and having successfully completed O/H Line work in BCCL or any other public sector undertaking or Govt. firm during last 7 years ending last day of the month previous to the one in which bid application are invited, should be either of the following:-

i) Three similar completed work each costing not less than the amount equal to 40% of the estimated cost.

Or.

ii) "TWO" similar completed works each costing not less than the amount equal to 50% of the estimated cost.

Or

iii) One Similar completed work costing not less than the amount equal to 80% of the Estimated Cost.

4. 10% Security money including earnest money will be deducted from the final bill till completion of the Guarantee period.

5. Please send authorized representative for Tender paper collection etc.

6. Management reserves the right to accept or reject the tender or part thereof without assigning any reason whatsoever.

**Area Manager (E &M)
C/V Area.**

Distribution:-

1. P.M. (Admn.), C.V. Area for display in Notice Board.
2. All A.M. (E&M), A-I to XI
3. All Colly, Engr (E&M), C/V Area.
4. Addl. G.M., C/V Area
5. A.F.M., C/V Area
6. Cashier, C.V. Area, for cost paper / E. Money
7. Tender File
8. Manager Publication for Hqt, Dhanbad for Web site publication.

BHARAT COKING COAL LTD.
CHUNCH VICTORIA AREA

Tender Paper

Ref.No. E&M/XII/BCCL/NIT/09-10/357-373

Dt. 22/23.02.10

Name of work : Renovation of 220V. O/H Line Sub – Station to Area Guest House at Begunia Colliery.

<u>Sl. No.</u>	<u>Particulars.</u>	<u>Qty.</u>	<u>Rate</u>	<u>Amount(Rs)</u>
1.	Erection, Laying & Stringing of AAAC / ACSR Conductor 3 Ph., 1 Neut. (ACSR Rabbit) Sag as per Rule.	300 Kgs.		
2.	Erecting of Pole by earth cutting and refilling etc. Pole up to 11 Mtrs. But not exceeding 13 Mtrs. (Pole supply by BCCL)	03 Nos.		
3.	Supply of Cement, Sand & Stone Chips for Cement concreting 1:3:6 (Cement, 3 coarse Sand , 6 graded nominal Size Stone chips) 1.5 Cum in each pole.	03 Nos.		
4.	Supply & Erection of 19/20 mm dia stay Set by earth cutting with Cement Concreting with Supply of Cement, Stone Chips, Sand including stay wire, Stay Insulator comp. set. (1:3:6)	10 "		
5.	Supply, Fabrication, Erection & Painting of Iron & Steel Materials such as Cross arms, Cradle guard bracket as per suitable size Clamp, Nut, Bolt, Washer etc.	625 Kgs.		
6.	Transportation of Poles from Workshop to Working Site.	03 Nos.		
7.	Supply of AAAC / ACSR Rabbit Conductor with transportation to worksite.	700 Mtrs.		
8.	Supply & Erection of Earth Wire from 7/16 SWG or 08 No. SWG G.I. Wire for its earth continuity	180 Mtrs.		
9.	Supply & Erection of Cradle Guard Wire 08 No. SWG G.I. Wire for Road, Basti Crossing (NIR).	225 Mtrs.		
10.	Supply & Erection of Shackle Insulator with G.I. Hardware fitting as per complete set.	40 Nos.		

<u>Sl. No.</u>	<u>Particulars.</u>	<u>Qty.</u>	<u>Rate</u>	<u>Amount(Rs)</u>
11.	Supply & Erection of 440 Volts Grade lighting Arrestor Complete with termination.	06 Nos.		
12.	Making of Earth Pit by earth cutting with refilling by Charcoal., Salt etc.	4 ”		
13.	Supply & Erection of Pole mounting Kit for Cable termination.	03 Sets.		
14.	Laying of Cable by 7 / 10 SWG G.I. Wire Stringing in pole to pole a Crossing of H.T. Overhead line & Sub-Stn.	35 Mtrs.		
15.	Dismantling of existing system Conductor & Pole.	218 Kgs.		
16.	Supply & Erection of 440 Volts Grade 400 Amps. (400 A) Main Switch 4 pole with erection and termination.	02 Nos.		
17.	Overhead line charging by individual staff Quarter & tree cutting.	L.S.		

.....
Total Rs.

(Rupees

..... Only)

Signature of Issuing Authority
C.V. Area

Signature of Contractor
With Seal & Date
