



# BIHARAT COKING COAL LIMITED

(A Subsidiary of Coal India Ltd)

OFFICE OF THE GENERAL MANAGER

LODNA AREA

Ref No. BCCL/ACT/VIL/NIT/2008-09/1729

Date: 16.12.2008

## NOTICE INVITING TENDERS

(A bridged N.I.T. for BCCL Web site)

Sealed percentage rate tenders in two parts are invited from experienced and eligible contractors for the following work :-

Sl. N	Name of work	Estimated cost (Approved)	Earnest money	Cost of Tender paper	Time of completion
1	Sealing of abandoned pits/shaft mouths and incline mouths in the different units under Lodna Area	Rs.12,28,187.59	Rs.12282/-	Rs.500/-	02 (Two) months

Issue of tender documents - Begins on 09.01.2009

Closes on 10.01.2009:

Issue of tender documents will be done on all working days during working hours except on Sundays & holidays. In the event of the specified date for submission/opening of bids declared a holiday by the employer, the bids will be received/opened on the appointed time on the next working day.

Date & time of opening of Tenders: 13.01.2009 at 3.30 P.M.

The tender documents can be had from the office of the General Manager, Lodna Area P.O. Khas Jeenagora, Dist. Dhanbad on deposition of requisite cost of tender paper in form of cash to the Cashier, Lodna Area.

### SPECIAL CONDITIONS FOR TENDERERS . DOWNLOADING THE TENDER DOCUMENT FROM BCCL WEB-SITE

- (1) Tenderers are required to deposit along with their tender, a Bank Draft of any Nationalized / Schedule Commercial Bank payable at Dhanbad exclusively towards the cost of Tender Document for the amount indicated as above, in a separate envelope. Any Bank Draft, prepared after the scheduled closure of sale of Tender Documents i.e. 10.01.2009 may be liable for rejection.
- (2) The contents of the Tender Documents available for sale in our offices, shall be deemed as authenticated and the responsibility of errors and omissions in the downloaded documents will lie with the tenderer.

The management of BCCL reserves right to reject any or all tender or split the work among two or more tenderers without assigning any reasons whatsoever.

Area Civil Engineer  
Lodna Area

Copy to:-

- 1) G.M (System), BCCL -alongwith CD for logging of N.I.T. Tender documents & BOQ in BCCL Website.
- 2) General Manager, Lodna Area.

**BHARAT COKING COAL LIMITED**  
(A Subsidiary of Coal India Limited)  
**OFFICE OF THE GENERAL MANAGER**  
**LODNA AREA**

1. Name of work :  
"SEALING OF ABANDONED PITS/SHAFTS MOUTHS & INCLINE  
MOUTHS IN THE DIFFERENT UNITS UNDER LODNA AREA  
(i) 1 & 2 PITS AT BAGDIGI (ii) 3 & 4 PITS AT JOYRAMPUR (iii) 1,2,3,4,5 & 6 PITS  
AT JEENAGORA (iv) PITS - SC, ST, DT & DD AT NTC/STC (v) 4 & 5 PITS AT BAGDIGI  
(vi) 16 SEAM AIR SHAFT AT LODNA COLLIERY (vii) 16 No. INCLINE MOUTH UNDER  
LODNA COLLIERY (BASED ON CPWD SOR 2002)
2. Name of contractor :  
Address :
3. N.I.T. Reference : Ref. No. BCCI/LA/Civil/NIT/2008-09/1729  
dated 16.12.2008.
4. Date of Receipt of tender : Up to 3.00 P.M. on 13.01.2008
5. Date of open of Tender : At 3.30 P.M. on 13.01.2008
6. Details of E.M.D. : No. \_\_\_\_\_ Date \_\_\_\_\_  
Rs. \_\_\_\_\_
7. Money Receipt No. : No \_\_\_\_\_ Date \_\_\_\_\_  
(for issue of tender  
paper)
8. Photocopy of PAN :
9. Credential against experience :

SIGNATURE OF ISSUING OFFICER

### DECLARATION

I hereby declare that my / our firm has not been banned or de-listed  
by any Government or Quassi Government agencies or PSU's.

Signature of the Tenderer  
With Seal/Mohar

**PART - B**  
**PRICE BID**

Issued to the Tenderer \_\_\_\_\_

Vide M/R No. \_\_\_\_\_

Date \_\_\_\_\_

For Rs.500/- only

Sign. of issuing authority \_\_\_\_\_

**BILL OF QUANTITY FOR THE WORK OF "SEALING OF ABANDONED PITS/SHAFT MOUTHS & INCLINE MOUTHS IN THE DIFFERENT UNITS UNDER LODNA AREA."**  
**(i) 1 & 2 PITS AT BAGDIGI (ii) 3 & 4 PITS AT JOYRAMPUR (iii) 1,2,3,4. & 6 PITS AT JEENAGORA (iv) PITS - SC,ST,DT & DD AT NTC/STC (v) 4 & 5 PITS AT BAGDIGI (vi) 16 SEAM AIR SHAFTS AT LODNA COLLIERY (vii) 16 No. INCLINE MOUTH UNDER LODNA COLLIERY (BASED ON CPWD SOR 2002)**

Sl. No.	Particulars	Qty.	unit	Rate	Amount
1	Earth work in excavation in foundation trenches or drains(not exceeding 1.5m in width or 10Sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m including getting out the excavated soil & disposal of surplus excavated soils as directed. i) All kinds of soil	240.20	/Cum.	Rs.93.55	Rs.22470.71
2	Dry bricks on edge flooring with bricks of class desig.50 on a bed of 12mm mud mortar including filling joints with Jamuna sand (with FPS bricks)	305.98	/Sqm	Rs.132.82	Rs.40,640.26
3	Providing & laying in position cement of specified grade excluding the cost of centring & shuttering. All work upto plinth level. i) 1:4:8(1 cement:4 coarse sand:8 graded stone aggr.40mm nominal size.	45.88	/Cum	Rs.1404.70	Rs.64,447.63
4	Brick work with F.P.S. bricks of class designation 50 in foundation and plinth in : Cement mortar 1:6 (1 cement : 6 fine sand)	413.16	/Cum	Rs.1257.53	Rs.5,19,561.09
5	Centering & shuttering including strutting,propping etc.and removal of form of:				
	(a) R C C Slab	575.24	/Sqm	Rs.111.20	Rs.63,966.68
	(b) Edge of slab	455.60	/Mtr.	Rs.29.90	Rs.13,622.44



6	Providing & laying in position cement of specified grade excluding the cost of centring & shuttering. All work upto plinth level. i) 1:2:4 (1 cement:2 coarse sand:4 graded stone aggr. 20mm nominal size).	14.29 /Cum	Rs.1843.00	Rs.26,336.47
7	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15° landings, balconies, shelves, chajjas, intels, bends, plin window sills, staircases and spiral stair cases upto floor five level excluding the cost of centring, shuttering, finishing and replacement with 1:2:4 in slab.	114.94 /Cum	Rs.2120.65	Rs.2,43,747.51
8	Reinforcement for RCC work including straightening, cutting, bending, placing in position & binding all complete. i) Cold twisted bar	9195.20 /Kg	Rs.21.85	Rs.2,00,915.12
9	12mm cement plaster cement of mix. i) 1:6 (1 cement:6 fine sand)	699.00 /Sqm	Rs.44.00	Rs.30,756.00
10	Earth work in excavation in foundation trenches or drains (not exceeding 1.5m in width or 10 Sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m including getting out the excavated soil & disposal of surplus excavated soils as directed within a lead of 50 M i) Ordinary rock	11020 /Cum	Rs.153.90	Rs.1,723.68

**TOTAL : Rs. 12,28,187.59**

**Compared by:**

I / we quote \_\_\_\_\_ % ( \_\_\_\_\_ ) above / below  
or at par on the estimate rates for all the above items.

the estimated cost as mentioned in the bill of quantity for estimated job  
amounting to Rs. \_\_\_\_\_ Rupees \_\_\_\_\_

**Name of the Contractor :**

**Signature of contractor**  
**Seal & Date**