

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Ltd.)
Office of the General Manager, Govindpur Area
P.O. Sonardih, Dist. Dhanbad

Ref No. GM/AR-III/ACE/Tender/

14555-82

Dated 30.09.2009

1/10

SHORT TENDER NOTICE

Sealed tenders are invited from registered and experienced contractors for the following works :-

Sl. No.	Name of work	Estimated cost (in Rs.)	Earnest Money	Cost of tender paper	Time of completion
1.	Strengthening and renovation of Auto workshop Sinidih of Area-III.	2,94,873.00	1%	Rs.250/-	2 months

Eligibility Criteria:-1 (a) The average annual financial turnover during the last three years ending 31st March of the previous year should be atleast 30% of the estimated cost. (b) Experience of having successfully completed similar works during last 7 (seven) years ending last day or month previous to the one in which bid applications are invited (i.e. eligibility period) should be either of the following. (C) (i) Three similar completed works each costing not less than the amount equal to 40% of the estimated cost. (ii) Two similar completed works each costing not less than the amount equal to 50% of the estimated cost. (iii) One similar completed works each costing not less than the amount equal to 80% of the estimated cost. 2) J.S.T. Clearance certificate 3) Permanent Account number of Income Tax.

The tender will be received on dated 13.10.2009 upto 3.00 p.m. in two parts and will be opened on the same day upto 3.30 p.m. in the presence of tenders or their authorised agents.

Without earnest money tender will be rejected. The tenderers are required to deposit the E.M. in the shape of demand draft or M.R. of Govindpur Area.

The bill of quantity will have to be obtained from office of the undersigned on production of M.R. upto 12.10.2009.

Authority is reserved to reject any or all the tenders without assigning any reason whatsoever.

It will be obligatory for the tenders to keep their offer for a period of 120 days from the date of opening of the tender.

Sale-Tax will be deducted as per rule from the bill of the Contractor. No conditional tender paper will be accepted.

No materials will be supplied to the contractor for doing this work.

The contractor will have to abide by all labour rules of the country/state.

30/9/09
Area Civil Engineer,
Govindpur Area

C.C. to :-

- 1) Addl. GM, Govindpur Area.
- 2) AFM Govindpur Area.
- 3) All Project Officers, Govindpur Area.
- 4) C.G.M/G. M., Area 1 to 12, E.J. Area, W.W.Z. Ropeways.
- 5) G.M. (Const), Koylanagar, Dhanbad.
- 6) Notice Board.
- 7) Builders Association of India, 16 LIG Housing Colony Dhanbad / Near Akashkinaree Weighbridge, P.O. Katrasgarh.
- 8) C.V.O., B.C.C.L., Koyla Bhawan.
- 9) General Manager (System), Koyla Bhawan, Dhanbad.

Bill of Quantity for the work of "Strengthening and renovation of Auto workshop Sinidih of Area-III."

Sl. No.	Particulars of the work	Unit of Qnty.	Estimated Qnty. of Work	B.C.C.I. scheduled rates	Amount (in Rs.)
1	P/L four course water proofing bitumen felt.	M ²	477.10	184.80	88168.08
2	Grading of roof with c.conc. (1:2:4).	M ³	4.69	3314.95	15547.11
3	B/w in f&p in cm (1:6)	M ³	8.30	2007.00	16658.10
4	B/w in s/s in cm (1:6)	M ³	4.41	2315.50	10211.35
5	Precast R.C.C slab / lintel.	M ³	0.45	6002.80	2701.26
6	Reinforcement for R.C.C	Kg	31.0	42.70	1323.70
7	12mm c.p. (1:6)	M ²	405.60	67.65	27438.84
8	12mm c.p. (1:4) with punning.	M ²	16.60	97.90	1625.14
9	18mm c.p. (1:4)	M ²	19.70	111.15	2189.65
10	18mm c.p. (1:4) with punning.	M ²	10.0	128.50	1285.0
11	40 mm thick p.s. flooring.	M ²	30.55	192.95	5894.62
12	Dismantling plaster.	M ²	324.0	8.20	2656.80
13	Dismantling floor.	M ²	18.0	40.50	729.00
14	Steel work welded in built up section.	Kg	290.0	46.35	13441.50
15	Making chases in wall upto 7.5 x 7.5cm.	M	4.8	36.65	175.92

3
299

16	Making hole upto 15x15cm	M	2.4	70.05	168.12
17	Dismantling R.C.C (1:2:4)	M ³	0.17	537.55	91.38
18	Extra for cutting reinforcement.	M ²	0.33	176.35	58.19
19	P/L P.C.C (1:4:8)	M ³	0.77	2296.15	1768.03
20	White washing two coats.	M ²	841.0	4.10	3448.10
21	Colour washing two coats.	M ²	1005.0	9.10	9145.50
	Painting with synthetic enamel paint.				
	a) Old work	M ²	50.5	22.85	1153.92
22	b) New work	M ²	19.0	33.25	631.75
23	Oil bound distempering.	M ²	74.80	14.90	1114.52
24	Finishing wall with water proofing c.p. (snowcem)	M ²	490.0	27.95	13695.50
25	P/L P.C.C (1:2:4)	M ³	0.68	3257.45	2215.06
26	Removing white wash colour wash.	M ²	1495.0	3.20	4784.00
27	E/w in exc. in f&t.	M ³	7.91	103.40	817.89
28	E/w over area excvn.	M ³	30.25	101.85	3080.96
29	Carriage of earth upto 1.00km.	M ³	30.25	49.42	1494.95
30	Clearing jungle.	% M ²	770.00	263.90	2032.03
	Fixing chaukhat in existing opening.				
	Door	No.	2	354.45	708.90
31	Window	No.	3	214.20	642.60

302

32	P/F WC pan with cistern.	No.	1	2304.65	2304.65
33	P/F 100mm soil pipe PVC	M	10.00	163.40	163.40
34	P/F 75mm vent pipe	M	4.0	95.0	380.0
35	P/F wash basin	No.	1.0	1201.70	1201.70
36	P/F mirror	No.	1.0	493.65	493.65
37	P/F glass shelves	No.	1.0	218.80	218.80
38	P/F rain water (PVC) pipe.	M	25.5	163.40	4166.70
39	P/F pvc palin bend	No.	6.0	134.20	805.20
40	P/F M.S. holder bat clamp	No.	28.0	65.35	1829.80
	P/F G.I. pipe complete				
	a) 20mm	M	26.0	133.85	3480.10
41	b) 15mm	M	6.0	105.85	635.10
	P/F 100x100x75mm Tee	No.	1.0	402.50	402.50
	P/F 100mm trap of self cleaning	No.	1.0	442.10	442.10
42	P/F grating 100mm dia	No.	1.0	16.45	16.45
43	Making connection of G.I. dist.	No.	1.0	166.05	166.05
44	P/F brass bib cock	No.	1.0	191.70	191.70
45	P/F brass stop cock	No.	1.0	191.70	191.70
				Total (Rs.)	2,54,187.07
	<u>Electric Work</u>				
1	Wiring for light, fan, tube point.	Pts.	29	305	8845.00
2	S/F/F 3 pin 5/6 amp plug socket.	No.	8	48	384.00

306

3	Wiring for power plug point.	No.	9	189	1341.00
4	Wiring for circuit wiring				
	With 2x1.5sqm	M	160	71	11360.00
	With 2x6sqm	M	100	127	12700.00
5	P/F 32 amp TPN distn. tap off box	No.	1	3680	3680.00
6	S/F/F power plug	No.	9	214	1926.00
7	Installation, testing, commissioning of ceiling fan.	No.	10	45	450.00
				Total (Rs.)	2,94,873.07
				Say (Rs.)	2,94,873.00

Note : Add _____% above/below from the estimated Cost.


 30/9/19
 Area Civil Engineer
 Govindpur Area

Signature of the Contractor