BHARAT COKING COAL LIMITED

(A Subsidiary of Coal India Ltd)

OFFICE OF THE GENERAL MANAGER

LODNA AREA

Ref. No. BCCl/LA/CIVIL/NIT/2008-09/ 2023 Date : 31.01.2009

NOTICE INVITING TENDERS

(A bridged N.I.T. for BCCL Web site)

Sealed percentage rate Tenders in two parts are invited from experienced and eligible contractors for the following works at Lodna Area :-

Sl. N	Name of work	Estimated cost (Approved)	Earnest money	Cost of Tender paper	Time of comple-tion
1	Brick on edge flooring back side of CISF Barrack, Jealgora under Lodna Area	Rs.2,58,392.94	Rs.2584/-	Rs.250/-	30 days
2	RCC Pavement of NTC,HEMM Workshop at NTC under Lodna Area	Rs.4,79,991.00	Rs.4800/-	Rs.250/-	45 days

Issue of tender documents – **Begins on 17.02.2009**
Closes on 18.02.2009:

Issue of tender documents will be done on all working days during working hours except on Sundays & holidays. In the event of the specified date for submission/opening of bids declared a holiday by the employer, the bids will be received/opened on the appointed time on the next working day.

Date & time of opening of Tenders **20.02.2009 at 3.30 P.M.**

The tender documents can be had from the office of the General Manager, Lodna Area P.O.Khas Jeenagora, Dist. Dhanbad on deposition of requisite cost of tender paper in form of cash to the Cashier, Lodna Area.

SPECIAL CONDITIONS FOR TENDERERS , DOWNLOADING THE TENDER DOCUMENT FROM BCCL WEB-SITE

(1) Tenderers are required to deposit along with their tender, a Bank Draft of any Nationalized / Schedule Commercial Bank payable at Dhanbad exclusively towards the cost of Tender Document for the amount indicated as above, in a separate envelope. Any Bank Draft, prepared after the scheduled closure of sale of Tender Documents i.e, 18.02.2009 may be liable for rejection.

(2) The contents of the Tender Documents available for sale in our offices, shall be deemed as authenticated and the responsibility of errors and omissions in the downloaded documents will lie with the tenderer.

The management of BCCL reserves right to reject any or all tender or split the work among two or more tenderers without assigning any reasons whatsoever.

Area Civil Engineer
Lodna Area

Copy to:-

1) G.M.(System), BCCL – alongwith C.D.for logging of N.I.T.,Tender documents & BOQ in BCCL Website.
2) General Manager , Lodna Area.

BHARAT COKING COAL LIMITED

(A Subsidiary of Coal India Ltd)

OFFICE OF THE GENERAL MANAGER

LODNA AREA

Ref. No. BCCL/LA/Civil/NIT/2008-09/2023 Date :31.01.2009

NOTICE INVITING TENDER

Sealed percentage rate tender in two parts (Part 'A' & Part 'B') are invited from the experienced and eligible contractors for the following works at Lodna Area.

Sl. No	Name of work	Estimated cost (Approved)	Earnest money	Cost of tender paper	Time of comple-tion
1	Brick on edge flooring back side of CISF Barrack, Jealgora under Lodna Area	Rs.2,58,392.94	Rs.2584/-	Rs.250/-	01(One) month
	RCC Pavement of NTC,HEMM Workshop at NTC under Lodna Area	Rs.4,79,991.00	Rs.4800/-	Rs.250/-	45 days

Issue of tender documents – **Begins on 17.02.2009**
Closes on 18.02.2009

Issue of tender documents will be done on all working days during working hours except on Sundays & holidays. In the event of the specified date for submission/opening of bids declared a holiday by the employer, the bids will be received/opened on the appointed time on the next working day.

Date and time of opening of tender : **20.02.2009 at 3.30 P.M.**

1) Eligibility criteria:

a) The intending tenderer must have in its name as a prime contractor experience of having successfully completed similar works during last 7 (seven) years ending last day of month previous to the one in which bid applications are invited (i.e. eligibility period) should be either of the following :-

Three similar completed works each costing not less than the amount equal to 40% of the estimated cost.

OR

Two similar completed works each costing not less than the amount equal to 50% of the estimated cost.

OR

One similar completed work costing not less than the amount equal to 80% of the estimated cost.

b) Average annual financial turnover of civil works during the last 3 (three) years, ending 31st March of the previous financial year, should be at least 30% of the estimated cost.

c) Similar work means : Civil surface work .

Cont'd

Note:- (i) Provision under eligibility criteria 1. (a) shall also include those similar work which have been started earlier than eligibility period of tender but completed during the eligibility period as per NIT.

(ii) As per eligibility criteria specified under Sl.No.1(a). Pre-qualification shall be done based on experience of successfully completed works and not on experience of work in progress.

2) The tender documents can be had from the office of the **General Manager, Lodna Area, Civil Engineering Department, P.O.Khas Jeenagora,Dist. Dhanbad from 17.02.2009 to 18.02.2009** on deposition of requisite cost of tender paper in form of cash to the Cashier, Lodna Area.

3) Completed sealed tender documents (Part 'A' & 'B') should be submitted at the same time. Part-'A' shall consist of any deviation from terms and conditions of the tender and additional terms and conditions if asked for, technical bid and credentials. Part-'B' shall consist of tender documents as sold to the tenderers duly filling in rates, amounts etc. i.e. price bid. The Earnest money deposit is to be submitted in a separate Envelope altogether superscribing "Earnest Money Deposit", and not inside the envelope containing Part-'A' or Part-'B' of the Bid. The Part-'A' & Part-'B' should also be put into separate sealed envelopes superscribed as such. Thereafter all the three envelopes should be submitted in a sealed envelope with appropriate superscription.

The tender will be received on **20.02.2009** upto **3.00 P.M. by the tender committee in the tender box at Civil Dept., Lodna Area,** and will be opened at **3.30 P.M.** on the same day i.e.on **20.02.2009** The part-II will be opened only after the department is satisfied that the criteria fixed are fulfilled and also the earnest money is deposited i.e. on acceptance of Part-'A'.

4) In case where tender documents are requested for transmission by post, these should be dispatched by registered A.D. The department is not responsible for any postal delay in such cases.

5) The earnest money is to be deposited as per detail given in the tender documents.

6) The tenderers have to submit Permanent Account No. of Income Tax (PAN No) credential copy.

7) Conditional tenders will not be accepted.

8) Issuance of tender documents does not mean that the parties are considered qualified.

9) The experience as given in the eligibility criteria should be in the name and style in which tender is filled. The experience in the name of some other firm/company will not be considered for this purpose.

10) The validity of the tender will be 120 days from the date of opening price bid or revised Price bid, if any.

Cont'd.

11) The management of BCCL reserves right to reject any or all tender or split the work among two or more tenderers with out assigning any reasons whatsoever.

12) Other details may be obtained from tender notice/tender documents/website no. **http://bccl.cmpdi.co.in**.

SPECIAL CONDITIONS FOR TENDERERS , DOWNLOADING THE TENDER DOCUMENT FROM BCCL WEB-SITE

13) Tenderers are required to deposit along with their tender, a Bank Draft of any Nationalized / Schedule Commercial Bank payable at Dhanbad exclusively towards the cost of Tender Document for the amount indicated as above, in a separate envelope. Any Bank Draft, prepared after the scheduled closure of sale of Tender Documents i.e. 18.02.2009 may be liable for rejection.

14) The contents of the Tender Documents available for sale in our offices, shall be deemed as authenticated and the responsibility of errors and omissions in the downloaded documents will lie with the tenderer.

Area Civil Engineer
Lodna Area

Copy to :-

1) All CGMs/GMs, Areas of BCCL. .
2) GM(System), BCCL for logging of N.I.T., Tender Document & BOQ on Website.
3) C.V.O., BCCL.
4) General Manager (Constn), CED. BCCL.
5) A.F.M, Lodna Area
6) TCM, AM(Plg)/SE(C), Lodna Area.
8) All Project Officers, Lodna Area – for display in Notice Board.
9) Notice Board, Lodna Area
10) Office copy/M.file

D E C L A R A T I O N

I hereby declare that my / our firm has not been banned or de-listed by any Government or Quassi Government agencies or PSU's.

Signature of the Tenderer
With Seal/Mohar

P A R T 'A'
BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Limited)

OFFICE OF THE GENERAL MANAGER
LODNA AREA

1. Name of work **:Sl.No.(1) Brick on edge flooring back side of CISF Barrack,Jealgora under Lodna Area.**
   Sl.No.(2) RCC Pavement of NTC,HEMM Workshop at NTC under Lodna Area.
2. **Name of contractor :**

   Address :

3. N.I.T. Reference : **Ref. No. BCCl/LA/Civil/NIT/2008-09/2023 dated 31.01.2009.**
4. Date of Receipt of tender : Up to **3.00** P.M. on **20.02.2009**
5. Date of open of Tender : **At 3.30** P.M. on **20.02.2009**
6. Details of E.M.D. : No. Date
   Rs._____
7. Money Receipt No. (for issue of tender paper) : No Date
   Rs._____
8. Photocopy of PAN :
9. Credential against experience :

SIGNATURE OF ISSUING OFFICE

P A R T - B

P R I C E B I D(Sl.No.1)

Issued to the Tenderer_____

Vide M/R No._____ Date_____

For Rs.250/- only

Sign.of issuing authority_____

BILL OF QUANTITY FOR THE WORK OF " BRICK ON EDGE FLOORING BACK SIDE OF CISF BARRACK, JEALGORA UNDER LODNA AREA."

Sl. No.	P a r t i c u l a r s	Qnty.	unit	Rate	Amount
1	Earth work in excavation in foundation trenches or drains(not exceeding 1.5m in width or 10Sqm on plan) including dressing of sides and ramming of bottoms,lift upto 1.5m including getting out the excavated soil & disposal of surplus excavated soils as directed. i) All kinds of soil	188.35	/Cum.	Rs.93.55	Rs.17,620.14
2	Brick on edge flooring with bricks of class design.50 including slurry etc. complete in cement mortar with F.P.S bricks.	1236.00	/Sqm	Rs.194.80	Rs.2,40,772.80
				TOTAL	**Rs.2,58,392.94**

Compared by:

I / we quote _____% (_____) above / below or at par on the estimate rates for all the above items.

Date:

Signature of Contractor
Seal & Date

P A R T – 'B'

P R I C E B I D (SL.NO.2)

Issued to the Tenderer_____
Vide M/R No. _____Dt._____
of Rs.250/- only
Sign.of issuing authority_____

BILL OF QUANTITY FOR THE WORK OF "RCC PAVEMENT OF NTC, WORKSHOP AT NTC UNDER LODNA AREA."

Sl. No.	P a r t i c u l a r s	Qnty.	unit	Rate	Amount
1	Earth work in excavation in foundation trenches or drains(not exceeding 1.5m in width or 10Sqm on plan) including dressing of sides and ramming of bottoms,lift upto 1.5m including getting out the excavated soil & disposal of surplus excavated soils as directed. i) All kinds of soil	92.92	/Cum.	Rs.93.55	Rs.8,692.66
2	Supply and filling in plinth with Jamuna sand under floors including, watering, ramming consolidating and dressing	92.92	/Cum	Rs.213.30	Rs.19,819.83
3	Providing & laying in position cement of specified grade excluding the cost of centring & shuttering.All work upto plinth level. i) 1:4:8(1 cement:4 coarse sand:8 graded stone aggr.40mm nominal size.	61.33	/Cum	Rs.1404.70	Rs.86,150.25
4	Reinforced cement concrete work in beams, suspended floors,roofs having slope upto 15 Deg. landings, balconies, shelves, chajjas, intels, bands,plin window,sills, staircases and spiral stair cases upto floor five level excluding the cost of centring, juttering, finishing and reinforcement with 1:2:4	92.92	/Cum	Rs.2120.65	Rs.1,97,050.79
5	Structural steel work in single section fixed without connecting plate including cutting, hoisting,fixing and applying a priming coat of approved steel primer all complete.	7434.00	/Kg.	Rs.21.95	Rs.1,63,176.30
6	Centring & shuttering including strutting Propping etc.& removal of form for	58.00	/Sqm	Rs..87.95	Rs.5,101.10

TOTAL : Rs. 4,79,991.00

Compared by:

I / we quote _____% (_____) above / below or at par on the estimate rates for all the above items.

Date :

Signature of Contractor
with Seal/Mohar