

BHARAT COKING COAL LTD.
(A Subsidiary of Coal India Ltd.)
OFFICE OF THE GENERAL MANAGER
LODNA AREA

Ref: No. BCCL/LA/Civil/NIT/09-10/1820

Dated:- 12.01.10

NOTICE INVITING TENDER

Sealed percentage rate tender in two parts (Part 'A' & part 'B') are invited from the experienced, and eligible contractors for the following work.

| SL No. | Name of work | Estimated Cost (Approved) | Earnest Money | Cost of tender Paper | Time of completion |
|--------|-----------------------------------------------------------------------------------|---------------------------|---------------|----------------------|--------------------|
| 1 | Construction of 5 Nos. Latrine with septic tank at Different place at Lodna Area. | 2,95,300.72 | 2953 | 250 | 15 |
| 2 | Construction of drain at Dumariya Tand Colony at Digwadih under Lodna Area. | 4,99,540.54 | 4996 | 250 | 20 |

- Availability of Tender documents:-** Tender document can be had from the office of the General manager, BCCL, Lodna Area, Lodna Area civil Engineering Department, P.O. Khas Jeenagora, dist. Dhanbad from 29.01.10 to 30.01.10 on deposition of requisite cost of tender paper in form of cash or Bank Draft of Nationalised bank in favour of Bharat Coking Coal Ltd. Payable at Dhanbad during office hours on all working days. In the event of the specified date for submission of bids being declared a holiday, the bid will be received/opened on the appointed on the next working day.
- Receipt Tender :-** The tender will be received on 01.02.10 up to 3.00 P.M. at Civil Engg. Deptt. Lodna Area, P.O. Khas jeenagora, Dist. Dhanbad. Complete sealed tender document (Part "A" & Part "B") should be submitted at the same time. Part 'A' shall consist of any deviation from terms and conditions of the tender and additional terms and condition if asked for, technical bid and credentials. Part 'B' shall consist of tender documents as sold to the Tenderers duly filling in rates, amounts etc. i.e. price bid. The earnest money deposit is to be submitted in a separate envelope altogether super scribing "Earnest Money Deposit" and not inside the envelope containing part-"A" or part-"B" of the Bid. The part-"A" & part-"B" should also be put into separate sealed envelopes super scribed as such. Thereafter all the three envelopes should be submitted in a sealed envelope with appropriate superscription.
- Opening of Tender :-** The Tender will be opened at 3.30 P.M. on 01.02.10 itself in presence of the intending Tenderers or their authorized representative in the office of the civil Engg. Deptt. Only Part -A will be opened and part 'B' will be opened only after acceptance of Part-'A'
- Eligibility Criteria :-**

The intending tender must have in its name as prime contractor experience of having successfully completed similar work during 7 (seven) years ending last day of the month previous to the one in which bid application are invited (i.e. eligibility period) should be either of the following :-

Three similar completed works is costing no less than the amount equal to 40 % of the estimated cost.

OR

Two similar completed work is costing lo less than the amount equal to 50% of the estimated cost.

OR

One similar completed work is costing lo less than the amount equal to 80% of the estimated cost.

Similar Work means : Development work and Building work

- Average annual financial turn over of civil works during the last three years ending 31st March of the pervious financial year should be at least 30% of the estimated cost.

The intending Tenderers must submit documentary evidence in support of (4) (a) and (b) above in the form of certified copy of work order, completion certificate, payment certificates. vouchers, indicating the

Duly signed by him/them.

- In case where tender documents are requested for transmission by post, these should be dispatched A.D. The department is not responsible for any postal delay in such cases.
- The earnest money is to be deposit as per detail given in the tender documents.
- Copy of TIN no.
- The Tenderers have to submit Permanent Account No. of Income Tax (PAN No).
- Conditional tenders will not be accepted.
- Issuance of tender documents does not mean that the parties are considered qualified.

Contd. P/2

- 11) The Experience as given in the eligibility criteria should be in the name and style in which tender is filled. The experience in the name of some other firm/company will not be considered for this purpose.
- 12) The validity of the tender will be 120 days from the date of opening price bid or revised Price bid, if any.
- 13) The management of BCCL reserves right to reject any or all tender or split the work among two or more Tenderers with out assigning any reasons whatsoever.
- 14) Other details may be obtained from tender notice/tender documents
- 15) Tenderers are required to deposit along with their tender, a bank Draft of any nationalized / Schedule Commercial bank payable at Dhanbad exclusively towards the cost of Tender Document for the amount indicated as above, in a separate envelope. Any bank Draft, prepared after the scheduled closure of sale of Tender Documents i.e. 30.01.10 may be liable for rejection.
- 16) The contents of the Tender Documents available for sale in our offices, shall be deemed as authenticated and the responsibility of errors and omissions in the downloaded documents will lie with Tenderers.
- 17) Firm registration or partnership deed & power of attorney / affidavit regarding proprietorship / article of association.
- 18) Every tender is required to be given on affidavit in the Performance given in the tender document on non judicial stamp paper.

Area Civil Engineer
Lodna Area

Copy to :-

- 1) All CGMS / GMS, Areas of BCCL.
- 2) GM (System), BCCL for logging of N.I.T. Tender Document & BOQ on Website.
- 3) C.V.O., BCCL. Koyla Bhawan
- 4) General Manager (Constn), CED.BCCL. Koyla Nagar
- 5) Addl. G.M/A.F.M. , Lodna Area
- 6) TCM, / SE(C), Lodna Area
- 7) All Project Officers, Lodna Area- For display in Notice Board.
- 8) Notice Board , Lodna Area 9) Office copy / M. copy.

NIT Ref. No. BCCL /LA/Civil/NIT/2009/1820

Date:- 12.01.10

Tender for the following work is invited by civil Engg. Deptt. Lodna Area on behalf of BCCL management.

| | Estimated Cost (Approved) | Earnest Money | Cost of tender Paper | Time of completion |
|-----------------------------------------------------------------------------------|---------------------------------|------------------|-------------------------|-----------------------|
| Construction of 5 Nos. Latrine with septic tank at Different place at Lodna Area. | 2,95,300.72 | 2953 | 250 | 15 |
| Construction of drain at Dumariya Tand Colony at Digwadiah under Lodna Area. | 4,99,540.54 | 4996 | 250 | 20 |

All other details i.e. Estimate cost of the work , completion period , cost of E.M.D. etc. can be seen on company's Website www.cmpdil.co.in

The sale period for the tender document : From 29.01.10. to 30.01.10

Date of receipt & opening of tender on 01.02.10 by 3.00 & 3.30 P.M. respectively

BHARAT COKING COAL LIMITED

(A subsidiary of Coal India Limited)

OFFICE OF THE GENERAL MANAGER

LODNA AREA

PART "A" (Serial 1)

1. Name of work :- Construction of 5 Nos. Larine with septic tank at Different place at Lodna Area.
- 2 Name of contractor :-
- Address :-
3. N.I.T. Reference :- BCCL/LA/Civil/NIT/09-10/1820
Dated : 12.01.10
- 4 Date of receipt of tender :- UP to 3.00 P.M. on 01.02.10
- 5 Date of open of Tender :- at 3.30 P.M. on 01.02.10
- 6 Details of E.M.D. :- No. Dated:
- 7 Money Receipt No. :- No. Dated:
- (for issue of tender paper) :-
- 8 Photocopy of PAN :-
- 9 Credential against experience:-

SIGNATURE OF ISSUING OFFICER

DECLARATION

I hereby declare that my / our firm has not been banned or de-listed by any Government or Quassi Government agencies or PSU's

Signature of the Tenderer
With Seal/Mohar

PART-B
PRICE BID SL.NO.1

Issued to the Tenderer _____
Vide M/R No. _____ Date:-
For Rs. 250/-

Sign. Of Issuing authority-----

Bill of quantity for the work of "Construction of 5 Nos. Larine with septic tank at Different place at Lodna Area.

| Sl No. | Particulars | Qty | Unit | Rate | Amount |
|--------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|----------|-----------|
| 1. | Earth working in excavation by mechanical means (hydraulic excavator) manual mean over areas (exceeding 30 cm in depth, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift up to 1.5m, disposed earth to be leveled and neatly dressed. All kinds of soil | 55.05 | Cum | 101.85 | 5606.84 |
| 2 | Brick flate soling | 47.20 | Cum | 92.82 | 438.10 |
| 3 | Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering – All work upto plinth level. 1:5:10 (1cement :5 coarse sand 10: graded stone aggregate 40mm nominal size) | 47.50 | Cum | 2.296.15 | 109067.12 |
| 4 | Brick work with F.P.S. brick of class designation foundation and plinth in:Cement 1:6 (1cement ; 6 coarse sand) | 33.85 | Cum | 2011.75 | 68097.73 |
| 5 | Brick work with F.P.S. brick of class designation 75 in superstructure above plinth level up to floor V level in all shapes and sizes in . cement mortar 1:6(1 cement 6 coarse sand0 | 16.00 | Cum | 2320.25 | 37124.00 |
| 6 | Reinforced cement concrete work in beam, suspended floor, roofs, having slope up to 15" landings, shelves, chajjas , lintels, bands, palin window sills, staircases and spiral stair cases up to floor five level excluding the cost of centering , shuttering , finishing and reinforcement with 1:2:4)1 cement : 2 coarse sand ;4 graded stone aggregate 20 mm nominal size. | 1.75 | Cum | 3673.85 | 6429.23 |
| 7 | Reinforcement for RCC work including straightening , cutting , bending , placing in position and binding all complete. Cold twisted bar | 140.00 | Kg | 42.70 | 5978.00 |
| 8 | 12 mm cement plaster of mixes 1:6(1cement :6 fine sand) | 145.10 | Sqm | 67.65 | 9816.01 |
| 9 | 25 mm thick PCC 1;2:4 (1cement :2 fine sand 4: Concrete) | 25.00 | Sqm | 106.15 | 2653.75 |
| 10 | 12 mm thick Plaster 1 :4(1cement :4 fine sand) | 115.00 | Sqm | 97.90 | 11258.50 |
| 11 | Providing and fixing AC sheet roofing | 17.85 | Sqm | 294.95 | 5264.85 |
| 12 | Proving and fixing MS door | 8.35 | Sqm | 1438.95 | 12015.23 |
| 13 | What washing two or more coat | 145.10 | Sqm | 6.75 | 979.42 |
| 14 | Painting two or more coat | 16.70 | Sqm | 33.25 | 555.27 |
| 15 | Providing and fixing WC pan 580 | 5 | No. | 534.60 | 2673.00 |
| 16 | Providing and fixing foot rest 25x125x2 | 5 | Pair | 111.70 | 558.50 |
| 17 | Providing and fixing P&S trap of 100 | 5 | No. | 442.10 | 2210.50 |
| 18 | Providing and fixing Tee GI 100x100x75 | 5 | No. | 402.50 | 2012.50 |
| 19 | Providing and fixing SCI pipe 100mm | 10 | No. | 451.00 | 4510.00 |
| 20 | Providing and fixing SCI pipe of 75mm | 10 | No. | 395.45 | 3954.50 |
| 21 | Providing and fixing feet rest 100mm | 5 | No. | 294.50 | 1222.50 |
| 22 | Providing and fixing terminal glass 100 | 5 | No. | 192.55 | 962.75 |
| 23 | Providing and fixing collar GI 100 | 5 | No. | 143.45 | 717.25 |
| 24 | Providing and fixing plain bend 100 | 5 | No. | 222.45 | 1112.25 |
| 25 | Providing and fixing MS filder bet clamb | 15 | No. | 65.35 | 980.25 |

Total 2,95,300.72

Compared By :-

I we quote _____ % () on above / below basis or as per on the estimate rate for the above items.

Name of Contractor :-

Signature of contractor
Seal& Date

BHARAT COKING COAL LIMITED

(A subsidiary of Coal India Limited)

OFFICE OF THE GENERAL MANAGER

LODNA AREA

PART "A" (Serial 2)

- | | | |
|------------------------------------|----|-----------------------------------------------------------------------------|
| 1. Name of work | :- | Construction of drain at Dumariya Tand Colony at Digwadih under Lodna Area. |
| 3 Name of contractor | :- | |
| Adress | :- | |
| 3. N.I.T. Reference | :- | BCCL/LA/Civil/NIT/09-10/ 1820 Dated : 12.01.10 |
| 4 Date of receipt of tender | :- | UP to 3.00 P.M. on 01.02.10 |
| 5 Date of open of Tender | :- | at 3.30 P.M. on 01.02.10 |
| 6 Details of E.M.D. | :- | No. Dated: |
| 7 Money Receipt No. | :- | No. Dated: |
| (for issue of tender paper) | :- | |
| 10 Photocopy of PAN | :- | |
| 11 Credential against experience:- | | |

SIGNATURE OF ISSUING OFFICER

DECLARATION

I hereby declare that my / our firm has not been banned or de-listed by any Government or Quassi Government agencies or PSU's

Signature of the Tenderer
With Seal/Mohar

PART-B
PRICE BID SL.NO.2

Issued to the Tenderer _____
Vide M/R No. _____ Date:-
For Rs. 250/-

Sign. Of Issuing authority-----

Bill of quantity for the work of "Construction of drain at Dumariya Tand Colony at Digwadih under Lodna Area.

| Sl No. | Particulars | Qty | Unit | Rate | Amount |
|--------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|------|----------|-------------|
| 1. | Earth working in excavation by mechanical means (hydraulic excavator) manual mean over areas (exceeding 30 cm in depth, 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift up to 1.5m, disposed earth to be leveled and neatly dressed. All kinds of soil | 419.48 | Cum | 101.85 | 42,724.03 |
| 2 | Brick flate soling | 700.92 | Cum | 92.82 | 6,5059.30 |
| 3 | Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering – All work upto plinth level. 1:5:10 (1cement :5 coarse sand 10: graded stone aggregate 40mm nominal size) | 31.62 | Cum | 2,296.15 | 72,604.24 |
| 4 | Brick work with F.P.S. brick of class designation foundation and plinth in:Cement 1:6 (1cement ; 6 coarse sand) | 97.09 | Cum | 2011.75 | 1,95,320.80 |
| 5 | 12 mm thick Plaster 1 :4(1cement :4 fine sand) | 860.50 | Sqm | 97.90 | 84,242.95 |
| 6 | 25 mm thick PCC 1;2:4 (1cement :2 fine sand 4: Concrete) | 326.20 | Sqm | 106.15 | 34,626.13 |
| 7 | Reinforced cement concrete work in beam, suspended floor, roofs, having slope up to 15" landings, shelves, chajjas , lintels, bands, palin window sills, staircases and spiral stair cases up to floor five level excluding the cost of centering , shuttering , finishing and reinforcement with 1:2:4)1 cement : 2 coarse sand ;4 graded stone aggregate 20 mm nominal size. | 0.70 | Cum | 3673.85 | 2,571.69 |
| 8 | Reinforcement for RCC work including straightening , cutting , bending , placing in position and binding all complete. Cold twisted bar | 56.00 | Kg | 42.70 | 2,391.20 |

Total 4,99,540.54

Compared By :-

I we quote _____ % (_____) on above / below basis or as per on the estimate rate for the above items.

Name of Contractor :-

Signature of contractor
Seal& Date