

BHARAT COKING COAL LIMITED

(A Subsidiary of Coal India Ltd.)

Office of the General Manager, Govindpur Area

P.O. Sonardih, Dist. Dhanbad

Ref. No. GM/AR-III/ACE/Tender/

40 204 - 32

Dated 16.03.2009

SHORT TENDER NOTICE

17

Sealed tenders are invited from registered and experienced contractors for the following works :-

Sl. No.	Name of work	Estimated cost (in Rs.)	Earnest Money	Cost of tender paper	Time of completion
1.	Construction of monsoon drain near Tewary Basti at Govindpur Colliery.	2,65,559.00	1%	Rs.250/-	1 month

Eligibility Criteria:-1 (a) The average annual financial turnover during the last three years ending 31st March of the previous year should be atleast 30% of the estimated cost. (b) Experience of having successfully completed similar works during last 7 (seven) years ending last day or month previous to the one in which bid applications are invited (i.e. eligibility period) should be either of the following. (C) (i) Three similar completed works each costing not less than the amount equal to 40% of the estimated cost.(ii) Two similar completed works each costing not less than the amount equal to 50% of the estimated cost.(iii) One similar completed works each costing not less than the amount equal to 80% of the estimated cost. 2) J.S.T. Clearance certificate 3) Permanent Account number of Income Tax.

The tender will be received on dated 28.03.2009 upto 11.00 a.m. in two parts and will be opened on the same day upto 11.30 a.m. in the presence of tenders or their authorised agents.

Without earnest money tender will be rejected. The tenderers are required to deposit the E.M. in the shape of demand draft or M.R. of Govindpur Area.

The bill of quantity will have to obtained from office of the undersigned on production of M.R. upto 27.03.2009.

Authority is reserved to reject any or all the tenders without assigning any reason whatsoever.

It will be obligatory for the tenders to keep their offer for a period of 120 days from the date of opening of the tender.

Sale-Tax will be deducted as per rule from the bill of the Contractor. No conditional tender paper will be accepted.

No materials will be supplied to the contractor for doing this work.

The contractor will have to abide by all labour rules of the country/state.

A.K. Srinivasa
16.3.09
Area Civil Engineer,
Govindpur Area

C.C. to :-

- 1) Addl. GM, Govindpur Area.
- 2) AFM Govindpur Area.
- 3) All Project Officers, Govindpur Area.
- 4) C.G.M/G. M., Area 1 to 12, E.J. Area, W.J.Area, W.W.Z Ropeways.
- 5) G.M. (Const), Koylanagar, Dhanbad.
- 6) Notice Board
- 7) Builders Association of India, 16 LIG Housing Colony Dhanbad / Near Akashkinaree Weighbridge, P.O. Katrasgarh.
- 8) C.V.O, B.C.C.L, Koyla Bhawan.
- 9) General Manager (System), Koyla Bhawan, Dhanbad.

**Bill of Quantity for the work of "Construction of monsoon drain near
Tewary Basti at Govindpur Colliery"**

Summary of Work of Amount

Sl. No.	Particulars of the work	Amount (in Rs.)
1	Construction of stone massonary monsoon drain near Tiuary Basti of Govindpur Colliery.	1,69,956.00
2	Construction of 2.50m span culvert near Tiuary Basti of Govindpur Colliery.	95,603.00
	Total (Rs.)	2,65,559.00

**1. Construction of stone massonary monsoon drain near Tiuary Basti of Govindpur
Colliery.**

Sl. No.	Particulars of the work	Unit of Qty.	Estimated Qty. of Work	B.C.C.L scheduled rates	Amount (in Rs.)
1	Earth work in excavation in foundation as per specification.	M ³	196.00	93.55	18335.80
2	P/L P.C.C (1:3:6) in foundation as per specification..	M ³	29.40	1324.30	38934.42
3	Stone massonary wall in cm (1:6) in foundation with quarry boulder as per specification.	M ³	115.50	732.38	84589.89
4	P/L PCC (1:2:4) as per specification.	M ³	3.5	1843.00	5805.45
5	25mm thick p.s. flooring (1:2:4) as per specification.	M ²	126.00	86.05	10842.30

Handwritten signature and date

A-K. Srivastava
16-3-09

6	Carriage of stone massonary wall qty quarry boulder upto 1km lead.	M ³	133.98	55.64	7454.64
7	Breaking of quarry boulder as per site required.	M ³	133.98	29.81	3993.94
Total (Rs.)					1,69,956.44
Say (Rs.)					1,69,956.00

2. Construction of 2.50m span culvert near Tiwary Basti of Govindpur Colliery.

Sl. No.	Particulars of the work	Unit of Qty.	Estimated Qty. of Work	B.C.C.L scheduled rates	Amount (in Rs.)
1	Earth work in excavation in foundation.	M ³	38.60	93.55	3611.03
2	P/L P.C.C (1:3:6) in foundation.	M ³	6.33	1468.25	9297.18
3	Brick on edge soaling with sand as per specification.	M ²	11.58	132.33	1532.38
4	Sand course filling in foundation as per specification.	M ³	1.15	213.30	245.29
5	Brick work in cm (1:6) in f&p as per specification.	M ³	37.64	1256.53	47295.78
6	R.C.C work in (1:2:4) slab as per specification.	M ³	4.56	2120.65	9670.16
7	Reinforcement for RCC work as per specification.	Kg	475.00	21.85	10378.75
8	Centering & shuttering including removing the same.	M ²	18.70	111.20	2079.44
9	P/L PCC (1:2:4) as per specification.	M ³	2.46	1843.00	4533.78

[Signature]
E. B. S.

A. K. Srinivasan
16.3.09

10	12mm c.p. (1:4) as per specification. with punning.	M ²	64.63	62.10	4013.52
11	Earth work in filling as per specification.	M ³	22.50	30.25	680.62
12	6mm thick c.p. (1:3)	M ²	11.40	40.00	456.00
13	Stone soaling on road as per specification.	M ²	20.00	68.15	1363.00
14	Carriage of quarry boulder at site	M ³	5.22	55.64	290.44
15	Breaking of quarry boulder as per site required	M ³	5.22	29.81	155.60
Total (Rs.)					95,602.97
Say (Rs.)					95,603.00

Total = Rs. (1,69,956 + 95,603)
= Rs. 2,65,559.00

Verified
21/11
E. B. S.

Note : Add ____% above/below from the estimated Cost.

A. K. Singhania
16/3/09
Area Civil Engineer
Govindpur Area

Signature of the Contractor