

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Ltd.)
Office of the General Manager, Govindpur Area
P.O. Sonardih, Dist. Dhanbad

Ref No. GM/AR-III/ACE/Tender/

391-418

Dated 10.04.2009

SHORT TENDER NOTICE

Sealed tenders are invited from registered and experienced contractors for the following

works Sl No.	Name of work	Estimated cost (in Rs.)	Earnest Money	Cost of tender paper Rs.250/-	Time of completion 1 month
1	Construction of retaining wall to protect back side of embankment of Bagdigi Jore (480 ft. long) at Govindpur Colliery of Govindpur Area.	4,96,800.00	1%		

Eligibility Criteria:-1 (a) The average annual financial turnover during the last three years ending 31st March of the previous year should be atleast 30% of the estimated cost. (b) Experience of having successfully completed similar works during last 7 (seven) years ending last day or month previous to the one in which bid applications are invited (i.e. eligibility period) should be either of the following. (C) (i) Three similar completed works each costing not less than the amount equal to 40% of the estimated cost.(ii) Two similar completed works each costing not less than the amount equal to 50% of the estimated cost.(iii) One similar completed works each costing not less than the amount equal to 80% of the estimated cost. 2) J.S.T. Clearance certificate 3) Permanent Account number of Income Tax.

The tender will be received on dated 23.04.2009 upto 3.00 p.m. in two parts and will be opened on the same day upto 3.30 p.m. in the presence of tenders or their authorised agents.

Without earnest money tender will be rejected. The tenderers are required to deposit the E.M. in the shape of demand draft or M.R. of Govindpur Area.

The bill of quantity will have to obtained from office of the undersigned on production of M.R. upto 22.04.2009.

Authority is reserved to reject any or all the tenders without assigning any reason whatsoever

It will be obligatory for the tenders to keep their offer for a period of 120 days from the date of opening of the tender.

Sale-Tax will be deducted as per rule from the bill of the Contractor. No conditional tender paper will be accepted.

No materials will be supplied to the contractor for doing this work.

The contractor will have to abide by all labour rules of the country/state.

10/4/09
Area Civil Engineer,
Govindpur Area

C.C. to :-

- 1) Addl. GM, Govindpur Area.
- 2) AFM Govindpur Area.
- 3) All Project Officers, Govindpur Area.
- 4) C.G.M/G. M., Area 1 to 12, E.J. Area, W.J.Area, W.W.Z Ropeways.
- 5) G M (Const), Koylanagar, Dhanbad.
- 6) Notice Board
- 7) Builders Association of India, 16 LIG Housing Colony Dhanbad / Near Akashkinaree Weighbridge, P.O. Katrasgarh.
- 8) C V O, B.C.C.L, Koyla Bhawan.
- 9) General Manager (System), Koyla Bhawan, Dhanbad.

Bill of Quantity for the work of "Construction of retaining wall to protect back side of embankment of Bagdigi Jore (480 ft. long) at Govindpur Colliery of Govindpur Area"

RETAINING WALL


Sl. No.	Particulars of the work	Unit of Qnty.	Estimated Qnty. of Work	B.C.C.L scheduled rates	Amount (in Rs.)
1	Earth work in excavation in foundation as per specification.	M ³	79.28	93.55	7416.64
2	Stone massonary wall in cm (1:6) with quarry boulder in foundation as per specification.	M ³	175.56	732.38	128576.63
3	P/L P.C.C 1:2:4 on top wall as per specification.	M ³	3.62	1843.00	6671.66
4	Pointing on stone massonary wall with cm (1:3) as per specification.	M ²	148.70	42.65	6342.05
5	Carriage of excavated quarry boulder with lead 3.00 km at site.	M ³	203.58	70.33	14317.78
6	Breaking of quarry boulder as site required as per specification.	M ³	203.58	29.81	6068.71
Total (Rs.)					1,69,393.47

EMBANKMENT WORK

Sl. No.	Particulars of the work	Unit of Qnty.	Estimated Qnty. of Work	B.C.C.L scheduled rates	Amount (in Rs.)
1	Earth work in excavation in rough foundation for embankment as per specification.	M ³	1121.36	103.65	116280.78

[Handwritten signature]

[Handwritten signature]

2.	Carriage of excavated earth work lead upto 1.00km lead	M ³	1121.86	34.77	39007.07
3	Stone dry stone pitching on side of embankment with quarry boulder.	M ²	758.36	68.15	51682.23
4	Pointing on stone pitching with cm (1:3) as per specification.	M ³	758.36	42.65	32344.05
5.	Carriage of excavated quarry boulder with lead 3.00 km as per specification.	M ³	879.69	70.33	61868.59
6	Breaking of quarry boulder as site required.	M ³	879.69	29.81	26223.55
<div>Verified  E. S. Ch</div>			Total (Rs.)		4,96,799.74
			Say (Rs.)		4,96,800.00

Note : Add ____% above/below from the estimated Cost.


 Area Civil Engineer
 Govindpur Area

Signature of the Contractor