

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Ltd.)
Office of the General Manager, Govindpur Area
P.O. Sonardih, Dist. Dhanbad

Ref. No. GM/AR-III/ACE/Tender/

6121-49

Dated 08.07.2009

SHORT TENDER NOTICE

Sealed tenders are invited from registered and experienced contractors for the following works :-

Sl. No.	Name of work	Estimated cost (in Rs.)	Earnest Money	Cost of tender paper	Time of completion
1.	False ceiling of the auditorium at the guest house of Govindpur Area.	3,95,377.37	1%	Rs.250/-	2 months

Eligibility Criteria:-1 (a) The average annual financial turnover during the last three years ending 31st March of the previous year should be atleast 30% of the estimated cost. (b) Experience of having successfully completed similar works during last 7 (seven) years ending last day or month previous to the one in which bid applications are invited (i.e. eligibility period) should be either of the following. (C) (i) Three similar completed works each costing not less than the amount equal to 40% of the estimated cost.(ii) Two similar completed works each costing not less than the amount equal to 50% of the estimated cost.(iii) One similar completed works each costing not less than the amount equal to 80% of the estimated cost. 2) J.S.T. Clearance certificate 3) Permanent Account number of Income Tax.

The tender will be received on dated 21.07.2009 upto 3.00 p.m. in two parts and will be opened on the same day upto 3.30 p.m. in the presence of tenders or their authorised agents.

Without earnest money tender will be rejected. The tenderers are required to deposit the E.M. in the shape of demand draft or M.R. of Govindpur Area.

The bill of quantity will have to obtained from office of the undersigned on production of M.R. upto 20.07.2009.

Authority is reserved to reject any or all the tenders without assigning any reason whatsoever.

It will be obligatory for the tenders to keep their offer for a period of 120 days from the date of opening of the tender.

Sale-Tax will be deducted as per rule from the bill of the Contractor. No conditional tender paper will be accepted.

No materials will be supplied to the contractor for doing this work.

The contractor will have to abide by all labour rules of the country/state.

A.K. Sivasubramanian
8.7.09.
Area Civil Engineer,
Govindpur Area

C.C. to :-

- 1) Addl. GM, Govindpur Area.
- 2) AFM Govindpur Area.
- 3) All Project Officers, Govindpur Area.
- 4) C.G.M/G. M., Area 1 to 12, E.J. Area, W.J.Area, W.W.Z Ropeways.
- 5) G.M. (Const), Koylanagar, Dhanbad.
- 6) Notice Board
- 7) Builders Association of India, 16 LIG Housing Colony Dhanbad / Near Akashkinaree Weighbridge, P.O. Katrasgarh.
- 8) C.V.O, B.C.C.L, Koyla Bhawan.
- 9) General Manager (System), Koyla Bhawan, Dhanbad.

Bill of Quantity for the work of "False ceiling of the auditorium at the guest house of Govindpur Area"

Sl. No.	Particulars of the work	Unit of Qty.	Estimated Qty. of Work	B.C.C.L scheduled rates	Amount (in Rs.)
1.	Wiring for light point, fan point with 1.5 sqmm F.R. PVC insulated copper conductor.	Point	40.0	305.00	12200.00
2.	Circuit wiring for submain with 2x4 sqmm+1x6 sqmm.	M	100.0	135.00	13500.00
3.	S/F/F of wall fan.	No.	10.0	1490.00	14900.00
4.	S/F/F of decorative light fittings.	No.	30.0	85.00	2550.00
5.	Circuit Submain wiring 1x4 88 mm.	Met.	130.0	97.00	12610.00
6.	Supplying & fixing distribution box	No.	1.0	4354.00	4354.00
	Add 12.5% tax on market rate item with 10% contractor profit on those items no. 3&4.				3926.25
				Total (Rs.)	64,040.25

Sl. No.	Particulars of the work	Unit of Qty.	Estimated Qty. of Work	B.C.C.L scheduled rates	Amount (in Rs.)
1.	P/F false ceiling with 12mm thick plain/semi perforated or design ceiling tiles of BWP Type.	M ²	309.29	202.45	62615.76
2.	P/F powder coated aluminium work consisting of teel angle section of appel make confirming I.S. 733 in frame of false ceiling.	Kg	702.75	364.45	256117.23

*Checked
B. Singh*

*A. K. Sivananda
8.7.09*

3.	Filling gaps between frame and wall by providing weather silicon sealant.	M	82.9	58.85	4878.66
4.	S/steel work welded in built up section.	Kg	50.0	46.35	2317.50
5.	Fixing chaukhat in existing opening.	No.	1.0	354.45	354.45
6.	Making opening in brick wall.	M ²	1.95	208.15	405.89
7.	B/W in f/p in c.m. (1:6)	M ³	1.52	2007.0	3050.64
8.	12mm c.p. (1:4) with punning.	M ²	6.25	97.9	611.87
9.	Painting door & window.	M ²	4.39	33.25	145.96
10.	Distempering with OBD.	M ²	56.32	14.9	839.16
Total (Rs.)					3,31,337.12

Total = Rs. (64,040.25 + 3,31,337.12)
= Rs. 3,95,377.37

checked as per estimate
By msl

Note : Add ____ % above/below from the estimated Cost.

Signature of the Contractor

A.K. Sivaratra
6-7-09
Area Civil Engineer
Govindpur Area