## BHARAT COKING COAL LIMITED

(A Subsidiary of Coal India Ltd.) Office of the General Manager, Govindpur Area P.O. Sonardih, Dist. Dhanbad

Ref. No. GM/AR-III/ACE/Tender/ 109/6-49

Dated 24.08.2009

## SHORT TENDER NOTICE

Sealed tenders are invited from registered and experienced contractors for the following works :-

| SI.<br>No. | Name of work   | Estimated cost (in Rs.) | Earnest<br>Money | Cost of tender paper | Time of completion |
|------------|--|-------------------------|------------------|----------------------|--------------------|
| 1          | Construction of 10 nos, ventilation stoppings in 3 seam at 33 <sup>rd</sup> west level at Block-IV Colliery. |                         | 1%               | Rs.250/-             | 1 month            |

Eligibility Criteria:-1 (a) The average annual financial turnover during the last three years ending 31st March of the previous year should be atleast 30% of the estimated cost. (b) Experience of having successfully completed similar works during last 7 (seven) years ending last day or month previous to the one in which bid applications are invited (i.e. eligibility period) should be either of the following. (C) (i) Three similar completed works each costing not less than the amount equal to 40%. of the estimated cost (ii) Two similar completed works each costing not less than the amount equal to 50% of the estimated cost (iii) One similar completed works each costing not less than the amount equal to 80% of the estimated cost. 2) J.S.T. Clearance certificate 3) Permanent Account number of Income Tax.

The tender will be received on dated 10.09.2009 upto 3.00 p.m. in two parts and will be opened on the same day upto 3.30 p.m. in the presence of tenders or their authorised agents.

Without earnest money tender will be rejected. The tenderers are required to deposit the E.M. in the shape of demand draft or M.R. of Govindpur Area.

The bill of quantity will have to obtained from office of the undersigned on production of M.R. upto 09.09.2009.

Authority is reserved to reject any or all the tenders without assigning any reason whatsoever

It will be obligatory for the tenders to keep their offer for a period of 120 days from the date of opening of the tender.

Sale-Tax will be deducted as per rule from the bill of the Contractor. No conditional tender paper will be accepted.

No materials will be supplied to the contractor for doing this work.

The contractor will have to abide by all labour rules of the country/state.

A-18 Shinnshave Area Civil Engineer - 0 9 Govindpur Area

## C.C. to :-

- Addl. GM, Govindpur Area
- AFM Govindpur Area
- All Project Officers, Govindpur Area
- C.G.M/G. M., Area 1 to 12, E.J. Area, W.J.Area, W.W.Z.Ropeways.
- 5) G.M. (Const), Koylanagar, Dhanbad.
- 6) Notice Board
- Builders Association of India, 16 LIG Housing Colony Dhanbad / Near Akashkinaree Weighbridge, P.O. Katrasgarh.
- C.V.O. B.C.C.L. Koyla Bhawan
- General Manager (System), Koyla Bhawan, Dhanbad.

## Bill of Quantity for the work of "Construction of 10 nos, ventilation stoppings in 3 seam at 33rd west level at Block-IV Colliery."

| S1. | Particulars of the work                                 | Unit           | Estimated | B.C.C.L     | Amount      |
|-----|---|----------------|-----------|-------------|-------------|
| No. |   | of             | Qnty. of  | scheduled   | (in Rs.)    |
|     |   | Qnty.          | Work      | rates       |             |
| 1.  | Recess cutting in coal /soft rock in                    | $M^3$          | 30.34     | 162,65      | 4934.80     |
|     | foundation as per specification.                        |                |           |             | 7           |
| 2.  | Brick work in cm (1:6) in foundation & plinth upto 1:00 | M <sup>3</sup> | 41.15     | 2121.75     | 87310.01    |
| 3.  | Brick work in cm (1:6) in s/s as per specification.     | M <sup>3</sup> | 80.69     | 2357.40     | 190218.60   |
| 4.  | 12mm thick c.p. (1:6) as per specification.             | $M^2$          | 507.29    | 67.65       | 34318.16    |
| 5.  | White washing two or 3 coat as per specification.       | $M^2$          | 507.29    | 6.75        | 3424.20     |
| 6.  | 12mm thick e.p. (1:4) with punning.                     | $M^2$          | 2.70      | 97.90       | 264.33      |
| 7.  | Carriage of materials by manual lead 3nos, 50m          |                |           | 7           | ,           |
|     | a) Cement   | М.Т.           | 9.985     | 7 31.92     | 318.72      |
|     | b) Sand   | $M^3$          | 45.21     | 61.17       | 2765.49     |
|     | c) Stone  | $M^3$          | 1.50      | 61.17       | - 91.75     |
|     | d) Bricks   | % No.          | 60920     | 114.17 1    | 6955.23     |
|     | cheeleed  |                |           | Total (Rs.) | 3,30,601.29 |

Note: Add \_ % above/below from the estimated Cost.

A-IC-Snivarave
Nov. B-09
Area Civil Engineer
Govindpur Area

Signature of the Contractor