

# BHARAT COKING COAL LIMITED

(A Subsidiary of Coal India Ltd.)

Office of the General Manager, Govindpur Area  
P.O. Sonardih, Dist. Dhanbad

Ref. No. GM/AR-III/ACE/Tender/

33404-32

Dated 19.01.2009

22

## SHORT TENDER NOTICE

Sealed tenders are invited from registered and experienced contractors for the following works :-

Sl No.	Name of work	Estimated cost (in Rs.)	Earnest Money	Cost of tender paper	Time of completion
1.	Construction of black top coal transportation road from 3 seam incline to workshop/substation at Block-IV, Govindpur Area.	4,55,883.43	1%	Rs.250/-	1 month

Eligibility Criteria:-1 (a) The average annual financial turnover during the last three years ending 31st March of the previous year should be atleast 30% of the estimated cost. (b) Experience of having successfully completed similar works during last 7 (seven) years ending last day or month previous to the one in which bid applications are invited (i.e. eligibility period) should be either of the following (C) (i) Three similar completed works each costing not less than the amount equal to 40% of the estimated cost. (ii) Two similar completed works each costing not less than the amount equal to 50% of the estimated cost. (iii) One similar completed works each costing not less than the amount equal to 80% of the estimated cost. 2) J.S.T. Clearance certificate 3) Permanent Account number of Income Tax.

The tender will be received on dated 02.02.2009 upto 3.00 p.m. and will be opened in same day upto 3.30 p.m. in the presence of tenders or their authorised agents.

Without earnest money tender will be rejected. The tenderers are required to deposit the E.M. in the shape of demand draft or M.R. of Govindpur Area.

The bill of quantity will have to be obtained from office of the undersigned on production of M.R. upto 31.01.2009.

Authority is reserved to reject any or all the tenders without assigning any reason whatsoever.

It will be obligatory for the tenders to keep their offer for a period of 120 days from the date of opening of the tender.

Sale-Tax will be deducted as per rule from the bill of the Contractor. No conditional tender paper will be accepted.

No materials will be supplied to the contractor for doing this work.

The contractor will have to abide by all labour rules of the country/state.

A. K. S. S. S. S.  
19.1.09  
Area Civil Engineer,  
Govindpur Area

C.C. to :-

- 1) Addl. GM, Govindpur Area.
- 2) AFM Govindpur Area.
- 3) All Project Officers, Govindpur Area.
- 4) C.G.M./G.M., Area I to 12, E.J. Area, W.J. Area, W.W.Z. Ropeways.
- 5) G.M. (Const), Koylanagar, Dhanbad.
- 6) Notice Board
- 7) Builders Association of India, 16 LIG Housing Colony Dhanbad / Near Akashkinaree Weighbridge, P.O. Katrasgarh
- 8) C.V.O., B.C.C.L., Koyla Bhawan
- 9) General Manager (System), Koyla Bhawan, Dhanbad.

**Bill of Quantity for the work of "Construction of black top coal transportation road from 3 seam incline to workshop/substation at Block-IV, Govindpur Area"**

Sl. No.	Particulars of the work	Unit of Qnty.	Estimated Qnty. of Work	B.C.C.L scheduled rates	Amount (in Rs.)
1.	Carriage of quarry/excavated each lead upto 1.00km.	m <sup>3</sup>	384.00	55.64	21365.76
2.	Breaking of quarry/excavated rock in required size as per direction of Engg./Inch.	m <sup>3</sup>	384.00	31.49	12092.16
3.	Supply & stacking graded stone aggregate 53 to 22.4mm size.	m <sup>3</sup>	242.00	432.55	104677.10
4.	Supply & stacking morrum at site.	m <sup>3</sup>	70.64	264.70	18698.41
5.	Laying water bound macadam with specified stone aggregate stone screening and blinding material including screening, sorting, spreading to template and consolidation with power road roller of 8 to 10 tonne capacity etc. complete (payment for stone aggregate, screenings, kankar, moorum and red bajri etc. to be made separately) : Subbase with stone aggregate 90mm to 45 mm including stone screening 13.2mm size.	m <sup>3</sup>	300.00	128.90	38670.00

*Verified*  
*[Signature]*  
*19-1-09*

*A.R. Sinhasana*  
*19-1-09*



6.	Laying water bound macadam with specified stone aggregate stone screening and blinding material including screening, sorting, spreading to template and consolidation with power road roller of 8 to 10 tonne capacity etc. complete (payment for stone aggregate, screenings, kankar, moorum and red bajri etc. to be made separately) : a) Base course with 63 – 45mm size including stone screening 13.2mm size.	m <sup>3</sup>	200.00	122.00	24400.00
7.	Surface dressing on new surface with paving bitumen of grade A-90/S-90 of approved quantity using 2.25kg of bitumen per/ m <sup>2</sup> with 1.65 m <sup>3</sup> of stone chipping 13.2mm nominal size per 100 m <sup>2</sup> consolidation with road roller 6 to 8mm.	m <sup>2</sup>	2000.00	44.10	88200.00
8.	2.5cm premix carpeting with 2.25cum and 1.12 cum of stone chipping of 13.2mm and 11.2mm respect. – do- with punning as short 80/100 & then mixed.	m <sup>2</sup>	1920.00	51.95	99744.00

Verified  
10/10/19  
19.09

A.K. Sivarava  
19.1.09

9.	P/L seal coat of premixed fine aggregate with bitumen 128 grade 80/100 per m <sup>3</sup> of fine aggregate and 0.60 cum aggregate of 100 m <sup>2</sup>	m <sup>2</sup>	1920.00	19.30	37056.00
10.	E/w in excavation over areas in soil including disposal of excavated soil lead upto 50mm.	m <sup>3</sup>	120.00	91.50	10980.00
Total (Rs.)					4,55,883.43

Verified  
19.1.09  
E.S.

Note : Add \_\_\_\_% above/below from the estimated Cost.

A.K. Srivastava  
19.1.09

Area Civil Engineer

Govindpur Area

Signature of the Contractor