

**BHARAT COKING COAL LIMITED**  
**(A Subsidiary of Coal India Limited)**  
**OFFICE OF THE GENERAL MANAGER, EJ AREA**  
**PO: BHOWRA (DHANBAD)**

Ref No- GM (EJA)/ACE/NIT/10-11/7588

Dated: 27.12.2010

**NOTICE INVITING TENDER**

Sealed tender in two parts (Part-I & Part-II) on overall percentage rate basis are invited from experienced and eligible contractors for the following works.

Sl No.	Name of work	Estimated work	Earnest money	Cost of Tender Paper	Time of completion
1.	Conversion of RCC roof into A.C sheet roof at Haripatti, Bhowra under EJ Area	135541.82	1355.00	100.00	Twenty Days
2.	Drilling 8" dia. Bore hole and installation of submersible pump including pipe line work etc. At Mahalboni officer's colony under EJ area for making arrangement of supply of drinking water in the colony	129385.93	1300.00	100.00	Twenty days

**AVAILABILITY OF TENDER DOCUMENT from 17.01.2011 to 19.01.2011**

Tender documents will be issued on all working days during working hours except on Sunday & holidays in the event of the specified date for the submission, opening of bids being declared a holidays the bids will be received opened on the appointed time on the next working day. The Tender is also available on web site: <http://bccl.cmpdi.co.in> and can be downloaded.

**TIME & DATE IF RECEIPT/OPENING OF TENDER**

The Tender will be received on dated 21.01.2011 from 10.00 AM to 1.00 PM in tender box at (1). CISF post near Koyla Nagar, BCCL, Dhanbad. (2) CISF'S office of EJ Area. And will be opened on 25.01.2011 at 4.00PM in the office of the ACE/EJA Area.

**ELIGIBILITY CRITERIA**

a). The intending tender must have in its name as a prime contractor experience of having successfully completed similar works during last 7(seven) years ending last days of the month previous to the one which bid applications are invited should be either of the following:- (1). Three similar completed works each costing not less than 40% of the estimated cost. Or (2). Two similar completed works each costing not less than 50% of the estimated cost or (3). One similar completed works costing not less than 80% of the estimated cost. **Similar work means: Building works for si. No. 1 & drilling, installation of submersible pump for sl no. 2.**

b). Average annual financial turnover of civil works during the last three years, ending years, ending 31<sup>st</sup>. March of the previous financial should be at least 30% of the estimated cost.

2. the tender documents can be had from the office of the undersigned during the period mentioned above on deposited of requisite cost of tender paper in form of cash bank draft of any nationalized bank/scheduled commercial bank approved by reserve bank of India in favour of "Bharat Coking Coal Limited" Payable at Dhanbad.

3. Completed sealed tender documents (Part I & II) should be submitted at the same time. Part I shall consists of term & conditions of the tender, additional terms and conditions if any, technical bid and credentials. Part II shall consists of tender documents as sold to the renderers duly filled in for rates, amount etc. i. e price bid. The earnest money deposited is to be submitted in a separate envelop subscribing "Earnest Money Deposited" All three envelopes should be submitted in one sealed envelope.

The Part II will be opened only after the department is satisfied that the criteria fixed are fulfilled i.e. acceptance of Part I

4. The earnest money is to be deposited as per details given in tender documents.

5. TIN No. is to be submitted.

6. The tenderers have to submit Permanent Account No. (PAN) of income Tax.

7. Conditional tenders will not be accepted.

8. Issuance of tender document does not mean that the parties are considered qualified.

9. The experience as given in the eligibility criteria should be in the name and style in which tender is filled . the experience in the name of some other form / company will not be considered for the purpose.

10. The validity of the tender will be 120 days from the date of opening of price bid.

11. The Management of BCCL reserves right to reject any or all the tender or split the work among two or more tenderers without assigning any reasons what so ever.

12. Other details may be obtained from detailed tender notice/tender document/web site <http://bccl/compdi.co.in>

13. The tender document has been downloaded from the above mentioned web site, the tenderers are required to deposit alone with their tender, a bank draft of any nationalized /scheduled commercial bank approved by reserve bank of India payable at Dhanbad exclusively towards the cost of tender document for the amount indicated as above, in the envelope as stated at clause 3 of this NIT. Any bank draft prepared after the schedule closure of sale of tender document may be liable to rejection.

14. The contents of the tender document available in our office. Shall be deemed as authentic. The bidder will be required to submit an undertaking that they will accept the tender document as available in the web site and their tender shall be rejected if any tempering in there in there in the tender document thus submitted.

**Area Civil Engineer/EJ Area.**

Copy to : -

1. The C.V.O. ,BCCL
2. All CGMS/GMs of Area of BCCL.
3. The General Manager (Civil), CED/Koyla Nagar.
4. H.O.D.(Admn.), BCCL /Koyla Nagar
5. The GM (SYSem), BCCL –With a request to display this NIT in BCCL web site with download facility.
6. The Addl. GM (EJA)/ The AFM(EJA)/ The Area Survey officer.
7. The Inspector I/C, CISF, Koyla Bhawan
8. The Inspector I/C, CISF, EJ Area.

**Conversion of RCC roof into A.C. Sheet at Harpatti, Bhowra under EJ Area.**

Sl. No.	Description of Item	Unit	Quantity	Rate	Rate to be quoted on overall %age basis
1	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead as per direction of Engineer in charge.1:3:6 or richer mix	cum	6.12	368.45	
2	Brick work with F.P.S bricks of class designation 75 in superstructure above plinth level upto floor V level in all shapes and sizes in : Cement Motar 1:6 (1 cement : 6 coarse sand)	cum	12.62	2315.5	
3	Structural steel work in single section fixed without connecting plate including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg.	228.05	42.15	
4	Providing non-asbestos high impact polypropylene reinforced cement 6 mm thick corrugated sheets (As per IS : 14871) roofing upto any pitch and fixing with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. plain and bitumen washers or with self drilling fasteners and EDPM washers etc. complete excluding the cost of purlins, rafters, and trusses, corrugated sheets and including cutting to size and shape whenever required.	sqm	69.94	294.95	
5	Grading roof for water proofing treatment withCement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size.	cum	1.29	3314.95	
6	12 mm cement plaster of mix : 1:6 (1 cement : 6 fine sand)	sqm	720.7	67.65	
7	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement : 4 fine sand)	sqm	13.37	97.9	

8	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete.25mm thick with 20mm normal size stone aggregate	sqm	59.45	141.6	
9	White washing with lime to give an even shade: New work (three or more coats)	sqm	720.7	6.75	
10	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: One or more coats on old work.	sqm	80.26	22.85	
11	Providing & fixing steel door.	sqm	3.34	1297.52	

NAME & ADDRESS OF THE TENDERER:

DETAILS OF EARNEST MONEY:

SIGNATURE OF TENDERER:

DATE:

**Area Civil Engineer/ E.J.AREA**

BILL OF QUANTITY FOR DRILLING 6" DIA BORE HOLE AND INSTALLATION OF SUBMERSIBLE PUMP INCLUDING PIPE LINE WORK etc. AT MOHALBONI OFFICERS' COLONY UNDER E.J AREA FOR MAKING ARRANGEMENT OF SUPPLY OF DRINKING WATER IN THE COLONY.

Sl.No.	Description	Qty	Unit	Rate (Rs.)	Rate to be quoted on overall % age basis
1.	Drilling 150 mm dia bore hole by using do—do- mechanical complete Job.				
	(a) 0 to 20 M	20.00	P.Mtr.	400.00	
	(b) 20 to 40 M	20.00	P.Mtr.	410.00	
	(c) 40 to 60 M	20.00	P.Mtr.	420.00	
	(d) 60 to 90 M	30.00	P.Mtr.	435.00	
	(e) 90 to 110 m	20.00	P.Mtr.	450.00	
2.	Supplying 7" dia P.V.C. casting pipe casting comp. job.	30.00	P.Mtr.	480.00	
3.	Lowering 6/7" casting pipe in the bore hoel	30.00	P.Mtr.	39.00	
4.	Sopplying 50 mm dia P.V.C. pipe	80.00	P.Mtr.	35.34	
5.	Lowering of P.V.C. pipe	30.00	P.Mtr.	16.00	
6.	Supplying sand fitting of 7-1/2 H.P .sumbersible pump complete job.	1 set	Each	23187.00	
7.	Supplying fitting & Fixing 3 phase 440 v, 50" , 3-1/2 H.P. ISI marked central point.	1 set	Each	6550.00	
8	P.V.C. flate cable 3 phase 440 v -do- do- etc. comp. job.	100.00	P. Mtr.	78.84	
9.	Earth work in excavation in foundation.	170 Cum	P.Cum	103.40	
10.	Providing /laying P.C.C. 1:4:8(1 cement :4 sand: 8 stone chips)	0.24 Cum	P.Cum	2296.15	
11.	Brick work in cement martar 1:6 (1 cement : 6 sand) in F&p of class 50)	1.64 Cum	P.Cum	2007.00	
12.	Brick work in cement martar 1:6 (1 cement : 6 sand) in superstructure of class 50.	4.03 Cum	P.Cum	2247.65	

13.	Providing & laying A.C. Sheet roofing – do-do as per spec. complete job.	3.90 Cum	P. Sqm	201.42	
14.	12 mm thick cement plaster 1:6 (1 cement : 6 sand) –do- -do- as per spec.comp.job.	35.49 Sqm.	P.Sqm.	Rs. 67.65	
15.	Colour washing two or more costs –do- -do- as per spec .complete job.	35.49 Sqm.	P.Sqm.	Rs. 9.10	
16.	Cleaning of jungle -do- -do- as per spec.complete job.	27.88 Sqm.	P.Sqm.	Rs. 263.90	
17.	Dry brick on edge soling - do -- do - as per spec comp.job.	26.27 Sqm.	P.Sqm.	Rs. 195.70	
18.	25mm thick flooring 1 : 2 : 4 (1 cement :2 sand : 4 stone chips) -do- -do- as per spec. complete job.	26.27 Sqm.	P.Sqm.	Rs. 141.11	

NAME & ADDRESS OF THE TENDERER

DETAILS OF EARNEST MONEY

SIGNATURE OF THE TENDERER

DATE:

**AREA CIVIL ENGINEER.**

**EASTERN JHARIA AREA.**