

**BHARAT COKING COAL LIMITED**  
**(A Subsidiary of Coal India Limited)**  
**OFFICE OF THE GENERAL MANAGER, EJ AREA**  
**P.O. : BHOWRA (DHANBAD)**

Ref. No. : GM(EJA)/ACE/NIT/10-11/376

Dated : 25.01.2011

**NOTICE INVITING TENDER**

Sealed Tender in two parts(Part-I & Part-II) on overall percentage rate basis are invited from experienced and eligible contractors for the following works

Sl.No.	Name of work	Estimated cost	Earnest money	Cost of Tender paper	Time of completion
1.	Repairing of damaged septic tank and compound wall of block qtrs. no. M/58 to M/67 near 6 no. Incline at Pathardih colliery under EJ Area.	133840.58	1340.00	100.00	Twenty days

**AVAILABILITY OF TENDER DOCUMENTS**

From 05.02.2011 to 09.02.2011

Tender documents will be issued on all working days during working hours except on Sunday & holiday in the event of the specified date for submission, opening of bids being declared a holiday the bids will be received opened on the appointed time on the next working day. The Tender document is also available on web site : <http://bccl:cmpdi:co:in> and can be downloaded.

**TIME & DATE IF RECEIPT/OPENING OF TENDER**

The Tender will be received on 11.02.2011 from 10.00AM to 1.00PM in Tender box at (1). CISF post near Koyla Bhawan gate, Koyla Nagar, BCCL, Dhanbad. (2). CISF'S office of EJ Area and opened on 14.02.2011 at 4.00 PM in the office of the ACE/EJ Area

**1. ELIGIBILITY CRITERIA**

- a). The intending Tenderer must have in its name as a prime contractor experience of having successfully completed similar works during last 7(seven) years ending last day of month previous to the one in which bid applications are invited should be either of the following :- (1). Three similar completed works each costing not less than 40 % of the estimated cost. Or (2). Two similar completed works each costing not less than 50 % of the estimated cost or (3). One similar completed work costing not less than 80 % of the estimated cost. **Similar work means : Building works**
- b). Average annual financial turnover of civil works during the last three years, ending 31<sup>st</sup>. March of the previous financial, should be at least 30 % of the estimated cost.
2. The Tender documents can be had from the office of the undersigned during the period mentioned above on deposition of requisite cost of Tender paper in form of cash bank draft of any nationalized bank/scheduled commercial bank approved by Reserve bank of India in favour of "Bharat coking coal limited" payable at Dhanbad.
3. Completed sealed Tender documents (Part I & II) should be submitted at the same time. **Part I** shall consists of terms & conditions of the Tender, additional terms and conditions if any, Technical bid and credentials. **Part II** shall consists of tender documents as sold to the tenderers duly filled in for rates, amount etc. i.e. price bid.  
The earnest money deposit is to be submitted in a separate envelop subscribing "Earnest Money Deposit"  
All three envelopes should be submitted in one sealed envelope.  
The Part II will be opened only after The department is satisfied that the criteria fixed are fulfilled i.e. acceptance of Part I
4. The earnest money is to be deposited as per detail given in Tender documents.
5. TIN No. Is to be submitted.
6. The Tenderers have to submit Permanent Account no.(PAN) of Income Tax.
7. Conditional tenders will not be accepted.
8. Issuance of Tender document does not mean that the parties are considered qualified.
9. The experience as given in the eligibility criteria should be in the name and style in which tender is filled. The experience in the name of some other firm/company will not be considered for this purpose.
10. The validity of the tender will be 120 days from the date of opening of price bid

11. The Management of BCCL reserves right to reject any or all the tender or split the work among two or more tenderers without assigning any reason what so ever.
12. Other details may be obtained from detailed Tender notice/Tender documents/web site <http://bccl.cmpdi.co.in>
13. The Tender documents has been downloaded from the above mentioned web site, the tenderers are required to deposit along with their tender, a bank draft of any nationalized/scheduled commercial bank approved by Reserve bank of India payable at Dhanbad exclusively towards the cost of tender documents for the amount indicated as above, in the envelope as stated at clause 3 of this NIT. Any bank draft prepared after the schedule closure of sale of tender documents may be liable to rejection.
14. The contents of the tender documents available in our office, shall be deemed as authentic. The bidder will be required to submit an undertaking that they will accept the tender documents as available in the web site and their tender shall be rejected if any tempering is there in the tender documents thus submitted.

Area Civil Engineer/EJ Area.

Copy to : -

1. The C.V.O., BCCL
2. All CGMs/GMs of Area of BCCL
3. The General Manager(Civil), CED/Koyla Nagar
4. H.O.D.(Admn.), BCCL/Koyla Nagar
5. The GM(System), BCCL – with a request to display this NIT in BCCL web site with download facility.
6. The Addl. GM(EJA)/The AFM(EJA)/The Area Survey officer
7. The Inspector I/C, CISF, Koyla Bhawan
8. The Inspector I/C, CISF, EJ Area.

Bill of quantity for the work," Repairing of damaged septic tank and compound wall of block qtrs. no. M/58 to M/67 near 6 no. Incline at Pathardih colliery under EJ Area.

Sl. No.	Description of Item	Unit	Quantity	Rate	Quoted rate in % (Above/Below)
1.	Brick work with F.P.S. bricks of class designation 50 in foundation and plinth in : Cement Mortar 1:6 (1cement : 6 coarse sand)	Cum	20.60	2007.00	
2.	Brick work with F.P.S. bricks of class designation 75 in superstructure above plinth level upto floor V level in all shapes and sizes in : Cement Mortar 1:6 (1cement : 6 coarse sand)	Cum	16.05	2247.65	
3.	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement : 4 fine sand)	Sqm	127.96	97.90	
4.	12 mm cement plaster of mix : 1:6 (1 cement : 6 fine sand)	Sqm	153.10	67.65	
5.	White washing with lime to give an even shade: Old work (two or more coats)	Sqm	246.00	4.10	
6.	Providing, hoisting and fixing upto floor five level precast reinforced cement concrete in vertical & horizontal fins individually or forming box louvers setting in cement mortar 1:2 (1 Cement : 2 coarse sand) including the cost of required centring, shuttering and finishing smooth with 6mm thick cement plaster 1 : 3(1 cement : 3 fine sand) on exposed surfaces complete but excluding the cost of reinforcement with 1 : 2 : 4(1 cement :2 coarse sand : 4 graded stone aggregate 20mm nominal size)	Cum	1.59	6745.50	
7.	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete cold twisted bars.	Kg	100.00	42.70	
8.	Extra for using coloured W.C. pan instead of white W.C. pan Orissa pattern W.C. pan 580x440 mm	Each	08	398.40	
9.	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors : 100mm inlet 100mm outlet.	Each	08	544.30	
10.	Providing and fixing on wall face unplasticised - Rigid PVC rain water pipes conforming to IS : 13592 Type A including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion. (i) Single socketed pipes. 110 mm. Diameter.	Metre	16.00	163.40	
11.	Providing and fixing a pair of white vitreous china foot rests of standard pattern for squatting pan water closet: 250 x 125 x 25 mm.	Pair	08	112.85	
12.	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 40mm thick with 20mm nominal size stone aggregate	Sqm.	20.60	192.95	
13.	Cleaning of septic tank.	Each.	05	500.00	

Name & Address of the Agency

Details of Earnest money :

Area Civil Engineer(EJ Area)

Signature of the Tenderer with date

