

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER, EJ AREA
P.O. : BHOWRA (DHANBAD)

Ref. No. : GM(EJA)/ACE/NIT/10-11/ 400

Dated : 27.01.2011

NOTICE INVITING TENDER

Sealed Tender in two parts(Part-I & Part-II) on overall percentage rate basis are invited from experienced and eligible contractors for the following works

Sl.No.	Name of work	Estimated work	Earnest money	Cost of Tender paper	Time of completion
1.	Construction of a room with G.I.Sheet roofing to install a Transformer & switch to start the production in panel "F" seam VIII of reverse incline Sudamdih under EJ Area.	115431.03	1154.00	100.00	Twenty days

AVAILABILITY OF TENDER DOCUMENTS

From 08.02.2011 to 12.02.2011

Tender documents will be issued on all working days during working hours except on Sunday & holiday in the event of the specified date for submission, opening of bids being declared a holiday the bids will be received opened on the appointed time on the next working day. The Tender document is also available on web site : <http://bccl:cmpdi:co:in> and can be downloaded.

TIME & DATE IF RECEIPT/OPENING OF TENDER

The Tender will be received on 15.02.2011 from 10.00AM to 1.00PM in Tender box at (1). CISF post near Koyla Bhawan gate, Koyla Nagar, BCCL, Dhanbad. (2). CISF'S office of EJ Area. and will be opened on 17.02.2011 at 4.00 PM in the office of the ACE/EJA.

1. ELIGIBILITY CRITERIA

- a). The intending Tenderer must have in its name as a prime contractor experience of having successfully completed similar works during last 7(seven) years ending last day of month previous to the one in which bid applications are invited should be either of the following :- (1). Three similar completed works each costing not less than 40 % of the estimated cost. Or (2). Two similar completed works each costing not less than 50 % of the estimated cost or (3). One similar completed work costing not less than 80 % of the estimated cost. **Similar work means : Building works.**
- b). Average annual financial turnover of civil works during the last three years, ending 31st. March of the previous financial, should be at least 30 % of the estimated cost.
2. The Tender documents can be had from the office of the undersigned during the period mentioned above on deposition of requisite cost of Tender paper in form of cash bank draft of any nationalized bank/scheduled commercial bank approved by Reserve bank of India in favour of "Bharat coking coal limited" payable at Dhanbad.
3. Completed sealed Tender documents (Part I & II) should be submitted at the same time. **Part I** shall consists of terms & conditions of the Tender, additional terms and conditions if any, Technical bid and credentials. **Part II** shall consists of tender documents as sold to the tenderers duly filled in for rates, amount etc. i.e. price bid.
The earnest money deposit is to be submitted in a separate envelop subscribing "Earnest Money Deposit"
All three envelopes should be submitted in one sealed envelope.
The Part II will be opened only after The department is satisfied that the criteria fixed are fulfilled i.e. acceptance of Part I
4. The earnest money is to be deposited as per detail given in Tender documents.
5. TIN No. Is to be submitted.
6. The Tenderers have to submit Permanent Account no.(PAN) of Income Tax.
7. Conditional tenders will not be accepted.
8. Issuance of Tender document does not mean that the parties are considered qualified.
9. The experience as given in the eligibility criteria should be in the name and style in which tender is filled. The experience in the name of some other firm/company will not be considered for this purpose.
10. The validity of the tender will be 120 days from the date of opening of price bid
11. The Management of BCCL reserves right to reject any or all the tender or split the work among two or more tenderers without assigning any reason what so ever.
12. Other details may be obtained from detailed Tender notice/Tender documents/web site <http://bccl:cmpdi:co:in>

13. The Tender documents has been downloaded from the above mentioned web site, the tenderers are required to deposit along with their tender, a bank draft of any nationalized/scheduled commercial bank approved by Reserve bank of India payable at Dhanbad exclusively towards the cost of tender documents for the amount indicated as above, in the envelope as stated at clause 3 of this NIT. Any bank draft prepared after the schedule closure of sale of tender documents may be liable to rejection.
14. The contents of the tender documents available in our office, shall be deemed as authentic. The bidder will be required to submit an undertaking that they will accept the tender documents as available in the web site and their tender shall be rejected if any tempering is there in the tender documents thus submitted.
15. The tenderer must submit an affidavit as per civil engineering manual and declaration that they have not been banned or delisted by any Govt. or Govt. Agency or PSUs.

Area Civil Engineer/EJ Area.

Copy to :-

1. The C.V.O., BCCL
2. All CGMs/GMs of Area of BCCL
3. The General Manager(Civil), CED/Koyla Nagar
4. H.O.D.(Admn.), BCCL/Koyla Nagar
5. The GM(System), BCCL – with a request to display this NIT in BCCL web site with download facility.
6. The Addl. GM(EJA)/The AFM(EJA)/The Area Survey officer
7. The Inspector I/C, CISF, Koyla Bhawan
8. The Inspector I/C, CISF, EJ Area.

Sl. No.	Description of work	Unit	Quantity	Rate	Rate quoted by the Tenderer(In figure & word).
1.	Earth work in excavation by mechanical means(Hydraulic excavator)/manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil and disposal of surplus excavated soil as directed within a lead of 50m.All kinds of soil.	Cum	11.58	103.40	
2.	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level. 1:4:8 (1 Cement : 4 fine sand : 8 graded stone aggregate 40 mm nominal size).	Cum	0.96	2296.15	
3.	Brick work with F.P.S. bricks of class designation 75 in superstructure above plinth level upto floor V level in all shapes and sizes in : Cement Mortar 1:6 (1cement : 6 coarse sand)	Cum	11.78	2007.00	
4.	Brick work with F.P.S. bricks of class designation 75 in superstructure above plinth level upto floor V level in all shapes and sizes in : Cement Mortar 1:6 (1cement : 6 coarse sand)	Cum	17.70	2315.50	
5.	Dry brick on edge flooring with bricks of class designation 50 on a bed of 12 mm mud mortar including filling joints with sand (with F.P.S. bricks)	Sqm	32.81	197.50	
6.	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level	Cum	4.99	3194.10	
7.	12 mm cement plaster of mix : 1:6 (1 cement : 6 fine sand)	Sqm	147.11	67.65	
8.	White washing with lime to give an even shade: New work(three or more coats).	Sqm	147.11	6.75	
9.	Providing corrugated G.S. sheet roofing including vertical/curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surfaces) excluding the cost of purlins, rafters, and trusses and including cutting to size and shape wherever required. 0.63mm thick with zinc coating not less than 275gm/m ²	Sqm	9.72	432.25	
10.	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6mm angle iron and 3mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer.	Sqm	4.46	1600.10	
11.	Using flats 30x6mm for diagonal braces and central cross piece Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15°, landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto floor five level excluding the cost of centring, shuttering, finishing and reinforcement with 1:2:4(1 cement:2 coarse sand:4 graded stone aggregate 20mm nominal size)	Cum	0.17	3673.85	
12.	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete . Mild steel and Medium Tensile steel bars	Kg	13.60	41.50	
13.	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	Sqm	10.04	33.25	
14.	Extra for providing and fixing wind ties of 40x6 mm flat iron section	Metre	16.00	73.65	

Name & Address of the Tenderer :

Details of Earnest Money :

Area Civil Engineer(EJA)

Signature of the Tender with date

