

**BHARAT COKING COAL LIMITED**  
**(A Subsidiary of Coal India Limited)**  
**OFFICE OF THE GENERAL MANAGER, EJ AREA**  
**P.O. : BHOWRA (DHANBAD)**

Ref. No. : BCCL/Civil/EJA/Tender/2010-11/700

Dated :11.02.2011

**TENDER NOTICE**

Sealed Tender on percentage basis (Above/Below) on prescribed bill of quantity is hereby invited for the following job/jobs from the resourceful and enlisted contractors which will be received and opened on 28.02.2010. from 10.00 AM to 1.00 PM. and will be opened on 02.03.2011 at 4.00 PM. The Tender will be opened in presence of the Tenderers/Quotationers or their authorized representatives. Details are as below : -

Sl.No.	Name of work	Estimated Cost(In Rs.)	Earnest Money (In Rs.)	Time of Completion
1.	Repair of qtr. of Sri. S.N.Ghosh at Gourkhuti, Bhowra under EJ Area	14397.33	145.00	Seven days
2.	Repair of latrine of qtr. of Sri. Jitendra Kumar Singh, clerk located at Gourkhuti, Bhowra.	12718.37	130.00	Seven days
3.	Repair & maintenance in the bungalow of Sri. A.B.Mukherjee at Gandhinagar, Bhowra.	16805.15	170.00	Seven days
4.	Repair work in qtr. of Sri. Gopal Chatterjee at 12 no., Bhowra under EJ Area	18198.78	185.00	Seven days
5.	Repair of the septic tank of Dr. B.K.Sinha under EJ Area	20495.25	205.00	Seven days

**AVAILABILITY OF TENDER PAPER : From 24.02.2011 to 26.02.2011**

**TERMS AND CONDITIONS :**

1. The estimate & specification of the work is available in the office of the undersigned during working hours on above mentioned period. Any other information can also be obtained from the undersigned
2. The quotationer have to submit Photo stat copy of PAN Card.
3. The tender has to deposit E.M. as stated above with A.F.M., EJ Area in cash . The Money receipt of EM should be attached with the tender. The tender without earnest money will be out rightly rejected.
5. The quotationer must submit an affidavit with their offer as per civil engg. Manual along with certification that they have not been banned or delisted by any Govt. Agencies or PAUs.
6. The contractors have to submit Permanent Account Number(PAN) income tax and TIN.
7. Authority reserves the rights to reject any or all the tenders received or split up and distribute the work between more than one contractor without assigning any reason what so ever
8. The rate should be quoted inclusive all taxes and royalty. The validity period of the tender will be 120 days , commenced from the date of opening of the Tender.
9. Materials required for the work are to be arranged / procured by the contractor at his own cost.
10. In case rate are not acceptable, the offer may be rejected.
11. The contractor should abide by the labour Act of Govt. of India.
12. Conditional tender will not be entertained.
13. The Tender document can also be downloaded from the BCCL web site <http://bccl.cmpdi.co.in>

Distribution : -

1. The All Project officer of EJ Area.
2. The Addl. GM/A.F.M.(EJA)
3. The A.F.M./A.S.O., EJ Area.
4. CISF Main gate, Koyla Bhawan
5. The Inspector, CISF, EJ Area.
6. The Inspector, CISF, Ropeway Area/ EWZ Area.
7. The Cashier/Notice Board, EJ Area.
8. M/S. Builders Association of India, 316 LIG, Housing colony, Dhanbad..

Area Civil Engineer(EJA)

Sl. No.	Description of work	Unit	Quantity	Rate	Rate quoted by the Tenderer(In figure & word).
1.	6mm cement plaster of mix: 1:3 (1 cement : 3 fine sand)	Sqm	16.62	62.15	
2.	12 mm cement plaster of mix : 1:6 (1 cement : 6 fine sand)	Sqm	25.00	67.65	
3.	Brick work with F.P.S. bricks of class designation 50 in foundation and plinth in : Cement Mortar 1:6 (1cement : 6 coarse sand)	Cum	1.23	2012.00	
4.	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 40mm thick with 20mm nominal size stone aggregate	Sqm	77.87	22.85	
5.	White washing with lime to give an even shade: old work(two or more coat).	Sqm	266.25	4.10	
6.	White washing with lime to give an even shade: old work(two or more coat).	Sqm	284.41	4.10	
7.	Providing non-asbestos high impact polypropylene reinforced cement 6 mm thick corrugated sheets (As per IS : 14871) roofing upto any pitch and fixing with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. plain and bitumen washers or with self drilling fasteners and EDPM washers etc. complete excluding the cost of purlins, rafters, and trusses, corrugated sheets and including cutting to size and shape wherever required.	Sqm	2.22	294.95	
8.	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats for old work.	Sqm	47.44	22.85	
9.	Providing, hoisting and fixing upto floor five level precast reinforced cement concrete in small lintels not exceeding 1.5m clear span upto floor five level including the cost of required centring, shuttering and finishing smooth with 6mm thick cement plaster 1 : 3(1 cement : 3 fine sand)on exposed surfaces but excluding the cost of reinforcement with 1 : 2 : 4(1: 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	Sqm	0.42	6002.80	
10.	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. Hot rolled deformed bars. .	Kg.	19.13	42.70	

Name & Address of the Tenderer :

Details of Earnest money :

Area Civil Engineer(EJA)

Signature of the Tenderer with Date

Sl. No.	Description of work	Unit	Quantity	Rate	Rate quoted by the Tenderer(In figure & word).
1.	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead as per direction of Engineer in charge.1:3:6 or richer mix.	Cum	0.42	368.45	
2.	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer in charge.	Cum	1.35	310.75	
3.	Excavation work in foundation trenches or drains not exceeding 1.5 m in width or 10 sqm on plan including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed within a lead of 50m. All kinds of soil.	Cum	5.09	103.40	
4.	Cleaning of septic tank.	Each	1	500.00	
5.	Brick work with F.P.S. bricks of class designation 50 in foundation and plinth in :cement mortar 1:6(1 cement: 6 coarse sand)	Cum	1.35	2007.00	
6.	Providing, hoisting and fixing upto floor five level precast reinforced cement concrete in small lintels not exceeding 1.5m clear span upto floor five level including the cost of required centring, shuttering and finishing smooth with 6mm thick cement plaster 1 : 3(1 cement : 3 fine sand)on exposed surfaces but excluding the cost of reinforcement with 1 : 2 : 4(1: 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	Cum	0.42	6002.80	
7.					
8.	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. Hot rolled deformed bars. .	Cum	34.00	42.70	
9.	Providing and fixing white vitreous china water closet squatting pan (Indian type) Long pattern W.C.Pan of size 580 mm.	Each	1	534.60	
10.	Providing and fixing a pair of white vitreous china foot rests of standard pattern for squatting pan water closet 250x130x30 mm.	Pair	1	111.70	
11.	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors sand cast iron S&S asper IS:1729	No..	1	442.10	
12.	Providing and fixing on wall face unplasticised - Rigid PVC rain water pipes conforming to IS : 13592 Type A including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion. (i) Single socketed pipes, 75 mm dia.	Metre	3.00	95.00	
13.	12 mm cement plaster of mix : 1:6 (1 cement : 6 fine sand)	Sqm	11.33	67.65	
14.	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	Sqm	32.09	8.20	

Name & Address of the Tenderer :

Details of Earnest money :

Area Civil Engineer(EJA)

Signature of the Tenderer with Date

Bill of quantity for the work," Repair & maintenance in the bungalow of Sri. A.B.Mukherjee at Gandhinagar,  
Bhowra.

Sl. No.	Description of work	Unit	Quantity	Rate	Rate quoted by the Tenderer(In figure & word).
1.	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer in charge.	Cum	2.26	310.75	
2.	Brick work with F.P.S. bricks of class designation 50 in superstructure above plinth level upto floor V level in all shapes and sizes in cement mortar 1:6(1 cement : 6 sand)	Cum	2.26	2315.50	
3.	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead. Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead as per direction of Engineer in charge.1:3:6 or richer mix.	Sqm	65.03	8.20	
4.	12 mm cement plaster of mix : 1:6 (1 cement : 6 fine sand)	Sqm	65.03	67.65	
5.	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade Old work (one or more coats)	Sqm	224.81	14.90	
6.	White washing with lime to give an even shade: old work(two or more coat).	Sqm	150.00	4.10	
7.	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats for old work.	Sqm	56.34	22.85	
8.	12 mm cement plaster finished with a floating coat of neat cement of mix :	Sqm	7.00	97.90	

Name & Address of the Tenderer :

Details of Earnest money :

Area Civil Engineer(EJA)

Signature of the Tenderer with Date

Sl. No.	Description of work	Unit	Quantity	Rate	Rate quoted by the Tenderer(In figure & word).
1.	Demolishing cement concrete manually / by mechanical means including disposal of material within 50 metres lead as per direction of Engineer in charge.1:3:6 or richer mix.	Cum	1.72	368.45	
2.	Grading roof for water proofing treatment with Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size.	Sqm	1.72	3314.95	
3.	Providing and fixing on wall face unplasticised - Rigid PVC rain water pipes conforming to IS : 13592 Type A including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion. (i) Single socketed pipes 110 mm. Dia.	metre	4.00	163.40	
4.	Painting top of roofs with bitumen of approved quality at 17kg per 10sqm impregnated with a coat of coarse sand at 60 cudm per 10sqm including cleaning the slab surface with brushes and finally with a piece of cloth lightly soaked in kerosene oil complete With residual type petroleum bitumen of penetration 80/100	Sqm	70.60	63.00	
5.	12 mm cement plaster of mix : 1:6 (1 cement : 6 fine sand)	Sqm	30.00	67.65	
6.	6mm cement plaster of mix: 1:3 (1 cement : 3 fine sand)	Sqm	10.00	62.15	
7.	Providing non-asbestos high impact polypropylene reinforced cement 6 mm thick corrugated sheets (As per IS : 14871) roofing upto any pitch and fixing with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. plain and bitumen washers or with self drilling fasteners and EDPM washers etc. complete excluding the cost of purlins, rafters, and trusses, corrugated sheets and including cutting to size and shape wherever required.	Sqm	4.46	294.95	
8.	Brick work with F.P.S. bricks of class designation 50 in superstructure above plinth level upto floor V level in all shapes and sizes in cement mortar 1:6(1 cement : 6 sand)	Cum	0.28	2315.50	
9.	White washing with lime to give an even shade: old work(two or more coat).	Sqm	284.92	4.10	
10.	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats for old work.	Sqm.	40.55	22.85	
11.	.Dismantling roofing including ridges, hips valleys and gutters etc., and stacking the material within 50 metres lead of Asbestos sheet.	Sqm	4.46	11.75	

Name & Address of the Tenderer :

Details of Earnest money :

Area Civil Engineer(EJA)

Signature of the Tenderer with Date

Bill of quantity for the work," Repair of the septic tank of Dr. B.K.Sinha under EJ Area.

Sl. No.	Description of work	Unit	Quantity	Rate	Rate quoted by the Tenderer(In figure & word).
1.	Brick work with F.P.S. bricks of class designation 75 in foundation and plinth in cement mortar 1 : 6(1 cement : 6 coarse sand).	Cum	0.82	2012.00	
2.	Cleaning of septic tank.	Each	1	600.00	
3.	12 mm cement plaster finished with a floating coat of neat cement of mix :	Sqm	33.45	97.90	
4.	Providing, hoisting and fixing upto floor five level precast reinforced cement concrete work in string courses, bands, copings, bed plates, anchor blocks, plain window sills and the like including the cost of required centring, shuttering, finishing smooth with 6mm thick cement plaster 1: 3(1 cement : 3 fine sand) on exposed surfaces complete but excluding cost of reinforcement with 1 : 2 : 4(1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	Cum	0.93	4882.25	
5.	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. Hot rolled deformed bars. White washing with lime to give an even shade: old work(two or more coat).	Kg.	66.00	42.70	
6.	Constructing brick masonry manhole in cement mortar 1:4 ( 1 cement : 4 coarse sand ) R.C.C. top slab with 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size), foundation concrete 1:4:8 mix (1 cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size) inside plastering 12 mm thick with cement mortar 1 : 3 (1 cement : 3 coarse sand) finished with floating coat of neat cement and making channel in cement concrete 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) finished with a floating coat of neat cement complete as per standard design.	Sqm	1	5000.00	
7.	Providing/Laying P.V.C. pipe	metre	12.70	110.00	
8.	Renewing glass panes, with putty and nails wherever necessary float glass panes of thickness 4 mm.	Sqm	2.97	427.60	

Name & Address of the Tenderer :

Details of Earnest money :

Area Civil Engineer(EJA)

Signature of the Tenderer with Date