

Bharat Coking Coal Limited
Chanch Victoria Area.XII

Ref No. E&M/XII/BCCL/NIT/2010-11/1005

Date: 11/14.05.10

Notice Inviting Tender

Sealed tenders are invited from experienced and bonafide Contractor / Agency for the under noted work. The tender should be submitted in two part, that is, Part I Containing Tech-Commercial bid and Part- II Containing Price bid, Part – I and Part-II envelope must be super-scribed and sealed. Sealed Part I & Part II envelope must be sealed in a third envelope.

Tenders must reach the office of the undersigned latest by 06.07.10 up to 1.00 P.M. and Tech-commercial bid will be opened on the same day at 3.00 P.M.

Sl. No	Description of work.	Tender Cost (Rs)	Estimated cost (Rs)	Earnest money (Rs)	Time of completion
1	Renovation of 220V, O/H Line sub-station. To Area Guest House at Begunia Colliery.	114/- including VAT (non refundable)	2,07969.00	2,080.00 (Refundable)	25 days

Tender issue up to 24.06.10 to 05.07.2010

Terms & Conditions:-

1. Tender paper can be obtained from the office of the undersigned on any working day on production of money Receipt for the cost of tender paper (Non- refundable).
2. earnest money as mentioned above should be deposited either in the form of Bank draft drawn in favor of BCCL, A-XII, payable at Barakar or may be deposited in cash with Finance Dept., up to 1.00 P.M. on week days and money receipt in original is to be submitted along with the offer, without E. Money no tender will be accepted.
3. **Other Requirements:-**
 - (a) Pan Card (zerox) (b) VAT (up to date) (c) E. Money receipt (in original) (d) Time of Completion (e) Validity of Tender should be 120 days from the date of opening of price bid (f) Guarantee period minimum six months after installation (g) Valid contractor License with Supervisory certificates for power line jobs applicable, (H. T/ L.T as applicable) (h) Service tax registration copy (i) Deed of Partnership , Residential proof and proof of commencement of business. (j) All documents should be self attested with date & seals. (k) Desirable Experience Credential.

The intending tenders must have in his name and experience and having successfully completed Electrical work in BCCL or any other public sector undertaking or Govt. firm during last 7 years ending last day of the month previous to the one in which bid application are invited, should be either of the following :-

- i) Three similar completed work each costing not less than the amount equal to 40 % of the estimated cost. Or
 - ii) “TWO” similar completed works each costing not less than the amount equal to 50% of the estimated cost. Or
 - iii) One similar completed works costing not less than the amount equal to 80% of the Estimated cost.
4. 10% Security money including earnest money will be deducted from the final bill till completion of Guarantee period.

5. Please send authorized representative for Tender paper collection etc.
6. Management reserves the right to accept or reject the tender or part there or without assigning any reason what so ever.

Area Manager (E&M)
C.V. Area XII

Distribution:-

1. P.M. (Admn.) C.V. Area for display in Notice Board.
2. All A.M. (E&M), A-I to XI.
3. All colly. Engr (E&M), C.V. Area.
4. Addl. G.M., C.V. Area.
5. A.F.M. , C.V. Area.
6. Cashier, C.V Area, for cost paper / E. Money.
7. Tender File.
8. Manager (publication). P.R. Division Koyla Bhawan. BCCL, Dhanbad
For web site.
9. CVO (vigilance), Koyla Bhawan, Dhanbad.

Bharat coking Coal Limited
Chanch Victora Area.XII

Tender Paper

Ref No. E&M/XII/BCCL/NIT/2010-11/1005

Date: 11/14.05.2010

Name of work: Renovation of 220V O/H line sub-station to Area Guest House at Begunia colliery.

Sl No	Details of job.	Quantity	Rate	Amount (Rs).
1	Erection. Laying & Stringing of AAAC/ACSR conductor 3 Ph., 1 Neut (ACSR Rabbit) Sag as per rule.	300 kg		
2	Erection of pole by earth cutting and refilling etc. Pole up to 11 Mtrs. But not exceeding 13 mtrs. Pole supply by BCCL)	3 Nos.		
3	Supply of cement, sand & stone chips for cement concreting 1:3:6 (1 Cement:3 coarse sand: 6 greaded nominal size stone chips) 1.5 cum in each pole.	3 Nos		
4	Supply & Erection of 19/20 mm dia stay set by earth cutting with cement concreting with supply of cement, stone chips, and including stay wire, stay Insulator comp. set.	10 Nos		
5	Supply, Fabrication, Erection & painting of Iron & Steel, Materials such as cross arms, cradle guard bracket as per suitable size clamp, Nut, Bolt, Washer etc.	625 Kg		
6	Transportation of poles from Workshop to working site.	3 Nos		
7	Supply of AAAC/ACSR Rabbit conductor with Transportation to worksite.	700 Mtrs.		
8	Supply & Erection of Earth wire from 7/16 SWG or 8 No. SWG, g>I wore for its earth continuity.	180 Mtrs		
9	Supply & Erection of Cradle Guard wire 8 Nos SWG G.I. wire for Road, Basti Crossing (NIR).	225 Mtrs.		
10	Supply & Erection of shackle Insulator with G.I. Hardware fitting as per complete set.	40 Nos		
11	Supply & Erection of 440 volts with Lighting Arrestor complete with termination.	6 Nos		
12	Making of earth pit by earth cutting with refilling by charcoal, salt etc.	4 Nos		
13	Supply & erection of pole mounting kit for cable termination.	3 Sets.		
14	Laying of cable by 7/10 SWG G.I. wire stringing in pole to pole a crossing of H.T. Overhead line & sub-station.	35 Meters		
15	Dismantling of existing system conductor & pole.	218 Kg		
16	Supply & Erection of 440 Volts Grade 400 Amps. (400A) main switch 4 pole with erection and termination.	2 Nos		
17	Overhead line charging by individual staff Quarter & tree cutting.	L.S		

Total: Rs.

(Rupees.....

.....)

Signature of issuing authority
C.V. Area XII

Signature of Contractor
with seal & date