

BHARAT COKING COAL LTD.

OFFICE OF THE GENERAL MANAGER
(A subsidiary of Coal India Limited)

Chanch Victoria Area-XII

Ref.No. : E&M/XII/BCCL/NIT/10-11/777-97

Date: 10/05/10

Notice Inviting Tender

Sealed tenders are invited from Experienced and bonafide Electrical License contractors in two part i.e.,- Technical Bid as Part-I and Price bid as Part-II. Both Part Bid has to be wax sealed and should be sealed in a third envelope super subscribing the nature of bid in each envelope and the bids for the reference as above to be submitted.

The sealed bids must have to reach the office of the undersigned on or before 01-06-2010 up to 1 P.M. in the Tender box. No. tender will not be accepted after the date and time. Only the Technical Bids will be opened on the same day at 3 P.M. in the presence of the intending bidders.

Sl.	Name of	Time of	Earnest	Tender	Estimated	work
		Cost Rs.	Cost Rs.			No.
						Rs. Completion

- Renovation and removal of violation for over railway traction line. 5.47 lacs Rs. 100/- + Rs.
5,500/- 30 Days
(Renovation of 11KV O/H line (Main Feeder) only VAT
From 33KV/11KV Sub-Stn to NLOCP and Laikdih Deep Colliery)

(Non- refundable)

(Refundable)

Tender issued on 22.05.10 to

31.05.10

Terms & Conditions:-

- Tender Paper can be obtained from the office of the undersigned on any working day except Sunday and holidays from 22.05.10 to 31.05.10 on production of tender cost cash money receipt issued by the cashier, Finance Department, BCCL C/V Area-XII or demand draft drawn of any nationalized Bank in favor of BCCL, Area-XII (payable at Barakar). No tender will be issued on 01-06-10. Earnest money can be also deposited/submitted in the similar manner and no cash Earnest money will be accepted on 01-06-10. Original cash

receipt for Earnest Money is to be deposited with the Technical Bid. Without earnest money no tender will be accepted and is to be treated as cancelled.

2. The technical Bid is to be incorporated with valid electrical contractors license, Supervisory License for 11KV Lines, VAT Registration, PAN Card, Service Tax Registration, Past Experiences, Deed of partnership/proprietorship, Letter of credit Card from bank, list of tools and plants, Company's Profile and Earnest Money. The following proof of documents in original and duly attested to be produced at the time of issuing tender paper and also to be submitted along with submission of tender for verification.

Technical Parameters:- The intending bidders must have in their name and having successfully completed the similar nature of work in Government/Public sector undertaking in last 7 years ending with the last day of the month previous to the one in which bid application are invited, should be as following:-

- (i) Three similar completed works each costing not less than the amount equal to 40% of the estimated cost Or
- (ii) "Two" similar completed works each costing not less than the amount equal to 50% of the estimated cost. Or
- (iii) One similar completed works each costing not less than the amount equal to 80% of the estimated cost.

Similar Nature of work Means:- Commissioning /Installation of 11KV O/H Line works.

- 4. 10% security money including the Earnest Money will be withheld for a defect liability/guarantee period of six months from the date of handing over.
- 5. The offer of intending bidders should be valid for 120 days.
- 6. All taxes/levies will be applied/charged upon bidders as per Company's rule.
- 7. All safety wears, tools and tackles has to be provided to the workmen is the sole responsibility of the intending bidder.
- 8. The tender paper will be issued to authorized signatories of the firm only and in any case no unauthorized agents will be entertained.
- 9. Managements reserves the right either to accept or reject the entire tender paper or part their off/split up the work without assigning any reasons whatsoever.

Area Manager(E&M)
BCCL;C/V Area-XII,

Distribution:-

- 1. Notice Board, BCCL Area I to XII for display.
- 2. All CGM/GM/AM (E&M) – Area- I to XII.
- 3. AFM, AGM and Cashier, BCCL, C/V Area-XII.
- 4. CGM (E&M), BCCL HQ, Koyla Bhawan, Dhanbad.
- 5. Chief Vigilance Officer, BCCL HQ, Koyla Bhawan, Dhanbad.
- 6. Manager Publication, BCCL HQ, Koyla Bhawan, Dhanbad (for website and

newspaper publication) 7. All Colliery Engineer (E&M), BCCL, C/V Area- XII.
8. Tender file.

BHARAT COKING COAL LIMITED

Chanch Victoria Area-XII

Tender Paper

Ref No. :- E&M/XII/BCCL/NIT/10-11/777-97

Dt.10/05/10.

Name of work:- Renovation of 11KV O/H Line start (Main feeder) from 33 KV/11 KV Sub-Stn to NLOCP and Laikdih Deep Colliery.

Sl.No.	Description of Job	Qty.	Rate
--------	--------------------	------	------

- | | | | |
|----|---|----------|--|
| 1. | Erection of Pole P.C.C./R.C.C. upto 11 mtrs but not exceeding 13 mtrs. Incl. earth digging& refilling etc. as required | 7 Nos | |
| | a) Supply of PCC pole/Pipe pole | 7 Nos | |
| 2. | Supply of cement, sand, stone chips for cement concreting 1:3:6(1 cement 3 coarse Sand, 6 graded stone chips aggregate 40mm nominal size)1.5 cum. | 7 Nos | |
| 3. | Supply & erection of Galv. Stay set with earth digging as reqd. with 19/20mm dia x 1.8 mtrs long stay rod, Anchor Plate of thick size 45cm x 45cm x 7.5mm thick Thumbles comp. incl. supply of cement, Sand, Stone Chips for its concreting with G.I. Stay Wire, Stay Insulator complete. | 16 Nos | |
| 4. | Supply, fabrication, erection & painting from Red Oxide of Iron & steel materials such as Cross arms Bracing, various sizes of clamps incl. suitable size nut, bolts, washer etc. | 672 kgs. | |

5. Supply & Erection of 11KV Pin insulator comp. with large steel head G.I. pin,nuts,washers etc.	8 Nos.
6. Supply & Erection of 11KV Disc insulator for 11KV O/H Lines with GI insulator fittings, ball and socket type & complet with G.I. strain clamps, bolts, nuts,washers etc.	18 Nos.
7 Supply & erection of AB switch 400Amps,11KV Grade fixing on pole G.I. Handle and G.I. pipe complete etc.	1 Nos.
8. Transporting of Pole from Laikdih Workshop to Works Site.	7 Nos.
9. Supply & creation of 11KV 400Amps Gang operation switch with fixing of pipe etc.	1 Nos.
10. Erection of AAAC/ACSR Dog conductor of 7/3.35mm dia and above incl. binding etc.	1963 kgs.
a) Dismantling for above existing conductor	1963 kgs.
11. Supply, Stringing & erection of continous earth wire 7/16 SWG/8 No.SWG G.I. Wire for earth continuity.	1270 Mtrs
12. Supply & erection of Cradle Guard wire for 8 no SWG G.I. wire (NIR) for road crossing.	200 Mtrs.
13. Making of earth pit as per rule with earth digging with refilling salt, G.I. pipe & Charcoal etc.	5 Nos.
14. Dismantling of existing damage O/H line with all materials and transporting of all materials working site to PS/S,LKD	L.S.
15. Supply & erection of 3 pieces Non-linear resistor type lightning arrestor suitable for 3 wire, 11KV O/H line with rated voltage 9KV(rms) with nominal discharge current rating of 5KVA comp. with G.I. clamping arrangement, G.I. bolts, nuts, washers etc.	2 sets.
16. Supply & erection of P.G. clamp for jumphering size "Dog to Dog conductor" (Cast aluminum including 2 Bolt, G.I.)	80 Nos.

17. Supply & painting of rail pole 105 Lbs with all
fixtures, fittings, proper scrubbing & two coats of
red oxide paint & final 2 coats aluminum paint complet 38 Nos.

Total Rs.

(Rupees

)

Signature of issuing authority
Contractor

Signature of

C/V Area
date.

with seal &