

BHARAT COKING COAL LTD.
OFFICE OF THE GENERAL MANAGER
(A subsidiary of Coal India Limited)
Chanck Victoria Area-XII

Ref.No. : E&M/XII/BCCL/NIT/10-11/1759

Date: 25/10/10

Notice Inviting Tender

Sealed tenders are invited from Licensed, Experienced and bonafide Electrical contractors in two part i.e.,- Technical Bid as Part-I and Price bid as Part-II. Both Part of the Bid has to be wax sealed separately and should be wax sealed in a third envelope super scribing the nature of bid in each envelope and the bids for the reference as above to be submitted.

The sealed bids must has to reach in the office of the undersigned on or before 16-11-2010 up to 1 P.M. in the Tender box. No. tender will not be accepted after the date and time. Only the Technical Bids will be opened on the same day at 4:00 P.M. in presence of the intending bidders.

Sl. No.	Name of work	Estimated Cost Rs.	Tender Cost Rs.	Earnest Money Rs.	Time of Completion
1.	Drawing of 11 KV O/H line for supplying power to submersible pump at Basnatimata Colliery.	3,79,163/-	114/- Incl. Vat (Non- refundable) (Refundable)	3800/-	15 days

Terms & Conditions:-

1. Tender Paper can be obtained from the office of the undersigned on any working day except Sunday and holidays from 04.11.10 to 15.11.10 on production of tender cost cash money receipt issued by the Cashier Finance Department, BCCL C/V Area-XII or demand draft drawn of any nationalized Bank in favor of BCCL, Area-XII (payable at Barakar). No tender paper will be issued on 16-11-10. Earnest money can be also deposited/ submitted in the similar manner and no cash Earnest money will be accepted on 16-11-10. Original cash receipt for Earnest Money is to be deposited with the Technical Bid. Without earnest money no tender will be accepted and is to be treated as cancelled. Tender documents can also be downloaded from our company's website www.bccl.cmpdi.co.in but cost of tender document is to be submitted along with bid document by Bank draft.

2. The technical Bid is to be incorporat with valid Electrical Contractors license, Supervisory License for 11KV Lines, VAT Registration, PAN Card, Service Tax Registration, Past Experiences, Deed of partnership/proprietorship, Letter of credit from bank, list of tools and plants, Company's Profile and Earnest Money. None submission of these documents may result in rejection of the submitted bids.

Contd. On pg.- 2

3. Technical Parameters:- The intending bidders must have in their name having successfully completed the similar nature of work in Government/Public sector undertaking in last 7 years ending with the last day of the month previous to the one in which bid application are invited, should be as following:-

- (i) Three similar completed works each costing not less than the amount equal to 40% of the estimated cost Or
- (ii) Two similar completed works each costing not less than the amount equal to 50% of the estimated cost. Or
- (iii) One similar completed works each costing not less than the amount equal to 80% of the estimated cost.

Similar Nature of work Means:- Commissioning /Installation of 11 KV grade Overhead Line works.

- 4. 10% security money including the Earnest Money will be withheld for a defect liability/guarantee period of six months from the date of handing over.
- 5. The offer of intending bidders should be valid for 120 days.
- 6. All taxes/levies will be applied/charged upon bidders as per Company's rule.
- 7. All safety wears, tools and tackles has to be provided to the workmen is to sole responsibility of the intending bidder.
- 8. The tender paper will be issued to authorized signatories of the firm only and in any case no unauthorized agents will be entertained.
- 9. Managements reserves the right either to accept or reject the entire tender paper or part there off/split up the work without assigning any reasons whatsoever.

Area Manager(E&M)
BCCL;C/V Area-XII,

Distribution:-

- 1. Notice Board, BCCL C/V Area -XII for display.
- 2. All CGM/GM/AM (E&M) – Area- I to Area- XII.
- 3. AFM, AGM and Cashier, BCCL, C/V Area-XII.
- 4. CGM (E&M), BCCL HQ, Koyla Bhawan, Dhanbad.
- 5. Chief Vigilance Officer, BCCL HQ, Koyla Bhawan, Dhanbad.
- 6. The General Manager System/Publication, BCCL HQ, Koyla Bhawan, Dhanbad (for website and newspaper publication)
- 7. All Colliery Engineer (E&M), BCCL, C/V Area- XII.
- 8. Tender file.

BHARAT COKING COAL LIMITED

Chanch Victoria Area-XII

Tender Paper

NIT No. :- E&M/XII/BCCL/NIT/10-11/1759

Dt. 25/10/10.

Name of work:-Drawing of 11 KV O/H line for supplying power to Submercible Pump at Basantimata Colliery.

Sl.No.	Description of Job	Qty.	Rate	Amount
1.	Erection of Pole 105 Lbs. Rail Pole/ P.C.C. 13 Mtrs incl. earth digging & refilling etc. as required.	14 Nos		
2.	Supply of cement, sand & stone chips for cement concreting 1:3:6 (1 Cement, 3 Coarse Sand, 6 Graded Stone Chips aggregate 40mm nominal size) 2.0 Cum.	14 Nos		
3.	Supply & Erection of Galv. Stay Set with earth digging as reqd. with 19/20 mm Dia x 1.8 Mtrs. long Stay Rod, Anchor plate of size 45cm X 45cm X 7.5 mm thick Thumbles complete incl. supply of cement, Sand, Stone Chips for its concreting with G.I. Stay Wire Insulator etc.	22 Nos		
4.	Supply, fabrication, erection & painting from Red Oxide of Iron & steel materials such as Cross arms Bracing, various sizes of clamps, incl. suitable size Nut, bolts, washers etc.	675 kgs.		
5.	Supply & Erection of 11 KV pin Insulator comp. with large steel haed G.I. Pin, Nuts, washer etc.	27 Nos		
6.	Supply & erection of 11 KV Disc Insulator for 11 KV O/H Line with G.I. Insulator fittings, Ball & Socket type & comp. with G.I. Strain Clamps, Bolts, Nuts, Washer, etc.	18 Nos		
7.	Transporting of Pole from RKSSY Workshop to worksite.	14 Nos		
8.	Erection of AAAC/ACSR Dog Conductor of 7/3.35 mm diameter and above incl. Binding etc.	712 Kgs		
9.	Supply, Stringing & erection of continous earth wire 7/16 SWG/ 8 no. SWG G.I. Wire for earth continuity.	600 Mtrs.		
10.	Supply & Erection of Cradle guard Wire for 8 No. SWG G.I. Wire (NIR) for road crossing.	200 Mtrs.		

11. Making of earth pit as per rule with earth digging with refilling Salt, G.I. Pipe and Charcoal etc.	5 Nos
12. Dismantling of existing damage O/H line with all materials & transporting of all materials working site to PS/S, B.Mata Workshop.	L.S.
13. Dismantling of P.C.C. Pole.	13 Nos
14. Supply & Erection of P.G. Clamp for jumpher size “ Dog to Dog Conductor” (Cast Aluminium incl. Two Bolt , G.I.).	36 Nos
15. Supply & Painting of Rail Pole 105 Lbs. with all fixture, fittings, proper scrubbing and two coats Red Oxide Paint and final two Coats Aluminum Paint comp.	14 Nos
16. Tree cutting and survey Pag marking, testing of O/H Line.	L.S.

Total Rs.

(Rupees.....
.....only)

Signature of issuing authority

C/V Area

Signature of Contractor

With seal and date.