

Office of the General Manager  
Bharat Coking Coal Limited  
(A subsidiary Of Coal India Limited)  
Chanch Victoria Area-XII

Ref.No.:E&M/XII/BCCL/NIT/10-11/1763

Date: 26-10-10

Notice Inviting Tender

Sealed Tenders are invited from Licensed, Experienced and Bonafide Electrical contractors in Two Parts i.e. Technical Bid as Part-I and Price Bid as Part-II. Both Part of the Bid has to be wax sealed separately and should be wax sealed in a third envelope super scribing the nature of bid in each envelope and the bids for the reference as above to be submitted.

The sealed bids must has to reach in the office of the undersigned on or before 12 - 11 - 10 up to 1 P.M. in the Tender Box. No tender will be accepted after the date and time. Only the Technical Bids will be opened on the same day at 4 P.M. in presence of the intending bidders.

Sl. No.	Name Of Work	Estimated Cost Rs.	Tender Cost Rs.	Earnest Money Rs.	Time of Completion
1.	Lighting of Ramkrishna Colony near D.B.O.C.P. Weigh Bridge at D.B.O.C.P.	3.99 Laes	114/- Inc. VAT (Non-Refundable)	4,000/- (Refundable)	30 days only.

Terms & Conditions :-

1. Tender Paper can be obtained from the office of the undersigned on any working day except Sunday and holidays from 01-11-10 to 11-11-10 on production of tender cost cash money receipt issued by the Cashier, Finance Department, BCCL C/V Area-XII or demand draft of any nationalized bank in favour of BCCL, Area-XII (Payable at Barakar). No Tender Paper will be issued on 12-11-10. Earnest Money can also be deposited / submitted in the similar manner and no cash Earnest Money will be accepted on 12-11-10. Original cash receipt for Earnest Money is to be deposited with the technical bid. Without Earnest Money no Tender will be accepted and is to be treated as cancelled. Tender documents can also be downloaded from our company's website [www.bccl.cmpdi.co.in](http://www.bccl.cmpdi.co.in) but cost of the tender document is to be submitted along with bid document by Bank Draft.
2. The technical bid is to be incorporated with valid Electrical Contractors License, Supervisory License for 1.1 KV lines, VAT registration, Pan Card, Service Tax Registration, Past experiences, Deed of partnership / proprietorship, Letter of Credit from Bank, List of Tools and Plants, Company's Profile, and Earnest Money.
3. Technical Parameters ; The intending Bidders must have in their name having successfully completed the similar nature of work in Government /Public Sector Undertaking in last 7 years ending with the last day of the month previous to the one in which bid applications are invited should be as follows :-

contd. on pg.- 2

  
26/10/10  
Area Manager (E & M)  
C V Area-XII, BCCL  
Barakar

Office of the General Manager  
Bharat Coking Coal Limited  
(A subsidiary Of Coal India Limited)  
Chanch Victoria Area-XII

- (i) Three similar completed works each costing not less than the amount equal to 40% of the estimated cost. Or
- (ii) Two similar completed works each costing not less than the amount equal to 50% of the estimated cost. Or
- (iii) One similar completed work costing not less than the amount equal to 80% of the estimated cost.

**SIMILAR NATURE OF WORK MEANS :- COMMISSIONING / INSTALLATION OF 1.1 KV GRADE OVERHEAD LINE WORKS.**

- 4. 10% security money including the Earnest Money will be withheld for a defect liability/guarantee period of six months from the date of handing over.
- 5. The offer of the intending bidders should be valid for 120 days.
- 6. All taxes/levies will be applied/charged upon bidders as per company's rule.
- 7. All safety wears, tools and tackles has to be provided to the workmen is the sole responsibility of the intending bidder.
- 8. The Tender Paper will be issued to authorized signatories of the firm only and in any case no unauthorized agents will be entertained.
- 9. Management reserves the right either to accept or reject the entire tender or part thereof/split up the work without assigning any reason whatsoever.

**Distribution :-**

- 1. Notice Board, BCCL, C/V Area-XII for display.
- 2. All CGM/GM/AM (E & M) – Area - I to Area – XII.
- 3. AFM, AGM & Cashier, BCCL, C/V Area-XII.
- 4. CGM (E & M), BCCL HQ, Koyla Bhawan, Dhanbad.
- 5. Chief Vigilance Officer, BCCL HQ, Koyla Bhawan, Dhanbad.
- 6. The General Manager ,System/Publication, BCCL HQ, Koyla Bhawan, Dhanbad.  
(For Uploading in Company's website/Newspaper Publication)
- 7. All Colliery Engineer (E & M), BCCL, C/V Area-XII.
- 8. Tender File.

  
Area Manager, E&M  
BCCL, C/V Area-XII  
Area Manager, E&M  
C/V Area-XII, BCCL  
Barakar




**Bharat Coking Coal Limited****OFFICE OF THE GENERAL MANAGER**

(A subsidiary of Coal India Limited)


**Chanch Victoria Area-XII****BID DOCUMENT****Name of Work : Lighting of Ramkrishna Colony near D.B.O.C.P weigh bridge at D.B.O.C.P.****NIT Ref. No.:E&M/XII/BCCL/NIT/10-11/1763****Date:26-10-10**

<u>Sl.No.</u>	<u>Details of Job</u>	<u>Quantity</u>	<u>Unit</u>	<u>Rate (Rs.)</u>	<u>Amount (Rs.)</u>
1.	Erection of Pole Tubelor/P.C.C. Upto 11 mtrs. But not exceeding 13 mtrs. Incl. earth digging and refilling etc. as reqd. ( Pole BCCL Supply ).	10 Nos.	Nos.		
2.	Supply of Cement, sand & stone Chips 1:3:6 (1 cement 3 coarse sand: 6 graded stone aggregate 40 mm nominal size) 1.5 cum.	10 Nos.	Nos.		
3.	Supplying and Erection of stay Set complete (galvanized) with earth digging as reqd. with 19/20 mm dia x 1.8 Mtrs. Long Stay Rod, Anchor plate of Size 45 cm x 45 cm x 7.5 mm thick thumbles comp. incl. supply of cement, sand, stone chips for its concreting with G.I. Stay wire, stay/guy Insulator etc.	12 Nos.	Nos.		
4.	Supplying & Erection of 110mm x 100 mm shackle/pin insulator of ISI Quality.	84 Nos.	Nos.		
5.	Supply, Fabrication, Erection & Painting from Red Oxide of Iron & Steel materials such as cross Arms bracing, various sizes of Clamps incl. suitable size Nut, Bolts, Washer etc.	750 Kgs.	Kgs.		

**Contd. On Pg-2**

  
26/10/10  
Area Manager, C.V. Area-XII, BCCL  
Barrack

<u>SL.No.</u>	<u>Details of Job</u>	<u>Quantity</u>	<u>Unit</u>	<u>Rate (Rs.)</u>	<u>Amount (Rs.)</u>
6.	Supply & Erection of Earth Continuous earth wire from 7/16 SWG 8 Nos. SWG G.I. wire for Earth continuity.	750 Mtrs.	Mtrs.		
7.	Laying & Stringing of AAAC/ ACSR Rabbit conductors with Sag incl. Jumphereing and binding etc.	390 Kgs.	Kgs.		
8.	Supply and Erection of 250 W x 220 V Metal Halide Vapour comp. Set with fixing in the top of pole incl. Fabrication of Swan Type 2" G.I. pipe P.V.C. Wire Clamp, Nuts, Bolts, Washer etc.	12 Nos.	Nos.		
9.	Transportation of poles from Workshop to work site.	10 Nos.	Nos.		
10.	Supply & Erection of Distribution Box with 40 Amps 2 Pole Power Contractor & Photo sensing device for Automatic ON - OFF Control and also Toggle Switch with indicating Lamp for the system Bye-Pass arrangement for manual operation Contractor Havells/L&T/ C&S Make Photosensor: ISL	1 Set	Set		
11.	Earthing as per I.E. Rule with Earth cutting with refilling Salt, Pipes & Charcoal etc.	2 Nos.	Nos.		
12.	Check Survey & Peg marking, Making of Approach Road and Line Testing changing complete.	L.S.	L.S.		


  
 26/7/10  
 Area Manager C & M  
 CV Area-XII PCC  
 Dabka

Contd. On Pg-3

<u>Sl.No.</u>	<u>Details of Job</u>	<u>Quantity</u>	<u>Unit</u>	<u>Rate (Rs.)</u>	<u>Amount (Rs.)</u>
13.	Making of Credle guard by Cross lacing of 8 No. G.I. Wire and installation at required Sections.	150 Mtr.	Mtr.		
14.	Supply of AAAC/ACSR Rabbit Conductor.	1 KM	KM		
15.	Supply & Erection of incoming and outgoing cable of 4 core 16 Sq. mm A1 Armoured.	15 Mtrs.	Mtrs.		

Amount in Words- \_\_\_\_\_  
 \_\_\_\_\_

Total (Rs.) \_\_\_\_\_  
 \_\_\_\_\_

  
 Issuing Authority  
 A.M. (E & M)  
 B.C.C.L. C/V Area XII  
 (E & M)  
 22/7/10

Signature with Seal  
 Contractor