

**Office of the General Manager  
Bharat Coking Coal Limited  
(A subsidiary Of Coal India Limited)  
Chanch Victoria Area-XII**

Ref.No.:E&M/XII/BCCL/NIT/10-11/ 1907

Date: 27-11-10

**Notice Inviting Tender**

Sealed Tenders are invited from Licensed , Experienced and Bonafide Electrical contractors in Two Parts i.e. Technical Bid as Part-I and Price Bid as Part-II. Both Part of the Bid has to be wax sealed separately and should be wax sealed in a third envelope super scribing the nature of bid in each envelope and the bids for the reference as above to be submitted.

The sealed bids must has to reach in the office of the undersigned on or before 14 - 12 - 10 up to 1 P.M. in the Tender Box. No tender will be accepted after the date and time. Only the Technical Bids will be opened on the same day at 4 P.M. in presence of the intending bidders.

Sl. No.	Name Of Work	Estimated Cost Rs.	Tender Cost Rs.	Earnest Money Rs.	Time of Completion
1.	Extension Of 3.3 KV O/H Line from NLOCP New Sub-Stn. to Chanch Colliery Sub- Stn.Under Laikdih.	4.11 Lacks.	114/- Inc. VAT (Non-Refundable)	4,150/- (Refundable)	30 days only.

**Terms & Conditions :-**

1. Tender Paper can be obtained from the office of the undersigned on any working day except Sunday and holidays from 01-12-10 to 13-12-10 on production of tender cost cash money receipt issued by the Cashier, Finance Department, BCCL C/V Area-XII or demand draft of any nationalized bank in favour of BCCL, Area-XII ( Payable at Barakar ). No Tender Paper will be issued on 14-12-10. Earnest Money can also be deposited /submitted in the similar manner and no cash Earnest Money will be accepted on 14-12-10. Original cash receipt for Earnest Money is to be deposited with the technical bid. Without Earnest Money no Tender will be accepted and is to be treated as cancelled. Tender documents can also be downloaded from our company's website [www.bccl.cmpdi.co.in](http://www.bccl.cmpdi.co.in) but cost of the tender document is to be submitted along with bid document by Bank Draft.
2. The technical bid is to be incorporated with valid Electrical Contractors License, Supervisory License for 3.3 KV lines, VAT registration, Pan Card, Service Tax Registration, Past experiences, Deed of partnership / proprietorship, Letter of Credit from Bank, List of Tools and Plants ,Company's Profile , and Earnest Money.
3. **Technical Parameters** ; The intending Bidders must have in their name having successfully completed the similar nature of work in Government /Public Sector Undertaking in last 7 years ending with the last day of the month previous to the one in which bid applications are invited should be as follows :-

contd. on pg.- 2

**Office of the General Manager  
Bharat Coking Coal Limited  
(A subsidiary Of Coal India Limited)  
Chanch Victoria Area-XII**

- (i) Three similar completed works each costing not less than the amount equal to 40% of the estimated cost. Or
- (ii) Two similar completed works each costing not less than the amount equal to 50% of the estimated cost. Or
- (iii) One similar completed work costing not less than the amount equal to 80% of the estimated cost.

**SIMILAR NATURE OF WORK MEANS :- COMMISSIONING / INSTALLATION  
OF 3.3 KV GRADE OVERHEAD LINE WORKS.**

- 4. 10% security money including the Earnest Money will be withheld for a defect liability/guarantee period of six months from the date of handing over.
- 5. The offer of the intending bidders should be valid for 120 days.
- 6. All taxes/levies will be applied/charged upon bidders as per company's rule.
- 7. All safety wears, tools and tackles has to be provided to the workmen is the sole responsibility of the intending bidder.
- 8. The Tender Paper will be issued to authorized signatories of the firm only and in any case no unauthorized agents will be entertained.
- 9. Management reserves the right either to accept or reject the entire tender or part thereof/split up the work without assigning any reason whatsoever.

**Area Manager,E&M  
BCCL, C/V Area-XII.**

**Distribution :-**

- 1. Notice Board, BCCL, C/V Area-XII for display.
- 2. All CGM/GM/AM (E & M) – Area - I to Area – XII.
- 3. AFM, AGM & Cashier, BCCL, C/V Area-XII.
- 4. CGM (E & M), BCCL HQ, Koyla Bhawan, Dhanbad.
- 5. Chief Vigilance Officer, BCCL HQ, Koyla Bhawan, Dhanbad.
- 6. The General Manager ,System/Publication, BCCL HQ, Koyla Bhawan, Dhanbad.  
(For Uploading in Company's website/Newspaper Publication)
- 7. All Colliery Engineer (E & M), BCCL, C/V Area-XII.
- 8. Tender File.

**Bharat Coking Coal Limited**  
**OFFICE OF THE GENERAL MANAGER**  
 (A subsidiary of Coal India Limited)  
**Chanch Victoria Area-XII**

**TENDER PAPER**

**TENDER NO :** E&M/XII/BCCL/NIT/10-11/1907

**Dtd.:**27-11-10

**Name of Work :** Extension of 3.3 K.V. O/H line form N.L.O.C.P. New Sub-Station to Chanch Colliery Sub-Stn. Under Laikdih

<b><u>Sl.No.</u></b>	<b><u>Details of Job</u></b>	<b><u>Quantity</u></b>	<b><u>Rate (Rs.)</u></b>	<b><u>Amount (Rs.)</u></b>
1.	Erection of pole Tubelor/PCC upto 11 Mtrs. but not exceeding 13 Mtrs. incl. earth digging & refilling etc. as reqd.(Pole BCCI Supply)	12 Nos.		
2.	Supply of Cement, Sand & Stone Chips for Cement concreting 1:3:6 ( 1 Cement, 3 Coarse Sand, 6 graded Stone Chips aggregate 40 mm nominal size) 1.5 cum.	12 Nos.		
3.	Supply & Erection of Galv. Stay Set with earth digging as reqd. with 19/20 mm Dia x 1.8 Mtrs. long Stay Rod, Anchor Plate Of Size 45 cm x 45 cm x 7.5 mm thick Thumbs comp. incl. supply of Cement, Sand, Stone Chips for its concreting with G.I. Stay Wire, Stay/ Guy Insulator etc.	24 Nos.		
4.	Supply, Fabrication, Erection & Painting from Red Oxide of Iron & Steel materials such as Cross Arms Bracing, various sizes of Clamps incl. suitable size Nut, Bolts, Washer etc.	650 kgs.		
5.	Supply & Erection of Earth continuous earth wire from 7/16 SWG/8 No. SWG G.I. wire for earth continuity.	400 Mtrs.		
6.	Laying & Stringing of AAAC/ACSR Dog Conductors with Sag incl. jumphering and Binding etc. ( Conductor BCCL Supply) Erection = 416 kgs			

Contd. on Page (2)

<u>Sl.No.</u>	<u>Details of Job</u>	<u>Quantity</u>	<u>Rate (Rs.)</u>	<u>Amount (Rs.)</u>
7.	Supplying & Erection of 11 KV Pin Insulators comp. with large Steel head G.I. Pin, Nuts, Washers etc. as reqd.	21 Nos.		
8.	Supplying & Erection of 11 KV Disc Insulators for 11 KV lines with G.I. Insulator fittings Ball and Socket type and complete with Galvanized strain clamps, bolts, nuts, washers etc. as reqd.	21 Nos.		
9.	Supplying & Erection of three pcs. Non linear resistor type lightning arrester suitable for 3 Wire, 11 KV O/H lines with rated Voltage 9 KV (rms) with a nominal discharge current rating of 5 K.A. and comp. with Galvanized clamping arrangement, G.I. Bolts, Nuts, Washers etc. as required.	6 Sets		
10.	Earthing as per I.E. Rule with Earth cutting and refilling by supplying Salt, Charcoal & Sand G.I. Pipe of 50 mm dia 3 Mtrs. long with Earth Electrode duly welded at the bottom.	4 Nos		
11.	Making of Credle Guard by cross lacing of 8 No. G.I. Wire at the sections from pole to pole as required for safety.	350 Mtrs		
12.	Supply of Swaged type Steel Tubular pole 11 Mtrs. long type Sp=54.	12 Nos		
13. (a)	Dismantling of old PCC/Tubular/ MS Rail poles at locations embedded in Cement Concrete.	9 Nos		
(b)	Transporting of pole from locations to Store by pulling Hand Cart.	9 Nos		
14. (a)	Dismantling of O/H lines comprising aluminium Conductor G.I. Wires, Crosss arms, Insulators etc.	1000 Kgs		
(b)	Handling of wires including making coils and transporting the same by Pulling Hand Cart.	1000 Kgs		

<u>Sl.No.</u>	<u>Details of Job</u>	<u>Quantity</u>	<u>Rate (Rs.)</u>	<u>Amount (Rs.)</u>
15.	Check Survey, Pit marking, making approach road, Obr cleaning, Tree cutting & Corridor Cleaning for the O/H Line.	L.S.		

Grand Total (Rs.)

Amount in Words-\_\_\_\_\_

\_\_\_\_\_  
\_\_\_\_\_

Issuing Authority  
A.M. (E & M)  
B.C.C.L. C/V Area XII

Signature with Seal  
Contractor