

**BHARAT COKING COAL LIMITED  
(A Subsidiary of Coal India Limited)  
OFFICE OF THE GENERAL MANAGER, EJ AREA  
P.O. : BHOWRA (DHANBAD)**

Ref. No. : GM(EJA)/ACE/NIT/10-11/ 474

Dated : 31.01.2011

**NOTICE INVITING TENDER**

Sealed Tender in two parts(Part-I & Part-II) on overall percentage rate basis are invited from experienced and eligible contractors for the following works

Sl.No.	Name of work	Estimated cost	Earnest money	Cost of Tender paper	Time of completion
1.	Daily maintenance work at near Nach ghar Riverside Guest house P.O.'office etc. Under EJ Area	179799.89	1800.00	100.00	Fifteen days
2.	Providing & laying PVC pipeline to supply drinking water at Mundapatti from Ghosai sthan Mandir at Sudamdih under EJ Area.	84098.03	841.00	100.00	Ten days
3.	Supplying and fixing of steel door & windows at different places under EJ Area.	121973.10	1220.00	100.00	One month

**AVAILABILITY OF TENDER DOCUMENTS**

From 14.02.2011 to 18.02.2011

Tender documents will be issued on all working days during working hours except on Sunday & holiday in the event of the specified date for submission, opening of bids being declared a holiday the bids will be received opened on the appointed time on the next working day. The Tender document is also available on web site : <http://bccl:cmpdi:co:in> and can be downloaded.

**TIME & DATE IF RECEIPT/OPENING OF TENDER**

The Tender will be received on 22.02.2011 from 10.00AM to 1.00PM in Tender box at (1). CISF post near Koyla Bhawan gate, Koyla Nagar, BCCL, Dhanbad. (2). CISF'S office of EJ Area and will be opened on 25.02.2011 at 4.00 PM in the office of the ACE/EJ Area.

**1. ELIGIBILITY CRITERIA**

- The intending Tenderer must have in its name as a prime contractor experience of having successfully completed similar works during last 7(seven) years ending last day of month previous to the one in which bid applications are invited should be either of the following :- (1). Three similar completed works each costing not less than 40 % of the estimated cost. Or (2). Two similar completed works each costing not less than 50 % of the estimated cost or (3). One similar completed work costing not less than 80 % of the estimated cost. **Similar work means : Pipeline works in Sl.No. 1 & 2 and Fabrication,erection work for Sl.No.3**
- Average annual financial turnover of civil works during the last three years, ending 31<sup>st</sup>. March of the previous financial, should be at least 30 % of the estimated cost.
- The Tender documents can be had from the office of the undersigned during the period mentioned above on deposition of requisite cost of Tender paper in form of cash bank draft of any nationalized bank/scheduled commercial bank approved by Reserve bank of India in favour of "Bharat coking coal limited" payable at Dhanbad.
- Completed sealed Tender documents (Part I & II) should be submitted at the same time. **Part I** shall consists of terms & conditions of the Tender, additional terms and conditions if any, Technical bid and credentials. **Part II** shall consists of tender documents as sold to the tenderers duly filled in for rates, amount etc. i.e. price bid.

The earnest money deposit is to be submitted in a separate envelop subscribing "Earnest Money Deposit"  
All three envelopes should be submitted in one sealed envelope.

The Part II will be opened only after The department is satisfied that the criteria fixed are fulfilled i.e. acceptance of Part I

- The earnest money is to be deposited as per detail given in Tender documents.
- TIN No. Is to be submitted.
- The Tenderers have to submit Permanent Account no.(PAN) of Income Tax.
- Conditional tenders will not be accepted.
- Issuance of Tender document does not mean that the parties are considered qualified.
- The experience as given in the eligibility criteria should be in the name and style in which tender is filled. The experience in the name of some other firm/company will not be considered for this purpose.

- 10.The validity of the tender will be 120 days from the date of opening of price bid
- 11.The Management of BCCL reserves right to reject any or all the tender or split the work among two or more tenderers without assigning any reason what so ever.
- 12.Other details may be obtained from detailed Tender notice/Tender documents/web site <http://bccl.cmpdi.co.in>
- 13.The Tender documents has been downloaded from the above mentioned web site, the tenderers are required to deposit along with their tender, a bank draft of any nationalized/scheduled commercial bank approved by Reserve bank of India payable at Dhanbad exclusively towards the cost of tender documents for the amount indicated as above, in the envelope as stated at clause 3 of this NIT. Any bank draft prepared after the schedule closure of sale of tender documents may be liable to rejection.
- 14.The contents of the tender documents available in our office, shall be deemed as authentic. The bidder will be required to submit an undertaking that they will accept the tender documents as available in the web site and their tender shall be rejected if any tempering is there in the tender documents thus submitted.

Area Civil Engineer/EJ Area.

Copy to :-

1. The C.V.O.,BCCL
2. All CGMs/GMs of Area of BCCL
3. The General Manager(Civil),CED/Koyla Nagar
4. H.O.D.(Admn.), BCCL/Koyla Nagar
5. The GM(System), BCCL – with a request to display this NIT in BCCL web site with download facility.
6. The Addl. GM(EJA)/The AFM(EJA)/The Area Survey officer
7. The Inspector I/C, CISF, Koyla Bhawan
8. The Inspector I/C, CISF, EJ Area.
9. Notice Board, EJ Area.

**Bill of quantity for the work," Daily maintenance work at near Nach ghar Riverside Guest house P.O.'office etc. Under EJ Area.**

Sl. No.	Description of work	Unit	Quantity	Rate	Rate quoted by the Tenderer(In figure & word).
1.	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer in charge. i). 80 mm. Dia. G.I.Pipe ii). 50 mm. Dia. G.I.Pipe iii). 40 mm. Dia. G.I.Pipe iv). 25 mm. Dia. G.I.Pipe v). 20 mm. Dia. G.I.Pipe vi). 15 mm. Dia. G.I.Pipe	metre	60.00 597.00 54.00 636.00 69.00 267.00	29.05 29.05 24.90 24.90 24.90 24.90	
2.	P/F. PVC Pipeline complete. i). 50 mm. Dia. PVC .Pipe ii). 40 mm. Dia. PVC .Pipe iii). 25 mm. Dia. PVC .Pipe iv). 20 mm. Dia. PVC .Pipe v). 15 mm. Dia. PVC .Pipe	metre	99.36 12.19 185.93 56.39 37.18	182.26 148.06 97.69 72.90 59.25	
3.	Providing and fixing G.I. Union in existing G.I. pipe line, cutting and threading the pipe and making long screws including excavation, refilling the earth or cutting of wall and making good the same complete wherever required. i). 50 mm. Dia. ii). 40 mm. Dia. iii). 80 mm. Dia. iv). 25 mm. Dia. v). 20 mm. Dia. vi). 15 mm. Dia.	Each	31 04 03 31 07 15	335.50 237.45 607.30 180.55 170.10 109.20	
4.	Providing and fixing gun metal gate valve with C.I. wheel of approved quality(screwed end ) i). 50 mm. Dia. ii). 25 mm. Dia. iii). 15 mm. Dia. iv). 40 mm. Dia.	Each	03 01 03 01 02	578.00 285.50 228.35 399.00 266.55	
5.	Providing and fixing PTMT pillar cock of approved quality and colour. 15mm nominal size, 125mm long,, weighing not less than 120gms.	Each	04	191.70	
6.	Providing and fixing brass stop cock of approved quality. 15mm. Nominal bore.	Each	19	191.70	
7.	Providing and fixing brass bib cock of approved quality.15 mm. Nominal bore.	Each	22	423.20	
8.	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete.50mm. to 80mm. Nominal bore.	litre	500	5.25	
.9.	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and base support for tank. 12 mm cement plaster of mix : 1:6 (1 cement : 6 fine sand)	Cum	20.00	101.85	
10.	Earth work in excavation over areas (exceeding 30cm in depth. 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m; disposed earth to be levelled and neatly dressed. All kinds of soil.				
11.	Labour charges for cleaning & refilling of pipe i). 80 mm. Dia. ii) 50 mm. Dia. iii) 40 mm. Dia. iv). 25 mm. Dia. v). 20 mm. Dia.	metre	60.00 597.00 54.00 636.00 69.00	45.82 35.02 33.76 30.25 26.68	

Name & Address of the Tenderer :

Details of Earnest money :

Area Civil Engineer/EJ Area.

Signature of the Tenderer with date

Bill of quantity for the work," Providing & laying PVC pipeline to supply drinking water at Mundapatti from Ghosai  
sthan Mandir at Sudamdih under EJ Area.

Sl. No.	Description of work	Unit	Quantity	Rate	Rate quoted by the Tenderer(In figure & word).
1.	P/F. PVC Pipeline complete. i). 80 mm. Dia. PVC .Pipe ii). 50 mm. Dia. PVC .Pipe iii). 40 mm. Dia. PVC .Pipe	metre	185.00	182.26	
		metre	185.00	148.06	
		metre	185.00	97.69	
2.	Providing G.I.Union. i). 50 mm. Dia. ii). 40 mm. Dia. iii). 25 mm. Dia.	Each	09	158.00	
		Each	08	108.00	
		Each	08	59.00	
		Each	04	166.05	
3.	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete.25mm to 40mm nominal bore Providing and fixing gun metal gate valve with C.I. wheel of approved quality(screwed end )	metre	60.00	24.90	
4.	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer in charge. 15mm 40mm nominal bore.	metre			

Name & Address of the Tenderer:

Details of Earnest money:

Area Civil Engineer/EJ Area.

Signature of the Tenderer with date

**Bill of quantity for the work, "Supplying & fixing of steel doors and windows at different places under EJ Area.**

Sl.No.	Description of Item	Unit	Quantity	Rate	Amount
1.	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete:	Kg	2115.00	46.35	98030.25
2.	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: One or more coats on old work	Sqm	186.11	22.85	4250.10
3	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead:	Each	55	54.60	3003.01
4	Fixing chowkhats in existing opening including embedding chowkhats in floors or walls cutting masonry for holdfasts embedding hold fasts in cement concrete blocks with cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size). Painting two coats of approved wood preservative to sides of chowkhats and making good the damages to walls and floors as required complete including disposal of rubbish to the dumping ground within 50 metres lead. a). Door chowkhats b). Window chowkhats	Each Each	35 20	354.45 214.20	12405.75 4284.00
					121973.10

Rate quoted In % Above/Below.....(In figure)/.....

Name & Address of Agency

Details of Earnest money

Signature with date of the Tenderer

