

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER, EJ AREA
P.O. : BHOWRA (DHANBAD)

Ref. No. : GM(EJA)/ACE/NIT/10-11/ 1099

Dated : 28.02.2011

NOTICE INVITING TENDER

Sealed Tender in two parts(Part-I & Part-II) on overall percentage rate basis are invited from experienced and eligible contractors for the following works

Sl.No.	Name of work	Estimated work	Earnest money	Cost of Tender paper	Time of completion
1.	Repairing of qtr.no. M/750 & M/1144 riverside of Sudamdih to shift the employee residing endanger zone area of EJA.	124667.27	1250.00	100.00	Ten days
2.	Sealing depillaring panel D5 in VI seam of preparatory stopping in different level.	92113.99	925.00	100.00	Ten days
3.	Repair work in the qtr. Of Sri Shailendra Tumane, Mining Sardar at Pathardih and Sri Prayag Visawkarma Qtr. No. M/771, Haulage operator of incline mine Sudamdih at EJ Area.	55515.45	560.00	100.00	Seven days
4.	Repairing of compound wall and other petty repair works in the bungalow of Dr. M.K.Saha located at riverside Sudamdih under EJ Area.	74525.45	750.00	100.00	Seven days
5.	Pables/Boulders(Rejected materials) cleaning near mixing chamber of VI seam Panel 'P2'	79601.76	800.00	100.00	Seven days

AVAILABILITY OF TENDER DOCUMENTS

From 05.03.2011 to 08.03.2011

Tender documents will be issued on all working days during working hours except on Sunday & holiday in the event of thr specified date for submission, opening of bids being declared a holiday the bids will be received opened on the appointed time on the next working day. The Tender document is also available on web site : <http://bccl:cmpdi.co.in> and can be downloaded.

TIME & DATE IF RECEIPT/OPENING OF TENDER

The Tender will be received on 10.03.2011 from 10.00AM to 1.00PM in Tender box at (1). CISF post near Koyla Bhawan gate, Koyla Nagar, BCCL, Dhanbad. (2). CISF'S office of EJ Area. (3). CISF's office of Ropeways Area. (4). CISF's office of EWZ Area and will be opened on 12.03.2011 at 11.00 AM in the office of the ACE/EJA.

1. ELIGIBILITY CRITERIA

- a). The intending Tenderer must have in its name as a prime contractor experience of having successfully completed similar works during last 7(seven) years ending last day of month previous to the one in which bid applications are invited should be either of the following :- (1). Three similar completed works each costing not less than 40 % of the estimated cost. Or (2). Two similar completed works each costing not less than 50 % of the estimated cost or (3). One similar completed work costing not less than 80 % of the estimated cost. **Similar work means : Building works for all works.**
- b). Average annual financial turnover of civil works during the last three years, ending 31st. March of the previous financial, should be at least 30 % of the estimated cost.
2. The Tender documents can be had from the office of the undersigned during the period mentioned above on deposition of requisite cost of Tenser paper in form of cash bank draft of any nationalized bank/scheduled commercial bank approved by Reserve bank of India in favour of "Bharat coking coal limited" payable at Dhanbad.
3. Completed sealed Tender documents (Part I & II) should be submitted at the same time. **Part I** shall consists of terms & conditions of the Tender, additional terms and conditions if any, Technical bid and credentials. **Part II** shall consists of tender documents as sold to the tenderers duly filled in for rates, amount etc. i.e. price bid.
The earnest money deposit is to be submitted in a separate envelop subscribing "Earnest Money Deposit"
All three envelopes should be submitted in one sealed envelope.
The Part II will be opened only after The department is satisfied that the criteria fixed are fulfilled i.e. acceptance of Part I
4. The earnest money is to be deposited as per detail given in Tender documents.
5. TIN No. Is to be submitted.
6. The Tenderers have to submit Permanent Account no.(PAN) of Income Tax.
7. Conditional tenders will not be accepted.
8. Issuance of Tender document does not mean that the parties are considered qualified.

9. The experience as given in the eligibility criteria should be in the name and style in which tender is filled. The experience in the name of some other firm/company will not be considered for this purpose.
10. The validity of the tender will be 120 days from the date of opening of price bid.
11. Complete set of Tender documents must be signed by the Tenderer. If any cutting/tempering found at the time of opening in the Tender documents, the tender will be rejected.
12. The Management of BCCL reserves right to reject any or all the tender or split the work among two or more tenderers without assigning any reason what so ever.
13. Other details may be obtained from detailed Tender notice/Tender documents/web site <http://bccl.cmpdi.co.in>
14. The Tender documents has been downloaded from the above mentioned web site, the tenderers are required to deposit along with their tender, a bank draft of any nationalized/scheduled commercial bank approved by Reserve bank of India payable at Dhanbad exclusively towards the cost of tender documents for the amount indicated as above, in the separate envelope marked as "Cost of Tender document". Any bank draft prepared after the schedule closure of sale of tender documents may be liable to rejection.
15. The contents of the tender documents available in our office, shall be deemed as authentic. The bidder will be required to submit an undertaking that they will accept the tender documents as available in the web site and their tender shall be rejected if any tempering is there in the tender documents thus submitted.
16. The tenderer must submit an affidavit on non judicial stamp paper for declaration that non of his relative/relatives are employee of BCCL, the documents submitted by the tenderer is genuine, authentic, true & valid and declaration that they have not been banned or delisted by any Govt. or Govt. Agency or PSUs.

Area Civil Engineer/EJ Area.

Copy to :-

1. The C.V.O., BCCL
2. All CGMs/GMs of Area of BCCL
3. The General Manager(Civil), CED/Koyla Nagar
4. H.O.D.(Admn.), BCCL/Koyla Nagar
5. The GM(System), BCCL – with a request to display this NIT in BCCL web site with download facility.
6. The Addl. GM(EJA)/The AFM(EJA)/The Area Survey officer
7. The Inspector I/C, CISF, Koyla Bhawan
8. The Inspector I/C., CISF, Ropeways Area/EWZ Area.
9. The Inspector I/C, CISF, EJ Area.
10. Notice Board, EJ Area.

Bill of quantity for the work, "Repairing of qtr.no. M/750 & M/1144 riverside of Sudamdih to shift the employee residing endanger zone area of EJA.

Sl. No.	Description of work	Unit	Quantity	Rate	Rate quoted by the Tenderer(In figure & word).
1.	White washing with lime to give an even shade: old work(two or more coat).	Sqm	276.58	4.10	
2.	Colour washing two coats complete..	Sqm	211.80	5.11	
3.	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats for old work. 6mm cement plaster of mix: 1:3 (1 cement : 3 fine sand)	Sqm	71.09	22.85	
4.	6mm cement plaster of mix: 1:3 (1 cement : 3 fine sand)	Sqm	9.35	62.15	
5.	Brick flat soling as per specification	Sqm	57.72	97.05	
6.	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25mm thick with 20mm nominal size stone aggregate	Sqm	120.11	141.11	
7.	Earth work in excavation by mechanical means(Hydraulic excavator)/manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil and disposal of surplus excavated soil as directed within a lead of 50m.	Cum	2.93	103.40	
8.	P/L. Cement concrete (1:4:8) as per specification	Cum	0.36	2296.15	
9.	B/W. In cement mortar 1: 6 in foundation	Cum	2.19	2007.00	
10.	Half B/W. (1:4) in S/S	Sqm	23.39	302.80	
11.	B/W. In cement mortar 1:6 in S/S.	Cum	0.61	2315.50	
12.	Grading of roof by PCC (1:2:4)	Cum	2.27	3314.95	
13.	Hot bitumen painting top of roof.	Sqm	74.55	63.00	
14.	12 mm. Cement plaster (1:6)	Sqm	191.70	67.65	
15.	S/F/F sal wood in frame work	Cum	0.76	30511.90	
16.	P/F. 2nd. Class 20 mm. teak shutters	Sqm	25.81	1360.95	

Name & Address of the Tenderer :

Details of Earnest money :

Area Civil Engineer(EJA)

Signature of the Tenderer with Date

Bill of quantity for the work," Sealing depillaring panel D5 in VI seam of preparatory stopping in
different level.

Sl. No.	Description of work	Unit	Quantity	Rate	Rate quoted by the Tenderer(In figure & word).
1.	1. Recess cutting in soft rock in floor.	Cum	4.83	162.65	
	2. B/W. In foundation 1:6..	Cum	7.93	2007.00	
	3. B/W. In S/S in 1:6	Cum	13.48	2315.50	
	4. 12 mm. Thick Cement plaster 1:6	Sqm	102.60	67.65	
	5. Carrying cost of materials				
	a). Bricks	%0	11000	79.53	
2.	1. Recess cutting in soft rock in floor	Cum	0.83	162.65	
	2. B/W. In foundation	Cum	4.10	2007.00	
	3. B/W. In S/S. 1:6	Cum	6.84	2315.50	
	4. 12 mm. Thick Cement plaster 1:6	Sqm	12.86	67.65	
	5. Carrying cost of materials				
	a). Bricks	%0	6000	79.53	
	b). Sand	Cum	3.00	42.61	
Add 12.5 % for Underground works on Estimated cost				10081.69	

Name & Address of the Tenderer :

Details of Earnest money :

Area Civil Engineer(EJA)

Signature of the Tenderer with Date

Bill of quantity for the work," Repair work in the qtr. Of Sri Shailendra Tumane, Mining Sardar at Pathardih and Sri Prayag Visawkarma Qtr. No. M/771, Haulage operator of incline mine Sudamdih at EJ Area.

Sl. No.	Description of work	Unit	Quantity	Rate	Rate quoted by the Tenderer(In figure & word).
1.	6 mm. Thick cement plaster (1:4) in ceiling	Sqm	43.58	62.15	
2.	P/F. 1 mm. Thick M.S. steel door	Sqm	5.01	1297.52	
3.	P/L. C.C. (1:2:4) on roof	Cum	3.73	3314.95	
4.	Removal of old tarfelt	Sqm	93.45	1.86	
5.	Bitumen painting on top of roof	Sqm	93.45	63.00	
6.	40 mm. Thick flooring (1:2:4)	Sqm	67.51	192.95	
7.	12 mm. Thick C.P. (1:6)	Sqm	88.00	67.65	
8.	W/W. Two coats	Sqm	472.00	4.10	
9.	Painting two coats	Sqm	72.00	22.85	
10.	Labour charges for jamming of doors	Each	03	354.45	
11.	Taking down old door's chowkhats	Each	03	56.60	
12.	Dismantling of old plaster & floor	Sqm	202.00	8.20	
13.	B/W. In C.M. (1:6) in S/S.	Cum	1.05	2315.50	

Name & Address of the Tenderer :

Details of Earnest money :

Area Civil Engineer(EJA)

Signature of the Tenderer with Date

Bill of quantity for the work," Repairing of compound wall and other petty repair works in the bungalow
of Dr. M.K.Saha located at riverside Sudamdih under EJ Area.

Sl. No.	Description of work	Unit	Quantity	Rate	Rate quoted by the Tenderer(In figure & word).
1.	E/work in excavation in foundation	Cum	9.85	103.40	
2.	Dressing the ground as per specification	% Sqm	50.18	512.10	
3.	B/W. In C.M. (1:6) in foundation	Cum	18.60	2007.00	
4.	B/W. In C.M. (1:6) in S/S.	Cum	5.73	2315.50	
5.	Providing glass panes complete	Sqm	1.49	427.60	
6.	Providing wash basin	Each	01	1332.90	
7.	Providing mirror as per specification	Each	01	493.65	
8.	P/F. A.C.Sheet roofing complete	Sqm	3.15	294.95	
9.	Providing bib cock 15 mm. Dia.	Each	04	207.00	
10.	Colour washing two coats on old work.	Sqm	620.00	5.11	
11.	Colour washing on new surface	Sqm	198.35	9.30	
12.	12 mm. Thick C.P. as per specification	Sqm	198.35	67.65	

Name & Address of the Tenderer :

Details of Earnest money :

Area Civil Engineer(EJA)

Signature of the Tenderer with Date

Bill of quantity for the work," Pables/Bouldres(Rejected materials) cleaning near mixing chamber of VI
seam Panel `P2`

Sl. No.	Description of work	Unit	Quantity	Rate	Rate quoted by the Tenderer(In figure & word).
1.	Supply of Labours	Each	477	149.00	
Add 12 % for under ground works 149.00 x 12 % of 149.00					

Name & Address of the Tenderer :

Details of Earnest money :

Area Civil Engineer(EJA)

Signature of the Tenderer with Date