# BHARAT COKING COAL LIMITED (A Subsidiary of Coal India Limited) OFFICE OF THE GENERAL MANAGER, EJ AREA P.O. : BHOWRA (DHANBAD)

#### Ref. No. : GM(EJA)/ACE/NIT/10-11/1130

Dated : 02.03.2011

#### **NOTICE INVITING TENDER**

Sealed Tender in two parts(Part-I & Part-II) on overall percentage rate basis are invited from experienced and eligible contractors for the following works

SI.No.	Name of work	Estimated work	Earnest	Cost of Tender	Time of
			money	paper	completion
1.	Repairing of qtr. no. M/333, 337, 347, 349 & 237 total 5 units Miners qtrs. at riverside of Sudamdih for shifting of qtr. under EJ Area.	235018.66	2350.00	100.00	Fifteen days

### AVAILABILITY OF TENDER DOCUMENTS From 08.03.2011 to 10.03.2011

Tender documents will be issued on all working days during working hours except on Sunday & holiday in the event of thr specified date for submission, opening of bids being declared a holiday the bids will be received opened on the appointed time on the next working day. The Tender document is also available on web site : <u>http://bccl:cmpdi:co:in</u> and can be downloaded.

### TIME & DATE IF RECEIPT/OPENING OF TENDER

The Tender will be received on 11.03.2011 from 10.00AM to 1.00PM in Tender box at (1). CISF post near Koyla Bhawan gate, Koyla Nagar, BCCL, Dhanbad. (2). CISF'S office of EJ Area (3). CISF's office, Ropeways Area and (4). CISF's office EWZ Area. and will be opened on 12.03.2011 at 11.00 AM in the office of the ACE/EJA.

### 1. ELIGIBILITY CRITERIA

a). The intending Tenderer must have in its name as a prime contractor experience of having successfully completed similar works during last 7(seven) years ending last day of month previous to the one in which bid applications are invited should be either

of the following :- (1). Three similar completed works each costing not less than 40 % of the estimated cost. Or (2). Two similar completed works each costing not less than 50 % of the estimated cost or (3). One similar completed work costing not less than 80 % of the estimated cost. **Similar work means : Building works for both works.** 

- b). Average annual financial turnover of civil works during the last three years, ending 31<sup>st</sup>. March of the previous financial, should be at least 30 % of the estimated cost.
- 2. The Tender documents can be had from the office of the undersigned during the period mentioned above on deposition of requisite cost of Tenser paper in form of cash bank draft of any nationalized bank/scheduled commercial bank approved by Reserve bank of India in favour of "Bharat coking coal limited" payable at Dhanbad.
- 3. Completed sealed Tender documents (Part I & II) should be submitted at the same time. **Part I** shall consists of terms & conditions of the Tender, additional terms and conditions if any, Technical bid and credentials. **Part II** shall consists of tender documents as sold to the tenderers duly filled in for rates, amount etc. i.e. price bid.

The earnest money deposit is to be submitted in a separate envelop subscribing "Earnest Money Deposit"

All three envelopes should be submitted in one sealed envelope.

The Part II will be opened only after The department is satisfied that the criteria fixed are fulfilled i.e. acceptance of Part I

- 4. The earnest money is to be deposited as per detail given in Tender documents.
- 5. TIN No. Is to be submitted.
- 6. The Tenderers have to submit Permanent Account no.(PAN) of Income Tax.
- 7. Conditional tenders will not be accepted.
- 8. Issuance of Tender document does not mean that the parties are considered qualified.
- 9. The experience as given in the eligibility criteria should be in the name and style in which tender is filled. The experience in the name of some other firm/company will not be considered for this purpose.
- 10. The validity of the tender will be 120 days from the date of opening of price bid

- 11. Complete set of Tender documents must be signed by the Tenderer. If any cutting/tempering found at the time of opening in the Tender documents, the tender will be rejected.
- 12. The Management of BCCL reserves right to reject any or all the tender or split the work among two or more tenderers without assigning any reason what so ever.
- 13.Other details may be obtained from detailed Tender notice/Tender documents/web site http://bccl.cmpdi.co.in
- 14.The Tender documents has been downloaded from the above mentioned web site, the tenderers are required to deposit along with their tender, a bank draft of any nationalized/scheduled commercial bank approved by Reserve bank of India payable at Dhanbad exclusively towards the cost of tender documents for the amount indicated as above, in the separate envelope marked as "Cost of Tender document". Any bank draft prepared after the schedule closure of sale of tender documents may be liable to rejection.
- 15. The contents of the tender documents available in our office, shall be deemed as authentic. The bidder will be required to submit an undertaking that they will accept the tender documents as available in the web site and their tender shall be rejected if any tempering is there in the tender documents thus submitted.
- 16. The tenderer must submit an affidavit on non judicial stamp paper for declaration that non of his relative/relatives are employee of BCCL, the documents submitted by the tenderer is genuine, authentic, true & valid and declaration that they have not been banned or delisted by any Govt. or Govt. Agency or PSUs.

Area Civil Engineer/EJ Area.

Copy to : -

- 1. The C.V.O., BCCL
- 2. All CGMs/GMs of Area of BCCL
- 3. The General Manager(Civil),CED/Koyla Nagar
- 4. H.O.D.(Admn.), BCCL/Koyla Nagar
- 5. The P.R.O./Koyla Bhawan with reques to publish in local Hindi news Paper.
- 6. The GM(System), BCCL with a request to display this NIT in BCCL web site with download facility.
- 7. The Addl. GM(EJA)/The AFM(EJA)/The Area Survey officer
- 8. The Inspector I/C, CISF, Koyla Bhawan
- 9. The Inspector I/C, CISF, Ropeways Area/EWZ Area.
- 10. The Inspector I/C, CISF, EJ Area.
- 11. Notice Board, EJ Area.

Bill ofquantity for the work," Repairing of qtr. no. M/333, 337, 347, 349 & 237 total 5 units Miners qtrs. at riverside of Sudamdih for shifting of qtr. under EJ Area.

.

SI. No.	Description of work	Unit	Quantity	Rate	Rate quoted by the Tenderer(In
					figure & word).
1.	White washing with lime to give an even shade: old work(two or more coat).	Sqm	703.53	4.10	
2.	Colour washing two coats complete	Sqm	512.73	5.11	
3.	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats for old work.	Sqm	194.05	22.85	
4.	Grading roof for water proofing treatment with Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size.	Sqm	6.38	3314.95	
5.	Painting top of roofs with bitumen of approved quality at 17kg per 10sqm impregnated with a coat of coarse sand at 60 cudm per 10sqm including cleaning the slab surface with brushes and finally with a piece of cloth lightly soaked in kerosene oil complete With residual type petroleum bitumen of penetration 80/100	Sqm	209.36	63.00	
6.	6mm cement plaster of mix: 1:3 (1 cement : 3 fine sand)	Sqm	112.50	62.15	
7.	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25mm thick with 20mm nominal size stone aggregate	Sqm	215.32	141.11	
8.	S/F/F Steel door as per specification	Sqm	25.09	1297.52	
9.	S/F/F Steel window as per specification(double leaf)	Sqm	5.58	1809.05	
10.	S/F/F Steel window as per specification(single leaf)	Sqm.	6.50	1842.17	
11.	Earth work in excavation by mechanical means(Hydraulic excavator)/manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil and disposal of surplus excavated soil as directed within a lead of 50m.All kinds of soil.	Cum	6.11	103.40	
12.	Brick work with F.P.S. bricks of class designation 50 in foundation and plinth in :cement mortar 1:6(1 cement: 6 coarse sand)	Cum	14.18	2007.00	
13.	Brick work with F.P.S. bricks of class designation 50 in superstructure above plinth level upto floor V level in all shapes and sizes in cement mortar 1:6(1 cement: 6 coarse sand)	Cum	6.56	2247.65	
14.	Earth work in excavation over areas (exceeding 30cm in depth. 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m; disposed earth to be levelled and neatly dressed All kinds of soil	Cum	41.84	101.85	
15.	Providing and fixing white vitreous china water closet squatting pan (Indian type) Long pattern W.C.Pan of size 580 mm	No.	5	534.60	
16.	Providing and fixing a pair of white vitreous china foot rests of standard pattern for squatting pan water closet:	Pair	5	112.85	
17	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors Sand cast iron S&S as per IS:3989	Each	5	544.30	
18.	Providing and fixing on wall face unplasticised - Rigid PVC rain water pipes conforming to IS : 13592 Type A including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion. (i) Single socketed pipes 110 mm. Dia.	metre	10.00	163.40	

# Page-2

19	Wiring to light point medium	Each	45	264.00	
20.	Wiring for fan point medium.	Each	10	264.00	
21.	Providing & fixing TP&N disconnection 32 Amp.	Each	5	768.00	
22.	12 mm cement plaster of mix : 1:6 (1 cement : 6 fine sand)	Sqm	365.00	67.65	

Name & Address of the Tenderer :

Details of Earnest money :

Area Civil Engineer(EJA)

Signature of the Tenderer with Date :