

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER, EJ AREA
P.O. : BHOWRA (DHANBAD)

Ref. No. : GM(EJA)/ACE/NIT/11-12/4102

Dated : 01.11.2011

NOTICE INVITING TENDER

Sealed Tender in two parts(Part-I & Part-II) on overall percentage rate basis are invited from experienced and eligible contractors for the following works

Sl.No.	Name of work	Estimated work	Earnest money	Cost of Tender paper	Time of completion
1.	Repair of Kali Mandir at Haripatti near Bhowra bazaar of EJ Area.	48475.00	485.00	100.00	Seven Days
2.	Partitioning of old binglow into two units at backside of W.T.P., Bhowra under EJ Area.	64618.00	646.00	100.00	Ten days
3.	Extension of existing transformer shed for installation of TSU 315 KVA, 3.3 KV/550 V at Bhowra(N) U/G mine, 7B incline.	118217.15	1185.00	100.00	Ten days
4.	Repairing/replacement of pipe with other miscellaneous works in drinking water pipe line at different places of Sudamdih under EJ Area.	54804.00	550.00	100.00	Ten days
5.	Internal electric wiring in qtr.no. M/724, 723, 721, 720, 701, 703, 801, 802, 688, 687, 750, 711, 712 at in between two railway line and Type II/84 & 19 at riverside Sudamdih.	70324.00	705.00	100.00	Ten days
6.	Repairing of main pucca drain of Su7damdih incline mine	54575.91	546.00	100.00	Ten days
7.	Reconstruction of new boundary wall of C.O.C.P. workshop, Sudamdih.	97743.43	980.00	100.00	Fifteen days
8.	Repair & maintenance work including changing of flush shutter and windows, sanitary works in suit no. 46 & 47 of Sri. S.N.Birni, electrical foreman in charge at main colony Sudamdih under EJA.	65924.15	660.00	100.00	Ten days

AVAILABILITY OF TENDER DOCUMENTS

From 09.11.2011 to 12.11.2011

Tender documents will be issued on all working days during working hours except on Sunday & holiday in the event of the specified date for submission, opening of bids being declared a holiday the bids will be received opened on the appointed time on the next working day. The Tender document is also available on web site : <http://bccl.gov.in> and can be downloaded.

TIME & DATE IF RECEIPT/OPENING OF TENDER

The Tender will be received on 15.11.2011 from 10.00AM to 1.00PM in Tender box at (1). CISF post near Koyla Bhawan gate, Koyla Nagar, BCCL, Dhanbad. (2). CISF'S office of EJ Area. (3). CISF's office of Ropeways Area. (4). CISF's office of EWZ Area and will be opened on 17.11.2011 at 4.00 PM in the office of the ACE/EJA.

1. ELIGIBILITY CRITERIA

- The intending Tenderer must have in its name as a prime contractor experience of having successfully completed similar works during last 7(seven) years ending last day of month previous to the one in which bid applications are invited should be either of the following :- (1). Three similar completed works each costing not less than 40 % of the estimated cost. Or (2). Two similar completed works each costing not less than 50 % of the estimated cost or (3). One similar completed work costing not less than 80 % of the estimated cost. **Similar work means : Building works for all works**
 - Average annual financial turnover of civil works during the last three years, ending 31st. March of the previous financial, should be at least 30 % of the estimated cost.
2. The Tender documents can be had from the office of the undersigned during the period mentioned above on deposition of requisite cost of Tenser paper in form of cash bank draft of any nationalized bank/scheduled commercial bank approved by Reserve bank of India in favour of "Bharat coking coal limited" payable at Dhanbad.

3. Completed sealed Tender documents (Part I & II) should be submitted at the same time. **Part I** shall consists of terms & conditions of the Tender, additional terms and conditions if any, Technical bid and credentials. **Part II** shall consists of tender documents as sold to the tenderers duly filled in for rates, amount etc. i.e. price bid.
The earnest money deposit is to be submitted in a separate envelop subscribing "Earnest Money Deposit"
All three envelopes should be submitted in one sealed envelope.
The Part II will be opened only after The department is satisfied that the criteria fixed are fulfilled i.e. acceptance of Part I
4. The earnest money is to be deposited as per detail given in Tender documents.
5. Latest sales tax clearance certificate must be submitted.
6. The Tenderers have to submit Photostat copy of Permanent Account no.card(PAN) of Income Tax.
7. Conditional tenders will not be accepted.
8. Issuance of Tender document does not mean that the parties are considered qualified.
9. The experience as given in the eligibility criteria should be in the name and style in which tender is filled. The experience in the name of some other firm/company will not be considered for this purpose.
10. The validity of the tender will be 120 days from the date of opening of price bid
11. Complete set of Tender documents must be signed by the Tenderer. If any cutting/tempering found at the time of opening in the Tender documents, the tender will be rejected.
12. The Management of BCCL reserves right to reject any or all the tender or split the work among two or more tenderers without assigning any reason what so ever.
13. Other details may be obtained from detailed Tender notice/Tender documents/web site <http://bccl.gov.in>
14. The Tender documents with prescribed format of Bank A/C. No. can be downloaded from the above mentioned web site, the tenderers are required to deposit along with their tender, a bank draft of any nationalized/scheduled commercial bank approved by Reserve bank of India payable at Dhanbad exclusively towards the cost of tender documents for the amount indicated as above, in the separate envelope marked as "Cost of Tender document". Any bank draft prepared after the schedule closure of sale of tender documents may be liable to rejection.
15. The contents of the tender documents available in our office, shall be deemed as authentic. The bidder will be required to submit an undertaking that they will accept the tender documents as available in the web site and their tender shall be rejected if any tempering is there in the tender documents thus submitted.
16. The tenderer must submit an affidavit on non judicial stamp paper for declaration that non of his relative/relatives are employee of BCCL, the documents submitted by the tenderer is genuine, authentic, true & valid and declaration that they have not been banned or delisted by any Govt. or Govt. Agency or PSUs.
17. The Tenderer must submit his Bank A/C. No. in the prescribed format. The prescribed format will be issued with the Tender document.
18. Any affidavit submitted by the Tenderer must be in "Non Judicial stamp paper"
19. The participants in the tender or their authorised representatives must present at the time of opening. In case of absent their envelopes will not be opened.

Area Civil Engineer/EJ Area.

Copy to :-

1. The C.V.O., BCCL
2. All CGMs/GMs of Area of BCCL
3. The General Manager(Civil), CED/Koyla Nagar
4. H.O.D.(Admn.), BCCL/Koyla Nagar
5. The GM(System), BCCL
6. The Addl. GM(EJA)/The AFM(EJA)/The Area Survey officer
7. The Inspector I/C, CISF, Koyla Bhawan
8. The Inspector I/C., CISF, Ropeways Area/EWZ Area.
9. The Inspector I/C, CISF, EJ Area.
10. Notice Board, EJ Area.

Estimate for the work," Repair of Kali Mandir at Haripatti near Bhowra bazaar of EJ Area.

Sl.No.	Description of Item	Quantity	Unit	Rate	Rate quoted by the Tenderer(In figure & word).
1.	Dismantling brick work	1.52	cum	310.75	
2.	Dismantling R.C.C. roof	1.30	cum	368.45	
3.	Brick work in superstructure in 1:6	3.39	Cum	2315.50	
4.	A.C.Sheet roofing	16.25	Sqm.	153.65	
5.	Earth filling	5.09	Cum.	45.70	
6.	Brick work in foundation/plinth in 1:6	2.35	Cum.	2007.00	
7.	12 mm. thick cement plaster 1:6	150.86	Sqm	67.65	
8.	Brick on edge soling.	66.88	sqm	195.70	
9.	40 mm. thick cement concrete flooring.	20.43	Sqm.	192.95	
10.	Snowcem.	150.86	Sqm.	30.80	
11.	P.C.C. 1:2:4 encasing steel.	0.07	Cum.	4953.40	

Name & Address of the Tenderer :

Details of Earnest money :

Area Civil Engineer(EJA)

Signature of the Tenderer with Date

Estimate for the work," Partitioning of old binglow into two units at backside of W.T.P., Bhowra under EJ Area.

Sl.No.	Description of Item	Quantity	Unit	Rate	Rate quoted by the Tenderer(In figure & word).
1.	Dismantling brick work	2.18	cum	310.75	
2.	Brick work in superstructure in 1:6	13.01	cum	2315.50	
3.	25 mm. thick cement concrete flooring.	30.83	Sqm	141.60	
4.	R.C.C. 1:2:4 in band	0.34	Cum.	3673.85	
5.	Precast R.C.C. slab	0.56	Cum.	6002.80	
6.	Tor. Steel reinforcement	63.00	Kg.	42.70	
7.	Steel door	3.58	Sqm	1297.52	
8.	Steel windows.	0.84	Sqm.	1809.05	
9.	12mm. thick cement plaster (1:3) with punning.	17.56	Sqm.	107.80	
10.	12mm. thick cement plaster in 1:6.	115.40	Sqm.	67.65	
11.	White washing.	806.78	Sqm.	4.10	
12.	Painting	130.30	Sqm.	22.85	

Name & Address of the Tenderer :

Details of Earnest money :

Area Civil Engineer(EJA)

Signature of the Tenderer with Date

Estimate for the work," Extension of existing transformer shed for installation of TSU 315 KVA, 3.3 KV/550 V at Bhowra(N) U/G mine, 7B incline.

Sl.No.	Description of Item	Quantity	Unit	Rate	Rate quoted by the Tenderer(In figure & word).
1.	Earth work in excavation	20.97	cum	103,40	
2.	P.C.C. in 1:3:6	5.02	cum	2713.05	
3.	Brick work in 1:6 in foundation & plinth.	22.47	Sqm	2007.00	
4.	P.C.C. 1:2:4	10.14	Cum.	3257.45	
5.	Brick on edge soling	19.50	Sqm.	191.50	
6.	12mm. thick cement plaster in 1:6.	64.10	Sqm.	67.65	
7.	Structural steel work(labour)	1725.67	Kg.	6.75	
8.	Labour cost for laying G.I.Sheet.	49.05	Sqm.	56.16	
9.	Painting on structural steel.	80.00	Sqm.	22.85	

Name & Address of the Tenderer :

Details of Earnest money :

Area Civil Engineer(EJA)

Signature of the Tenderer with Date

Bill of quantity for the work," Repairing/replacement of pipe with other miscellaneous works in drinking water pipe line at different places of Sudamdih under EJ Area.

Sl. No.	Description of work	Unit	Quantity	Rate	Rate quoted by the Tenderer(In figure & word).
1.	P/Laying PVC Pipe complete				
	a). 15 mm. dia.	metre	51.37	59.25	
	b). 20 mm. dia	metre	83.54	72.90	
	c). 50 mm. dia.	metre	6.00	182.26	
2.	Providing G.I.Union complete				
	a). 15 mm. dia.	no.	02	75.90	
	b). 20 mm. dia	no.	05	96.80	
	c). 25 mm. dia.	no.	10	107.25	
	d) 50 mm. dia.	no.	12	235.60	
3.	Providing & fixing 15 mm. dia. bib cock.	metre	179.72	97.69	
4.	Providing connection complete	no.	13	166.05	
5.	Providing gate valves				
	a). 15 mm. dia.	no.	05	228.35	
	b). 20 mm. dia	no.	01	333.25	
	c). 25 mm. dia.	no.	01	285.50	
	d). 80 mm. dia.	no.	04	1369.25	
6.	P/F G.I.Pipe 25 mm. dia.	metre	3.35	179.65	
7.	Providing & fixing W.C.Pan 580 mm.	Each.	01	534.60	
8.	Providing & fixing low level cistern(10 lts)	Each.	01	709.75	
9.	Providing lead joint 150 mm. dia.	Each	12	123.30	
10.	Providing lead joint 100 mm. dia.	Each	16	82.25	
11.	Supplying lead	Quintal.	1.10	6742.20	
12.	Providing & fixing 100mm. dia. collar	Each	01	2893.35	
13.	Providing & fixing wash basin complete.	Each	01	596.20	
14.	Dismantling G.I.Pipe				
	a). 15 mm.to 40 mm dia.	Quintal	0.40	6742.20	
	b). Above 40 mm. dia.	Each	01	139.75	

Name & Address of the Tenderer :

Details of Earnest money :

Area Civil Engineer(EJA)

Signature of the Tenderer with Date

Estimate for the work," Internal electric wiring in qtr.no. M/724, 723, 721, 720, 701, 703, 801, 802, 688, 687, 750, 711, 712 at in between two railway line and Type II/84 & 19 at riverside Sudamdih.

Sl.No.	Description of Item	Quantity	Unit	Rate	Rate quoted by the Tenderer(In figure & word).
1.	Wiring for light/fan point	166	No.	305.00	
2.	Supplying & fixing suitable G.I.Box with 6mm 15/6 amp. Socket.	46	No.	161.00	
3.	Providing & fixing disconnection fuse switch as per specification.	16	No.	768.00	

Name & Address of the Tenderer :

Details of Earnest money :

Area Civil Engineer(EJA)

Signature of the Tenderer with Date

Estimate for the work," Repairing of main pucca drain of Su7damdih incline mine

Sl.No.	Description of Item	Quantity	Unit	Rate	Rate quoted by the Tenderer(In figure & word).
1.	Brick work in 1:6 in foundation & plinth.	18.625	Cum.	2007.00	
2.	12 mm. thick cement plaster 1:4 with punning	114.47	Sqm.	97.90	
3.	Providing & laying cement concrete 1:2:4 as per specification.	16	Cum.	3194.10	

Name & Address of the Tenderer :

Details of Earnest money :

Area Civil Engineer(EJA)

Signature of the Tenderer with Date

Estimate for the work," Reconstruction of new boundary wall of C.O.C.P. workshop, Sudamdih.

Sl.No.	Description of Item	Quantity	Unit	Rate	Rate quoted by the Tenderer(In figure & word).
1.	Dismantling brick work.	4.03	cum	310.75	
2.	Brick flat soling complete	5.02	Sqm	97.05	
3.	Providing & laying C.C. 1:3:6	1.33	Cum	2560.20	
4.	Brick work in cement mortar 1:6 in F/P.	15.25	Cum.	2007.00	
5.	Brick work in cement mortar 1:6 in superstructure.	18.18	Cum.	2315.50	
6.	Brick work 7 cm. thick in 1:3 complete.	9.89	Sqm.	214.85	
7.	P/L cement concrete 1:2:4	0.07	Cum.	3194.10	
8.	12 mm. thick cement plaster 1:6	164.47	Sqm.	67.65	
9.	Colour washing two coats	164.47	Sqm.	9.30	
10.	12mm. thick cement plaster 1:4 with punning.	41.82	Sqm.	97.90	

Name & Address of the Tenderer :

Details of Earnest money :

Area Civil Engineer(EJA)

Signature of the Tenderer with Date

Estimate for the work," Repair & maintenance work including changing of flush shutter and windows, sanitary works in suit no. 46 & 47 of Sri. S.N.Birni, electrical foreman in charge at main colony Sudamdih under EJA.

Sl.No.	Description of Item	Quantity	Unit	Rate	Rate quoted by the Tenderer(In figure & word).
1.	White washing two coats	331.13	Sqm.	4.10	
2.	Distemping two coats with oil bound.	158.36	Sqm.	14.90	
3.	Painting two coats	62.10	Sqm.	22.85	
4.	P/L. C.C. 1:2:4 on roof grading.	5.75	Cum.	3314.95	
5.	Bitumen painting on roof	143.86	Sqm.	63.00	
6.	6 mm. thick cement plaster 1:3	53.15	Sqm.	62.15	
7.	12 mm. thick cement plaster 1:6	35.30	Sqm.	67.65	
8.	P/F. 35mm. thick flush shutter.	6.69	Sqm.	1099.65	
9.	P/F. glazed window (2 nd . Class teakwood).	2.60	Sqm.	1718.30	
10.	Dismantling door & window	05	No.	56.60	
11.	Fixing of door.	03	No.	354.45	
12.	Fixing of window.	02	No.	214.20	
13.	B/W.in C.M. 1:6 in superstructure.	2.70	Cum.	2007.00	
14.	Providing & fixing W.C.Pan 580mm size.	01	No.	398.40	
15.	Providing & fixing self cleaning trap 100mm. dia.	01	No.	544.30	
16.	P/F. 110mm. dia. PVC waste pipe	30.00	Metre	163.40	
17.	P/F. foot rest 250x135x25 mm. size.	01	Pair.	112.85	
18.	P/F. 110 mm. dia. Bend.	09	No.	134.20	
19.	P/F. 110 mm. dia. Shoe.	03	No.	263.10	

Name & Address of the Tenderer :

Details of Earnest money :

Area Civil Engineer(EJA)

Signature of the Tenderer with Date