

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER, EJ AREA
P.O. : BHOWRA (DHANBAD)

Ref. No. : BCCL/Civil/EJA/Tender/2011-12/4111

Date : 02/11//2011

TENDER NOTICE

Sealed Tender on percentage basis (Above/Below) on prescribed bill of quantity is hereby invited for the following job/jobs from the resourceful and experienced contractors which will be received and opened on 12.11.2011. from 10.00 AM to 1.00 PM. and 15.11.2011 at 4.00 P.M. respectively. The Tender will be opened in presence of the Tenderers/Quotationers or their authorized representatives. Details are as below : -

Sl.No.	Name of work	Estimated Cost(In Rs.)	Earnest Money (In Rs.)	Time of Completion
1	Removal of ash/garbage from Hari Patti near transformer at Uppar Bazar,Bhowra.	Rs.17,152.00	Rs.175.00	7 days
2	White/Colour washing,painting with electrical wiring in the Qtrs.of Sri Raj Kr.Prasad,Bh(S) located atg New Qtrs.Bhowra under EJA.	Rs.16,461.25	Rs.165.00	7 days
3.	Repairing & heightening of water reservoir at TOP Bhowra.	Rs. 9,989.00	Rs.100.00	7 days
4.	Reapir of "Madarsa Bldg."at 12 No.Bhowra	Rs.20,777.88	Rs.210.00	7 days.
5.	Repair work in the Qtrs of Sri Ramashis Singh at Gourkhuti under EJ Area.	Rs.14,044.00	Rs.140.00	7 days
6.	Repair work in the Qtrs.of Sri Gopal Roy at 7B colony,Bhowra under EJ Area.	Rs.28.309.00	Rs.285.00	7 days
7.	Repairing of septic tank of the Qtrs.of Sri B.Jha,SE(E&M),Patherdih Q.No.2C/10 at Main colony,Sudamdih.	Rs.22,026.87	Rs.220.00	7 days
8.	Roof repairing of garage and inor flooring work in W,C. room in Main hospital Sudamdih,EJA.	Rs.15,226.04	Rs.155.00	7 days
9.	Repair & Maint.work in the Qtrs.of Sri Lalit Narayan Pd. "B" type at 7 No.Bhowra,EJA.	Rs.19,541.00	Rs.200.00	7 days.
10	General Maint.work in Kali Mandirf at Kumhar Basti Bhowra under EJA.	Rs. 6,991.00	Rs.70.00	7 days
11	White washing ,colour washing & painting of Gourkhuti Sheo Mandir under Ej Area	Rs.7,955.00	Rs.80.00	7 days
12	Repair work in the newly allotted Qtrs. to Sri Ayodhya Pd. At Durga Mandir colony,Bhowra,EJA.	Rs.25,956.00	Rs.260.00	7 days
13	Construction of retaining wall 1.0 M thick in IV seam at Sudamdih Incline Mine.	Rs.29,422.75	Rs.295.00	1 month

TERMS AND CONDITIONS The estimate & specification of the work can be obtained from the office or can be downloaded from BCCL web site <http://bccl.gov.in> from 08.11.2011 to 10.11.2011. Any other information can also be obtained from the undersigned.

2. The quotationer have to submit Photo stat copy of PAN Card and latest sales tax clearance certificate
3. **The tender has to deposit E.M. as stated above with A.F.M., EJ Area in cash . The Money receipt of EM should be attached** with the tender. The tender without earnest money will be out rightly rejected.
5. The quotationer must submit an affidavit with their offer as per civil engg. Manual along with certification that they have not been banned or delisted by any Govt. Agencies or PAUs.
6. The contractors have to submit Permanent Account Number(PAN) income tax and TIN.
7. Authority reserves the rights to reject any or all the tenders received or split up and distribute the work between more than one contractor without assigning any reason what so ever
8. The rate should be quoted inclusive all taxes and royalty. The validity period of the tender will be 120 days , commenced from the date of opening of the Tender.
9. Materials required for the work are to be arranged / procured by the contractor at his own cost.
10. In case rate are not acceptable, the offer may be rejected.
11. The contractor should abide by the labour Act of Govt. of India.
12. Conditional tender will not be entertained.
13. The Tenderer must sumit his Bank A/C. No. in the prescribed format. The prescribed format can be obtained from the office of the Area Civil Engineer(EJA). In case of absence of the prescribed format of Bank A/C. No. tender will not be entertained.
14. Any affidavit submitted by the Tenderer must be in "Non Judicial stamp paper"
19. The participants in the tender or their authorised representatives must present at the time of opening. In case of absent their document will not be entertained.

Distribution : -

1. The C.V.O.,BCCL
2. All CGMs/GMs of Area of BCCL
3. The General Manager(Civil),CED/Koyla Nagar
4. H.O.D.(Admn.), BCCL/Koyla Nagar
5. The GM(System), BCCL
6. The Addl. GM(EJA)/The AFM(EJA)/The Area Survey officer(EJA)
7. The Inspector I/C, CISF, Koyla Bhawan
8. The Inspector I/C. CISF, Ropeway Area/EWZ Area.
9. The Inspector I/C, CISF, EJ Area.
10. Notice Board, EJ Area.

Area Civil Engineer/EJA

Removal of ash/garbage from Hari Patti near transformear at Uppar Bazar,Bhowra.

Sl.No.	Description of work	Quantity	Unit	Rate	Rate to be quoted on Ove
1.	Removing ash/garbage	179.90	P.Cum.	43.80	
2.	Transporting ash/garba 1.00 KM lead.	215.80	P.Cum.	42.97	

Name & address of the tenderer

Details of Earnest Money

Signature of the tenderer

D a t e

Area Civil Engineer/EJA

Bill of quantity for repair and heightening of Water reservoir at TOP Bhowra.

Sl.No.	Description of work	Quantity	Unit	Rate	Rate to be quoted on overall %age.
1.	Dismantling of Brick work	2.10	P.Cum.	310.75	
2	Half brick work (1:4)	18.67	P.Sqm.	257.80	
3.	12 mm thick Cement plaster (1:4)with punning.	34.56	P.Sqm.	97.90	
4.	25mm thick cement concrete flooring	8.08	P.Sqm.	141`.11	

Name & address of the tenderer

Details of Earnest Money

Signature of the tenderer

Date

Area Civil Engineer/EJA

Bill of quantity for white washing/colour washing, painting with Internal electrical wiring in the Quarters of Sri Raj Kumar Prasad, Bh(S) located at new Qtrs. colony Bhowra under EJ Area.

Sl.No.	Description of work	Quantity	Unit	Rate	Rate to be quoted on overall %age basis
1.	Wiring of light/fan point.	36.00	Each	305.00	
2	Wiring for 6 pin 15/16 Amp.socket.	11.00	Each	161.00	
3..	White washing two coats	300.00	P.Sqm.	4.10	
4.	Colour washing two coats	150.00	P.Sqm.	5.11	
5.	Painting two coats complete.	75.00	P.Sqm.	22.85	

Name & address of the tenderer

Details of Earnest Money

Signature of the tenderer

Date

Area Civil Engineer/EJA

Bill of quantity for repair work in the Qtrs.of Sri Gopal Roy at 7B colony,Bhowra under EJ Area.

Sl.No.	Description of work	Quantity	Unit	Rate	Rate to be quoted overall %age basis.
1.	Removing old roof treatment	1.84	P.Cum.	368.45	
2.	Roof grading with P.C.C.	1.84	P.Cum.	3314.95	
3.	Bitumen painting on roof.	75.80	P.Sqm.	63.00	
4.	A.C.sheet providing	5.57	P.Sqm.	294.95	
5.	12mm thick CP (1:6)				
6.	6 mm thick ceiling plaster (1:3)	60.94	P.Sqm.	67.65	
		10.00	P.Sqm.	62.15	
7.	25mm thick cement concrete flooring	40.13	P.Sqm.	141.11	
8.	Pre cast RCC slab	0.31	P.Cum	6002.80	
9.	Tor steel reinforcement	25.65	P.Kg.	42.70	
10.	White washing	200.00	P.Sqm.	4.10	
11.	Painting	30.00	P.Sqm.	22.85	
12.	Removing tree roots	3.00	Each	81.70	

Name & address of the tenderer

Details of Earnest Money

Signature of the tenderer

Date

Area Civil Engineer/EJA

Bill of quantity for repair work in the Qtrs.of Sri Ramashis Singh ast Gourkhuti under EJ Area.

Sl.No.	Description of work	Quantity	Unit	Rate	Rate to be quoted on overall %age basis
1.	25mm thick cement concrete flooring.	42.31	P.Sqm	141.60	
2.	12mm C.P.(1:6)	30.00	P.Sqm..	67.65	
3.	12mm C.P.(1:4)punning	8.45	P.Sqm.	97.90	
4	A.C.sheet roofing	5.43	P.Sq.m.	153.65	
5.	Brick wwork 1:6 in F&P.	0.53	P.Cum.	2007.00	
6.	6mm ceiling plaster (1:3)	5.00	P.Sqm.	62.15	
7.	White washing	240.00	P.Sqm.	6.75	
8.	Painting	37.95	P.Sqm.	22.85	
9.	Cleaning of septic latrine	1 No.	Each	500.00	

Name & address of the tenderer

Details of Earnest Money

Signature of the tenderer

D a t e

Area Civil Engineer/EJA

Bill of quantity for repair of Madarsa Building at 12 No.Bhowra under EJ Area.

Sl.No.	Description of work	Quantity	Unit	Rate	Raste to be quoted on overall %age basis.
1.	Brick on edge soling	23.96	P.Sqm.	191.50	
2.	25mm cement concrete flooring	23.96	P.Sqm.	141.11	
3.	Grading roof with PCC(1:2:4)	0.72	P.Sqm.	3314.95	
4.	Wood work in choukhat	0.07	P.Cum.	30511.90	
5.	30mm thick panelled shutter	3.79	P.Sqm.	810.90	
6.	12mm C.P(1:6)	20.00	P.Sqm.	67.65	
7.	Dry distemper	124.20	P.Sqm.	12.35	
8.	Painting	22.27	P.Sqm	22.85	
9.	Bitumen painting on roof surface.	28.84	P.Sqm.	63.00	

Name & address of the tenderer

Details of Earnest Money

Signature of the tenderer

D a t e

Area Civil Engineer/EJA

Bill of quantity for white washing and painting of Gourkhuti Shiv Mandir under EJ Area.

Sl.No.	Description	Quantity	Unit	Rate	Rate to be quoted on over %age Basis.
1.	Colour washing	333.45	P.Sqm.	4.87	
2.	Removing old Colour wash	333.45	P.Sqm.	3.20	
3.	Oil bound distemper.	66.52	P.Sqm.	13.85	
4.	Removing old distemper	66.52	P.Sqm.	4.25	
5.	Painting on old surface	58.99	P.Sqm.	22.85	
6.	Skirting paint	16.44	P.Sqm.	25.85	
7.	Patch repair wall plaster (1:4)	20.00	P.Sqm.	114.35	

Name & address of the tenderer

Details of Earnest Money

Signature of the tenderer

D a t e

Area Civil Engineer/EJA

Bill of quantity for general Maintenance in Kali Mandir at Kumhar Basti,Bhowra under E.J. Area.

Sl. No.	Description of work	Quantity	Unit	Rate	Rate to be quoted on overall %age basis.
1	Removing distemper	107.57	P.Sqm.	4.25	
2.	Oil bound distemper	107.57	P.Sqm.	14.90	
3.	White washing	58.71	P.Sqm.	4.10	
4.	Colour washing	110.92	P.Sqm.	4.87	
5.	Painting on old work	31.21	P.Sqm.	22.85	
6.	Patch repair in wall plaster (1:4)	15.00	P.Sqm.	114.35	
7.	Half brick work (1:4)	6.68	P.Sqm.	257.80	

Name & address of the tenderer

Details of Earnest Money

Signature of the tenderer

D a t e

Area Civil Engineer/EJA

Bill of quantity for repair work in the Qtr. of Sri Lalit Narayan Prasad 'B'
type Qtrs. at 7 No. Bhowra under EJ Area.

Sl.No.	Description of work	Quantity	Unit	Rate	Rate to be quoted on over all % age basis.
1.	Dismantling old P.C.C.	1.48	P.Cum.	310.75	
2.	Roof grading with PCC	1.48	P.Cum.	3314.95	
3.	Neat cement punning	59.16	P.Sqm.	21.40	
4.	6mm ceiling plaster (1:3)	11.70	P.Sqm.	62.15	
5.	12mm C.P.(1:6)	9.806	P.Sqm.	67.65	
6.	PVC door frame	4.57	P.Mtr.	141.00	
7.	PVC door shutter	3.18	P.Sqm.	2190.50	
8.	12mm c.P.(1:4) with punning.	5.00	P.Sqm.	97.90	
9.	White washing	250.00	P.Sqm.	4.10	
10.	Painting	53.41	P.Sqm.	22.85	
11.	Half brick work(1:4)	4.55	P.Sqm.	257.80	

Name & address of the tenderer

Details of Earnest Money

Signature of the tenderer

Date

Area Civil Engineer/EJA

Bill of quantity for repair work in the newly allotted Qtrs.to Sri Ayodhya Pd.Durga Mandir colony,Bhowra under E.J. Area.

Sl.No.	Description of work	Quantity	Unit	Rate	Rate to be quoted on overall % age basis
1.	Dissmantling of PCC roof.	1.49	P.Cum.	368.45	
2.	Roof grading work with PCC	1.49	P.Cum.	3314.95	
3.	Bitumen painting on roof	61.31	P.Sqm.	63.00	
4.	12mm CP (1:6)	25.00	P.Sqm.	67.65	
5.	25mm thick cement concrete	29.72	P.Sqm.	141.60	
6.	Dismantling of Pre cast RCC Slab.	0.347	P.Cum.	537.55	
7.	Brick (1:6) in F&P.	0.466	P.Cum.	2007.00	
8.	12mm CP (1:4) with punning	5.20	P.Sqm.	97.90	
9.	P & F steel door	1.67	P.Sqm.	1297.52	
10.	White washing	200.00	P.Sqm.	4.10	
11.	Painting	38.04	P.Sqm.	22.85	
12.	Pre cast RCC slab	0.347	P.Cum.	6002.80	
13.	Tor steel reinforcement	24.00	P.Kg.	42.70	
14.	110 mm PVC pipe	3.00	P.Mtr.	163.40	
15.	75 mm PVC pipe	2.50	P.Mtr.	95.00	
16.	PVC Cowel.	1.00	Each	192.25	
17.	W.C.Pan	1.00	Each	534.60	
18.	Foot rest	1 .00	Pair	111.70	
19.	'P' trap	1.00	Each	544.30	

Name & address of the tenderer

Details of Earnest Money

Signature of the tenderer

D a t e

Area Civil Engineer/EJA

Bill of quantity for construction of retaining wall IV seam at Sudamdih Incline Mine.

Sl.No.	Description	Quantity	Unit	Rate	Rate to be quoted on Overall %age basis.
1	Recess cutting floor In stone	1.92	P.Cum.	332.45	
2.	Side cutting in coal	3.20	P.Cum.	162.65	
3.	Cement brick work in Foundation	6.40	P.Cum.	2007.00	
4.	Cement brick work in superstructure	5.76	P.Cum.	2247.65	
5.	Cement plaster with Punning both side	18.48	P.Sqm.	97.90	
6.	Carrying cost of Materials.				
	(a) Bricks	6200	P.%0	79.53	
	(b) Sand	4.00	P.Cum.	42.61	

Name & address of the tenderer

Details of Earnest Money

Signature of the tenderer

Date

Area Civil Engineer/EJA

Bill of quantity for repairing of garrage and minor flooring works in W.C.rooms in main Hospital Sudamdih,EJ Area.

Sl.No	Description of work	Quantity	Unit	Rate	Rate to be quoted on Overall %age basis.
1.	Providing for four coarse Bitumen felt as pear spec.	41.15	P.Sqm.	184.80	
2.	25mm thick cement concret (1:2:4) in flooring campus.	31.78	P.Sqm.	141.10	
3.	40mm thick flooring 1:2:4 As per spec.	16.26	P.Sqm.	192.95	

Name & address of the tenderer

Details of Earnest Money

Signature of the tenderer

Date

Area Civil Engineer/EJA

Bill of quantity for repairing of septic tank of the Qtrs. of Sri B.Jha S.E.(E&M) Patherdih

Colliery Bungalow No.2C/10 located at Main colony Sudamdih under EJ Area.

Sl.No.	Description of work	Quantity	Unit	Rate	Rate to be quoted On overall %age basis.
1.	Earth work excavation in Foundation.	10.19	Cum.	103.40	
2.	Brick flat soling as per spec.	5.57	P.Sqm.	110.97	
3.	Providing & laying cement Concrete (1:3:6) as per Spec.	0.42	P.Cum.	2713.05	
4.	Brick work in cement Mortar (1:6) in Foundation	4.66	P.Cum.	2007.00	
5.	12mm thick cement Plaster (1:4) with punning.	26.41	P.Sqm.	97.90	
6.	Pre cast RCC slab (1:2:4) as Per spec.	0.56	P.Cum.	4880.15	
7.	Providing reinforcement For RCC.	44.80	P.Kg.	41.50	
8.	Providing & fixing 80 mm Dia PVC pipe	9.14	P.Mtr.	293.81	

Name & address of the tenderer

Details of Earnest Money

Signature of the tenderer

Date

Area Civil Engineer/EJA

