

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Ltd)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Ref. No. BCCL/XII/ACE/QTN/2011-12/21/ 1309

Dates: 05.07.2011

QUOTATION NOTICE

Sealed Quotations on percentage rate basis are invited from the bonafide & experienced contractors for the following works:

Sl.No.	Name of the work	Estimated cost	Earnest Money	Time of completion
1.	Repairing & replacement of G.I. pipe from main road side of Lalbazar to filter plant at DOCP.	Rs. 52082.00	Rs. 521.00	20 days
2.	Maintenance of GM's office at Begunia.	Rs. 36785.00	Rs. 368.00	10 days
3.	Closing of 2 (two) nos. approach of abandoned mines at near sand bunker and near W.T.P. plant of Victoria west colliery (Re-Quotation).	Rs. 9407.00	Rs. 95.00	10 days
4.	Repairing of roof, heightening of wall, making boundary wall & providing iron gate for electrical sub-station of DOCP.	Rs. 58942.00	Rs. 590.00	30 days
5.	Cleaning of workshop premises, drains and 2 nos. culverts of jore with approaches at DBOCP.	Rs. 52433.00	Rs. 525.00	20 days
6.	Cleaning of drain, ash and garbages in CMWO colony of Laikdih.	Rs. 68723.00	Rs. 688.00	20 days

Terms and conditions:

- Completed sealed **Quotations will be received on 18.07.2011 up to 3.00 P.M.** at the following places. Quotation may opt any one place to submit their quotation as per their convenience.
 - In the office of the General Manager, C.V. Area-XII, AT-Begunia, P.O –Barakar(W.B.)
 - At BCCL H.Q. i.e. C.I.S.F. post, near Koyala Bhawan gate, Koyala Nagar, Dhanbad.
 - Office of the ACE, CCWO, W.W.Z. Area, Saraidhela, Dhanbad.
 - Office of the ACE, CHD, Jagjiban Nagar, Dhanbad.
- Quotations will be opened on 20.07.2011 at 11.30 A.M.** in the office of the Area Civil Engineer, C.V. Area-XII, AT-Begunia, P.O –Barakar(W.B.).
- Specification of work shall be governed by DSR-2007 & C.P.W.D specification.
- Terms and conditions as per C.I.L. C.E. manual shall be applicable against the quotations submitted against this Quotation Notice.
- Completed sealed Quotations shall consist of (1) EMD in the shape of cash receipt obtained from the finance deptt. C.V. Area-XII or DD from any Scheduled/Nationalised Bank, (2) Experience certificate, (3) Copy of Pan card, (4) Copy of VAT/Sales Tax clearance certificate along with VAT/Sales Tax registration No.(TIN), (5) Declaration and (6) EFT (Electronic Fund Transfer) & ECS (Electronic Clearance System) as per the format issued along with the Tender paper and (7) BOQ along with quoted rate by the Tenderer.
- The quoted rate shall include all taxes and levies.
- Statutory deductions for Income Tax and Sales Tax shall be made as per Rules and notifications.
- The contractor has to abide by the Rules of Contract Labour Regulation & Abolition Act-.
- Validity of tender shall be 120 days from the date of opening of the tender.
- Interested parties can collect the BOQ and other related papers of the Quotation from the office of the Area Civil Engineer, C.V. Area-XII, AT-Begunia, P.O –Barakar(W.B.). **from 12.07.2011 to 16.07.2011 during** office hours except Sunday and Holiday. BOQ and other relevant pages (Declaration & EFT form) can be down loaded from BCCL website- <http://www.bccl.gov.in>
- No conditional tender shall be accepted.
- The contractors have to be acquainted with the site condition
- Unless otherwise mentioned, no material will be issued by the department.
- Successful tender has to deposit 5% Performance Security (including 1% EMD) and another 5% Security Deposit will be deducted from the Running Account/ Final Bill.
- The management of BCCL reserves right to reject any or all tender or split the work among two or more tenderers without assigning any reasons whatsoever.

Area Civil Engineer
Chanch Victoria Area-XII

Copy to :-

- GM, Chanch Victoria Area-XII.
- GM (Civil), BCCL, Koyla Nagar.
- All CGM/GM of Areas/Projects under BCCL.
- Addl. GM, Chanch Victoria Area-XII.
- A.F.M., Chanch Victoria Area-XII.
- All P.O.s of Chanch Victoria Area-XII.
- Cashier, C.V. Area-XII
- Incharge,, CIFS Post, Koyala Bhawan gate, Koyala Nagar,
- Assistant Commandant, CIFS, C.V. Area-XII-with 2 copies of NIT for displaying on Notice Board.
- Builders Association of India, Central Akashkinaree Kanta, Katras Garh, Dhanbad-828113.
- ACE CCWO, W.W.Z Area saraidhela, Dhanbad.
- ACE CHD, jagiban Nagar, Dhanbad
- Notice Board.**

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Ltd)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII

1. Name of Work: **“Repairing & replacement of G.I. pipe from main road side of Lalbazar to filter plant at DOCP.”**

2. Name of Tenderer :

3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/ /

Date: 04.07.2011

5. Details of E.M.D. No:

Date:

BILL OF QUANTITY: (Sl. No. 1)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.44.2	Dismantling G.I pipes (external work) including excavation and refilling trenches after taking out the pipes, manually /by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge. Above 40 mm nominal bore.	121.95	Meter.	29.05	3,542.64
2/ 15.44.1	Dismantling G.I pipes (external work) including excavation and refilling trenches after taking out the pipes, manually /by mechanical means including stacking of pipes within 50 metres lead as per direction of Engineer-in-charge : 15 mm to 40 mm nominal bore.	30.48	Meter	24.90	758.95
3/ 18.12.8	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work 80 mm dia nominal bore.	18.29	Meter.	458.15	8,379.56
4/ 18.12.5	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work 40 mm nominal bore.	115.85	Meter	280.10	32,449.58
5/ 18.13.1	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete : 25 to 40 mm nominal bore.	25.00	Each	166.05	4,151.25
6/ 18.13.2	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete : 50 to 80 mm nominal bore.	1.00	Each	423.20	423.20
7/ 18.47.8	Providing and fixing G.I. Union in existing G.I. pipe line, cutting and threading the pipe and making long screws including excavation, refilling the earth or cutting of wall and making good the same complete wherever required: 80 mm nominal bore.	1.00	Each	607.30	607.30
8/ 18.47.6	Providing and fixing G.I. Union in existing G.I. pipe line, cutting and threading the pipe and making long screws including excavation, refilling the earth or cutting of wall and making good the same complete wherever required: 50 mm nominal bore.	1.00	Each	335.50	335.50
9/ 18.12.3	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work 25 mm dia nominal bore.	9.14	Meter	156.85	1,433.60
	Total			Rs.	52,081.58
			Say	Rs.	52,082.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote ____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Ltd)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII

1. Name of Work: “**Maintenance of GM’s office at Begunia.**”

2. Name of Tenderer :

3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/ /

Date: 04.07.2011

5. Details of E.M.D. No:

Date:

BILL OF QUANTITY: (Sl. No.-2)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ M.R.	Providing & fixing	1.00	Each	1,352.23	1,352.23
2/ M.R.	Providing & fixing brass handle of all	1.00	Each	522.10	522.10
3/ M.R.	Providing & fixing Aldrop /sliding door bolt.	1.00	Each	567.50	567.50
4/ M.R.	Providing & fixing door stopper of all.	1.00	Each	195.78	195.78
5/	Providing glass sheet.	2.32	Sqm	340.00	788.80
6/ M.R.	Providing & fixing cover with fitting charge.	1.00	Each	2,060.00	2,060.00
7/ 21.1.1.1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS : 733 and IS : 185, fixed with rawl plugs and scriws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC / neoprene felt etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing/paneling, c.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing and paneling to be paid for separately): Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15).	10.60	Kg.	290.45	3,078.77
8/ 6.1.2 (A.R)	Brick work with F.P. S bricks of class designation 50 in foundation and plinth in : cement mortar 1:6 (1 cement : 6 coarse sand).	4.00	Cum	2,007.00	8,028.00
9/ 13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 Cement : 4 fine sand).	15.77	Sqm	97.90	1,543.88
10/ 0114	Cleaning of drain labour charged	8.00	Each	135.25	1,082.00
11/ 15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 meter lead: of area 3 sq. metres and below.	1.00	Each	54.60	54.60
12/ 10.2	Structural work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting fixing in position and applying a priming coat of approved steel primer all complete.	65.00	Kg	46.35	3,012.76

Contd. P-3

13/ 14.2.1	Fixing chowkhats in existing opening including embedding chowkhats in floors or walls cutting masonry for holdfasts embedding hold fasts in cement concrete blocks with cement concrete 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) painting two coats of approved wood preservative to sides of chowkhats and making good the damages to walls and floors and required complete including disposal of rubbish to the dumping ground within 50 meters lead: Door chowkhats.	1.00	Each	354.45	354.45
14/ M.R.	Providing and fixing mirror.	1.00	Each	1,063.75	1,063.75
15/ 0111	Supplying carpenter of all complete.	3.00	Each	151.50	454.50
16/ 21.3.1	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with PVC/ neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge (cost of aluminium snap beading shall be paid in basic item) : with float glass panes of 4.0 mm thickness.	1.638	Sqn	554.95	909.00
17/ 9.35.2	Providing and fixing in wall lining flat pressed three layer (medium density) particle board or graded wood pre-laminated one side decorative lamination Grade I, Type II IS: 12823 marked including priming coat on unexposed surface, with necessary fixing arrangement and screws etc. complete: 18 mm thick.	1.97	Sqm	1,024.30	2,017.87
18/ 9.37.1	Providing and fixing plywood 4 mm thick one side decorative veneer conforming to IS: 1328 (type-1) for plain lining / cladding with necessary screws, priming coat on unexposed surface with: Decorative veneer facings of approved manufacture.	1.97	Sqm	577.40	1,137.47
19/ 9.46.3	Providing and fixing curtain rods of 1.25 mm thick chromium plated brass plate, with two chromium plated brass brackets fixed with C.P. brass screws and wooden plugs, etc., wherever necessary complete: 25mm dia.	7.75	Meter	299.30	2,319.57
20/ M. R.	French spirit polishing on wood work of area 10.28 sqm.	1.00	LS	3500.00	3500.00
21/ 11.3.1	Cement concrete flooring 1:2:4 (1 cement :2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 12.5 mm nominal size stone aggregate.	0.81	Sqm	192.95	156.28
22/ 14.45.1	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : Old work (one or more coats).	80.56	Sqm	14.90	1,200.34
23/ 13.43.1	Applying one coat of cement primer of approved brand and manufacture on wall surface: Cement primer.	80.56	Sqm	17.20	1,385.63
	Total			Rs.	36,785.27
			Say	Rs.	36,785.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____ % (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer

BHARAT COKING COAL LIMITED

(A Subsidiary of Coal India Ltd)

OFFICE OF THE GENERAL MANAGER

CHANCH-VICTORIA AREA-XII

1. Name of Work: **“Closing of 2 (two) nos. approach of abandoned mines at near sand bunker and near W.T.P. plant of Victoria west colliery (Re-Quotation).”**

2. Name of Tenderer :

3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/ /

Date: 04.07.2011

5. Details of E.M.D. No:

Date:

BILL OF QUANTITY (Sl. No. 3)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 6.4.2	Brick work with F.P.S. bricks of class designation 50 in superstructure above above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:6 (1 cement: 6 coarse sand)	3.21	Cum	2315.50	7432.75
2/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 cement: 6 fine sand).	6.36	Sqm	67.65	430.25
3/ 2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5m, including getting out the excavated soil and disposal surplus excavated soil as directed, within a lead of 50 m. All kind of soil.	0.79	Cum	103.40	81.68
4/ 4.1.8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level: 1:4:8 (1 cement: 4 coarse sand: 8 graded stone aggregate 40mm nominal size).	0.105	Cum	2449.00	257.14
5/ 6.1.2	Brick work with F.P.S. bricks of class designation 50 in foundation and plinth in: cement mortar 1:6 (1 cement: 6 coarse sand)	0.48	Cum	2007.00	963.36
6/ 1.2.8	Carriage of material by manual labour up to 150 M Lead (a) Bricks	1418.00	0/00 nos.	114.17	161.89
1.2.5	(b) Sand	1.23	Cum	61.17	75.23
1.2.5	(c) Metal	0.093	Cum	61.17	5.68
	Total			Rs.	9,407.98
			Say	Rs.	9,407.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote ____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Ltd)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII

1. Name of Work: **“Repairing of roof, heightening of wall, making boundary wall & providing iron gate for electrical sub-station of DOCP.”**

2. Name of Tenderer :

3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/20/1306

Date: 04.07.2011

5. Details of E.M.D. No:

Date:

BILL OF QUANTITY (Sl. No. 4)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 2.6.1-2.3	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30 cm in depth, 1.5 in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5m, disposed earth to be leveled and neatly dressed. All kinds of soil.	6.00	Cum	88.00	528.00
2/ 4.1.8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level:1:4:8 (1 cement: 4 coarse sand: 8 graded stone aggregate 40 mm nominal size).	1.40	Cum	2,449.00	3,428.60
3/ 6.1.2 (A.R)	Brick work with F.P. S bricks of class designation 50 in foundation and plinth in : cement mortar 1:6 (1 cement : 6 coarse sand).	4.54	Cum	2,007.00	9,111.78
4/ 6.1.1	Brick work with F.P. S bricks of class designation 50 in foundation and plinth in : cement mortar 1:4 (1 cement : 4 coarse sand).	19.51	Cum.	243.43	4,749.32
5/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	29.13	Sqm	8.20	238.86
6/ 6.4.2 (A.R)	Brick work with F.P.S bricks of class designation 50 in superstructure above plinth level up to floor V level in all shapes and sizes in cement mortar 1:6 (1 Cement: 6 coarse sand).	7.01	Cum	2,137.95	14,987.03
7/ 13.1.2	12 mm cement plaster of mix : 1:6 (1 Cement : 6 fine sand).	101.25	Sqm	67.65	6,849.56
8/ 12.15.1	Painting top of roofs with bitumen of approved quality at 17kg per 10 sqm impregnated with a coat of coarse sand at 60 cudm per 10sqm including cleaning the slab surface with brushes and finally with a piece of cloth lightly soaked in kerosene oil complete.	102.41	Sqm	63.00	6,451.83
9/ 10.5.1	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6 mm angle iron and 3mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer. Using M.S. angels 40x40x 6 mm for diagonal braces.	7.43	Sqm	1,695.40	12,596.82
	Total			Rs	58,941.80
			Say	Rs.	58,942.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____ % (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Ltd)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII

1. Name of Work: **“Cleaning of workshop premises, drains and 2 nos. culverts of jore with approaches at DBOCP.”**

2. Name of Tenderer :

3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/20/1306

Date: 04.07.2011

5. Details of E.M.D. No:

Date:

BILL OF QUANTITY (Sl. No. 5)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ (A.R.)	Cleaning at katcha/ pucca drain including disposal of extrented materials such as liquid mud sludge, materials etc. within a lead of 50 meters as direction of Engineer-in-charge.	477.52	Cum	108.09	51,615.14
2/ 2.31	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	309.76	100sqm	263.90	817.46
	Total			Rs.	52,432.60
			Say	Rs.	52,433.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Ltd)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII

1. Name of Work: “**Cleaning of drain, ash and garbages in CMWO colony of Laikdih.**”
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/ / Date: 0 .07.2011
5. Details of E.M.D. No: Date:

BILL OF QUANTITY (Sl. No. 6)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ A.R.	Cleaning of katcha/ pucca drain including disposal of extracted materials such as liquid mud, earth sludge etc with disposal of exerted material up to 50 meter.	305.52	Cum	108.09	33,023.66
2/ 2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50. All kind of soil.	9.26	Cum	103.40	957.48
3/ A.R.	Cleaning of deporited domestic ash, garbage rubbish etc. with disposal up to 50 meter lead.	120.63	Cum	89.55	10,802.42
4/ 1.1.3	Carriage of earth ash, sludge, garbages, etc. by mechanical transport including loading and unloading up to 1.00 K.M.	557.18	Cum	42.97	23,942.02
	Total			Rs	68,723.58
			Say	Rs.	68,723.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote ____% (_____) above / below the estimated cost.
Our quoted offer amounts to Rs. _____ (Rupees _____)
_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer

FOR PAYMENT TO CONTRACTORS
Triplicate)

(Note: To be submitted in

PROFORMA FOR COLLECTING PAYMENT THROUGH ELECTRONIC MODE INCLUDING ELECTRONIC FUND TRANSFER (EFT) & ELECTRONIC CLEARING SYSTEM (ECS)

1	Vendor/ supplier/ contractor/ customer's name & address (with telephone number & Fax number)	
2	Particulars of Bank Account	
	a) Bank Name	
	b) Branch Name (Including RTGS Code)	
	Address	
	Telephone No. & Fax No.	
	c) 9 – Digit Code Number of the Bank & Branch (Appearing on the MICR Cheque issued on the bank) or 5 digit code number of SBI	
	d) Account Type (S.B. Account/ Current Account or Cash Credit with code 10/11/13)	
	e) Ledger No./ Ledger Folio No.	
	f) Account Number (Core Banking) & Style of Account (As appearing on the cheque Book)	

3. DATE OF EFFECT:

I hereby declare that the particulars given above are correct & complete. If the transaction is delayed or not effected at all for reasons of incomplete or incorrect information, I would not hold the user institution responsible. I have read the option invitation letter and agree to discharge responsibility expected of me as a participant under the scheme. Any bank charges levied by the bank of such e-transfer shall be borne by us.

Date:-

contractor

(_____)
 Signature of customer/ vendor/ supplier/

Certified that the particulars furnished above are correct as per our records.

the Bank

(_____)
 Signature of the authorized officials from

DECLARATION

I, -----, Partner/Legal Attorney/ Accredited Representative of M/S -----

-----, solemnly declare that :

1. We are submitting Tender for the Work -----

----- against Tender

Notice No.-----

dt -----

2. None of the Partners of our firm is relative of employee of Bharat Coking Coal Ltd.
3. All information furnished by us in respect of fulfillment of eligibility criteria and qualification information of this Tender is complete, correct and true.
4. None of the partners of the Firm has either individually or collectively been involved in criminal offences.
5. I hereby declare that /our firm has not been banned or delisted by any Govt. or Quasi Govt. agencies or PSUs.
6. All documents/ credentials submitted alongwith this Tender are genuine, authentic, true and valid.
7. If any information and document submitted is found to be false/ incorrect any time, department may cancel my Tender and action as deemed fit may be taken against us, including termination of the contract, forfeiture of all dues including Earnest Money and banning / delisting of our firm and all partners of the firm etc.

Signature of the Tenderer

Dated-----