(A Subsidiary of Coal India Ltd)

#### OFFICE OF THE GENERAL MANAGER CHANCH-VICTORIA AREA-XII

P.O.-BARAKAR - 713324, DIST-BURDWAN (W.B.)

Phone: 06540-272126; FAX 0341-2520063

Ref. No. BCCL/XII/ACE/QTN/2011-12/29/1366

#### **QUOTATION NOTICE**

Dates: 08.08.2011

Sealed Quotations on percentage rate basis are invited from the bonafide & experienced contractors for the following works:

	Search Submitted on beredinage rate only are myrica from the			ine foliowing works:
Sl.No.	Name of the work	Estimated cost	Earnest Money	Time of completion
1.	Petty repair/ maintenance work of weigh bridge room at R.K. weigh, DBOCP.	Rs. 6909.00	Rs. 70.00	10 days
2.	Cleaning of existing drains and cutting of kutcha drain in and around workshop complex and 33 KV sub-station at NLOCP.	Rs. 57601.00	Rs.577.00	15 days
3.	Repairing roof and ceiling of CISF barrack at Basanti Mata colliery.	Rs.29881.00	Rs.299.00	10 days
4.	Petty repair & maintenance of Qtr. No. C/3, Lalbazar of DOCP	Rs. 14671.00	Rs. 147.00	10 days

- 1. Completed sealed Quotations will be received on 18.08.2011 up to 3.00 P.M. at the following places. Quotation may opt any one place to submit their quotation as per their convenience.
  - In the office of the General Manager, C.V. Area-XII, AT-Begunia, P.O -Barakar(W.B.) ii)
    - At BCCL H.Q. i.e. C.I.S.F. post, near Koyala Bhawan gate, Koyala Nagar, Dhanbad.
  - iii) Office of the ACE, CCWO, W.W.Z. Area, Saraidhela, Dhanbad.
  - Office of the ACE, CHD, Jagjiban Nagar, Dhanbad. iv)
- d on 20.08..2011 at 11.30 A.M. in the office of the Area Civil Engineer, C.V. Area-XII, AT-Begunia, P.O -Barakar(W.B.).
- Specification of work shall be governed by DSR-2007 & C.P.W.D specification.
- Terms and conditions as per C.I.L. C.E. manual shall be applicable against the quotations submitted against this Quotation Notice.
- Completed sealed Quotations shall consist of (1) EMD in the shape of cash receipt obtained from the finance deptt. C.V. Area-XII or DD from any Scheduled/Nationalised Bank, (2) Experience certificate, (3) Copy of Pan card, (4) Copy of VAT/Sales Tax clearance certificate along with VAT/Sales Tax registration No.(TIN), (5) Declaration and (6) EFT (Electronic Fund Transfer) & ECS (Electronic Clearance System) as per the format issued along with the Tender paper and (7) BOQ along with quoted rate by the Tenderer.
- The quoted rate shall include all taxes and levies.
- Statutory deductions for Income Tax and Sales Tax shall be made as per Rules and notifications.
- The contractor has to abide by the Rules of Contract Labour Regulation & Abolition Act-.
- Validity of tender shall be 120 days from the date of opening of the tender.
- 10. Interested parties can collect the BOQ and other related papers of the Quotation from the office of the Area Civil Engineer, C.V. Area-XII, AT-Begunia, P.O -Barakar(W.B.). from 13.08.2011 to 17.08.2011 during office hours except Sunday and Holiday. BOQ and other relevant pages (Declaration & EFT form) can be down loaded from BCCL website- http://www.bccl.gov.in
- No conditional tender shall be accepted.
- 12. The contractors have to be acquainted with the site condition
- 13. Unless otherwise mentioned, no material will be issued by the department.
- 14. Successful tender has to deposit 5% Performance Security (including 1% EMD) and another 5% Security Deposit will be deducted from the Running Account/ Final Bill.
- 15. The management of BCCL reserves right to reject any or all tender or split the work among two or more tenderers without assigning any reasons whatsoever.

Area Civil Engineer Chanch Victoria Area-XII

#### Copy to :-

- 1) GM, Chanch Victoria Area-XII.
- GM (Civil), BCCL, Koyla Nagar.
   All CGM/GM of Areas/Projects under BCCL.
- Addl. GM, Chanch Victoria Area-XII.
- A.F.M., Chanch Victoria Area-XII.
- All P.O.s of Chanch Victoria Area-XII. Cashier, C.V. Area-XII
- Incharge,, CISF Post, Koyala Bhawan gate, Koyala Nagar,
- Assistant Commandant, CISF, C.V. Area-XII-with 2 copies of NIT for displaying on Notice Board.
- 10) Builders Association of India, Central Akashkinaree Kanta, Katras Garh, Dhanbad-828113.
- ACE CCWO, W.W.Z Area saraidhela, Dhanbad. ACE CHD, jagiban Nagar, Dhanbad
- Notice Board.

(A Subsidiary of Coal India Ltd) OFFICE OF THE GENERAL MANAGER CHANCH-VICTORIA AREA-XII

- 1. Name of Work: "Petty repair/ maintenance work of weigh bridge room at R.K. weigh, DBOCP."
- 2. Name of Tenderer:
- 3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/29/1366 5. Details of E.M.D. No:

Date: 08.08.2011

Date:

#### BILL OF QUANTITY: (Sl. No. 1)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.7.4	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meter lead as per direction of Engineer-in-charge. In cement mortar	0.289	Cum	310.75	89.80
2/ 4.1.2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level: 1:1.5.3 (1 cement: 1.5 coarse sand: 3 graded stone aggregate 20 mm nominal size).	0.113	Cum	3,629.80	410.16
3/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	24.27	Sqm	8.20	199.01
4/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	25.53	Sqm	67.65	1,727.10
5/ 14.6.1	Renewing glass panes, with wooden fillets wherever necessary: Float glass panes of thickness 4mm	1.73	Sqm.	498.55	862.49
6/ 13.39.2	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats ) with a base coat of whiting.	127.36	Sqm	9.10	1,158.91
7/ 9.48.2	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. all complete: fixed to openings / wooden frames with rawl plugs screws etc.	24.00	Kg.	64.40	1,545.60
8/ 9.3.1	Providing wood work in frames of false ceiling, partitions etc. sawn and put up in position. Sal wood.	0.017	Cum	29,107.80	494.83
9/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	18.43	Sqm	22.85	421.12
	TOTAL			Rs.	6,909.02
			Say	Rs.	6,909.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote% (	) above / below the estimated
cost. Our quoted offer amounts to Rs(	Rupees
) incl	uding the above percentage.
SIGNATURE OF ISSUING OFFICER	Signature & seal of Tenderer

(A Subsidiary of Coal India Ltd)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII

- 1. Name of Work: "Cleaning of existing drains and cutting of kutcha drain in and around workshop complex and 33 KV sub-station at NLOCP."
- 2. Name of Tenderer:
- 3. Address:

4. NIT No.: BCCL/XII/ACE/QTN/2011-12/29/1366 Date: 08.08.2011

5. Details of E.M.D. No: Date:

## **BILL OF QUANTITY: (Sl. No.-2)**

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ (A.R.)	Cleaning at katcha/ pucca drain including disposal of excreted materials such as liquid mud sludge, materials etc. within a lead of 50 meters as direction of Engineer-incharge.	251.81	Cum	108.09	27,218.14
2/ 2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kind of soil.	176.72	Cum	103.40	18,27285
3/ 15.9.2	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-incharge: in cement mortar.	1.86	Cum	370.75	689.60
4/ A.R.	random rubble masonry with colliery good O.B. with cement mortar 1: 6 (1 cement: 6 coarse sand) in F& P	2.12	cum	1,374.45	2,913.83
5/ A.R.	Random rubble masonry with colliery good O.B. with cement mortar 1:6 (1 cement: 6 coarse sand) in S.S.	3.54	Cum	1,746.80	6,163.67
6/ 13.33.1	Pointing on stone work with cement mortar 1:3 (1 cement: 3 fine sand): Flush/ Ruled pointing.	37.17	Sqm	62.50	2,323.12
	TOTAL			Rs.	57,601.21
			Say	Rs.	57,601.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote% (	) above / below the estimated
Our quoted offer amounts to Rs	( Rupees
	) including the above percentage.
SIGNATURE OF ISSUING OFFICER	Signature & seal of Tenderer

(A Subsidiary of Coal India Ltd)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII

- 1. Name of Work: "Repairing roof and ceiling of CISF barrack at Basanti Mata colliery."
- 2. Name of Tenderer:
- 3. Address:

4. NIT No.: BCCL/XII/ACE/QTN/2011-12/29/1366 Date: 08.08.2011

5. Details of E.M.D. No: Date:

## BILL OF QUANTITY (Sl. No. 3)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ BCCL '85'	Removal old and damaged tarfelt.	187.87	Sqm	1.86	349.44
2/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	71.21	Sqm	8.20	583.92
3/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	39.02	Sqm	67.65	2,639.70
4/ 13.16.1	6mm cement plaster of mix: 1:3 (1 cement: 3 fine sand).	45.28	Sqm	62.15	2,814.15
5/ 22.14.1	Grading roof for water proofing treatment with cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	3.84	Cum	3,314.95	12,729.41
12.15.1	Painting top of roofs with bitumen of approved quality at 17kg per 10sqm impregnated with a coat of coarse sand at 60 cudm per 10sqm including cleaning the slab surface with brushes and finally with a piece of cloth lightly soaked in kerosene oil complete: with residual type petroleum bitumen of penetration 80/100	170.86	Sqm	63.00	10,764.18
	Total			Rs.	29,880.80
			Say	Rs.	29,881.00

(A Subsidiary of Coal India Ltd)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII

- 1. Name of Work: "Petty repair & maintenance of Qtr. No. C/3, Lalbazar of DOCP."
- 2. Name of Tenderer:

3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/29/1366 Date: 08.08.2011

5. Details of E.M.D. No: Date:

## BILL OF QUANTITY (Sl. No. 4)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-incharge. 1:3:6 or richer mix.	0.55	Cum	368.45	202.64
2/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat sement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	22.65	Sqm	143.75	3,255.93
3/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	27.68	Sqm	8.20	226.97
4/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	27.68	Sqm	67.65	1,872.55
5/ 9.1.3	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position. Kiln seasoned and chemically treated Hollock wood.	0.06	Cum	31,339.40	1,880.36
6/ 9.5.2	Providing and fixing paneled or paneled and glazed shutters for doors, windows and clerestory windows including ISI marked black enameled M.S. butt hinges with necessary screws excluding, paneling which will be paid for separately. 30 mm thick shutters.	1.57	Sqm	810.90	1,224.46
7/ 10.5.2	Providing and fixing 1mm thick m.S. sheet door with frame of 40x40x6mm angle iron and 3mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer. Using flats 30x6 mm for diagonal braces and central cross piece.	1.81	Sqm	1,600.10	2,896.18
8/ 12.40.2	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS: 13592 Type A including jointing with seal ring conforming to IS: 5382 leaving 10 mm gap for thermal expansion. (i) single socketed pipes. 110 mm diameter.	3.65	Metre	163.40	596.41
9/ 12.42.5.2	Providing and fixing on wall face unplasticised – PVC moulded fittings / accessories for unplasticised Rigid PVC rain water pipes conforming to IS: 13592 Type A including jointing with seal ring conforming to IS: 5382 leaving 10 mm gap for thermal expansion. 110mm bend.	1.00	Each	134.20	134.20

Contd. P/3

10/	White washing with lime to give an even shade: Old	161.33	Sam	4.10	661.45
14.42.1	work (two or more coats).	101.55	Sqiii	4.10	001.43
11/	Colour washing such as green, blue of buff to give an				
13.39.1	even shade: New work (two or more coats ) with a	76.51	Sqm	9.30	711.54
	base coat of white washing with lime.				
12/	Painting with synthetic enamel paint of approved				
14.54.1	brand and manufacture of required colour to give an	44.12	Sqm	22.85	1,008.14
	even shade: one or more coats on old work.				
_	TOTAL			Rs.	14,670.83
			Say	Rs.	14,671.00

Having gone through the Tender documents & elements of work in the bill of quantity !-			
I / we quote% (	) above / below the estimated		
Our quoted offer amounts to Rs ( Rupees			
) incl	uding the above percentage.		
SIGNATURE OF ISSUING OFFICER	Signature & seal of Tenderer		

# FOR PAYMENT TO CONTRACTORS *Triplicate*)

(Note: To be submitted in

PROFORMA FOR COLLECTING PAYMENT THROUGH ELECTRONIC MODE INCLUDING ELECTRONIC FUND TRANSFER (EFT) & ELECTRONIC CLEARING SYSTEM (ECS)

1	Vendor/ supplier/ contractor/ customer's name & address (with telephone number & Fax number)	
2	Particulars of Bank Account	
	a) Bank Name	
	b) Branch Name	
	(Including RTGS Code)	
	Address	
	Telephone No. & Fax No.	
	c) 9 – Digit Code Number of the Bank & Branch	
	(Appearing on the MICR Cheque issued on the	
	bank) or 5 digit code number of SBI	
	d) Account Type	
	(S.B. Account/ Current Account or Cash Credit	t
	with code 10/11/13) e) Ledger No./ Ledger Folio No.	
	f) Account Number (Core Banking) & Style of	f
	Account	
	(As appearing on the cheque Book)	
or ins	<u>DATE OF EFFECT:</u> I hereby declare that the particulars given above are correct not effected at all for reasons of incomplete or incorrect stitution responsible. I have read the option invitation be spected of me as a participant under the scheme. Any basisfer shall be borne by us.	ct information, I would not hold the user etter and agree to discharge responsibility
Da	ate:-	(
	S	ignature of customer/ vendor/ supplier/
COI	ontractor	
Се	ertified that the particulars furnished above are correct as p	
the	e Bank	ignature of the authorized officials from

# ANNEX-III

# **DECLARATION**

I,	, Partner/Legal Attorney/ Accredited Representative of M/S
	, solemnly declare that :
1.	We are submitting Tender for the Work
	against Tender
	Notice No dt
2. 3.	None of the Partners of our firm is relative of employee of Bharat Coking Coal Ltd.  All information furnished by us in respect of fulfillment of eligibility criteria and qualification information of this Tender is complete, correct and true.
4. 5.	None of the partners of the Firm has either individually or collectively been involved in criminal offences.  I hereby declare that /our firm has not been banned or delisted by any Govt. or Quasi Govt. agencies or PSUs.
6. 7.	All documents/ credentials submitted alongwith this Tender are genuine, authentic, true and valid. If any information and document submitted is found to be false/ incorrect any time, department may cancel my Tender and action as deemed fit may be taken against us, including termination of the contract, forfeiture of all dues including Earnest Money and banning / delisting of our firm and all partners of the firm etc.
	Signature of the Tenderer
	Dated