



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063



Ref. No. BCCL/XII/ACE/QTN/2011-12/49/1564

Dates: 24.10.2011

QUOTATION NOTICE

Sealed Quotations on percentage rate basis are invited from the bonafide & experienced contractors for the following works: Terms and conditions:

Sl.No.	Name of the work	Estimated cost	Earnest Money	Time of completion
1.	Cleaning of jungle, bushes and leveling dressing work at ECO Park, Junkundar.	Rs. 33,173.00	Rs. 335.00	15 days
2.	Repairing & maint. Of lamp cabin of palasia at B. Mata Colliery.	Rs.29,514.00	Rs. 300.00	20 days.
3.	Repairing of collapsed/ damaged courtyard wall for Qtr No. J-9,F-2, & F-3 at Bramsthan, NLOCP.	Rs. 18,631.00	Rs. 190.00	20 days
4.	Repairing & maint. Of drinking water pipe line 'J' Block at B. Mata Colliery.	Rs. 32,403.00	Rs. 325.00	10 days
5.	Repairing & renovation of Agent & Manager office at Basanti Mata Colliery.	Rs. 26,472.00	Rs. 265.00	25 days
6	Laying pipe line from Laikdih pit to main pipe line through Pressure filter.	Rs. 44,067.00	Rs. 445.00	10 days
7	Repairing & maint of 4 Units qtr at staff colony Damagoria (B/2, B/3, B/5 & B/9)	Rs. 49,102.00	Rs. 500.00	30 days
8	Repairing & maint. Of Hospital Building at Lal bazaar under DOCP.	Rs. 79,800.00	Rs. 800.00	30 days.
9	Repairing & maintenance one unit Bunglow type staff qtr. At Lalbazar DOCP occupied by T.N. Choudary.	Rs. 19,000.00	Rs. 190.00	15 days
10	Re-const. of Boundary wall at Coal stock yard, Begunia.	Rs. 24,574.00	Rs. 250.00	15 days.
11	Repairing of 16 Nos 6" dia sluice valve over sub main pipe lines in different colonies under Laikdih, NLOCP & Chanch.	Rs. 27,421.00	Rs. 275.00	10 days.
12	Repairing clearing & re-laying of pipe line at Project Colony, NLOCP (for block No. E, F & H)	Rs. 26,624.00	Rs.270.00	10 days.
13	Repairing of pipe line in Project Officer's bunglow (BD-1) & in 'B' & 'C' type qtr. At Babudanga More.	Rs. 22,981.00	Rs. 230.00	10 days.
14	Repairing and maint. Of One unit Qtr. At Junkundar Pathak (Qtr. No. CTQ/JUN/2).	Rs. 13,320.00	Rs. 135.00	15 days.
15	Installation of sintex with water connection at B.Mata.	Rs. 7,875.00	Rs. 80.00	5 days.

- Interested parties can collect the BOQ and other related papers of the Quotation from the office of the Area Civil Engineer, C.V. Area-XII, AT-Begunia, P.O –Barakar(W.B.). **From 12.11.2011 to 16.11.2011** during office hours except Sunday and Holiday. BOQ and other relevant pages (Declaration & EFT form) can be down loaded from BCCL website- <http://www.bccl.gov.in>
- Completed sealed Quotations will be received on **17.11.2011 up to 3.00 P.M.** at the following places. Quotation may opt any one place to submit their quotation as per their convenience.
 - In the office of the General Manager, C.V. Area-XII, AT-Begunia, P.O –Barakar(W.B.)
 - At BCCL H.Q. i.e. C.I.S.F. post, near Koyala Bhawan gate, Koyala Nagar, Dhanbad.
 - Office of the ACE, CCWO, W.W.Z. Area, Saraidhela, Dhanbad.
 - Office of the ACE, CHD, Jagjiban Nagar, Dhanbad.
- Quotations will be opened on **19.11.2011 at 11.30 A.M.** in the office of the Area Civil Engineer, C.V. Area-XII, AT-Begunia, P.O –Barakar(W.B.).
- Specification of work shall be governed by DSR-2007 & C.P.W.D specification.
- Terms and conditions as per C.I.L. C.E. manual shall be applicable against the quotations submitted against this Quotation Notice.

ContdP/2

-P/2-

6. Completed sealed Quotations shall consist of (1) EMD in the shape of cash receipt obtained from the finance deptt. C.V. Area-XII or DD from any Scheduled/Nationalised Bank, (2) Experience certificate, (3) Copy of Pan card, (4) Copy of VAT/Sales Tax clearance certificate along with VAT/Sales Tax registration No.(TIN), (5) Declaration and (6) EFT (Electronic Fund Transfer) & ECS (Electronic Clearance System) as per the format issued along with the Tender paper and (7) BOQ along with quoted rate by the Tenderer.
7. The quoted rate shall include all taxes and levies.
8. Statutory deductions for Income Tax and Sales Tax shall be made as per Rules and notifications.
9. The contractor has to abide by the Rules of Contract Labour Regulation & Abolition Act-.
10. Validity of tender shall be 120 days from the date of opening of the tender.
11. The contractors have to be acquainted with the site condition
12. Unless otherwise mentioned, no material will be issued by the department
13. Successful tender has to deposit 5% Performance Security (including 1% EMD) and another 5% Security Deposit will be deducted from the Running Account/ Final Bill.
14. The management of BCCL reserves right to reject any or all tender or split the work among two or more tenderers without assigning any reasons whatsoever.

Sd/
Area Civil Engineer
Chanch Victoria Area-XII

Copy to :-

- 1) GM, Chanch Victoria Area-XII.
- 2) GM (Civil), BCCL, Koyla Nagar.
- 3) All CGM/GM of Areas/Projects under BCCL.
- 4) Addl. GM, Chanch Victoria Area-XII.
- 5) A.F.M., Chanch Victoria Area-XII.
- 6) All P.O.s of Chanch Victoria Area-XII.
- 7) Cashier, C.V. Area-XII
- 8) Incharge,, CISF Post, Koyala Bhawan gate, Koyala Nagar,
- 9) Assistant Commandant, CISF, C.V. Area-XII-with 2 copies of NIT for displaying on Notice Board.
- 10) Builders Association of India, Central Akashkinaree Kanta, Katras Garh, Dhanbad-828113.
- 11) ACE CCWO, W.W.Z Area saraidhela, Dhanbad.
- 12) ACE CHD, jagiban Nagar, Dhanbad



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: “Cleaning of jungle, bushes and leveling dressing work at ECO Park, Junkundar.”
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/49/1564

Date: 24.10.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 1)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 2.31	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	10,839.72	100 sqm	263.90	28,606.02
2/ 2.28.1	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15cm deep and disposal of rubbish, lead up to 50m and lift up to 1.5m. All kind of soil.	891.82	100 Sqm	512.10	4,567.01
	TOTAL			Rs.	33,173.03
			Say	Rs.	33,173.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



- 1 .Name of Work: **“Repairing & maint. Of lamp cabin of palasia at B. Mata Colliery.”**
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/49/1564

Date: 24.10.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 2)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 22.14.1	Grading roof for water proofing treatment with cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	4.03	sqm	3,314.95	13,559.24
2/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	26.41	Sqm	8.20	216.56
3/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	26.41	Sqm	67.65	1,786.63
4/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat sement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	20.00	Sqm	143.75	2,875.00
5/ 12.15.1	Painting top of roofs with bitumen of approved quality at 17kg per 10sqm impregnated with a coat of coarse sand at 60 cudm per 10sqm including cleaning the slab surface with brushes and finally with a piece of cloth lightly soaked in kerosene oil complete: with residual type petroleum bitumen of penetration 80/100	110.22	Sqm	63.00	6,943.86
6/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	243.77	Sqm	4.10	999.45
7/ 13.39.1	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats) with a base coat of white washing with lime.	252.00	Sqm	9.30	2,343.60
8/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	42.00	Sqm	22.85	989.70
	TOTAL			Rs.	29,514.04
			say	Rs.	29,514.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Repairing of collapsed/ damaged courtyard wall for Qtr No. J-9,F-2, & F-3 at Bramsthan, NLOCP.”**
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/49/1564

Date: 24.10.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 3)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.7.4	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meter lead as per direction of Engineer-in-charge. In cement mortar	3.20	Cum	310.75	994.40
2/ 6.12.2	Half brick masonry with F.P.S. brick of class designation in foundations and plinth in . cement mortar 1:4 (1 cement: 4 coarse sand).	17.54	Sqm	257.20	4,511.29
3/ 6.13.2	Half brick masonry with F.P.S bricks of class designation 50 in superstructure above plinth level up to floor V level Cement mortar 1:4 (1 cement: 4 coarse sand)	17.54	Sqm	273.45	4,796.31
4/ 6.1.2	Brick work in F.P.S bricks of class designation 50 in foundation and plinth in: Cement mortar 1:6 (1 cement: 6 coarse sand).	0.41	Cum	2,007.00	822.87
5/ 6.4.2 (A.R.)	Brick work in F.P.S. bricks of class designation 50 in superstructure above plinth level up to floor V level in all shapes and sizes in : cement mortar 1:6 (1 cement : 6 coarse sand).	0.41	Cum	2,137.95	876.56
6/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	86.16	Sqm	67.65	5,828.72
	TOTAL			Rs.	18,631.44
			Say	Rs.	18,631.00

Having gone through the Tender documents & elements of work in the bill of quantity:-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



- 1 .Name of Work: **“Repairing & maint. Of drinking water pipe line ‘J’ Block at B. Mata Colliery.”**
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/49/1564

Date: 24.10.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 4)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.44.2	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including staking of pipes within 50 metres lead as per direction of Engineer-in-charge: above 40 mm nominal bore.	34.00	Metre	29.05	987.70
2/ 18.10.6 A.R.	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc. 50 mm dia nominal bore.	34.00	Metre.	262.25	8,916.50
3/ 18.12.6	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. 50 mm dia nominal bore.	58.00	Meter.	280.10	16,245.80
4/ 18.12.2	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc.20 mm dia nominal bore.	50.00	Meter.	116.60	5,830.00
5/ 18.13.2	Making connection of G.I. distribution branch with G.I. main of following sized by providing and fixing tee, including cutting and threading the pipe etc. complete: 50 to 80 mm nominal bore.	1.00	Each	423.20	423.20
	TOTAL			Rs.	32,403.20
			Say	Rs.	32,403.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer


13/ 17.31	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats C.P. brass screws and washers complete.	1.00	Each	493.65	493.65
14/ 18.15.1	Providing and fixing brass bib cock of approved quality 15 mm nominal bore.	1.00	Each	191.70	191.70
15/ 17.28.1.2	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. 40 mm dia.	1.00	Each	47.95	47.95
16/ M.R.	Providing fitting fixing 6 mm thick table top glass.	1.00	Each	475.00	475.00
17/ 17.7.1	Providing and fixing wash basin with C.I. brackets, 15mm C.P. brass pillar taps, 32mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White vitreous china wash basin size 630x450 mm with a paie 15 mm C.P. brass pillar tap.	1.00	Each	1,332.90	1,332.90
18/	Providing fitting fixing glass show case.	1.00	Each	242.00	242.00
19/ 12.15.1	Painting top of roofs with bitumen of approved quality at 17kg per 10sqm impregnated with a coat of coarse sand at 60 cudm per 10sqm including cleaning the slab surface with brushes and finally with a piece of cloth lightly soaked in kerosene oil complete: with residual type petroleum bitumen of penetration 80/100	74.34	Sqm	63.00	4,683.42
20/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	25.00	Sqm	67.65	1,619.25
	TOTAL			Rs	26,472.03
			Say	Rs.	26,472.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.
Our quoted offer amounts to Rs. _____ (Rupees _____
_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Coal India Ltd.

- BILL OF QUANTITY: (Sl. No. 6)**

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.45.2	Dismantling C.I. pipes including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means breaking lead caulked joints, melting of lead and making into blocks including stacking of pipes, lead at site within 50 metre leas as per direction of Engineer-in-charge: Above 150 mm dia up to 300mm dia.	7.00	Metre	86.00	602.00
2/ 18.83.7	Labour for cutting C.I. pipe with steel saw. 300 mm diameter C.I. pipe.	1.00	Each cut	111.40	111.40
3/ 18.26.1	Providing and laying flanged C.I. standard specials such as tees, bends, collars, tapers, caps etc., suitable for flanged jointing as per IS: 1538: Over 300 mm dia.	135.00	quintal	5,123.45	6,916.65
4/ 18.28.6 18.28.3	Providing lead caulked joints to spun iron or C.I. pipes and specials including testing of joints but excluding the cost of pig lead: i) 300 mm diameter pipe. ii) 150 mm diameter pipe.	4.00 1.00	Each Each	246.35 123.30	985.40 123.30
5/ 18.29	supplying pig lead at site of work.	0.374	Quintal.	6,742.20	2,521.50
6/ A.R.	Labour charges for laying C.I. pipes.	5.50	Meter.	51.85	285.17
7/ 15.45.1	Dismantling C.I. pipes including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means breaking lead caulked joints, melting of lead and making into blocks including stacking of pipes, lead at site within 50 metre leas as per direction of Engineer-in-charge: up to 150 mm diameter.	85.00	Metre	63.45	5,393.25
8/ A.R.	Carriage of M.S. pipes including loading & unloading up to 3 K.M.	85.00	Metre	L.S.	1,819.30
9/ M.R.	Supplying and fabrication of M.S. flanges to M.S. Pipes.	16.00	Each	600.00	9,600.00
10/ 2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kind of soil.60.00 meter x 0.90x0.500	27.00	Cum	103.40	2,791.00
11/ A.R.	Labour charges for laying 150 mm dia M.S. Pipes.	120.00	Meter	20.15	2,418.00
12/ 18.31.3.1	Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately): Class I	2.00	Each	3,689.10	7,378.20
13/ 18.30.4	Providing flanged joints to double flanged C.I./D.I. pipes and specials including testing of joints: 150 mm diameter pipe.	20.00	Each	156.90	3,122.00
	TOTAL			Rs.	44,067.00

Having gone through the Tender documents & elements of work in the bill of quantity:-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____)

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Repairing & maint of 4 Units qtr at staff colony Damagoria (B/2, B/3, B/5 & B/9).”**
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/49/1564

Date: 24.10.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 7)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat sement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	79.66	Sqm	143.75	11,451.12
2/ 10.2	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete:.	74.00	Kg	46.35	3,429.90
3/ 9.1.3	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position. Kiln seasoned and chemically treated Hollock wood.	0.23	Cum	31,339.40	7,208.06
4/ 9.5.2.2	Providing and fixing paneled or paneled and glazed shutters for doors, windows and clerestory windows including ISI marked black enameled M.S. butt hinges with necessary screws excluding, paneling which will be paid for separately. 30 mm thick shutters.	8.80	Sqm	810.90	7,135.92
5/ 13.16.1	6mm cement plaster of mix: 1:3 (1 cement: 3 fine sand).	13.93	Sqm	62.15	865.74
6/ 6.13.2	Half brick masonry with F.P.S bricks of class designation 50 in superstructure above plinth level up to floor V level Cement mortar 1:4 (1 cement: 4 coarse sand)	0.97	Sqm	273.45	265.24
7/ 22.14.1	Grading roof for water proofing treatment with cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	0.194	sqm	3,314.95	643.10
8/ 13.18	Neat cement punning.	5.10	Sqm	21.40	109.14
9/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	746.63	Sqm	4.10	3,061.18
10/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	220.09	Sqm	22.85	5,029.05
11/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	48.00	Sqm	67.65	3,247.20
12/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	1.50	Cum	368.45	552.67
13/ 13.39.1	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats) with a base coat of white washing with lime.	210.63	Sqm	9.30	1,958.85
14/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	25.00	Sqm	8.20	205.00
15/ 14.2.1 14.2.2	Fixing chowkhats in existing opening including embedding chowkhats in floors or walls cutting masonry for holdfasts embedding hold fasts in cement concrete blocks with cement concrete 1:3:6 (1 Cement: 3 coarse sand: 6 graded stone aggregate 20 mm nominal size). Painting two coats of approved wood preservative to sides of chowkhats and making good the damages to walls and floors as required complete including disposal of rubbish to the dumping ground within 50 meters lead: i) Door chowkhats. ii) Window chowkhats.	1.00 1.00	Each Each	354.45 214.20	354.45 214.20

Contd.....P/2

16/ 15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 meters lead: of are 3 sq. metres and below.	8.00	Each	54.60	436.80
17/ 9.53	Providing 40x5 mm flat iron hold fast 40 cm long including fixing to frame with 10 mm diameter bolts, nuts and wooden plugs and embeddings in cement concrete block 30x10x15cm 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).	37.00	Each	61.50	2,275.50
18/ 9.63.3	Providing and fixing ISI marked oxidesed M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete: 150x10 mm	10.00	Each	23.40	234.00
19/ 9.66.2	Providing and fixing ISI marked oxidesed M.S. handles conforming to IS:4992 with necessary screws etc. complete.100mm	6.00	Each	7.75	46.50
20/ 13.50.1	Applying priming coat: with ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood).	22.88	Sqm	16.55	378.66
	TOTAL			Rs.	49,102.28
			Say	Rs.	49,102.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote ____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees_____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Repairing & maint. Of Hospital Building at Lal bazaar under DOCP.”**

2. Name of Tenderer :

3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/49/1564

Date: 24.10.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 8)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	5.56	Cum	368.45	2,048.58
2/ 22.14.2	Grading roof for water proofing treatment with cement concrete 1:3 (1 cement: 3 coarse sand:).	1.50	sqm	5,045.35	7,568.02
3/ 22.8.1	Providing and laying four courses water proofing treatment with bitumen felt over roofs consisting of first and third courses of blown bitumen 85/25 or 90/15 conforming to IS: 702 applied hot @ 1.45 kg per square metre of area for each course, second course of roofing felt type 3 grade-I (Hessian based self finished bitumen felt) and fourth and final course of stone frit 6mm and down size or pea-sized gravel spread at 6 cubic diameter per square metre including preparation of surface but excluding grading complete with Bitumen felt(Hessian base) type 3 grade I conforming to IS : 1322.	200.00	Sqm	184.80	36,960.00
4/ 13.16.1	6mm cement plaster of mix: 1:3 (1 cement: 3 fine sand).	45.00	Sqm	62.15	2,796.75
5/ A.R.	Cleaning septic tank.	2.00	Each	1,000.00	2,000.00
6/ 5.12	Providing, hoisting and fixing up to floor five level precast reinforced cement concrete work in string courses, bands copings, bed plates, anchor blocks, plain window sills and the like including the cost of required centering, shuttering, finishing smooth with 6 mm thick cement plaster 1:3 (1 cement: 3 fine sand) on exposed surfaces complete but excluding cost of reinforcement with 1:2:4 (1 cement : 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	0.63	Cum	4,880.15	3,074.49
7/ 5.22.3	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete . Cold twisted bars.	50.00	K.G.	42.70	2,135.00
8/ 17.35.1.1	Providing and fixing soil, waste and vent pipes: 100 mm dia. Sand cast iron S & S pipe as per IS: 1729.	8.00	Meter	451.00	3,608.00
9/ 17.13.1	Providing and fixing white vitreous china wat4er closet squatting pan (Indian type) Long pattern W.C. pan of size 580mm	2.00	Each	534.60	1,069.20
10/ 17.60.1.2	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors: sand cast iron S & S as per IS: 1729.	2.00	Each	442.10	884.20
11/ 17.17.1	Providing and fixing a pair of white vitreous china foot rests of standard pattern for squatting pan water closet: 250x130x30mm	2.00	Pair	111.70	223.40
12/ 18.12.2	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc.20 mm dia nominal bore.	14.00	Meter.	116.60	1,632.40
13/ 18.13.1	Making connection of G.I. distribution branch with G.I. main of following sized by providing and fixing tee, including cutting and threading the pipe etc. complete: 25 to 40 mm nominal bore.	1.00	Each	166.05	166.05

Contd....P/2

14/ 18.48	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI: 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	500.00	Per Litre.	5.25	2,625.00
15/ 6.1.2	Brick work in F.P.S bricks of class designation 50 in foundation and plinth in: Cement mortar 1:6 (1 cement: 6 coarse sand).	1.00	Cum	2,007.00	2,007.00
16/ 13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:4 (1 Cement: 4 fine sand).	5.00	Sqm	97.90	489.50
17/ 4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level: 1:2.4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	0.11	Cum	3,257.45	358.31
18/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	50.00	Sqm	67.65	3,382.50
19/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	648.44	Sqm	4.10	2,658.60
20/ 13.39.1	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats) with a base coat of white washing with lime.	150.00	Sqm	9.30	1,395.00
21/ 14.5.1	Renewing glass panes, with putty and nails wherever necessary: float glass panes of thickness 4 mm.	2.00	Sqm	427.60	855.20
22/ 2.31	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	100.00	100 sqm	263.90	263.90
23/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	70.00	Sqm	22.85	1,599.50
	TOTAL			Rs.	79,800.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote ____% (_____) above / below the estimated cost.
Our quoted offer amounts to Rs. _____ (Rupees _____
_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063



1. Name of Work:“**Repairing & maintenance one unit Bunglow type staff qtr. At Lalbazar DOCP occupied by T.N. Choudary.**”
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/49/1564
5. Details of E.M.D. No: Rs: Date: 24.10.2011
Date:

BILL OF QUANTITY: (Sl. No. 9)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	48.00	Sqm	8.20	393.60
2/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	23.00	Sqm	67.65	1,555.95
3/ 13.16.1	6mm cement plaster of mix: 1:3 (1 cement: 3 fine sand).	25.00	Sqm	62.15	1,553.75
4/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	0.84	Cum	368.45	309.49
5/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat sement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	34.75	Sqm	143.75	499.31
6/ 10.2	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete:..	74.25	Kg	46.15	3,426.63
7/ 9.1.3	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position. Kiln seasoned and chemically treated Hollock wood.	0.035	Cum	31,339.40	1,096.87
8/ 9.5.2.2	Providing and fixing paneled or paneled and glazed shutters for doors, windows and clerestory windows including ISI marked black enameled M.S. butt hinges with necessary screws excluding, paneling which will be paid for separately. 30 mm thick shutters.	1.37	Sqm	810.90	1,110.93
9/ 13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:4 (1 Cement: 4 fine sand).	36.24	Sqm	97.90	3,547.89
10/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	246.22	Sqm	4.10	1,009.50
	TOTAL			Rs.	18,999.92
			Say	Rs.	19,000.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote ____% (_____) above / below the estimated cost.
Our quoted offer amounts to Rs. _____ (Rupees _____
_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER
Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Re-const. of Boundary wall at Coal stock yard, Begunia..”**

2. Name of Tenderer :

3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/49/1564

Date: 24.10.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 10)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kind of soil.	16.41	Cum	103.40	1,696.79
2/ 6.1.2	Brick work in F.P.S bricks of class designation 50 in foundation and plinth in: Cement mortar 1:6 (1 cement: 6 coarse sand).	3.81	Cum	2,007.00	7,446.67
3/ 6.4.2 (A.R.)	Brick work in F.P.S. bricks of class designation 50 in superstructure above plinth level up to floor V level in all shapes and sizes in : cement mortar 1:6 (1 cement : 6 coarse sand).	3.81	Cum	2,137.95	8,145.58
4/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	62.54	Sqm	67.65	4,230.83
5/ 10.1	Structural still work in single section fixed with or without connecting including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	19.17	Kg	42.15	808.01
6/ 16.17.1	Fencing with R.C.C. post placed at required distance, ambded in cement concrete blocks, every 15 th post, last but one end post and corner post shall be strutted on both sides and end post one side only, provided with horizontal lines and two diagonals of barbed wire 9.38 kg per 100 metres (min) between the two posts fitted and fixed with G.I. staples on wooden plugs or G.I. binding wire tied to 6 mm bar nibs fixed while casting the post (cost of R.C.C posts, struts, earth work and concrete to be paid for separately) :- Payment to be made per meter cost of total length of barbed wire used. With G.I. barbed wire.	73.15	Meter	5.85	427.92
7/ 4.2.3	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets etc, up to floor five level, excluding the cost of centering, shuttering and finishing: 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size)	0.063	Cum	3,579.10	225.50
8/ 13.39.1	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats) with a base coat of white washing with lime.	62.54	Sqm	9.30	581.62
9/ 1.1.2	Carriage of earth lead up to 1 K.M.	16.41	Cum	49.42	810.98
	TOTAL			Rs.	24,573.90
			Say	Rs.	24,574.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Repairing of 16 Nos 6” dia sluice valve over sub main pipe lines in different colonies under Laikdih, NLOCP & Chanch.”**
2. Name of Tenderer :
3. Address:
4. NIT No. : BCCL/XII/ACE/QTN/2011-12/49/1564 Date: 24.10.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 11)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ A.R.	Repairing of sluice valve of 6” dia including taking down and reaffixing in position.	16.00	Each	1,400.00	22,400.00
2/ 18.30.4	Providing flanged joints to double flanged C.I /D.I. pipes and specials including testing of joints: 150 mm diameter pipe.	32.00	Each	156.90	5,020.80
	TOTAL			Rs.	27,420.80
			Say	Rs.	27,421.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063



1. Name of Work: “Repairing clearing & re-laying of pipe line at Project Colony, NLOCP (for block No. E, F & H).”
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/49/1564 Date: 24.10.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 12)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.44.1	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including staking of pipes within 50 metres lead as per direction of Engineer-in-charge: 15 to 40 mm nominal bore.	130.00	Metre	24.90	3,237.00
2/ 15.44.2	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including staking of pipes within 50 metres lead as per direction of Engineer-in-charge: above 40 mm nominal bore.	52.00	Metre	29.05	1,501.60
3/ 15.53.1	Dismantling of C.I. sluice valve including stacking of useful materials within a lead of 50 meter Up to 150 mm diameter.	1.00	Each	52.70	52.70
4/ A.R.	Labour charges for relaying G.I. pipes complete excluding the cost of trenching & refilling etc. 40 mm dia nominal bore.	105.00	Meter.	15.90	1,669.50
5/ A.R.	Labour charges for relaying G.I. pipes complete excluding the cost of trenching and refilling etc.com	22.00	Meter	17.18	377.96
6/ 18.12.5 (A.R.)	Providing and fixing G.I. pipes complete with G.I. fittings excluding trenching and refilling etc. 40 mm dia nominal bore.	25.00	Meter.	201.75	5,043.73
7/ 18.12.6 (A.R.)	Providing and fixing G.I. pipes complete with G.I. fittings excluding trenching and refilling etc. 50 mm dia nominal bore.	30.00	Meter.	262.25	7,867.50
8/ 18.12.1 (A.R.)	Providing and fixing G.I. pipes complete with G.I. fittings excluding trenching and refilling etc. 15 mm dia nominal bore.	22.00	Meter.	76.20	1,676.40
9/ 18.31.1.1	Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately): Class I	1.00	Each	2,468.05	2,468.05
10/ 18.30.2	Providing flanged joints to double flanged C.I /D.I. pipes and specials including testing of joints: 100 mm diameter pipe.	2.00	Each	113.00	226.00
11/ 18.47.5 18.47.6	Providing and fixing G.I. union in existing G.I. pipe line, cutting and threading the pipe and making long screws including excavation, refilling theearth or cutting of wall and making good the same complete wherever required: i) 40 mm nominal bore. ii) 50 mm nominal bore.	2.00 1.00	Each Each	237.45 335.50	474.90 335.50
12/ 18.13.2	Making connection of G.I. distribution branch with G.I. main of following sized by providing and fixing tee, including cutting and threading the pipe etc. complete: 50 to 80 mm nominal bore.	4.00	Each	423.20	1,692.80
	TOTAL			Rs.	26,224.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.
Our quoted offer amounts to Rs. _____ (Rupees _____
_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: “Repairing of pipe line in Project Officer’s bungalow (BD-1) & in ‘B’ & ‘C’ type qtr. At Babudanga More.”
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/49/1564 Date: 24.10.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 13)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.52	Dismantling of flushing cistern of any size including stacking of useful materials near the site and disposal of unserviceable materials within 50 meter lead.	3.00	Each	143.75	430.05
2/ 17.18.2	Providing and fixing P.V.C. low level flushing cistern with manually controlled device (handle lever) conforming to IS: 7231, with all fittings and fixtures complete. 10 litre capacity- Coloured.	3.00	Each	783.85	2,351.55
3/ 17.20.1	Providing and fixing solid plastic seat with lid for pedestal type W.C. pan complete: White solid plastic seat with lid.	3.00	Each	334.95	1,004.85
4/ 17.28.2.1	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. 32 mm dia.	2.00	Each	46.80	93.60
5/ M.R.	Providing and fixing brass bib cock of approved quality 15 mm dia nominal bore.	4.00	Each	80.00	320.00
6/ M.R.	Providing & fixing brass stop cock of approved quality 15 mm dia nominal bore.	2.00	Each	95.00	190.00
7/ 18.10.1	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc. 15 mm dia nominal bore.	3.00	Metre.	105.85	316.65
8/ 18.12.3	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. 25 mm dia nominal bore.	14.00	Meter.	156.85	2,195.90
9/ (A.R.)	Providing & fixing PVC pipe complete with G.I. fittings excluding trenching and refilling etc. com.	27.00	Meter.	100.40	2,710.80
10/ 2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kind of soil.	1.00	Cum	103.40	103.40
11/ 18.13.2	Making connection of G.I. distribution branch with G.I. main of following sized by providing and fixing tee, including cutting and threading the pipe etc. complete: 50 to 80 mm nominal bore.	1.00	Each	423.20	423.20
12/ 15.44.2	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including staking of pipes within 50 metres lead as per direction of Engineer-in-charge: above 40 mm nominal bore.	36.00	Metre	29.05	1,045.80
13/ (A.R.) 18.12.6 18.12.7	Providing and fixing G.I. pipes complete with G.I. fittings excluding trenching and refilling etc. i) 50 mm dia nominal bore. ii) 65 mm dia nominal bore.	24.00 12.00	Meter. meter	262.25 338.30	6,294.00 4,059.60
14/ 18.17.4	Providing and fixing un metal gate valve with C.I. wheel of approved quality (screwed end): 50 mm nominal bore.	1.00	Each	578.20	578.20
15/ 18.47.6 18.47.7	Providing and fixing G.I. union in existing G.I. pipe line, cutting and threading the pipe and making long screws including excavation, refilling theearth or cutting of wall and making good the same complete wherever required: i) 50 mm nominal bore. ii) 65 mm dia nominal bore.	 1.00 1.00	 Each Each	 335.50 528.30	 335.50 528.30
	TOTAL			Rs.	22,981.40
			Say	Rs.	22,981.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____ % (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063



1. Name of Work: “Repairing and maint. Of One unit Qtr. At Junkundar Pathak (Qtr. No. CTQ/JUN/2).”
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/49/1564 Date: 24.10.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 14)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	38.93	Sqm	8.20	319.22
2/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	38.93	Sqm	67.65	2,633.61
3/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	0.45	Cum	368.45	165.80
4/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	18.52	Sqm	143.75	2,662.25
5/ M.R.	Taking down damaged W.C. pan.	1.00	Each	100.00	100.00
6/ 17.13.1	Providing and fixing white vitreous china water closet squatting pan (Indian type) Long pattern W.C. pan of size 580mm	1.00	Each	534.60	534.60
7/ M.R.	Providing & fixing PVC vent pipe 75 mm dian nominal bore.	3.00	Meter.	70.00	210.00
8/ 17.17.1	Providing and fixing a pair of white vitreous china foot rests of standard pattern for squatting pan water closet: 250x130x30mm	1.00	Pair	111.70	111.70
9/ 17.40.1.1	Providing and fixing heel rest sanitary bend Sand cast iron S & S as per IS – 1729	1.00	Each	244.50	244.50
10/ 19.1.1	Providing, laying and jointing glazed stoneware pipes grade ‘A’ with stiff mixture of cement mortar in the proportion of 1:1 (1 cement:1 fine sand) including testing of joints etc. complete: 100 mm diameter.	7.00	Meter	105.90	741.30
11/ M.R.	Septic tank cleaning.	1.00	Each	300.00	300.00
12/ 6.12.2	Half brick masonry with F.P.S. brick of class designation in foundations and plinth in . cement mortar 1:4 (1 cement: 4 coarse sand).	2.68	Sqm	257.20	689.29
13/ 13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:4 (1 Cement: 4 fine sand).	7.12	Sqm	97.90	697.04
14/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	483.92	Sqm	4.10	1,984.07
15/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	84.34	Sqm	22.85	1,927.16
	TOTAL			Rs.	13,320.54
			Say	Rs.	13,320.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote ____% (_____) above / below the estimated cost.
Our quoted offer amounts to Rs. _____ (Rupees _____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
 (A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063



1. Name of Work: “Installation of sintex with water connection at B.Mata.”

2. Name of Tenderer :

3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/49/1564

Date: 24.10.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 15)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 18.48	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI: 12701 marked with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	1,500.00	Per Litre.	5.25	7,875.00
	TOTAL			Rs.	7,875.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote ____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer

FOR PAYMENT TO CONTRACTORS

(Note: To be submitted in Triplicate)

PROFORMA FOR COLLECTING PAYMENT THROUGH ELECTRONIC MODE INCLUDING ELECTRONIC FUND TRANSFER (EFT) & ELECTRONIC CLEARING SYSTEM (ECS)

1	Vendor/ supplier/ contractor/ customer's name & address (with telephone number & Fax number)	
2	Particulars of Bank Account	
	a) Bank Name	
	b) Branch Name (Including RTGS Code)	
	Address	
	Telephone No. & Fax No.	
	c) 9 – Digit Code Number of the Bank & Branch (Appearing on the MICR Cheque issued on the bank) or 5 digit code number of SBI	
	d) Account Type (S.B. Account/ Current Account or Cash Credit with code 10/11/13)	
	e) Ledger No./ Ledger Folio No.	
	f) Account Number (Core Banking) & Style of Account (As appearing on the cheque Book)	

3. DATE OF EFFECT:

I hereby declare that the particulars given above are correct & complete. If the transaction is delayed or not effected at all for reasons of incomplete or incorrect information, I would not hold the user institution responsible. I have read the option invitation letter and agree to discharge responsibility expected of me as a participant under the scheme. Any bank charges levied by the bank of such e-transfer shall be borne by us.

Date: -

contractor

(_____)
Signature of customer/ vendor/ supplier/

Certified that the particulars furnished above are correct as per our records.

(_____)
Signature of the authorized officials from the Bank

DECLARATION

I, _____, Partner/Legal Attorney/ Accredited Representative of M/S _____
_____, solemnly declare that :

1. We are submitting Tender for the Work _____
_____ against Tender

Notice No. _____ dt _____
2. None of the Partners of our firm is relative of employee of Bharat Coking Coal Ltd.
3. All information furnished by us in respect of fulfillment of eligibility criteria and qualification information of this Tender is complete, correct and true.
4. None of the partners of the Firm has either individually or collectively been involved in criminal offences.
5. I hereby declare that /our firm has not been banned or delisted by any Govt. or Quasi Govt. agencies or PSUs.
6. All documents/ credentials submitted alongwith this Tender are genuine, authentic, true and valid.
7. If any information and document submitted is found to be false/ incorrect any time, department may cancel my Tender and action as deemed fit may be taken against us, including termination of the contract, forfeiture of all dues including Earnest Money and banning / delisting of our firm and all partners of the firm etc.

Signature of the Tenderer

Dated _____