



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063



Ref. No. BCCL/XII/ACE/QTN/2011-12/50/1592

Dates: 11.11.2011

QUOTATION NOTICE

Sealed Quotations on percentage rate basis are invited from the bonafide & experienced contractors for the following works: Terms and conditions:

Sl.No.	Name of the work	Estimated cost	Earnest Money	Time of completion
1.	Outer repairing works of 4 units 'A' type qtr No. A/13, 14, 15, & 16 at R.S. Colony, Begunia.	Rs. 69,104.00	Rs. 695.00	30 days
2.	Supplying & fitting of sluice valve with fitting in different place at Basantimata Colliery.	Rs. 26,819.00	Rs 270.00	20 days.
3.	Repairing of damaged pipe line and providing 9 Nos community taps at Bramsthan colony of NLOCP.	Rs. 44,995.00	Rs. 450.00	20 days
4.	Repairing of roof with PCC, floor, inside plaster wall ceiling etc. room for project officer Bunglow (Mr. K.V. Raman) Damagoria under C.V. Area.	Rs. 30,094.00	Rs. 305.00	20 days
5.	Repairing & maint. For 4 units NHS type qtr at R.K. Colony under B. Mata Colliery.	Rs. 37,754.00	Rs. 380.00	25 days
6	Rep./maint. Of 2 Units CMWO qtr. At Lalbazar (Qtr. No. D/6 & B/3) at Damagoria colliery.	Rs.23,995.00	Rs. 240.00	20 days
7	Overhauling and maintenance of filter beds at water treatment plant, Basantimata.	Rs. 42,334.00	Rs. 425.00	30 days
8	Cleaning of jungle and bushes of coal depot near Kalayan chak Quarry.	Rs. 14,054.00	Rs. 145.00	10 days.
9	Cleaning of drain from Laikdih staff colony to Bank of India, Laikdih including all adjacent drain.	Rs. 24,012.00	Rs. 245.00	15 days
10	Making pump foundation, changing of pipe and development work for pump shed for filter plant.	Rs. 29,393.00	Rs. 295.00	15 days.
11	Repairing & maint of weigh bridge near Rly. Siding DOCP.	Rs. 10,959.00	Rs. 110.00	10 days.
12	Cleaning, surface dressing of Bank of Barakar river at Begunia.	Rs. 8,159.00	Rs. 85.00	10 days.
13	Repair of Transformer room at Sushil incline Basantimata Colliery.	Rs. 32,559.00	Rs. 330.00	20 days.

- Interested parties can collect the BOQ and other related papers of the Quotation from the office of the Area Civil Engineer, C.V. Area-XII, AT-Begunia, P.O –Barakar(W.B.). **From 22.11.2011 to 26.11.2011** during office hours except Sunday and Holiday. BOQ and other relevant pages (Declaration & EFT form) can be down loaded from BCCL website- <http://www.bccl.gov.in>
- Completed sealed Quotations will be received on **28.11.2011 up to 3.00 P.M.** at the following places. Quotation may Opt. any one place to submit their quotation as per their convenience.
 - In the office of the General Manager, C.V. Area-XII, AT-Begunia, P.O –Barakar(W.B.)
 - At BCCL H.Q. i.e. C.I.S.F. post, near Koyala Bhawan gate, Koyala Nagar, Dhanbad.
 - Office of the ACE, CCWO, W.W.Z. Area, Saraidhela, Dhanbad.
 - Office of the ACE, CHD, Jagjiban Nagar, Dhanbad.
- Quotations will be opened on **30.11.2011 at 11.30 A.M.** in the office of the Area Civil Engineer, C.V. Area-XII, AT-Begunia, P.O –Barakar(W.B.).
- Specification of work shall be governed by DSR-2007 & C.P.W.D specification.
- Terms and conditions as per C.I.L. C.E. manual shall be applicable against the quotations submitted against this Quotation Notice.

ContdP/2

6. Completed sealed Quotations shall consist of (1) EMD in the shape of cash receipt obtained from the finance deptt. C.V. Area-XII or DD from any Scheduled/Nationalised Bank, (2) Experience certificate, (3) Copy of Pan card, (4) Copy of VAT/Sales Tax clearance certificate along with VAT/Sales Tax registration No.(TIN), (5) Declaration and (6) EFT (Electronic Fund Transfer) & ECS (Electronic Clearance System) as per the format issued along with the Tender paper and (7) BOQ along with quoted rate by the Tenderer.
7. The quoted rate shall include all taxes and levies.
8. Statutory deductions for Income Tax and Sales Tax shall be made as per Rules and notifications.
9. The contractor has to abide by the Rules of Contract Labour Regulation & Abolition Act-.
10. Validity of tender shall be 120 days from the date of opening of the tender.
11. The contractors have to be acquainted with the site condition
12. Unless otherwise mentioned, no material will be issued by the department
13. Successful tender has to deposit 5% Performance Security (including 1% EMD) and another 5% Security Deposit will be deducted from the Running Account/ Final Bill.
14. It should be ensured that there must be provision for engagement of 25% PAPs.
15. The management of BCCL reserves right to reject any or all tender or split the work among two or more tenderers without assigning any reasons whatsoever.

Sd/
Area Civil Engineer
Chanch Victoria Area-XII

Copy to :-

- 1) GM, Chanch Victoria Area-XII.
- 2) GM (Civil), BCCL, Koyla Nagar.
- 3) All CGM/GM of Areas/Projects under BCCL.
- 4) Addl. GM, Chanch Victoria Area-XII.
- 5) A.F.M., Chanch Victoria Area-XII.
- 6) All P.O.s of Chanch Victoria Area-XII.
- 7) Cashier, C.V. Area-XII
- 8) Incharge,, CISF Post, Koyala Bhawan gate, Koyala Nagar,
- 9) Assistant Commandant, CISF, C.V. Area-XII-with 2 copies of NIT for displaying on Notice Board.
- 10) Builders Association of India, Central Akashkinaree Kanta, Katras Garh, Dhanbad-828113.
- 11) ACE CCWO, W.W.Z Area saraidhela, Dhanbad.
- 12) ACE CHD, jagiban Nagar, Dhanbad



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Outer repairing works of 4 units ‘A’ type qtr no. A/13, 14, 15, & 16 at R.S. Colony, Begunia.”**
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/50/1592

Date: 11.11.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 1)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	350.00	Sqm	67.65	23,677.50
2/ 12.40.2	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS: 13592 Type A including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion. (i) single socketed pipes. 110 mm diameter.	48.76	Metre	163.40	7,967.38
3/ 12.42.5.2	Providing and fixing on wall face unplasticised – PVC moulded fittings / accessories for unplasticised Rigid PVC rain water pipes conforming to IS: 13592 Type A including jointing with seal ring conforming to IS: 5382 leaving 10 mm gap for thermal expansion. 110mm bend.	8.00	Each	134.20	1,073.60
4/ 13.11	18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement: 5 coarse sand) finished with a top layer 6 mm thick cement plaster 1:6 (1 cement: 6 fine sand).	12.00	Sqm	111.15	1,333.80
5/ 10.2	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete:.	262.29	Kg	46.35	12,157.14
6/ A.R.	Providing and fixing sheet of all complete.	13.16	Sqm	514.89	6,775.95
7/ 13.39.1	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats) with a base coat of white washing with lime.	412.43	Sqm	9.30	3,835.59
8/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	200.00	Sqm	8.20	1,640.00
9/ 10.2	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete:.	83.20	Kg	46.35	3,856.32
10/ 13.61.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work.	6.64	Sqm	35.35	234.72
11/ 12.11	Extra for providing and fixing wind ties of 40x6 mm flat iron section.	49.37	Metre	73.65	3,636.10
12/ 15.3	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.	0.50	Cum	537.65	268.82
13/ 12.43.2	Providing and fixing unplasticised- PVC pipe clips of approved design to unplasticised – PVC rain water pipes by means of 50x50x50 mm hard wood plugs, screwed with M.S. screws of required length including cutting brick work and fixing in cement mortar 1:4 (1 Cement: 4 coarse sand) and making good the wall etc. complete. 110 mm	20.00	Each	96.90	1,938.00

Contd...P/2

14/ 14.2.1	Fixing chowkhats in existing opening including embedding chowkhats in floors or walls cutting masonry for holdfasts embedding hold fasts in cement concrete blocks with cement concrete 1:3:6 (1 Cement: 3 coarse sand: 6 graded stone aggregate 20 mm nominal size). Painting two coats of approved wood preservative to sides of chowkhats and making good the damages to walls and floors as required complete including disposal of rubbish to the dumping ground within 50 meters lead: Door chowkhats.	2.00	Each	354.45	708.90
	TOTAL			Rs.	69,103.82
			Say	Rs.	69,104.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063



- 1 .Name of Work: “Supplying & fitting of sluice valve with fitting in different place at Basantimata Colliery.”
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/50/1592 Date: 11.11.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 2)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 18.31.3.1	Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately): Class I	2.00	Each	3,689.10	7,378.70
2/ 18.31.1.1	Providing and fixing C.I. sluice valves (with cap) complete with bolts, nuts, rubber insertions etc. (the tail pieces if required will be paid separately): Class I	1.00	Each	2,468.05	2,468.05
3/ 18.26.1	Providing and laying flanged C.I. standard specials such as tees, bends, collars tapers, caps etc., suitable for flanged jointing as per IS 1538: up to 300 mm dia.	1.40	Quintal	5,123.45	7,172.83
4/ 18.29	Supplying pig lead at site of work.	0.136	Quintal	6,742.20	916.91
5/ 18.28.3	Providing lead caulked joints to spun iron or C.I. pipes and specials including testing of joints but excluding the cost of pig lead: 300 mm diameter pipe.	4.00	Each	123.30	493.20
6/ 18.30.4 18.30.1	Providing flanged joints to double flanged C.I /D.I. pipes and specials including testing of joints: i) 150 mm diameter pipe. ii) 100 mm diameter pipe.	4.00 2.00	Each Each	156.90 113.00	627.60 226.00
7/ 6.1.2	Brick work in F.P.S bricks of class designation 50 in foundation and plinth in: Cement mortar 1:6 (1 cement: 6 coarse sand).	2.00	Cum	2,007.00	4,415.40
8/ 13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:4 (1 Cement: 4 fine sand).	6.69	Sqm	97.90	654.95
9/ 5.12	Providing, hoisting and fixing up to floor five level precast reinforced cement concrete work in string courses, bands copings, bed plates, anchor blocks, plain window sills and the like including the cost of required centering, shuttering, finishing smooth with 6 mm thick cement plaster 1:3 (1 cement: 3 fine sand) on exposed surfaces complete but excluding cost of reinforcement with 1:2:4 (1 cement : 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	0.33	Cum	4,882.15	1,611.10
10/ 5.22.3	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete . Cold twisted bars.	20.00	K.G.	42.70	854.00
	TOTAL			Rs.	26,818.74
			Say	Rs	26,819.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote ____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063



1. Name of Work: **“Repairing of damaged pipe line and providing 9 Nos community taps at Bramsthan colony of NLOCP.”**
2. Name of Tenderer
3. Address:
4. NIT No. : BCCL/XII/ACE/QTN/2011-12/50/1592 Date: 11.11.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 3)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.45.1	Dismantling C.I. pipes including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means breaking lead caulked joints, melting of lead and making into blocks including stacking of pipes, lead at site within 50 metre leas as per direction of Engineer-in-charge: up to 150 mm diameter.	7.00	Metre	63.45	444.15
2/ A.R	Labour charges for laying 150 mm dia MS pipe /CI pipe.	5.50	Meter	20.15	110.82
3/ (A.R.) 18.12.6 18.12.1	Providing and fixing G.I. pipes complete with G.I. fittings excluding trenching and refilling etc. i) 50 mm dia nominal bore. ii) 15 mm dia nominal bore.	36.00 8.10	Meter. Meter	262.25 76.20	9,441.00 617.22
4/ M.R.	Providing & laying PVC pipe complete with GI fittings including trenching & filling etc. i) 25 mm dia nominal bore. ii) 40 mm dia nominal bore. iii) 50 mm dia nominal bore.	50.00 24.00 68.00	Meter Meter Meter	118.25 182.75 238.05	5,912.50 4,386.00 16,187.40
5/ M.R	Providing and fixing collar joint of C.I. with rubbed band for asbestor cement pipe	2.00	Each	800.00	1,600.00
6/ 15.44.2	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including staking of pipes within 50 metres lead as per direction of Engineer-in-charge: above 40 mm nominal bore.	40.00	Metre	29.05	1,162.00
7/ M.R	Labour charges for relaying 50mm dia G.I. pipes excluding cost of excavation & refilling.	12.00	Meter	17.20	206.40
8/ 18.13.2	Making connection of G.I. distribution branch with G.I. main of following sized by providing and fixing tee, including cutting and threading the pipe etc. complete: 50 to 80 mm nominal bore.	6.00	Each	423.20	2,539.20
9/ M.R.	Providing & fixing PVC bibcock of approved quality.	9.00	Each	25.00	225.00
10/ 18.17.4	Providing and fixing un metal gate valve with C.I. wheel of approved quality (screwed end): 50 mm nominal bore.	2.00	Each	578.20	1,156.40
11/ 18.47.6	Providing and fixing G.I. union in existing G.I. pipe line, cutting and threading the pipe and making long screws including excavation, refilling theearth or cutting of wall and making good the same complete wherever required: 50 mm nominal bore.	3.00	Each	335.50	1,006.50
	TOTAL			Rs.	44,995.00

Having gone through the Tender documents & elements of work in the bill of quantity:-

I / we quote _____ % (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Repairing of roof with PCC, floor, inside plaster wall ceiling etc. room for project officer Bunglow (Mr. K.V. Raman) Damagoria under C.V. Area.”**

2. Name of Tenderer :

3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/50/1592

Date: 11.11.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 4)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ BCCL SOR	Removing of old tar felt.	144.07	Sqm	1.86	267.97
2/ 22.14.1	Grading roof for water proofing treatment with cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	5.00	Cum	3,314.25	16,571.25
3/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	1.43	Cum	368.45	526.88
4/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	64.49	Sqm	143.75	9,270.43
5/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	43.12	Sqm	8.20	353.58
6/ 13.16.1	6mm cement plaster of mix: 1:3 (1 cement: 3 fine sand).	22.30	Sqm	62.15	1,385.94
7/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	20.81	Sqm	67.65	1,407.79
8/ 14.45.1	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade: old work (one or more coats).	20.81	Sqm	14.90	310.07
	TOTAL			Rs.	30,093.91
			Say	Rs.	30,094.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote ____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Repairing & maint. For 4 units NHS type qtr at R.K. Colony under B. Mata Colliery.”**
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/50/1592

Date: 11.11.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 5)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	827.00	Sqm	4.10	3,390.70
2/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	146.00	Sqm	22.85	3,336.10
3/ 15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 meters lead: of are 3 sq. metres and below.	8.00	Each	54.60	436.80
4/ 10.2	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete:..	123.25	Kg	46.35	5,712.64
5/ 9.1.3	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position. Kiln seasoned and chemically treated Hollock wood.	0.054	Cum	31,339.00	1,692.31
6/ 9.53	Providing 40x5 mm flat iron hold fast 40 cm long including fixing to frame with 10 mm diameter bolts, nuts and wooden plugs and embeddings in cement concrete block 30x10x15cm 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).	8.00	Each	61.50	492.00
7/ SOR 1985	Providing & fitting flat 9 mm hold fast.	6.40	Sqm	572.50	3,664.00
8/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	103.00	Sqm	67.65	6,967.95
9/ 5.12	Providing, hoisting and fixing up to floor five level precast reinforced cement concrete work in string courses, bands copings, bed plates, anchor blocks, plain window sills and the like including the cost of required centering, shuttering, finishing smooth with 6 mm thick cement plaster 1:3 (1 cement: 3 fine sand) on exposed surfaces complete but excluding cost of reinforcement with 1:2:4 (1 cement : 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	0.43	Cum	4,880.15	2,098.46
10/ 5.22.3	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete . Cold twisted bars.	30.00	K.G.	42.70	1,281.00
11/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	60.40	Sqm	143.75	8,682.50
	TOTAL			Rs	37,754.46
			Say	Rs.	37,754.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer

13/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	50.00	Sqm	8.20	410.00
14/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	0.75	Cum	368.45	276.33
	TOTAL			Rs.	23,995.35
			Say	Rs	23,995.00


Having gone through the Tender documents & elements of work in the bill of quantity:-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



4. NIT No. : BCCL/XII/ACE/QTN/2011-12/50/1592 Date: 11.11.2011
5. Details of E.M.D. No: Rs: Date:

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ A.R.	Overhauling cleaning, erection & painting of all equipment of R.G. filter of under drainage system and carefully taking out of filter medias and spreading spreading the same in low land out outside of the plant and charging of new filter medias of various sized in uniform layers i/c arrangement of bye pass system for continuous supply of water during shut down period of hopper cleaning (Cost of filter medias will be paid separately).	1.00	Each	18,500.00	18,500.00
2/ A.R	Cleaning, washing of hopper bottom setting tank (all deposited sludge and foreign materials are to be taken out side of the plant within a lead of 50 meter.	1.00	Each	3,100.00	3,100.00
3/ A.R.	Supplying laying of filter medias of required sizes and gradient.	200.00	cft.	30.00	6,000.00
4/ A.R.	Providing & fixing of defective parts of Mushroom valves as per specification 250 mm dia.	1.00	Each	4,002.50	4,002.50
5/ A.R.	Repairing of rof recorder with repairing of defective parts.	1.00	Each	800.00	800.00
6/ A.R.	Repairing of sluice valve 100 mm dia.	2.00	Each	1,466.00	2,932.00
7/ A.R.	Repairing of sluice valve 250 mm dia.	1.00	Each	2,242.50	2,242.50
8/ 18.30.2 18.30.6	Providing flanged joints to double flanged C.I /D.I. pipes and specials including testing of joints: i) 100 mm diameter pipe. ii) 250 mm diameter pipe	4.00 2.00	Each Each	113.00 236.75	452.00 447.50
9/ A.R.	Cleaning of cleaned water sluice including washing with bleaching powder and disposal of silt mud etc. within a lead of 50 met as per direction of E/inc.	1.00	Each	2,028.75	2,028.75
10/ 18.12.8	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. 80 mm dia nominal bore.	3.00	Meter.	440.30	1,320.90
11/ 18.46.8	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc .complete (New work).80 mm nominal bore.	1.00	Each	507.40	507.40
	TOTAL			Rs.	42,333.55
			Say	Rs.	42,333.55

I / we quote _____ % (_____) above / below the estimated cost.
Our quoted offer amounts to Rs. _____ (Rupees _____) including the above percentage.

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063



1. Name of Work: “Cleaning of jungle and bushes of coal depot near Kalayan chak Quarry.”
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/50/1592 Date: 11.11.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 8)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 2.31	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	5,325.50	100 sqm	263.90	14,053.99
	TOTAL			Rs.	14,053.99
			Say	Rs.	14,054.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063



- 1 .Name of Work: “Cleaning of drain from Laikdih staff colony to Bank of India, Laikdih including all adjacent drain.”
2. Name of Tenderer:
3. Address:
4. NIT No. : BCCL/XII/ACE/QTN/2011-12/50/1592 Date: 11.11.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 9)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ A.R	Cleaning of Katch /pucca drain including disposal of exterminated material such as liquid mud, sludge etc up to 50 mter. Lead as drain by Engineer-in-charge.	222.15	Cum	108.09	24,012.19
	TOTAL			Rs.	24,012.19
			Say	Rs.	24,012.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote ____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063



1. Name of Work: **“Making pump foundation, changing of pipe and development work for pump shed for filter plant.”**
2. Name of Tenderer:
3. Address:
4. NIT No. : BCCL/XII/ACE/QTN/2011-12/50/1592 Date: 11.11.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 10)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kind of soil.	1.49	Cum	103.40	154.06
2/ 4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level: 1:2.4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	0.84	Cum	3,257.45	2,736.25
3/ 6.1.2	Brick work in F.P.S bricks of class designation 50 in foundation and plinth in: Cement mortar 1:6 (1 cement: 6 coarse sand).	3.70	Cum	2,007.00	7,425.90
4/ 4.3.1	Centering and shuttering including strutting, propping etc. and removal of form work for: Foundation, footing, bases for columns.	0.418	Sqm	119.25	49.84
5/ 10.19	Providing and fixing M.S. round holding down bolts with nuts and washer plates complete.	25.15	Kg	52.05	1,309.05
6/ 10.2	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete:.	109.88	Kg	46.35	5,092.93
7/ 11.3.1	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat sement including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate.	15.60	Sqm	192.95	3,010.02
8/ 18.12.8 18.12.5 18.12.3	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. i) 80 mm dia nominal bore. ii) 40 mm dia nominal bore. iii) 25 mm dia nominal bore.	6.00 12.00 6.00	Meter. Meter Meter	458.15 219.60 156.85	2,748.90 2,635.20 941.10
9/ 18.46.5	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc .complete (New work).40 mm nominal bore.	3.00	Each	164.20	492.60
10/ 18.17.1	Providing and fixing un metal gate valve with C.I. wheel of approved quality (screwed end): 25 mm nominal bore.	1.00	Each	285.50	285.50
11/ 18.28.1	Providing lead caulked joints to spun iron or C.I. pipes and specials including testing of joints but excluding the cost of Pig lead: 100 mm diameter pipe.	2.00	Each	82.25	164.50
12/ 18.29	Supplying pig lead at site of work.	0.044	Quintal	6,742.20	296.65

Contd....P/2

13/ M.R.	Cleaning of old pipe i) Fitter ii) Labour	2.00 6.00	Each each	250.00 165.00	500.00 990.00
14/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	1.18	Cum	368.45	434.77
15/ 10.20	Providing and fixing bolts including nuts and washers complete.	2.00	Kg	62.75	125.50
	TOTAL			Rs	29,392.77
			Say	Rs.	29,393.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Repairing & maint of weigh bridge near Rly. Siding DOCP.”**
2. Name of Tenderer :
3. Address:
4. NIT No. : BCCL/XII/ACE/QTN/2011-12/50/1592 Date: 11.11.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 11)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	12.66	Sqm	8.20	103.81
2/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	12.66	Sqm	67.65	856.45
3/ 9.1.3	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position. Kiln seasoned and chemically treated Hollock wood.	0.03	Cum	31,339.40	940.18
4/ 9.21.1	Providing and fixing ISI marked flush door shutters conforming to IS: 2202 (part- I) non- decorative type, core of block board construction with frame of 1 st class hard wood and will matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters: 35 mm thick including ISI marked stainless steel butt hinges with necessary screws.	1.88	Sqm	929.95	1,748.30
5/ 14.5.1	Renewing glass panes, with putty and nails wherever necessary: float glass panes of thickness 4 mm.	0.82	Sqm	427.60	350.63
6/ 9.62.1	Providing and fixing ISI marked oxidized M.S. sliding door bolts with nuts and screws etc. complete: 300x16 mm	1.00	Each	79.60	79.60
7/ 9.63.1	Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete: 250x10 mm	1.00	Each	33.90	33.90
8/ 9.83	Providing and fixing IS: 3564 marked Aluminium die cast body tubular type universal hydraulic door closer with necessary accessories and screws etc. complete.	1.00	Each	610.60	610.60
9/ 12.15.1	Painting top of roofs with bitumen of approved quality at 17kg per 10sqm impregnated with a coat of coarse sand at 60 cudm per 10sqm including cleaning the slab surface with brushes and finally with a piece of cloth lightly soaked in kerosene oil complete: with residual type petroleum bitumen of penetration 80/100	26.58	Sqm	63.00	1,674.54
10/ 14.45.1	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade: old work (one or more coats).	94.55	Sqm	14.90	1,408.79
11/ 10.2	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete:.	54.00	Kg	46.35	2,502.90

Contd...P/2

12/ 13.61.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work.	8.34	Sqm	35.35	294.81
13/ 14.2.1	Fixing chowkhats in existing opening including embedding chowkhats in floors or walls cutting masonry for holdfasts embedding hold fasts in cement concrete blocks with cement concrete 1:3:6 (1 Cement: 3 coarse sand: 6 graded stone aggregate 20 mm nominal size). Painting two coats of approved wood preservative to sides of chowkhats and making good the damages to walls and floors as required complete including disposal of rubbish to the dumping ground within 50 meters lead: Door chowkhats.	1.00	Each	354.45	354.45
	TOTAL			Rs.	10,958.96
			Say	Rs.	10,959.00

Having gone through the Tender documents & elements of work in the bill of quantity:-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____
_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063



1. Name of Work: “Cleaning, surface dressing of Bank of Barakar river at Begunia.
2. Name of Tenderer :
3. Address:
4. NIT No. : BCCL/XII/ACE/QTN/2011-12/50/1592 Date: 11.11.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 12)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 2.31	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	1,086.93	100 sqm	263.90	2,868.40
2/ 2.6.1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth. 1.5m in width as well as 10sqm on plan) including disposal of excavated earth, lead up to 50m and lift up to 1.5m, disposed earth to be leveled and neatly dressed. All kinds of soil.	17.68	Cum	101.85	1,800.71
3/ 2.28.1	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15cm deep and disposal of rubbish, lead up to 50m and lift up to 1.5m. All kind of soil.	510.95	100 Sqm	512.10	2,616.57
4/ 1.1.2	Carriage of material by mechanical transport including loading, un loading and stacking. Lead up to 1 K.M. Earth	17.68	Cum	49.42	873.75
	TOTAL			Rs.	8,159.43
			Say	Rs.	8,159.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote ____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: “Repair of Transformer room at Sushil incline Basantimata Colliery.”
2. Name of Tenderer :
3. Address:
4. NIT No. : BCCL/XII/ACE/QTN/2011-12/50/1592 Date: 11.11.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 13)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 12.15.1	Painting top of roofs with bitumen of approved quality at 17kg per 10sqm impregnated with a coat of coarse sand at 60 cudm per 10sqm including cleaning the slab surface with brushes and finally with a piece of cloth lightly soaked in kerosene oil complete: with residual type petroleum bitumen of penetration 80/100	152.00	Sqm	63.00	9,576.00
2/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	1.86	Cum	368.45	685.31
3/ 11.3.1	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat sement including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate.	51.00	Sqm	192.95	9,840.45
4/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	65.52	Sqm	67.65	4,432.42
5/ 6.1.2	Brick work in F.P.S bricks of class designation 50 in foundation and plinth in: Cement mortar 1:6 (1 cement: 6 coarse sand).	2.35	Cum	2,007.00	4,716.45
6/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	528.35	Sqm	4.10	2,166.23
7/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	50.00	Sqm	22.85	1,142.50
	TOTAL			Rs.	32,559.36
			Say	Rs.	32,559.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote ____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer

FOR PAYMENT TO CONTRACTORS

(Note: To be submitted in Triplicate)

PROFORMA FOR COLLECTING PAYMENT THROUGH ELECTRONIC MODE INCLUDING ELECTRONIC FUND TRANSFER (EFT) & ELECTRONIC CLEARING SYSTEM (ECS)

1	Vendor/ supplier/ contractor/ customer's name & address (with telephone number & Fax number)	
2	Particulars of Bank Account	
	a) Bank Name	
	b) Branch Name (Including RTGS Code)	
	Address	
	Telephone No. & Fax No.	
	c) 9 – Digit Code Number of the Bank & Branch (Appearing on the MICR Cheque issued on the bank) or 5 digit code number of SBI	
	d) Account Type (S.B. Account/ Current Account or Cash Credit with code 10/11/13)	
	e) Ledger No./ Ledger Folio No.	
	f) Account Number (Core Banking) & Style of Account (As appearing on the cheque Book)	

3. DATE OF EFFECT:

I hereby declare that the particulars given above are correct & complete. If the transaction is delayed or not effected at all for reasons of incomplete or incorrect information, I would not hold the user institution responsible. I have read the option invitation letter and agree to discharge responsibility expected of me as a participant under the scheme. Any bank charges levied by the bank of such e-transfer shall be borne by us.

Date: -

contractor

(_____)
Signature of customer/ vendor/ supplier/

Certified that the particulars furnished above are correct as per our records.

(_____)
Signature of the authorized officials from the Bank

DECLARATION

I, _____, Partner/Legal Attorney/ Accredited Representative of M/S _____
_____, solemnly declare that :

1. We are submitting Tender for the Work _____
_____ against Tender

Notice No. _____ dt _____

2. None of the Partners of our firm is relative of employee of Bharat Coking Coal Ltd.
3. All information furnished by us in respect of fulfillment of eligibility criteria and qualification information of this Tender is complete, correct and true.
4. None of the partners of the Firm has either individually or collectively been involved in criminal offences.
5. I hereby declare that /our firm has not been banned or delisted by any Govt. or Quasi Govt. agencies or PSUs.
6. All documents/ credentials submitted along with this Tender are genuine, authentic, true and valid.
7. I/ We hereby agree and assure the management that provision of engagement of 25% PAPs will be followed as per contract.
8. If any information and document submitted is found to be false/ incorrect any time, department may cancel my Tender and action as deemed fit may be taken against us, including termination of the contract, forfeiture of all dues including Earnest Money and banning / delisting of our firm and all partners of the firm etc.

Signature of the Tenderer

Dated_____