



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063



Ref. No. BCCL/XII/ACE/QTN/2011-12/58/1677

Dates: 03.12.2011

QUOTATION NOTICE

Sealed Quotations on percentage rate basis are invited from the bonafide & experienced contractors for the following works: Terms and conditions:

Sl.No.	Name of the work	Estimated cost	Earnest Money	Time of completion
1.	Repairing & maint of 2 (Two) units NHS qtr. No. 65 & 70 at Depo colony, Damagoria colliery.	Rs. 39,042.00	Rs. 391.00	20 days.
2.	Providing pipe line connection from main pipe line to Block No. DB-6 & DB-7 at R.K. Colony.	Rs. 32,946.00	Rs. 330.00	15 days.
3.	Making approach at Bilaspuria dhowrah of Damagoria of Damagoria colliery.	Rs. 74,078.00	Rs. 741.00	25 days
4.	Re- arrangement of pipe line at Laikdih camp office.	Rs. 43,280.00	Rs. 435.00	15 days
5.	Repairing & maint of 2 (Two) units NHS qtr. No. DBB/3/5 and DBB/1/7 at R.K. Colony, DBOCP.	Rs. 50,698.00	Rs. 510.00	25 days
6	Repairing & maint. Of 2 units NHS qtrs at Bramsthan colony . (D-3 & A-5).	Rs.45,245.00	Rs.455.00	20 days
7	Repairing and maint of 3 units qtrs. At Nichu dhowrah of V. West colliery (Qtr. No. 26/5. 18/1 & 19/1).	Rs. 39,104.00	Rs. 395.00	25 days
8	Petty repairing & maint of Thana building chirkunda under C.V. Area.	Rs. 12,691.00	Rs. 130.00	15 days.
9.	Repairing & maint. of 2 (Two) units NHS qtr. at Project colony of Damagoria (B-1 & B-9).	Rs. 36,062.00	Rs. 365.00	20 days
10	Repairing & cleaning of septic tank for new colony B. Mata Colliery at different site.	Rs. 16,498.00	Rs. 165.00	15 days
11	Repairing & maint. one unit NHS type qtr. at Mugma under B. Mata colliery Qtr. No. -10.	Rs. 36,253.00	Rs. 365.00	15 days
12	Repairing & maint of 2 units 'B' type qtrs. At Chanch more DBOCP.	Rs. 24,598.00	Rs. 250.00	20 days
13	Repairing & maint. of 3.3 KVA sub-station at NLOCP.	RS. 25,880.00	Rs. 260.00	15 days
14	Repairing & maint. For R.K.S.S.Y weigh bridge at DBOCP under C.V. Area. Including maitn. Of boundry wall stock yard & repairing of check post including office of DBOCP.	Rs. 43,562.00	Rs. 440.00	15 days
15	Precast RCC slab for main drain which have passes main entrance of DOCP office & replacement of Chowkhats of Toilets door & painting the same of DOCP office under C.V. Area.	Rs. 8,741.00	Rs. 90.00	10 days.

- Interested parties can collect the BOQ and other related papers of the Quotation from the office of the Area Civil Engineer, C.V. Area-XII, AT-Begunia, P.O –Barakar(W.B.). **From 10.12.2011 to 14.12.2011** during office hours except Sunday and Holiday. BOQ and other relevant pages (Declaration & EFT form) can be down loaded from BCCL website- <http://www.bccl.gov.in>
- Completed sealed Quotations will be received on **15.12.2011 up to 3.00 P.M.** at the following places. Quotation may Opt. any one place to submit their quotation as per their convenience.
 - In the office of the General Manager, C.V. Area-XII, AT-Begunia, P.O –Barakar(W.B.)
 - At BCCL H.Q. i.e. C.I.S.F. post, near Koyala Bhawan gate, Koyala Nagar, Dhanbad.
 - Office of the ACE, CCWO, W.W.Z. Area, Saraidhela, Dhanbad.
 - Office of the ACE, CHD, Jagjiban Nagar, Dhanbad.
- Quotations will be opened on **17.12.2011 at 11.30 A.M.** in the office of the Area Civil Engineer, C.V. Area-XII, AT-Begunia, P.O –Barakar(W.B.).
- Specification of work shall be governed by DSR-2007 & C.P.W.D specification.
- Terms and conditions as per C.I.L. C.E. manual shall be applicable against the quotations submitted against this Quotation Notice.

ContdP/2

-P/2-

6. Completed sealed Quotations shall consist of (1) EMD in the shape of cash receipt obtained from the finance deptt. C.V. Area-XII or DD from any Scheduled/Nationalised Bank, (2) Experience certificate, (3) Copy of Pan card, (4) Copy of VAT/Sales Tax clearance certificate along with VAT/Sales Tax registration No.(TIN), (5) Declaration and (6) EFT (Electronic Fund Transfer) & ECS (Electronic Clearance System) as per the format issued along with the Tender paper and (7) BOQ along with quoted rate by the Tenderer.
7. The quoted rate shall include all taxes and levies.
8. Statutory deductions for Income Tax and Sales Tax shall be made as per Rules and notifications.
9. The contractor has to abide by the Rules of Contract Labour Regulation & Abolition Act-.
10. Validity of tender shall be 120 days from the date of opening of the tender.
11. The contractors have to be acquainted with the site condition
12. Unless otherwise mentioned, no material will be issued by the department
13. Successful tender has to deposit 5% Performance Security (including 1% EMD) and another 5% Security Deposit will be deducted from the Running Account/ Final Bill.
14. It should be ensured that there must be provision for engagement of 25% PAPs.
15. The management of BCCL reserves right to reject any or all tender or split the work among two or more tenderers without assigning any reasons whatsoever.

Sd/
Area Civil Engineer
Chanch Victoria Area-XII

Copy to :-

- 1) GM, Chanch Victoria Area-XII.
- 2) GM (Civil), BCCL, Koyla Nagar.
- 3) All CGM/GM of Areas/Projects under BCCL.
- 4) Addl. GM, Chanch Victoria Area-XII.
- 5) A.F.M., Chanch Victoria Area-XII.
- 6) All P.O.s of Chanch Victoria Area-XII.
- 7) Cashier, C.V. Area-XII
- 8) Incharge,, CISF Post, Koyala Bhawan gate, Koyala Nagar,
- 9) Assistant Commandant, CISF, C.V. Area-XII-with 2 copies of NIT for displaying on Notice Board.
- 10) Builders Association of India, Central Akashkinaree Kanta, Katras Garh, Dhanbad-828113.
- 11) ACE CCWO, W.W.Z Area saraidhela, Dhanbad.
- 12) ACE CHD, jagiban Nagar, Dhanbad



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Repairing & maint of 2 (Two) units NHS qtr. No. 65 & 70 at Depo colony, Damagoria colliery.”**
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/58/1677 Date: 03.12.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 1)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	52.22	Sqm	143.75	7,506.62
2/ 10.2	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete:.	193.90	Kg	46.35	8,987.26
3/ 13.16.1	6mm cement plaster of mix: 1:3 (1 cement: 3 fine sand).	17.85	Sqm	62.15	1,109.37
4/ 9.5.2.2	Providing and fixing paneled or paneled and glazed shutters for doors, windows and clerestory windows including ISI marked black enameled M.S. butt hinges with necessary screws excluding, paneling which will be paid for separately. 30 mm thick shutters.	6.24	Sqm	810.90	5,060.01
5/ 17.13.1	Providing and fixing white vitreous china water closet squatting pan (Indian type) Long pattern W.C. pan of size 580mm	2.00	Each	534.60	1,069.20
6/ 17.60.1.2	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors: sand cast iron S & S as per IS: 1729.	2.00	Each	442.10	884.20
7/ 17.17.1	Providing and fixing a pair of white vitreous china foot rests of standard pattern for squatting pan water closet: 250x130x30mm	2.00	Pair	111.70	223.40
8/ 9.1.2	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position. Sal wood	0.073	Cum	30,511.90	2,227.36
9/ 9.53	Providing 40x5 mm flat iron hold fast 40 cm long including fixing to frame with 10 mm diameter bolts, nuts and wooden plugs and embeddings in cement concrete block 30x10x15cm 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).	12.00	Each	61.50	738.00
10/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	330.00	Sqm	4.10	1,353.00
11/ 13.39.1	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats) with a base coat of white washing with lime.	130.00	Sqm	9.30	1,209.00
12/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	70.00	Sqm	22.85	1,599.50
13/ M.R.	Supplying sweeper of all.	1.00	Each	150.00	150.00
14/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	1.25	Cum	368.45	460.56
15/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	40.00	Sqm	67.65	2,706.00
16/ 5.12	Providing, hoisting and fixing up to floor five level precast reinforced cement concrete work in string courses, bands copings, bed plates, anchor blocks, plain window sills and the like including the cost of required centering, shuttering, finishing smooth with 6 mm thick cement plaster 1:3 (1 cement: 3 fine sand) on exposed surfaces complete but excluding cost of reinforcement with 1:2:4 (1 cement : 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	0.10	Cum	4,880.15	488.01
17/ 5.22.3	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete . Cold twisted bars.	30.00	K.G.	42.70	1,381.00

Contd.....P/2

18/ 15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 meters lead: of are 3 sq. metres and below.	5.00	Each	54.60	273.00
19/ 14.2.1 14.2.2	Fixing chowkhats in existing opening including embedding chowkhats in floors or walls cutting masonry for holdfasts embedding hold fasts in cement concrete blocks with cement concrete 1:3:6 (1 Cement: 3 coarse sand: 6 graded stone aggregate 20 mm nominal size). Painting two coats of approved wood preservative to sides of chowkhats and making good the damages to walls and floors as required complete including disposal of rubbish to the dumping ground within 50 meters lead: i) Door chowkhats. ii) Window chowkhats.	3.00 2.00	Each Each	354.45 214.20	1,063.35 428.40
20/ 9.63.3	Providing and fixing ISI marked oxidesed M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete: 150x10 mm	4.00	Each	23.40	93.60
21/ 9.66.2	Providing and fixing ISI marked oxidesed M.S. handles conforming to IS:4992 with necessary screws etc. complete.100mm	4.00	Each	7.75	31.00
	TOTAL			Rs.	39,041.84
			Say	Rs.	39,042.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____ % (_____) above / below the estimated cost.
Our quoted offer amounts to Rs. _____ (Rupees _____
_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



- 1 .Name of Work: **“Providing pipe line connection from main pipe line to Block No. DB-6 & DB-7 at R.K. Colony.”**
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/58/ 1677 Date: 03.12.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 2)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ M.R.	Providing & laying PVC pipes complete with G.I. Fitting excluding trenching and resitting etc. com.				
	i) 25 mm dia nominal bore.	205.00	Meter	118.25	24,241.25
	ii) 20 mm dia nominal bore.	95.00	meter	87.17	8,281.15
2/ 18.13.2	Making connection of G.I. distribution branch with G.I. main of following sized by providing and fixing tee, including cutting and threading the pipe etc. complete: 50 to 80 mm nominal bore.	1.00	Each	423.20	423.20
	TOTAL			Rs.	32,945.60
			Say	Rs	32,946.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Making approach at Bilaspuria dhowrah of Damagoria of Damagoria colliery.”**

2. Name of Tenderer

3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/58/1677

Date: 03.12.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 3)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 2.6.1- 2.35	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth. 1.5m in width as well as 10sqm on plan) including disposal of excavated earth, lead up to 50m and lift up to 1.5m, disposed earth to be leveled and neatly dressed. All kinds of soil.	28.80	Cum	(101.85-13.85)=88/-	2,534.40
2/ A.R.	Providing and laying brick flat soiling of all complete.	163.03	Sqm	111.09	18,111.00
3/ 16.42	Cement concrete 1:2:4 (1 Cement: 2 coarse sand: 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete.	16.38	Cum	3,262.05	53,432.37
	TOTAL			Rs	74,077.77
			Say	Rs.	74,078.00

Having gone through the Tender documents & elements of work in the bill of quantity:-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063



1. Name of Work: **“Re- arrangement of pipe line at Laikdih camp office.”**
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/58/1677 Date: 03.12.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 4)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.44.1	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including staking of pipes within 50 metres lead as per direction of Engineer-in-charge: 15 to 40 mm nominal bore.	108.00	Metre	24.90	2,689.20
2/ 18.12.6 18.12.5	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. i) 50 mm dia nominal bore. ii) 40 mm dia nominal bore.	72.00 6.00	Meter. Meter	280.10 219.60	20,167.20 1,317.60
3/ 18.46.6 18.46.3	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc .complete (New work). i) 50 mm nominal bore. ii) 25 mm dia nominal bore.	2.00 2.00	Each Each	235.60 107.25	471.20 214.50
4/ 18.17.1 18.16.1	Providing and fixing gunmetal gate valve with C.I. wheel of approved quality (screwed end): 25 mm nominal bore. Providing and fixing brass stop cock of approved quality. 15 mm nominal bore	6.00 10.00	Each Each	285.60 191.70	1,713.60 1,917.00
5/ 18.13.1	Making connection of G.I. distribution branch with G.I. main of following sized by providing and fixing tee, including cutting and threading the pipe etc. complete: 25 to 40 mm nominal bore.	6.00	Each	166.05	996.30
6/ A.R.	Providing & fitting P.V.C pipe 25 mm dia nominal bore.	32.00	Meter	100.53	3,216.96
7/ A.R.	Labour cost for laying G.I. Pipe 25 mm dia nominal bore.	30.00	Meter	30.41	912.30
8/ 18.12.1	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. 15 mm dia nominal bore.	3.65	Meter.	(94.05-17.85)= 76.20	278.13
9/ M.R.	Providing and fitting water sprinkler of all	4.00	Each	1,400.00	5,600.00
10/ M.R.	Providing and fitting G.I. flange of all.	1.00	Pair	200.00	200.00
11/ 15.45.1	Dismantling C.I. pipes including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means breaking lead caulked joints, melting of lead and making into blocks including stacking of pipes, lead at site within 50 metre lead as per direction of Engineer-in-charge: up to 150 mm diameter.	3.00	Metre	63.45	190.35
12/ A.R.	Laying 6” dia pipe M.S.Pipe.	3.00	Meter	51.20	153.60
13/ 18.21.2.1	Providing and fixing uplasticised PVC connection pipe with brass unions: 15 mm nominal bore.	1.00	Each	44.75	44.75
14/ 17.28.1.2	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. 40 mm dia.	1.00	Each	47.95	47.95
15/ 18.16.1	Providing and fixing brass stop cock of approved quality. 15 mm nominal bore.	1.00	Each	191.70	191.70
16/ 18.15.1	Providing and fixing brass bib cock of approved quality 15 mm nominal bore.	1.00	Each	191.70	191.70
17/ 10.1	Structural still work in single section fixed with or without connecting including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	13.71	Kg	42.15	577.87
18/ 6.12.2	Half brick masonry with F.P.S. brick of class designation in foundations and plinth in . cement mortar 1:4 (1 cement: 4 coarse sand).	2.62	Sqm	257.25	673.99

Contd....P/2

19/ 13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:4 (1 Cement: 4 fine sand).	1.85	Sqm	97.90	181.11
20/ 4.1.8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level:1:4:8 (1 cement: 4 coarse sand: 8 graded stone aggregate 40 mm nominal size)	0.044	Cum	2,449.00	107.75
21/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	0.37	Sqm	143.75	53.18
22/ 17.31	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats C.P. brass screws and washers complete.	1.00	Each	493.65	493.65
23/ 9.83	Providing and fixing IS: 3564 marked Aluminium die cast body tubular type universal hydraulic door closer with necessary accessories and screws etc. complete.	1.00	Each	610.60	610.60
24/ 2.6.1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth. 1.5m in width as well as 10sqm on plan) including disposal of excavated earth, lead up to 50m and lift up to 1.5m, disposed earth to be leveled and neatly dressed. All kinds of soil.	0.67	Cum	101.85	68.23
	TOTAL			Rs.	43,280.42
			Say	Rs	43,280.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.
Our quoted offer amounts to Rs. _____ (Rupees _____
_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Repairing & maint of 2 (Two) units NHS qtr. No. DBB/3/5 and DBB/1/7 at R.K. Colony, DBOCP.”**

2. Name of Tenderer :

3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/58/1677

Date: 03.12.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 5)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 10.2	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete..	302.66	Kg	46.35	14,028.29
2/ 14.2.1 14.2.2	Fixing chowkhats in existing opening including embedding chowkhats in floors or walls cutting masonry for holdfasts embedding hold fasts in cement concrete blocks with cement concrete 1:3:6 (1 Cement: 3 coarse sand: 6 graded stone aggregate 20 mm nominal size). Painting two coats of approved wood preservative to sides of chowkhats and making good the damages to walls and floors as required complete including disposal of rubbish to the dumping ground within 50 meters lead: i) Door chowkhats. ii) Window chowkhats.	6.00 2.00	Each Each	354.45 214.20	2,126.70 428.40
3/ 2.31	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	22.29	100 sqm	263.90	58.82
4/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	82.46	Sqm	143.75	11,853.62
5/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	1.25	Cum	368.45	460.56
6/ 15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 meters lead: of are 3 sq. metres and below.	8.00	Each	54.60	436.80
7/ 9.5.2.2	Providing and fixing paneled or paneled and glazed shutters for doors, windows and clerestory windows including ISI marked black enameled M.S. butt hinges with necessary screws excluding, paneling which will be paid for separately. 30 mm thick shutters.	3.34	Sqm	810.90	2,708.40
8/ 13.11	18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement: 5 coarse sand) finished with a top layer 6 mm thick cement plaster 1:6 (1 cement: 6 fine sand).	14.30	Sqm	111.15	1,589.45
9/ 13.16.1	6mm cement plaster of mix: 1:3 (1 cement: 3 fine sand).	14.00	Sqm	62.15	870.10
10/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	70.00	Sqm	67.65	4,735.50
11/ 6.13.2	Half brick masonry with F.P.S bricks of class designation 50 in superstructure above plinth level up to floor V level Cement mortar 1:4 (1 cement: 4 coarse sand)	2.22	Sqm	273.45	607.05
12/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	330.00	Sqm	4.10	1,353.00
13/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	72.00	Sqm	22.85	1,645.20
14/ 17.13.1	Providing and fixing white vitreous china water closet squatting pan (Indian type) Long pattern W.C. pan of size 580mm	2.00	Each	534.60	1,069.20
15/ 17.60.1.2	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors: sand cast iron S & S as per IS: 1729.	2.00	Each	442.10	884.20
16/ 17.17.1	Providing and fixing a pair of white vitreous china foot rests of standard pattern for squatting pan water closet: 250x130x30mm	2.00	Pair	111.70	223.40

Contd....P/2

17/ 5.12	Providing, hoisting and fixing up to floor five level precast reinforced cement concrete work in string courses, bands copings, bed plates, anchor blocks, plain window sills and the like including the cost of required centering, shuttering, finishing smooth with 6 mm thick cement plaster 1:3 (1 cement: 3 fine sand) on exposed surfaces complete but excluding cost of reinforcement with 1:2:4 (1 cement : 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	0.036	Cum	4,880.15	175.68
18/ 5.22.3	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete . Cold twisted bars.	15.00	K.G.	42.70	640.50
19/ 5.3	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15* landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:2 4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	0.148	Cum	3,496.35	517.45
20/ 10.1	Structural still work in single section fixed with or without connecting including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	14.55	Kg	42.15	613.28
21/ 5.9.19	Centering and shuttering including strutting, propping etc. and removal of form for: Weather shade, chajjas, corbels etc., including edges.	3.00	Sqm	258.60	775.80
22/ 9.63.3	Providing and fixing ISI marked oxidesed M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete: 150x10 mm	4.00	Each	23.40	93.60
23/ 9.66.2	Providing and fixing ISI marked oxidesed M.S. handles conforming to IS:4992 with necessary screws etc. complete.100mm	4.00	Each	7.75	31.00
24/ 9.1.2	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position. Sal wood	0.0370	Cum	30,511.90	1,128.94
25/ 9.53	Providing 40x5 mm flat iron hold fast 40 cm long including fixing to frame with 10 mm diameter bolts, nuts and wooden plugs and embeddings in cement concrete block 30x10x15cm 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).	6.00	Each	61.50	369.00
26/ 0112 0114	Supplying carpenter for adjusting door windows: i) Carpenter ii) helper	1.00 1.00	Each Each	141.60 135.25	141.60 135.25
27/ M.R.	Supplying sweeper of all.	1.00	Each	150.00	150.00
28/ 13.39.1	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats) with a base coat of white washing with lime.	90.00	Sqm	9.30	837.00
	TOTAL			Rs.	50,697.79
			Say	Rs.	50,698.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____


_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063



1. Name of Work: “Repairing & maint. Of 2 units NHS qtrs at Bramsthan colony . (D-3 & A-5).”
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/58/1677 Date: 03.12.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 6)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 meters lead: of are 3 sq. metres and below.	9.00	Each	54.60	491.40
2/ 10.2	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	367.00	Kg	46.35	17,010.45
3/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	1.62	Cum	368.45	596.88
4/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	66.72	Sqm	143.75	9,591.00
5/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	182.24	sqm	8.20	1,494.36
6/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	131.13	Sqm	67.65	8,870.94
7/ 13.16.1	6mm cement plaster of mix: 1:3 (1 cement: 3 fine sand).	51.11	Sqm	62.15	3,176.48
8/ 17.13.1	Providing and fixing white vitreous china water closet squatting pan (Indian type) Long pattern W.C. pan of size 580mm	1.00	Each	534.60	534.60
9/ 17.17.1	Providing and fixing a pair of white vitreous china foot rests of standard pattern for squatting pan water closet: 250x130x30mm	1.00	Pair	111.70	111.70
10/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	420.00	Sqm	4.10	1,722.00
11/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	72.00	Sqm	22.85	1,645.20
	TOTAL			Rs.	45,245.01
			Say	Rs.	45,245.00

Having gone through the Tender documents & elements of work in the bill of quantity:-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Repairing and maint of 3 units qtrs. At Nichu dhowrah of V. West colliery (Qtr. No. 26/5. 18/1 & 19/1).”**

2. Name of Tenderer :

3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/58/1677

Date: 03.12.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 7)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	40.00	Sqm	143.75	5,750.00
2/ 10.2	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete..	330.00	Kg	46.35	15,295.50
3/	Fixing chowkhats in existing opening including embedding chowkhats in floors or walls cutting masonry for holdfasts embedding hold fasts in cement concrete blocks with cement concrete 1:3:6 (1 Cement: 3 coarse sand: 6 graded stone aggregate 20 mm nominal size). Painting two coats of approved wood preservative to sides of chowkhats and making good the damages to walls and floors as required complete including disposal of rubbish to the dumping ground within 50 meters lead:				
14.2.1	i) Door chowkhats.	6.00	Each	354.45	2,126.70
14.2.2	ii) Windows chowkhats.	1.00	Each	214.20	214.20
4/ 9.5.2.2	Providing and fixing paneled or paneled and glazed shutters for doors, windows and clerestory windows including ISI marked black enameled M.S. butt hinges with necessary screws excluding, paneling which will be paid for separately. 30 mm thick shutters.	3.34	Sqm	810.90	2,708.40
5/ 9.63.3	Providing and fixing ISI marked oxidesed M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete: 150x10 mm	4.00	Each	23.40	93.60
6/ 9.66.2	Providing and fixing ISI marked oxidesed M.S. handles conforming to IS:4992 with necessary screws etc. complete.100mm	4.00	Each	7.75	31.00
7/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	420.00	Sqm	4.10	1,722.00
8/ 13.39.1	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats) with a base coat of white washing with lime.	150.00	Sqm	9.30	1,395.00
9/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	90.00	Sqm	22.85	2,056.50
10/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	30.00	Sqm	67.65	2,029.50
11/ A.R.	Providing and fixing A.C. Sheet roofing.	15.00	Sqm	266.60	3,999.00
12/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	0.50	Cum	368.45	184.22
13/ 9.1.2	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position. Sal wood	0.0370	Cum	30,511.90	1,128.94

Contd....P/2

14/ 9.53	Providing 40x5 mm flat iron hold fast 40 cm long including fixing to frame with 10 mm diameter bolts, nuts and wooden plugs and embeddings in cement concrete block 30x10x15cm 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).	6.00	Each	61.50	369.00
	TOTAL			Rs.	39,103.56
			Say	Rs.	39,104.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote ____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063



1. Name of Work: “Petty repairing & maint of Thana building chirkunda under C.V. Area.”
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/58/1677 Date: 03.12.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 8)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 14.63.1	Distempering with 1 st quality acrylic washable distemper (ready made) of approved manufacture and of required shade and colour complete, as per manufacture's specification.	67.64	Sqm	13.85	936.81
2/ 13.39.2	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats) with a base coat of whitening.	422.86	Sqm	9.10	3,848.02
3/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	334.00	Sqm	4.10	1,369.40
4/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	125.00	Sqm	22.85	2,856.25
5/ 13.50.1	Applying priming coat: with ready mixed pink or Grey primer of approved brand and manufacture on wood work (hard and soft wood).	42.75	Sqm	16.55	707.51
6/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	32.52	sqm	8.20	266.66
7/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	40.00	Sqm	67.65	2,706.00
	TOTAL			Rs.	12,690.65
			Say	Rs.	12,691.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063



1. .Name of Work: **“Repairing & maint. Of 2 (Two) units NHS qtr. at Project colony of Damagoria (B-1 & B-9).”**
2. Name of Tenderer:
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/58/1677 Date: 03.12.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 9)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 9.1.2	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position. Sal wood	0.185	Cum	30,511.90	5,644.70
2/ 9.53	Providing 40x5 mm flat iron hold fast 40 cm long including fixing to frame with 10 mm diameter bolts, nuts and wooden plugs and embeddings in cement concrete block 30x10x15cm 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).	36.00	Each	61.50	2,214.00
3/ 9.5.2.2	Providing and fixing paneled or paneled and glazed shutters for doors, windows and clerestory windows including ISI marked black enameled M.S. butt hinges with necessary screws excluding, paneling which will be paid for separately. 30 mm thick shutters.	6.68	Sqm	810.90	5,416.81
4/ 10.2	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete:.	124.84	Kg	46.35	5,786.33
5/ 14.2.1	Fixing chowkhats in existing opening including embedding chowkhats in floors or walls cutting masonry for holdfasts embedding hold fasts in cement concrete blocks with cement concrete 1:3:6 (1 Cement: 3 coarse sand: 6 graded stone aggregate 20 mm nominal size). Painting two coats of approved wood preser4vative to sides of chowkhats and making good the damages to walls and floors as required complete including disposal of rubbish to the dumping ground within 50 meters lead: Door chowkhats.	3.00	Each	354.45	1,063.35
6/ 13.11	18 mm cement plaster in two coats under layer 12 mm thick cement plaster 1:5 (1 cement: 5 coarse sand) finished with a top layer 6 mm thick cement plaster 1:6 (1 cement: 6 fine sand).	22.00	Sqm	111.15	2,445.30
7/ 13.16.1	6mm cement plaster of mix: 1:3 (1 cement: 3 fine sand).	21.03	Sqm	62.15	1,307.01
8/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	40.00	Sqm	67.65	2,706.00
9/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	330.00	Sqm	4.10	1,353.00
10/ 13.39.1	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats) with a base coat of white washing with lime.	130.00	Sqm	9.30	1,209.00
11/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	70.00	Sqm	22.85	1,599.50
12/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	30.55	Sqm	143.75	4,391.56
13/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	0.50	Cum	368.45	184.22
14/ 15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 meters lead: of are 3 sq. metres and below.	3.00	Each	54.60	163.80

Contd....P/2

15/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	40.00	sqm	8.20	328.00
16/ 9.63.3	Providing and fixing ISI marked oxidesed M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete: 150x10 mm	8.00	Each	23.40	187.20
17/ 9.66.2	Providing and fixing ISI marked oxidesed M.S. handles conforming to IS:4992 with necessary screws etc. complete.100mm	8.00	Each	7.75	62.00
	TOTAL			Rs.	36,061.78
			Say	Rs.	36,062.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063



1. Name of Work: “Repairing & cleaning of septic tank for new colony B. Mata Colliery at different site.”
2. Name of Tenderer:
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/58/1677 Date: 03.12.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 10)
(Qty. For 1 No)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.7.4	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meter lead as per direction of Engineer-in-charge. In cement mortar	0.56	Cum	310.75	174.02
2/ 6.1.2	Brick work in F.P.S bricks of class designation 50 in foundation and plinth in: Cement mortar 1:6 (1 cement: 6 coarse sand).	0.56	Cum	2,007.00	1,123.92
3/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	2.55	Sqm	67.65	170.50
4/ 13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:4 (1 Cement: 4 fine sand).	1.93	Sqm	97.90	188.94
5/ 5.12	Providing, hoisting and fixing up to floor five level precast reinforced cement concrete work in string courses, bands copings, bed plates, anchor blocks, plain window sills and the like including the cost of required centering, shuttering, finishing smooth with 6 mm thick cement plaster 1:3 (1 cement: 3 fine sand) on exposed surfaces complete but excluding cost of reinforcement with 1:2:4 (1 cement : 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	0.14	Cum	4,882.15	683.50
6/ 5.22.3	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete . Cold twisted bars.	8.40	K.G.	42.70	358.68
7/ M.R.	Cleaning of septic tank.	1.00	Each	600.00	600.00
	TOTAL			Rs	3,299.56
	(such as 5 Nos=3,299.56x5)=			Rs.	16,497.80
			Say	Rs.	16,498.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: “Repairing & maint. NHS type qtr. at Mugma under B. Mata colliery Qtr. No. -10 & Qtr. No. 7.”
2. Name of Tenderer :
3. Address:
4. NIT No. : BCCL/XII/ACE/QTN/2011-12/58/1677 Date: 03.12.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 11)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.13.1	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead: of area 3 sq. metres and below.	5.00	Each	21.40	107.00
2/ 9.1.3	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position. Kiln seasoned and chemically treated Hollock wood.	0.15	Cum	31,339.40	4,700.91
3/ 9.5.2.2	Providing and fixing paneled or paneled and glazed shutters for doors, windows and clerestory windows including ISI marked black enameled M.S. butt hinges with necessary screws excluding, paneling which will be paid for separately. 30 mm thick shutters.	4.40	Sqm	810.90	3,243.60
4/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	53.85	sqm	8.20	441.57
5/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	53.85	Sqm	67.65	3,642.95
6/ 13.16.1	6mm cement plaster of mix: 1:3 (1 cement: 3 fine sand).	12.63	Sqm	62.15	784.95
7/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	1.17	Cum	368.45	431.08
8/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	23.97	Sqm	143.75	3,445.68
9/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	100.51	Sqm	4.10	412.09
10/ 13.39.1	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats) with a base coat of white washing with lime.	76.51	Sqm	9.30	711.54
11/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	34.71	Sqm	22.85	793.12
				Rs.	18,714.49
	TOTAL (A)		Say	Rs.	18,714.00

Contd....P/2

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	0.71	Cum	368.45	261.60
2/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	29.36	Sqm	143.75	4,220.50
3/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	58.00	sqm	8.20	475.60
4/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	58.00	Sqm	67.65	3,923.70
5/ 13.16.1	6mm cement plaster of mix: 1:3 (1 cement: 3 fine sand).	7.99	Sqm	62.15	496.58
6/ 15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 meters lead: of are 3 sq. metres and below.	3.00	Each	54.60	163.80
7/ 9.1.3	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position. Kiln seasoned and chemically treated Hollock wood.	0.09	Cum	31,339.40	2,820.54
8/ 9.5.2.2	Providing and fixing paneled or paneled and glazed shutters for doors, windows and clerestory windows including ISI marked black enameled M.S. butt hinges with necessary screws excluding, paneling which will be paid for separately. 30 mm thick shutters.	3.61	Sqm	810.90	2,927.35
9/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	160.08	Sqm	4.10	656.32
10/ 13.39.1	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats) with a base coat of white washing with lime.	75.48	Sqm	9.30	701.96
10/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	39.00	Sqm	22.85	891.15
	TOTAL (B)			Rs.	17,539.10
			Say	Rs.	17,539.00
	TOTAL (A) + (B) =			Rs.	36,253.00

Having gone through the Tender documents & elements of work in the bill of quantity:-

I / we quote _____% (_____) above / below the estimated cost.
Our quoted offer amounts to Rs. _____ (Rupees _____
_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063



1. Name of Work: “Repairing & maint of 2 units ‘B’ type qtrs. At Chanch more DBOCP.”
2. Name of Tenderer :
3. Address:
4. NIT No. : BCCL/XII/ACE/QTN/2011-12/58/1677 Date: 03.12.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 12)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 14.44	Distempering with dry distemper of approved brand and manufacture (one or more coats) and of required shade on old work to give an even shae.	268.29	Sqm	12.35	3,313.38
2/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	274.00	Sqm	4.10	1,123.40
3/ 13.39.2	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats) with a base coat of whitening.	100.00	Sqm	9.10	910.00
4/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	130.42	Sqm	22.85	2,980.09
5/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	114.33	sqm	8.20	937.50
6/ 13.16.1	6mm cement plaster of mix: 1:3 (1 cement: 3 fine sand).	34.33	Sqm	62.15	2,133.60
7/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	80.00	Sqm	67.65	5,412.00
8/ 13.1.1	12 mm cement plaster of mix: 1:4 (1 Cement: 4 fine sand).	15.00	Sqm	77.55	1,163.25
9/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	25.00	Sqm	143.75	3,593.75
10/ 15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 meters lead: of are 3 sq. metres and below.	2.00	Each	54.60	109.20
11/ 9.5.2.2	Providing and fixing paneled or paneled and glazed shutters for doors, windows and clerestory windows including ISI marked black enameled M.S. butt hinges with necessary screws excluding, paneling which will be paid for separately. 30 mm thick shutters.	2.90	Sqm	810.90	2,351.61
12/ 12.40.1	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS: 13592 Type A including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion. (i) single socketed pipes. 75 mm diameter.	6.00	Metre	95.00	570.00
	TOTAL			Rs.	24,597.78
			Say	Rs.	24,598.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.
Our quoted offer amounts to Rs. _____ (Rupees _____)
_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Repairing & maint. of 3.3 KVA sub-station at NLOCP.”**
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/58/1677 Date: 03.12.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 13)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 14.45.1	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade: old work (one or more coats).	447.73	Sqm	14.90	6,671.17
2/ 14.64.1	Finishing walls with water proofing cement paint of required shade: Old work (one or more coats applied @ 2.20kg/10sqm) over priming coat of primer applied @ 0.80 litres/ 10sqm complete including cost of priming coat.	191.00	Sqm	27.95	5,338.45
3/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	63.71	Sqm	4.10	261.21
4/ 15.9.2	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meter lead as per direction of Engineer-in-charge: in cement mortar.	3.10	Cum	370.75	1,149.17
5/ A.R.	Stone masonry wall (1 cement: 6 coarse sand) in super structure excluding cost of stone.	3.50	Cum	1,746.80	6,113.80
6/ 6.4.2 (A.R.)	Brick work in F.P.S. bricks of class designation 50 in superstructure above plinth level up to floor V level in all shapes and sizes in : cement mortar 1:6 (1 cement : 6 coarse sand).	1.00	Cum	2,137.95	2,137.95
7/ 13.33.1	Pointing on stone work with cement mortar 1:3 (1 cement: 3 fine sand): Flush/ Ruled pointing.	24.72	Sqm	62.50	1,545.00
8/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	7.24	Sqm	67.65	489.76
9/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	95.11	Sqm	22.85	2,173.26
	TOTAL			Rs.	25,879.77
			Say	Rs.	25,880.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063



1. Name of Work: **“Repairing & maint. For R.K.S.S.Y weigh bridge at DBOCP under C.V. Area. Including maintn. Of boundary wall stock yard & repairing of check post including office of DBOCP.”**
2. Name of Tenderer:
3. Address:
4. NIT No. : BCCL/XII/ACE/QTN/2011-12/58/1677 Date: 03.12.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 14)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.7.4	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meter lead as per direction of Engineer-in-charge. In cement mortar	2.07	Cum	310.75	643.25
2/ 6.4.2 (A.R.)	Brick work in F.P.S. bricks of class designation 50 in superstructure above plinth level up to floor V level in all shapes and sizes in : cement mortar 1:6 (1 cement : 6 coarse sand).	4.23	Cum	2,137.95	9,043.57
3/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	47.96	Sqm	67.65	3,244.49
4/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	0.35	Cum	368.45	128.95
5/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	14.68	Sqm	143.75	2,110.25
6/ 15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 meters lead: of are 3 sq. metres and below.	1.00	Each	54.60	54.60
7/ 9.1.3	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position. Kiln seasoned and chemically treated Hollock wood.	0.03	Cum	31,339.40	940.18
8/ 13.42	Distempering with 1 st quality acrylic washable distemper (ready mixed) of approved manufacturer and of required shade and colour complete. As per manufacturer's specification. Two or more coats on new work.	99.53	Sqm	23.55	2,343.93
9/ M.R.	Dismantling iron gate.	2.00	Each	400.00	800.00
10/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	124.15	Sqm	4.10	509.02
11/ 13.39.1	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats) with a base coat of white washing with lime.	819.66	Sqm	9.30	7,622.83
12/ 10.1	Structural still work in single section fixed with or without connecting including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	85.50	Kg	42.15	3,591.18
13/ 10.1	Structural still work in single section fixed with or without connecting including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	63.00	Kg	42.15	2,655.45
14/ 9.119	Providing and fixing factory made P.V.C doorframe of size 50x47mm with a wall thickness of 5mm, made out of extruded 5mm rigid PVC foam sheet mitred at corners and joined with 2 Nos . of 150 mm long brackets of 15x15mm M.S. square tube, the vertical door profiles to be reinforced with 19x19mm M.S. square tube of 19 gauge, EPDM rubber gasket weather seal to be provided through out the frame. The door frame to be fixed to the wall using M.S. screws of 65/100mm size complete as per manufacturers specification and direction of Engineer-in-charge.	4.87	Metre	353.10	1,719.59

Contd....P/2

15/ 9.120.1	Providing and fixing to existing door frames. 30mm thick factory made panel PVC door shutter consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19mm x 19mm for styles and 15 x 15 mm for top & bottom rails. MS. Frame shall have a coat of steel primers of approved make and manufacture. M.S. frame covered with 5 mm thick heat molded PVC. 'C' channel of size 30mm thickness, 70 mm width out of which 50mm shall be flat and 20 mm shall be tapered in 45 degree angle on either side forming styles: and 5mm thick. 95mm wide PVC sheet out of which 75 mm shall be flat and 20 mm shall be tapered in 45 degree on the inner side to form top and bottom rail and 115 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm shall be tapered on both side to form lock rail. Top, bottom and lock rail shall be provided either side of the panel. 10mm (5mm x 2) thick, 20 mm wide cross PVC sheet be provided as gap insert for top rail & bottom rail. Paneling of 5mm thick Bothe side PVC sheet to be fitted in the M/S. frame welded/ sealed to the styles & rail with 7mm (5mm +2mm) thick x 15 mm wide PVC sheet beading on inner side, and joined together with solvent cement adhesive. An additional 5 mm thick PVC strip of 20mm width is to be stuck on the interior side of the 'C' channel using PVC solvent adhesive etc. complete as per direction of Engineer-in-charge. Manufacturer's specification & drawing (for W.C. and bathroom door shutter).	1.59	Sqm	2,109.95	3,354.82
16/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	16.13	Sqm	8.20	132.26
17/ A.R.	Providing and laying brick flat soiling CD50	6.81	Sqm	111.09	756.52
18/ 11.3.1	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate.	5.57	Sqm	192.95	1,074.73
19/ 6.12.2	Half brick masonry with F.P.S.CD 50 brick of class designation in foundations and plinth in . cement mortar 1:4 (1 cement: 4 coarse sand).	2.60	Sqm	257.25	668.85
20/ 13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:4 (1 Cement: 4 fine sand).	18.28	Sqm	97.90	1,789.61
21/ 11.3 (A.R.)	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	0.46	Sqm	143.75	66.12
22/ M.R.	Providing fitting fixing of PVC bib cock.	3.00	Each	40.00	120.00
23/ 18.16.1	Providing and fixing brass stop cock of approved quality. 15 mm nominal bore.	1.00	Each	191.70	191.70
	TOTAL			Rs.	43,561.90
			Say	Rs.	43,562.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Precast RCC slab for main drain which have passes main entrance of DOCP office & replacement of Chowkhats of Toilets door & painting the same of DOCP office under C.V. Area.”**

2. Name of Tenderer :

3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/58/1677

Date: 03.12.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 15)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 5.12	Providing, hoisting and fixing up to floor five level precast reinforced cement concrete work in string courses, bands copings, bed plates, anchor blocks, plain window sills and the like including the cost of required centering, shuttering, finishing smooth with 6 mm thick cement plaster 1:3 (1 cement: 3 fine sand) on exposed surfaces complete but excluding cost of reinforcement with 1:2:4 (1 cement : 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	0.64	Cum	4,880.15	3,123.29
2/ 5.22.3	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete . Cold twisted bars.	24.54	K.G.	42.70	1,047.85
3/ 9.1.3	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position. Kiln seasoned and chemically treated Hollock wood.	0.03	Cum	31,339.40	940.18
4/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	4.07	Sqm	22.85	93.00
5/ 4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level: 1:2.4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	0.60	Cum	3,257.45	1,954.47
6/ 2.6.1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth. 1.5m in width as well as 10sqm on plan) including disposal of excavated earth, lead up to 50m and lift up to 1.5m, disposed earth to be leveled and neatly dressed. All kinds of soil.	1.21	Cum	101.85	123.23
7/ A.R.	Providing and laying single layer Brick flat soiling	7.97	Sqm	111.09	885.38
8/ 15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 meters lead: of are 3 sq. metres and below.	1.00	Each	54.60	54.60
9/ 9.53	Providing 40x5 mm flat iron hold fast 40 cm long including fixing to frame with 10 mm diameter bolts, nuts and wooden plugs and embeddings in cement concrete block 30x10x15cm 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).	6.00	Each	61.50	369.00
10/ M.R.	Providing and fixing wooden shutter in new chowkhats .	1.00	Each	150.00	150.00
	TOTAL			Rs.	8,741.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer

FOR PAYMENT TO CONTRACTORS

(Note: To be submitted in Triplicate)

PROFORMA FOR COLLECTING PAYMENT THROUGH ELECTRONIC MODE INCLUDING ELECTRONIC FUND TRANSFER (EFT) & ELECTRONIC CLEARING SYSTEM (ECS)

1	Vendor/ supplier/ contractor/ customer's name & address (with telephone number & Fax number)	
2	Particulars of Bank Account	
	a) Bank Name	
	b) Branch Name (Including RTGS Code)	
	Address	
	Telephone No. & Fax No.	
	c) 9 – Digit Code Number of the Bank & Branch (Appearing on the MICR Cheque issued on the bank) or 5 digit code number of SBI	
	d) Account Type (S.B. Account/ Current Account or Cash Credit with code 10/11/13)	
	e) Ledger No./ Ledger Folio No.	
	f) Account Number (Core Banking) & Style of Account (As appearing on the cheque Book)	

3. DATE OF EFFECT:

I hereby declare that the particulars given above are correct & complete. If the transaction is delayed or not effected at all for reasons of incomplete or incorrect information, I would not hold the user institution responsible. I have read the option invitation letter and agree to discharge responsibility expected of me as a participant under the scheme. Any bank charges levied by the bank of such e-transfer shall be borne by us.

Date: -

contractor

(_____)
Signature of customer/ vendor/ supplier/

Certified that the particulars furnished above are correct as per our records.

(_____)
Signature of the authorized officials from the Bank

DECLARATION

I, _____, Partner/Legal Attorney/ Accredited Representative of M/S _____

_____, solemnly declare that :

1. We are submitting Tender for the Work _____

_____ against Tender

Notice No. _____

dt _____

- 2. None of the Partners of our firm is relative of employee of Bharat Coking Coal Ltd.
- 3. All information furnished by us in respect of fulfillment of eligibility criteria and qualification information of this Tender is complete, correct and true.
- 4. None of the partners of the Firm has either individually or collectively been involved in criminal offences.
- 5. I hereby declare that /our firm has not been banned or delisted by any Govt. or Quasi Govt. agencies or PSUs.
- 6. All documents/ credentials submitted along with this Tender are genuine, authentic, true and valid.
- 7. I/ We hereby agree and assure the management that provision of engagement of 25% PAPs will be followed as per contract.
- 8. If any information and document submitted is found to be false/ incorrect any time, department may cancel my Tender and action as deemed fit may be taken against us, including termination of the contract, forfeiture of all dues including Earnest Money and banning / delisting of our firm and all partners of the firm etc.

Signature of the Tenderer

Dated _____