



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063



Ref. No. BCCL/XII/ACE/QTN/2011-12/53/1649

Dates: 26.11.2011

QUOTATION NOTICE

Sealed Quotations on percentage rate basis are invited from the bonafide & experienced contractors for the following works: Terms and conditions:

Sl.No.	Name of the work	Estimated cost	Earnest Money	Time of completion
1.	Repairing & maint. Of 1 (one) unit NHS qtr No. 5 at R.S. Colony, Begunia.	Rs.11,823.00	Rs. 120.00	10 days.
2.	Repairing & maint. Of 1 (one) unit NHS qtr. No. N/6 at D.R. Colony, Begunia.	Rs. 13,470.00	Rs.135.00	15 days.
3.	Repairing of damaged septic tanks and cover slabs at R.K. Colony.	Rs. 36,650.00	Rs. 370.00	30 days
4.	Repairing & maint. Of 1 (one) unit CMWO type qtr No. 1/3 at Manberia Colony, V. West colliery.	Rs. 11,377.00	Rs. 115.00	15 days
5.	Repairing & maint. Of one unit old NHS type qtr. at staff colony DOCP. Qtr No. B/11.	Rs. 16,663.00	Rs. 167.00	15 days
6	Repairing and maint. Of one unit LCH qtr at Laikdih Workers colony (Qtr. No. LCH A-7)	Rs. 15,051.00	Rs. 151.00	15 days
7	Development work at junction of guest house and G.M.'s Bungalow.	Rs. 88,298.00	Rs. 885.00	30 days
8	Roof with ceiling repairing of CISF barrack at DOCP.	Rs. 23,014.00	Rs. 231.00	15 days.
9	Repairing of trammer shed at palasia west at B.Mata Colliery.	Rs. 22,405.00	Rs. 225.00	15 days
10	Repairing & maint. Of store building at B. Mata colliery.	Rs. 32,714.00	Rs. 330.00	15 days.
11	Repairing & maint. Of 5 units NHS type qtr. At New colony block no.- G at B. Mata Colliery, Qtr. No. 10,9,1,5 & 2.	Rs. 52,991.00	Rs. 530.00	35 days.
12	Repairing & maint. Of 2 unit 'B' type qtr. At Babudangal more (Qtr No. B/1 & B/4).	Rs. 23,068.00	Rs. 231.00	20 days.
13	Repairing of concrete road at Junction point of main road and Area Office road.	Rs. 4,878.00	Rs. 50.00	10 days.
14	Repairing & maint. Of 1 (one) unit NHS qtr. No. 11 and changing door in Qtr No. CT/1 at R.S. Colony, Begunia.	Rs. 16,528.00	Rs. 166.00	10 days.

- Interested parties can collect the BOQ and other related papers of the Quotation from the office of the Area Civil Engineer, C.V. Area-XII, AT-Begunia, P.O –Barakar(W.B.). **From 03.12.2011 to 07.12.2011** during office hours except Sunday and Holiday. BOQ and other relevant pages (Declaration & EFT form) can be down loaded from BCCL website- <http://www.bccl.gov.in>
- Completed sealed Quotations will be received on **08.12.2011 up to 3.00 P.M.** at the following places. Quotation may Opt. any one place to submit their quotation as per their convenience.
 - In the office of the General Manager, C.V. Area-XII, AT-Begunia, P.O –Barakar(W.B.)
 - At BCCL H.Q. i.e. C.I.S.F. post, near Koyala Bhawan gate, Koyala Nagar, Dhanbad.
 - Office of the ACE, CCWO, W.W.Z. Area, Saraidhela, Dhanbad.
 - Office of the ACE, CHD, Jagjiban Nagar, Dhanbad.
- Quotations will be opened on **10.12.2011 at 11.30 A.M.** in the office of the Area Civil Engineer, C.V. Area-XII, AT-Begunia, P.O –Barakar(W.B.).
- Specification of work shall be governed by DSR-2007 & C.P.W.D specification.
- Terms and conditions as per C.I.L. C.E. manual shall be applicable against the quotations submitted against this Quotation Notice.

6. Completed sealed Quotations shall consist of (1) EMD in the shape of cash receipt obtained from the finance deptt. C.V. Area-XII or DD from any Scheduled/Nationalised Bank, (2) Experience certificate, (3) Copy of Pan card, (4) Copy of VAT/Sales Tax clearance certificate along with VAT/Sales Tax registration No.(TIN), (5) Declaration and (6) EFT (Electronic Fund Transfer) & ECS (Electronic Clearance System) as per the format issued along with the Tender paper and (7) BOQ along with quoted rate by the Tenderer.
7. The quoted rate shall include all taxes and levies.
8. Statutory deductions for Income Tax and Sales Tax shall be made as per Rules and notifications.
9. The contractor has to abide by the Rules of Contract Labour Regulation & Abolition Act-.
10. Validity of tender shall be 120 days from the date of opening of the tender.
11. The contractors have to be acquainted with the site condition
12. Unless otherwise mentioned, no material will be issued by the department
13. Successful tender has to deposit 5% Performance Security (including 1% EMD) and another 5% Security Deposit will be deducted from the Running Account/ Final Bill.
14. It should be ensured that there must be provision for engagement of 25% PAPs.
15. The management of BCCL reserves right to reject any or all tender or split the work among two or more tenderers without assigning any reasons whatsoever.

Sd/
Area Civil Engineer
Chanch Victoria Area-XII

Copy to :-

- 1) GM, Chanch Victoria Area-XII.
- 2) GM (Civil), BCCL, Koyla Nagar.
- 3) All CGM/GM of Areas/Projects under BCCL.
- 4) Addl. GM, Chanch Victoria Area-XII.
- 5) A.F.M., Chanch Victoria Area-XII.
- 6) All P.O.s of Chanch Victoria Area-XII.
- 7) Cashier, C.V. Area-XII
- 8) Incharge,, CISF Post, Koyala Bhawan gate, Koyala Nagar,
- 9) Assistant Commandant, CISF, C.V. Area-XII-with 2 copies of NIT for displaying on Notice Board.
- 10) Builders Association of India, Central Akashkinaree Kanta, Katras Garh, Dhanbad-828113.
- 11) ACE CCWO, W.W.Z Area saraidhela, Dhanbad.
- 12) ACE CHD, jagiban Nagar, Dhanbad



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Repairing & maint. Of 1 (one) unit NHS qtr No. 5 at R.S. Colony, Begunia.”**
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/53/1649

Date: 26.11.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl No. 1)

SL.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	20.00	Sqm	143.75	2,875.00
2/ 10.2	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete..	50.00	Kg	46.35	2,317.50
3/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	0.48	Cum	368.45	176.85
4/ 15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 meters lead: of are 3 sq. metres and below.	2.00	Each	54.60	109.20
5/ 14.2.1	Fixing chowkhats in existing opening including embedding chowkhats in floors or walls cutting masonry for holdfasts embedding hold fasts in cement concrete blocks with cement concrete 1:3:6 (1 Cement: 3 coarse sand: 6 graded stone aggregate 20 mm nominal size). Painting two coats of approved wood preservative to sides of chowkhats and making good the damages to walls and floors as required complete including disposal of rubbish to the dumping ground within 50 meters lead: Door chowkhats.	1.00	Each	354.45	354.45
6/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	15.00	Sqm	67.65	1,014.75
7/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	165.00	Sqm	4.10	676.50
8/ 13.39.1	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats) with a base coat of white washing with lime.	65.00	Sqm	9.30	604.50
9/ 6.12.2	Half brick masonry with F.P.S. brick of class designation in foundations and plinth in . cement mortar 1:4 (1 cement: 4 coarse sand).	6.00	Sqm	257.25	1,543.50
10/ 13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:4 (1 Cement: 4 fine sand).	12.00	Sqm	97.90	1,174.80
11/ 13.16.1	6mm cement plaster of mix: 1:3 (1 cement: 3 fine sand).	1.00	Sqm	62.15	62.15
12/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	40.00	Sqm	22.85	914.00
TOTAL				Rs.	11,823.20
			Say	Rs.	11,823.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____ % (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Repairing & maint. Of 1 (one) unit NHS qtr. No. N/6 at D.R. Colony, Begunia..”**
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/53/1649 Date: 26.11.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 2)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	23.00	Sqm	143.75	3,306.25
2/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	20.00	Sqm	67.65	1,353.00
3/ 10.2	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete..	50.00	Kg	46.35	2,317.50
4/ 14.2.1	Fixing chowkhats in existing opening including embedding chowkhats in floors or walls cutting masonry for holdfasts embedding hold fasts in cement concrete blocks with cement concrete 1:3:6 (1 Cement: 3 coarse sand: 6 graded stone aggregate 20 mm nominal size). Painting two coats of approved wood preservative to sides of chowkhats and making good the damages to walls and floors as required complete including disposal of rubbish to the dumping ground within 50 meters lead: Door chowkhats.	1.00	Each	354.45	354.45
5/ 9.1.3	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position. Kiln seasoned and chemically treated Hollock wood.	0.074	Cum	31,339.40	2,319.11
6/ 9.53	Providing 40x5 mm flat iron hold fast 40 cm long including fixing to frame with 10 mm diameter bolts, nuts and wooden plugs and embeddings in cement concrete block 30x10x15cm 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).	6.00	Each	61.50	369.00
7/ 13.16.1	6mm cement plaster of mix: 1:3 (1 cement: 3 fine sand).	18.20	Sqm	62.15	1,331.13
8/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	165.00	Sqm	4.10	676.50
9/ 13.39.1	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats) with a base coat of white washing with lime.	65.00	Sqm	9.30	604.50
10/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	35.00	Sqm	22.85	799.75
11/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix	0.50	cum	368.45	184.22
12/ 15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 meters lead: of are 3 sq. metres and below.	1.00	Each	54.60	54.60
TOTAL				Rs.	13,470.01
			Say	Rs	13,170.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____)



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Repairing of damaged septic tanks and cover slabs at R.K. Colony.”**
3. Name of Tenderer
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/50/1649

Date: 26.11.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 3)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.7.4	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meter lead as per direction of Engineer-in-charge. In cement mortar	1.15	Cum	310.75	357.36
2/ 6.1.2	Brick work in F.P.S bricks of class designation 50 in foundation and plinth in: Cement mortar 1:6 (1 cement: 6 coarse sand).	2.50	Cum	2,007.00	5,017.50
3/ 13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:4 (1 Cement: 4 fine sand).	16.29	Sqm	97.90	1,594.79
4/ 5.13	Providing, hoisting and fixing up to floor five level precast reinforced cement concrete in small lintels not exceeding 1.5m clear span up to floor five level including the cost of required centering, shuttering and finishing smooth with 6 mm thick cement plaster 1:3 (1 cement: 3 fine sand) on exposed surfaces but excluding the cost of reinforcement with 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	2.94	Cum	6,002.80	17,648.23
5/ 5.22.3	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. Cold twisted bars.	176.40	K.G.	42.70	7,532.28
6/ A.R.	Cleaning of septic tank.	9.00	Each	500.00	4,500.00
TOTAL				Rs.	36,650.16
			Say	Rs.	36,650.00

Having gone through the Tender documents & elements of work in the bill of quantity:-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____)

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Repairing & maint. Of 1 (one) unit CMWO type qtr No. 1/3 at Manberia Colony, V. West colliery.”**
2. Name of Tenderer :
3. Address:
4. NIT No. : BCCL/XII/ACE/QTN/2011-12/53/1649 Date: 26.11.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 4)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	23.78	Sqm	143.75	3,418.37
2/ 10.2	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete:..	68.00	Kg	46.35	3,151.80
3/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	27.17	Sqm	67.65	1,838.05
4/ 14.2.1 14.2.2	Fixing chowkhats in existing opening including embedding chowkhats in floors or walls cutting masonry for holdfasts embedding hold fasts in cement concrete blocks with cement concrete 1:3:6 (1 Cement: 3 coarse sand: 6 graded stone aggregate 20 mm nominal size). Painting two coats of approved wood preservative to sides of chowkhats and making good the damages to walls and floors as required complete including disposal of rubbish to the dumping ground within 50 meters lead: i) Door chowkhats. ii) Window chokhats	1.00 1.00	Each Each	354.45 214.20	354.45 214.20
5/ 15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 meters lead: of are 3 sq. metres and below.	2.00	Each	54.60	109.20
6/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	0.57	Cum	368.45	210.01
7/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	165.00	Sqm	4.10	676.50
8/ 13.39.1	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats) with a base coat of white washing with lime.	65.00	Sqm	9.30	604.50
9/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	35.00	Sqm	22.85	799.75
TOTAL				Rs.	11,376.83
			Say	Rs.	11,377.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____ % (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX : 0341-2520063

Annex-I



1. Name of Work: **“Repairing & maint. Of one unit old NHS type qtr. at staff colony DOCP. Qtr No. B/11.”**
2. Name of Tenderer:
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/53/1649

Date: 26.11.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 5)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	0.45	Cum	368.45	165.80
2/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	18.58	Sqm	143.75	2,670.87
3/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	37.35	Sqm	8.20	306.27
4/ 13.16.1	6mm cement plaster of mix: 1:3 (1 cement: 3 fine sand).	10.22	Sqm	62.15	635.17
5/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	27.13	Sqm	67.65	1,835.34
6/ 9.1.3	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position. Kiln seasoned and chemically treated Hollock wood.	0.03	Cum	31,339.41	940.18
7/ 9.5.2.2	Providing and fixing paneled or paneled and glazed shutters for doors, windows and clerestory windows including ISI marked black enameled M.S. butt hinges with necessary screws excluding, paneling which will be paid for separately. 30 mm thick shutters.	1.49	Sqm	810.90	1,208.24
8/ 10.2	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete..	50.00	Kg	46.35	2,317.50
9/ 9.53	Providing 40x5 mm flat iron hold fast 40 cm long including fixing to frame with 10 mm diameter bolts, nuts and wooden plugs and embeddings in cement concrete block 30x10x15cm 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).	4.00	Each	61.50	246.00
10/ 9.63.1	Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete: 250x10 mm	1.00	Each	33.90	33.90
11/ 9.62.1	Providing and fixing ISI marked oxidized M.S. sliding door bolts with nuts and screws etc. complete: 300x16 mm	1.00	Each	79.60	79.60
12/ A.R.	Providing & fixing A.C. Sheet with J or L hooks including labour charge of all as per directed by Engineer-in-charge.	4.46	Sqm	266.60	1,189.03
13/ 6.4.2 (A.R.)	Brick work in F.P.S. bricks of class designation 50 in superstructure above plinth level up to floor V level in all shapes and sizes in : cement mortar 1:6 (1 cement : 6 coarse sand).	0.51	Cum	2,137.95	1,090.35

Contd...P/2

14/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	49.62	Sqm	4.10	203.44
15/ 13.39.1	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats) with a base coat of white washing with lime.	280.57	Sqm	9.30	2,609.30
16/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	49.58	Sqm	22.85	1,132.90
	Total			Rs.	16,663.89
			Say	Rs.	16,663.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: “Repairing and maint. Of one unit LCH qtr at Laikdih Workers colony (Qtr. No. LCH A-7).”
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/53/1649

Date: 26.11.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 6)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	16.38	Sqm	8.20	134.32
2/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	1.30	Cum	368.45	478.99
3/ 15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 meters lead: of are 3 sq. metres and below.	2.00	Each	54.60	109.20
4/ 10.25.2	Steel work welded in built up section/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	39.51	Kg.	51.20	2,022.91
5/ 6.12.2	Half brick masonry with F.P.S. brick of class designation in foundations and plinth in . cement mortar 1:4 (1 cement: 4 coarse sand).	2.14	Sqm	257.20	550.40
6/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	16.38	Sqm	67.65	1,108.10
7/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	53.48	Sqm	143.75	7,687.75
8/ A.R.	Providing and fitting 6 mm thick A.C. Sheet.	5.11	Sqm	271.85	1,389.15
9/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	206.00	Sqm	4.10	844.60
10/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	31.75	Sqm	22.85	725.48
TOTAL				Rs.	15,050.90
			Say	Rs	15,051.00

Having gone through the Tender documents & elements of work in the bill of quantity:-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Development work at junction of guest house and G.M.’s Bungalow.”**
2. Name of Tenderer :
3. Address:
4. NIT No. : BCCL/XII/ACE/QTN/2011-12/53/1649 Date: 26.11.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 7)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 2.6.1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth. 1.5m in width as well as 10sqm on plan) including disposal of excavated earth, lead up to 50m and lift up to 1.5m, disposed earth to be leveled and neatly dressed. All kinds of soil.	148.51	Cum	101.85	15,125.74
2/ 1.1.2	Carriage of material by mechanical transport including loading, un loading and stacking. Lead up to 1 K.M. Earth	159.90	Cum	49.42	7,902.25
3/ 2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kind of soil.	11.39	Cum	103.40	1,177.72
4/ 4.1.8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level:1:4:8 (1 cement: 4 coarse sand: 8 graded stone aggregate 40 mm nominal size)	4.92	Cum	2,449.00	12,049.08
5/ 6.1.2	Brick work in F.P.S bricks of class designation 50 in foundation and plinth in: Cement mortar 1:6 (1 cement: 6 coarse sand).	10.83	Cum	2,007.00	21,735.81
6/ 7.1 (A.R.)	Labour cost for random rubble masonry with hard stone in foundation and plinth including labeling up with cement concrete 1:6:12 (1 cement: 6 coarse sand:12 graded stone aggregate 20 mm nominal size) at plinth label with cement mortar 1:6 (1 cement: 6 coarse sand)	5.88	Cum	1,453.78	8,548.22
7/ 4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level: 1:2.4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	0.47	Cum	3,257.45	1,531.00
8/ 4.3.1	Centering and shuttering including strutting, propping etc. and removal of form work for: Foundation, footing, bases for columns.	3.09	Sqm	119.25	368.48
9/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	40.13	Sqm	67.65	2,714.79
10/ 13.33.1	Pointing on stone work with cement mortar 1:3 (1 cement: 3 fine sand): Flush/ Ruled pointing.	14.49	Sqm	62.50	905.62
11/ 23.2	Supplying and staking of good earth at site including royalty and carriage up to 1 KM (earth measured in stacks will be reduced by 20% for payment).	11.58	Cum	144.05	1,668.09
12/ 5.12	Providing, hoisting and fixing up to floor five level precast reinforced cement concrete work in string courses, bands copings, bed plates, anchor blocks, plain window sills and the like including the cost of required centering, shuttering, finishing smooth with 6 mm thick cement plaster 1:3 (1 cement: 3 fine sand) on exposed surfaces complete but excluding cost of reinforcement with 1:2:4 (1 cement : 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	0.084	Cum	4,880.15	409.93

14/ 5.22.3	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete . Cold twisted bars.	60.00	K.G.	42.70	2,562.00
15/ 5.9.3	Centering and shuttering including strutting, propping etc. and removal of form for: suspended floors, roofs, landing, balconies and access platform.	5.00	Sqm	187.35	936.75
16/ 23.4.1	Supplying and stacking at site dump manure from approved source, including carriage up to 1 KM (manure measured in stacks will be reduced by 8% for payment): Screened through sieve of I.S designation 20mm.	10.00	Cum	82.90	829.00
17/ 16.15.1	Supplying at site: R.C.C. standards post/struts/rails/pales of mix 1:1.5:3 (1 cement: 1.5 coarse sand: 3 graded stone aggregate 12.5 nominal size) with wooden plugs of 6mm bar nibs wherever required as per direction of Engineer-in-charge including fixing (cost of earth works in excavation, concrete works in foundation to be paid separately).	0.29	Cum	12,473.10	3,617.19
18/ 16.17.1	Fencing with R.C.C. post placed at required distance, imbedded in cement concrete blocks, every 15 th post, last but one end post and corner post shall be strutted on both sides and end post one side only, provided with horizontal lines and two diagonals of barbed wire 9.38 kg per 100 metres (min) between the two posts fitted and fixed with G.I. staples on wooden plugs or G.I. binding wire tied to 6 mm bar nibs fixed while casting the post (cost of R.C.C posts, struts, earth work and concrete to be paid for separately) :- Payment to be made per meter cost of total length of barbed wire used. With G.I. barbed wire.	234.69	Meter	5.85	1,372.93
19/ A.R.	Providing and laying single brick flat soiling.	5.94	Sqm	111.09	659.87
20/ 13.39.1	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats) with a base coat of white washing with lime.	40.13	Sqm	9.30	373.20
21/ 11.37	Providing and laying ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacture of 1 st quality conforming to IS: 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 cement: 4 coarse sand) including pointing the joints with cement and matching pigment etc., complete.	1.50	Sqm	598.65	897.97
22/ 1.1.4	Carriage of material by mechanical transport including loading, un loading and stacking. Lead up to 6 K.M. excavated rock.	5.88	Cum	79.07	464.93
Total				Rs.	88,298.01
			Say	Rs.	88,298.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Roof with ceiling repairing of CISF barrack at DOCP.”**
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/53/1649

Date: 26.11.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 8)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 12.15.1	Painting top of roofs with bitumen of approved quality at 17kg per 10sqm impregnated with a coat of coarse sand at 60 cudm per 10sqm including cleaning the slab surface with brushes and finally with a piece of cloth lightly soaked in kerosene oil complete: with residual type petroleum bitumen of penetration 80/100	244.00	Sqm	63.00	15,372.00
2/ 13.1.1	12 mm cement plaster of mix: 1:4 (1 Cement: 4 fine sand).	22.76	Sqm	77.55	1,765.03
3/ 15.7.4	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meter lead as per direction of Engineer-in-charge. In cement mortar	2.42	Cum	310.75	752.01
4/ 12.40.1	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS: 13592 Type A including jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion. (i) single socketed pipes. 75 mm diameter.	6.40	Metre	95.00	608.00
5/ 13.16.1	6mm cement plaster of mix: 1:3 (1 cement: 3 fine sand).	64.21	Sqm	62.15	3,990.65
6/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	64.21	Sqm	8.20	526.52
Total				Rs.	23,014.21
			Say	Rs.	23,014.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____ % (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: “Repairing of trammer shed at palasia west at B.Mata Colliery.”
2. Name of Tenderer:
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/53/1649

Date: 26.11.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 9)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.7.4	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meter lead as per direction of Engineer-in-charge. In cement mortar	2.11	Cum	310.75	655.68
2/ 6.1.2	Brick work in F.P.S bricks of class designation 50 in foundation and plinth in: Cement mortar 1:6 (1 cement: 6 coarse sand).	4.54	Cum	2,007.00	9,111.78
3/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	25.55	Sqm	67.65	1,728.45
4/ 13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:4 (1 Cement: 4 fine sand).	6.69	Sqm	97.90	654.95
5/ 15.28.1	Dismantling roofing including ridges, hips valleys and gutters etc., and stacking the material with 50 metres lead of: G.S. Sheet.	37.17	Sqm	24.70	918.10
6/ 12.1.3	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal / vertical or curved surfaces) excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than 275gm/ m2	14.86	Sqm	432.75	6,430.67
7/ A.R.	Labour charge for cost of CGI sheet roofing including J or L hooks with labour as directed by Engineer-in-charge.	22.31	Sqm	69.50	1,550.54
8/ 12.4.2	Providing ridges or hips of width 60cm over all width plain G.S. sheet fixed with polymer coated J. or L hooks, bolts and nuts 8 mm dia. G.I. limpet and bitumen washers complete. 0.63mm thick with zinc coating not less than 275gm/m2	5.00	Meter	270.95	1,354.75
Total				Rs.	22,404.92
			Say	Rs.	22,405.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Repairing & maint. Of store building at B. Mata colliery.”**
2. Name of Tenderer:
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/53/1649

Date: 26.11.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 10)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.28.1	Dismantling roofing including ridges, hips valleys and gutters etc., and stacking the material with 50 metres lead of: G.S. Sheet.	97.58	Sqm	24.70	2,410.22
2/ 15.7.4	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meter lead as per direction of Engineer-in-charge. In cement mortar	3.74	Cum	310.75	1,162.20
3/ 18.12.6	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. 50 mm dia nominal bore.	30.48	Meter.	280.10	8,537.44
4/ 12.1.3	Providing corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead and including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal / vertical or curved surfaces) excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. 0.63 mm thick with zinc coating not less than 275gm/ m2	11.61	Sqm	432.25	5,018.42
5/ 6.4.2 (A.R.)	Brick work in F.P.S. bricks of class designation 50 in superstructure above plinth level up to floor V level in all shapes and sizes in : cement mortar 1:6 (1 cement : 6 coarse sand).	3.74	Cum	2,137.95	7,995.93
6/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	44.61	Sqm	67.65	3,017.86
7/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	0.59	Cum	368.45	217.38
8/ 22.14.1	Grading roof for water proofing treatment with cement concrete 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	0.85	cum	3,314.95	2,817.70
9/ 12.15.1	Painting top of roofs with bitumen of approved quality at 17kg per 10sqm impregnated with a coat of coarse sand at 60 cudm per 10sqm including cleaning the slab surface with brushes and finally with a piece of cloth lightly soaked in kerosene oil complete: with residual type petroleum bitumen of penetration 80/100	24.39	Sqm	63.00	1,536.57
TOTAL				Rs	32,713.72
			Say	Rs.	32,714.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Repairing & maint. Of 5 units NHS type qtr. At New colony block no.- G at B. Mata Colliery, Qtr. No. 10,9,1,5 & 2.”**

2. Name of Tenderer :

3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/53/1649

Date: 26.11.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 11)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	3.42	Cum	368.45	1,260.10
2/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	140.33	Sqm	143.75	20,172.43
3/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	125.00	Sqm	8.20	1,025.00
4/ 13.16.1	6mm cement plaster of mix: 1:3 (1 cement: 3 fine sand).	50.00	Sqm	62.15	3,107.50
5/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	75.00	Sqm	67.65	5,073.75
6/ 9.5.2.2	Providing and fixing paneled or paneled and glazed shutters for doors, windows and clerestory windows including ISI marked black enameled M.S. butt hinges with necessary screws excluding, paneling which will be paid for separately. 30 mm thick shutters.	15.33	Sqm	810.90	12,431.09
7/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	586.65	Sqm	4.10	2,405.27
8/ 13.39.1	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats) with a base coat of white washing with lime.	374.05	Sqm	9.30	3,478.66
9/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	176.69	Sqm	22.85	4,037.36
TOTAL				Rs.	52,991.16
			Say	Rs.	52,991.00

Having gone through the Tender documents & elements of work in the bill of quantity:-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____)

_____ including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
 (A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063



1. Name of Work: “Repairing & maint. Of 2 unit ‘B’ type qtr. At Babudangal more (Qtr No. B/1 & B/4).”

2. Name of Tenderer :

3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/53/1649

Date: 26.11.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 12)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	94.33	Sqm	8.20	773.50
2/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	1.26	Cum	368.45	464.24
3/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	61.11	Sqm	67.65	4,134.09
4/ 13.16.1	6mm cement plaster of mix: 1:3 (1 cement: 3 fine sand).	33.22	Sqm	62.15	2,064.62
5/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	50.74	Sqm	143.75	7,293.81
6/ 9.21.1	Providing and fixing ISI marked flush door shutters conforming to IS: 2202 (part- 1) non- decorative type, core of block board construction with frame of 1 st class hard wood and will matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters; 35 mm thick including ISI marked stainless steel butt hinges with necessary screws.	1.59	Sqm	929.95	1,478.62
7/ 13.61.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work.	3.37	Sqm	33.25	112.05
8/ 6.12.2	Half brick masonry with F.P.S. brick of class designation in foundations and plinth in . cement mortar 1:4 (1 cement: 4 coarse sand).	7.49	Sqm	257.20	1,926.42
9/ 13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:4 (1 Cement: 4 fine sand).	14.97	Sqm	97.90	1,465.56
10/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	61.50	Sqm	22.85	1,405.27
11/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	475.68	Sqm	4.10	1,950.20
TOTAL				Rs.	23,068.38
			Say	Rs.	23,068.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____ % (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Repairing of concrete road at Junction point of main road and Area Office road.”**
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/53/1649

Date: 26.11.2011

5. Details of E.M.D. No:

Rs:

Date:

BILL OF QUANTITY: (Sl. No. 13)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 16.42	Cement concrete 1:2:4 (1 Cement: 2 coarse sand: 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete.	1.48	Cum	3,262.05	4,827.83
2/ 2.28.1	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15cm deep and disposal of rubbish, lead up to 50m and lift up to 1.5m. All kind of soil.	9.75	100 Sqm	512.10	49.92
	TOTAL			Rs.	4,877.75
			Say	Rs.	4,878.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____ % (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



Bharat cocking coal Limited
(A Subsidiary of Coal India Limited)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Annex-I



1. Name of Work: **“Repairing & maint. Of 1 (one) unit NHS qtr. No. 11 and changing door in Qtr No. CT/1 at R.S. Colony, Begunia..”**
2. Name of Tenderer :
3. Address:
4. NIT No. : BCCL/XII/ACE/QTN/2011-12/53/1649 Date: 26.11.2011
5. Details of E.M.D. No: Rs: Date:

BILL OF QUANTITY: (Sl. No. 13)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 10.2	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	161.00	Kg	46.35	7,462.35
2/ 14.2.1	Fixing chowkhats in existing opening including embedding chowkhats in floors or walls cutting masonry for holdfasts embedding hold fasts in cement concrete blocks with cement concrete 1:3:6 (1 Cement: 3 coarse sand: 6 graded stone aggregate 20 mm nominal size). Painting two coats of approved wood preservative to sides of chowkhats and making good the damages to walls and floors as required complete including disposal of rubbish to the dumping ground within 50 meters lead: Door chowkhats.	4.00	Each	354.45	1,417.80
3/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	15.76	Sqm	143.75	2,265.50
4/ 17.13.1	Providing and fixing white vitreous china water closet squatting pan (Indian type) Long pattern W.C. pan of size 580mm	1.00	Each	534.60	534.60
5/ 13.16.1	6mm cement plaster of mix: 1:3 (1 cement: 3 fine sand).	2.04	Sqm	62.15	126.78
6/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	20.00	Sqm	67.65	1,353.00
7/ 17.60.1.2	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors: sand cast iron S & S as per IS: 1729.	1.00	Each	442.10	442.10
8/ 17.17.1	Providing and fixing a pair of white vitreous china foot rests of standard pattern for squatting pan water closet: 250x130x30mm	1.00	Pair	111.70	111.70
9/ M.R.	Engaging sweeper for cleaing.	1.00	Each	150.00	150.00
10/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	0.37	Cum	368.45	136.32
11/ 15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 meters lead: of are 3 sq. metres and below.	4.00	Each	54.60	218.40
12/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	165.00	Sqm	4.10	676.50
13/ 13.39.1	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats) with a base coat of white washing with lime.	65.00	Sqm	9.30	604.50
14/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	45.00	Sqm	22.85	1,028.25
TOTAL				Rs.	16,527.80
			Say	Rs.	16,528.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____)

Including the above percentage

FOR PAYMENT TO CONTRACTORS*(Note: To be submitted in Triplicate)*

PROFORMA FOR COLLECTING PAYMENT THROUGH ELECTRONIC MODE INCLUDING ELECTRONIC FUND TRANSFER (EFT) & ELECTRONIC CLEARING SYSTEM (ECS)

1	Vendor/ supplier/ contractor/ customer's name & address (with telephone number & Fax number)	
2	Particulars of Bank Account	
	a) Bank Name	
	b) Branch Name (Including RTGS Code)	
	Address	
	Telephone No. & Fax No.	
	c) 9 – Digit Code Number of the Bank & Branch (Appearing on the MICR Cheque issued on the bank) or 5 digit code number of SBI	
	d) Account Type (S.B. Account/ Current Account or Cash Credit with code 10/11/13)	
	e) Ledger No./ Ledger Folio No.	
	f) Account Number (Core Banking) & Style of Account (As appearing on the cheque Book)	

3. DATE OF EFFECT:

I hereby declare that the particulars given above are correct & complete. If the transaction is delayed or not effected at all for reasons of incomplete or incorrect information, I would not hold the user institution responsible. I have read the option invitation letter and agree to discharge responsibility expected of me as a participant under the scheme. Any bank charges levied by the bank of such e-transfer shall be borne by us.

Date: -

contractor

(_____)
Signature of customer/ vendor/ supplier/

Certified that the particulars furnished above are correct as per our records.

(_____)
Signature of the authorized officials from the Bank

DECLARATION

I, -----, Partner/Legal Attorney/ Accredited Representative of M/S -----
-----, solemnly declare that :

1. We are submitting Tender for the Work -----
----- against Tender
Notice No.----- dt -----
2. None of the Partners of our firm is relative of employee of Bharat Coking Coal Ltd.
3. All information furnished by us in respect of fulfillment of eligibility criteria and qualification information of this Tender is complete, correct and true.
4. None of the partners of the Firm has either individually or collectively been involved in criminal offences.
5. I hereby declare that /our firm has not been banned or delisted by any Govt. or Quasi Govt. agencies or PSUs.
6. All documents/ credentials submitted along with this Tender are genuine, authentic, true and valid.
7. I/ We hereby agree and assure the management that provision of engagement of 25% PAPs will be followed as per contract.
8. If any information and document submitted is found to be false/ incorrect any time, department may cancel my Tender and action as deemed fit may be taken against us, including termination of the contract, forfeiture of all dues including Earnest Money and banning / delisting of our firm and all partners of the firm etc.

Signature of the Tenderer

Dated-----