



**Bharat cooking coal Limited**  
(A Subsidiary of Coal India Limited)  
**OFFICE OF THE GENERAL MANAGER**  
**CHANCH-VICTORIA AREA-XII**  
**P.O.-BARAKAR – 713324, DIST-BURDWAN ( W.B.)**  
**Phone : 06540-272126 ; FAX 0341-2520063**



Ref. No. BCCL/XII/ACE/QTN/2011-12/56/1654

Dates: 28.11.2011

**QUOTATION NOTICE**

Sealed Quotations on percentage rate basis are invited from the bonafide & experienced contractors for the following works: Terms and conditions:

Sl.No.	Name of the work	Estimated cost	Earnest Money	Time of completion
1.	Cleaning of jungle and barbed wire fencing at Magazine complex.	Rs. 25,107.00	Rs. 255.00	15 days.
2.	Repairing & maint of Durga & Kali mandir at Chanch colony.	Rs. 20,679.00	Rs. 210.00	15 days.
3.	Making watch tower at roof top of CISF barrack at DBOCP.	Rs. 65,024.00	Rs. 651.00	30 days
4.	Accommodate water supply arrangement at existing VTC under C.V. Area.	Rs. 18,741.00	Rs. 190.00	15 days
5.	Repairing and maint. Of one Unit NHS qtr. At Bramsthan colony (Qtr. No. K-5)	Rs. 13,743.00	Rs. 140.00	10 days
6	Repairing of collapsed court yard wall and other misc civil works in qtrs No DB/B -10 at R.K. Colony.	Rs. 17,241.00	Rs. 175.00	10 days
7	Repairing & replacement of damage pipe line for minor type qtr at B.Mata colliery.	Rs. 43,525.00	Rs. 436.00	10 days
8	Repairing & maint. Of 2 units 'C' type qtr at B.Mata colliery for shifting of CISF personal from B. Mata Barrack (Qtr. No C/type 7 & 8)	Rs. 35,313.00	Rs. 355.00	20 days.
9	Cleaning of drain, ash and garbages in project colony, NLOCP.	Rs. 16,745.00	Rs. 170.00	10 days
10	White washing, colour washing, painting of 3 Nos. welfare center at Damagoria colliery.	Rs. 6,703.00	Rs. 70.00	10 days.
11	Remaking of drain at CMWO colony Laikdih.	Rs. 9,113.00	Rs. 95.00	10 days.
12	Making one culvert on drain to connect PWD road to laikdih Durga Mandir.	Rs. 14,193.00	Rs. 145.00	15 days.
13	Re-construction of drain with cover slabs and barbed wire fencing with RCC post, back site of proposed transformer room of V. West colliery.	Rs. 32,827.00	Rs. 330.00	20 days.
14	Renovation of kitchen shed at CISF Barrack Begunia.	Rs. 57,597.00	Rs. 576.00	30 days.

- Interested parties can collect the BOQ and other related papers of the Quotation from the office of the Area Civil Engineer, C.V. Area-XII, AT-Begunia, P.O –Barakar(W.B.). **From 08.12.2011 to 12.12.2011** during office hours except Sunday and Holiday. BOQ and other relevant pages (Declaration & EFT form) can be down loaded from BCCL website- <http://www.bccl.gov.in>
- Completed sealed Quotations will be received on **13.12.2011 up to 3.00 P.M.** at the following places. Quotation may Opt. any one place to submit their quotation as per their convenience.
  - In the office of the General Manager, C.V. Area-XII, AT-Begunia, P.O –Barakar(W.B.)
  - At BCCL H.Q. i.e. C.I.S.F. post, near Koyala Bhawan gate, Koyala Nagar, Dhanbad.
  - Office of the ACE, CCWO, W.W.Z. Area, Saraidhela, Dhanbad.
  - Office of the ACE, CHD, Jagjiban Nagar, Dhanbad.
- Quotations will be opened on **15.12.2011 at 11.30 A.M.** in the office of the Area Civil Engineer, C.V. Area-XII, AT-Begunia, P.O –Barakar(W.B.).
- Specification of work shall be governed by DSR-2007 & C.P.W.D specification.
- Terms and conditions as per C.I.L. C.E. manual shall be applicable against the quotations submitted against this Quotation Notice.

**Contd .....P/2**

6. Completed sealed Quotations shall consist of (1) EMD in the shape of cash receipt obtained from the finance deptt. C.V. Area-XII or DD from any Scheduled/Nationalised Bank, (2) Experience certificate, (3) Copy of Pan card, (4) Copy of VAT/Sales Tax clearance certificate along with VAT/Sales Tax registration No.(TIN), (5) Declaration and (6) EFT (Electronic Fund Transfer) & ECS (Electronic Clearance System) as per the format issued along with the Tender paper and (7) BOQ along with quoted rate by the Tenderer.
7. The quoted rate shall include all taxes and levies.
8. Statutory deductions for Income Tax and Sales Tax shall be made as per Rules and notifications.
9. The contractor has to abide by the Rules of Contract Labour Regulation & Abolition Act-.
10. Validity of tender shall be 120 days from the date of opening of the tender.
11. The contractors have to be acquainted with the site condition
12. Unless otherwise mentioned, no material will be issued by the department
13. Successful tender has to deposit 5% Performance Security (including 1% EMD) and another 5% Security Deposit will be deducted from the Running Account/ Final Bill.
14. It should be ensured that there must be provision for engagement of 25% PAPs.
15. The management of BCCL reserves right to reject any or all tender or split the work among two or more tenderers without assigning any reasons whatsoever.

**Sd/**  
**Area Civil Engineer**  
Chanch Victoria Area-XII

Copy to :-

- 1) GM, Chanch Victoria Area-XII.
- 2) GM (Civil), BCCL, Koyla Nagar.
- 3) All CGM/GM of Areas/Projects under BCCL.
- 4) Addl. GM, Chanch Victoria Area-XII.
- 5) A.F.M., Chanch Victoria Area-XII.
- 6) All P.O.s of Chanch Victoria Area-XII.
- 7) Cashier, C.V. Area-XII
- 8) Incharge,, CISF Post, Koyala Bhawan gate, Koyala Nagar,
- 9) Assistant Commandant, CISF, C.V. Area-XII-with 2 copies of NIT for displaying on Notice Board.
- 10) Builders Association of India, Central Akashkinaree Kanta, Katras Garh, Dhanbad-828113.
- 11) ACE CCWO, W.W.Z Area saraidhela, Dhanbad.
- 12) ACE CHD, jagiban Nagar, Dhanbad



**Bharat cocking coal Limited**  
(A Subsidiary of Coal India Limited)  
**OFFICE OF THE GENERAL MANAGER**  
**CHANCH-VICTORIA AREA-XII**  
**P.O.-BARAKAR – 713324, DIST-BURDWAN ( W.B.)**  
**Phone : 06540-272126 ; FAX 0341-2520063**

**Annex-I**



1. Name of Work: **“Cleaning of jungle and barbed wire fencing at Magazine complex.”**
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/56/1654

Date: 28.11.2011

5. Details of E.M.D. No:

Rs:

Date:

**BILL OF QUANTITY: (Sl. No. 1)**

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 2.31	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	4,607.84	100 sqm	263.90	12,160.08
2/ 2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kind of soil.	2.10	Cum	103.40	217.14
3/ 16.15.1	Supplying at site: R.C.C. standards post/struts/rails/pales of mix 1:1.5:3 (1 cement: 1.5 coarse sand: 3 graded stone aggregate 12.5 nominal size) with wooden plugs of 6mm bar nibs wherever required as per direction of Engineer-in-charge including fixing (cost of earth works in excavation, concrete works in foundation to be paid separately).	0.44	Cum	12,473.10	5,488.16
4/ 4.1.5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level: 1:3:6 (1 cement: 3 coarse sand: 6 graded stone aggregate 20 mm nominal size).	2.00	Cum	2,791.05	5,582.10
5/ 16.17.1	Fencing with R.C.C. post placed at required distance, ambedded in cement concrete blocks, every 15 <sup>th</sup> post, last but one end post and corner post shall be strutted on both sides and end post one side only, provided with horizontal lines and two diagonals of barbed wire 9.38 kg per 100 metres (min) between the two posts fitted and fixed with G.I. staples on wooden plugs or G.I. binding wire tied to 6 mm bar nibs fixed while casting the post (cost of R.C.C posts, struts, earth work and concrete to be paid for separately) :- Payment to be made per meter cost of total length of barbed wire used. With G.I. barbed wire.	283.64	Meter	5.85	1,659.29
<b>TOTAL</b>				<b>Rs.</b>	<b>25,106.77</b>
			<b>Say</b>	<b>Rs.</b>	<b>25,107.00</b>

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote \_\_\_\_\_ % ( \_\_\_\_\_ ) above / below the estimated cost.

Our quoted offer amounts to Rs. \_\_\_\_\_ ( Rupees \_\_\_\_\_

\_\_\_\_\_ ) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



**Bharat cocking coal Limited**  
(A Subsidiary of Coal India Limited)  
**OFFICE OF THE GENERAL MANAGER**  
**CHANCH-VICTORIA AREA-XII**  
**P.O.-BARAKAR – 713324, DIST-BURDWAN ( W.B.)**  
**Phone : 06540-272126 ; FAX 0341-2520063**

**Annex-I**



1. Name of Work: **“Repairing & maint of Durga & Kali mandir at Chanch colony.”**
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/56/1654

Date: 28.11.2011

5. Details of E.M.D. No:

Rs:

Date:

**BILL OF QUANTITY: (Sl. No. 2)**

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	0.41	Cum	368.45	151.06
2/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	16.95	Sqm	143.75	2,436.56
3/ 11.37	Providing and laying ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacture of 1 <sup>st</sup> quality conforming to IS: 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 cement: 4 coarse sand ) including pointing the joints with cement and matching pigment etc., complete.	23.42	Sqm	598.65	14,020.38
4/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	662.43	Sqm	4.10	2,715.96
5/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	59.32	Sqm	22.85	1,355.46
<b>TOTAL</b>				<b>Rs.</b>	<b>20,679.42</b>
			<b>Say</b>	<b>Rs</b>	<b>20,679.00</b>

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote \_\_\_\_\_% ( \_\_\_\_\_ ) above / below the estimated cost.

Our quoted offer amounts to Rs. \_\_\_\_\_ ( Rupees \_\_\_\_\_

\_\_\_\_\_ ) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



**Bharat cocking coal Limited**  
(A Subsidiary of Coal India Limited)  
**OFFICE OF THE GENERAL MANAGER**  
**CHANCH-VICTORIA AREA-XII**  
**P.O.-BARAKAR – 713324, DIST-BURDWAN ( W.B.)**  
**Phone : 06540-272126 ; FAX 0341-2520063**

**Annex-I**



1. Name of Work: **“Making watch tower at roof top of CISF barrack at DBOCP.”**
2. Name of Tenderer
3. Address:
4. NIT No. : BCCL/XII/ACE/QTN/2011-12/56/1654 Date: 28.11.2011
5. Details of E.M.D. No: Rs: Date:

**BILL OF QUANTITY: (Sl. No. 3)**

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.7.4	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meter lead as per direction of Engineer-in-charge. In cement mortar	1.40	Cum	310.75	435.05
2/ 2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kind of soil.	1.13	Cum	103.40	116.84
3/ 2.27	Supplying and filling in plinth with jamuna sand under floors including, watering, ramming consolidating and dressing complete.	0.11	Cum	301.50	33.16
4/ 4.1.8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level:1:4:8 (1 cement: 4 coarse sand: 8 graded stone aggregate 40 mm nominal size)	0.14	Cum	2,449.00	342.86
5/ 6.1.2	Brick work in F.P.S bricks of class designation 50 in foundation and plinth in: Cement mortar 1:6 (1 cement: 6 coarse sand).	1.37	Cum	2,021.85	2,769.93
6/ 6.4.2	Brick work in F.P.S. bricks of class designation 50 in superstructure above plinth level up to floor V level in all shapes and sizes in : cement mortar 1:6 (1 cement : 6 coarse sand).	11.05	Cum	2,257.50	24,945.37
7/ 5.3	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	2.19	Cum	3,673.85	8,045.73
8/ 5.9.3	Centering and shuttering including strutting, propping etc. and removal of form for: suspended floors, roofs, landing, balconies and access platform.	22.20	Sqm	187.35	4,159.17
9/ 5.9.5	Centering and shuttering including strutting, propping etc. and removal of form for: Lintels, beams, plinth beams, girders, bressumers and cantilevers.	2.02	Sqm	162.65	328.55
10/ 5.22.3	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete . Cold twisted bars.	175.20	K.G.	42.70	7,481.04
11/ 10.2	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete..	85.34	Kg	46.35	3,955.50
12/ 10.25.2	Steel work welded in built up section/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	61.25	Kg.	51.20	3,136.00
13/					

<b>14/ 11.3 A.R.</b>	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	19.53	Sqm	143.75	2,807.43
<b>15/ 13.39.2</b>	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats ) with a base coat of whitening.	81.83	Sqm	9.30	761.01
<b>16/ 13.61.1</b>	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work.	5.12	Sqm	35.25	170.24
	<b>TOTAL</b>			<b>Rs</b>	<b>65,023.67</b>
			<b>Say</b>	<b>Rs.</b>	<b>65,024.00</b>

Having gone through the Tender documents & elements of work in the bill of quantity:-

I / we quote \_\_\_\_\_ % ( \_\_\_\_\_ ) above / below the estimated cost.

Our quoted offer amounts to Rs. \_\_\_\_\_ (Rupees \_\_\_\_\_

\_\_\_\_\_ ) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



**Bharat cocking coal Limited**  
(A Subsidiary of Coal India Limited)  
**OFFICE OF THE GENERAL MANAGER**  
**CHANCH-VICTORIA AREA-XII**  
**P.O.-BARAKAR – 713324, DIST-BURDWAN ( W.B.)**  
**Phone : 06540-272126 ; FAX 0341-2520063**

**Annex-I**



1. Name of Work: “Accommodate water supply arrangement at existing VTC under C.V. Area.”
2. Name of Tenderer :
3. Address:
4. NIT No. : BCCL/XII/ACE/QTN/2011-12/56/1654 Date: 28.11.2011
5. Details of E.M.D. No: Rs: Date:

**BILL OF QUANTITY: (Sl. No. 4)**

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 6.4.2 (A.R.)	Brick work in F.P.S. bricks of class designation 50 in superstructure above plinth level up to floor V level in all shapes and sizes in : cement mortar 1:6 (1 cement : 6 coarse sand).	0.56	Cum	2,137.95	1,197.25
2/ 5.12	Providing, hoisting and fixing up to floor five level precast reinforced cement concrete work in string courses, bands copings, bed plates, anchor blocks, plain window sills and the like including the cost of required centering, shuttering, finishing smooth with 6 mm thick cement plaster 1:3 (1 cement: 3 fine sand ) on exposed surfaces complete but excluding cost of reinforcement with 1:2:4 (1 cement : 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	0.11	Cum	4,880.15	536.81
3/ 5.22.3	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete . Cold twisted bars.	10.00	K.G.	42.70	427.00
4/ A.R	Providing and laying single brick flat soiling class designation 50	1.85	Sqm	111.09	205.51
5/ 13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:4 (1 Cement: 4 fine sand).	2.09	Sqm	97.90	204.61
6/ 13.60.1	Wall painting with plastic emulsion paint of approved brand and manufacture to give en even shade: Two or more coats on new work.	69.60	Sqm	40.05	2,787.48
7/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	10.00	Sqm	67.65	676.50
8/ 10.2	Structural steel work riveted, bolted or welded in built up section, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete..	15.00	Kg	46.35	695.25
9/ 14.2.2	Fixing chowkhats in existing opening including embedding chowkhats in floors or walls cutting masonry for holdfasts embedding hold fasts in cement concrete blocks with cement concrete 1:3:6 (1 Cement: 3 coarse sand: 6 graded stone aggregate 20 mm nominal size). Painting two coats of approved wood preservative to sides of chowkhats and making good the damages to walls and floors as required complete including disposal of rubbish to the dumping ground within 50 meters lead: Window chowkhats.	1.00	Each	214.20	214.20
10/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	8.91	sqm	8.20	73.06
11/ 13.10	15mm cement plaster 1:3 (1 cement:3 coarse sand) finished with a floating coat of neat cement on the rough side of single or half brick wall.	8.91	Sqm	128.50	1,144.93
12/ 18.12.3	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. 25 mm dia nominal bore.	60.00	Meter.	156.85	9,411.00

Contd...P/2

<b>13/ 18.17.1</b>	Providing and fixing un metal gate valve with C.I. wheel of approved quality (screwed end): 25 mm nominal bore.	2.00	Each	285.50	571.00
<b>14/ 18.46.3</b>	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc .complete (New work).25 mm nominal bore.	4.00	Each	107.25	429.00
<b>15/ 18.13.1</b>	Making connection of G.I. distribution branch with G.I. main of following sized by providing and fixing tee, including cutting and threading the pipe etc. complete: 25 to 40 mm nominal bore.	1.00	Each	166.05	166.05
<b>TOTAL</b>				<b>Rs.</b>	<b>18,740.65</b>
			<b>Say</b>	<b>Rs</b>	<b>18,741.00</b>

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote \_\_\_\_\_% ( \_\_\_\_\_ ) above / below the estimated cost.

Our quoted offer amounts to Rs. \_\_\_\_\_ ( Rupees \_\_\_\_\_

\_\_\_\_\_ ) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer





**Bharat cocking coal Limited**  
(A Subsidiary of Coal India Limited)  
**OFFICE OF THE GENERAL MANAGER**  
**CHANCH-VICTORIA AREA-XII**  
**P.O.-BARAKAR – 713324, DIST-BURDWAN ( W.B.)**  
**Phone : 06540-272126 ; FAX 0341-2520063**

**Annex-I**



1. Name of Work: **“Repairing and maint. Of one Unit NHS qtr. At Bramsthan colony (Qtr. No. K-5).”**
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/56/1654

Date: 28.11.2011

5. Details of E.M.D. No:

Rs:

Date:

**BILL OF QUANTITY: (Sl. No. 5)**

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	10.73	sqm	8.20	87.99
2/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	1.18	Cum	368.45	434.77
3/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	48.44	Sqm	143.75	6,963.25
4/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	12.31	Sqm	67.65	832.77
5/ 15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 meters lead: of are 3 sq. metres and below.	2.00	Each	54.60	109.20
6/ 10.25.2	Steel work welded in built up section/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	66.00	Kg.	51.20	3,379.20
7/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	240.00	Sqm	4.10	984.00
8/ 13.61.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work.	6.90	Sqm	33.25	229.42
9/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	31.60	Sqm	22.85	722.06
TOTAL				Rs	13,742.66
			Say	Rs.	13,743.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote \_\_\_\_\_% ( \_\_\_\_\_ ) above / below the estimated cost.

Our quoted offer amounts to Rs. \_\_\_\_\_ ( Rupees \_\_\_\_\_

\_\_\_\_\_ ) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



**Bharat cocking coal Limited**  
(A Subsidiary of Coal India Limited)  
**OFFICE OF THE GENERAL MANAGER**  
**CHANCH-VICTORIA AREA-XII**  
**P.O.-BARAKAR – 713324, DIST-BURDWAN ( W.B.)**  
**Phone : 06540-272126 ; FAX 0341-2520063**

**Annex-I**



1. Name of Work: “Repairing of collapsed court yard wall and other misc civil works in qtrs No DB/B -10 at R.K. Colony.”

2. Name of Tenderer :

3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/56/1654

Date: 28.11.2011

5. Details of E.M.D. No:

Rs:

Date:

**BILL OF QUANTITY: (Sl. No. 6)**

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.7.4	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meter lead as per direction of Engineer-in-charge. In cement mortar	2.21	Cum	310.75	686.75
2/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	0.77	Cum	368.45	283.70
3/ 6.12.2	Half brick masonry with F.P.S. brick of class designation in foundations and plinth in . cement mortar 1:4 (1 cement: 4 coarse sand).	12.17	Sqm	257.20	3,130.12
4/ 6.13.2	Half brick masonry with F.P.S bricks of class designation 50 in superstructure above plinth level up to floor V level Cement mortar 1:4 ( 1 cement: 4 coarse sand )	12.17	Sqm	289.65	3,525.04
5/ 6.1.2	Brick work in F.P.S bricks of class designation 50 in foundation and plinth in: Cement mortar 1:6 (1 cement: 6 coarse sand).	0.11	Cum	2,007.00	220.77
6/ 6.4.2 (A.R.)	Brick work in F.P.S. bricks of class designation 50 in superstructure above plinth level up to floor V level in all shapes and sizes in : cement mortar 1:6 (1 cement : 6 coarse sand).	0.11	Cum	2,137.95	235.17
7/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	51.32	Sqm	67.65	3,471.79
8/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	36.24	Sqm	143.75	5,209.50
9/ 13.39.1	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats ) with a base coat of white washing with lime.	51.32	Sqm	9.30	477.27
<b>TOTAL</b>				<b>Rs.</b>	<b>17,240.70</b>
			<b>Say</b>	<b>Rs</b>	<b>17,241.00</b>

Having gone through the Tender documents & elements of work in the bill of quantity:-

I / we quote \_\_\_\_\_% ( \_\_\_\_\_ ) above / below the estimated cost.

Our quoted offer amounts to Rs. \_\_\_\_\_ ( Rupees \_\_\_\_\_

\_\_\_\_\_ ) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



**Bharat cocking coal Limited**  
(A Subsidiary of Coal India Limited)  
**OFFICE OF THE GENERAL MANAGER**  
**CHANCH-VICTORIA AREA-XII**  
**P.O.-BARAKAR – 713324, DIST-BURDWAN ( W.B.)**  
**Phone : 06540-272126 ; FAX 0341-2520063**

**Annex-I**



1. Name of Work: **“Repairing & replacement of damage pipe line for minor type qtr at B.Mata colliery.”**
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/56/1654

Date: 28.11.2011

5. Details of E.M.D. No:

Rs:

Date:

**BILL OF QUANTITY: (Sl. No. 7)**

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.44.1	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including staking of pipes within 50 metres lead as per direction of Engineer-in-charge: 15 to 40 mm nominal bore.	50.00	Metre	24.90	1,245.00
2/ 15.44.2	Dismantling G.I. pipes (external work) including excavation and refilling trenches after taking out the pipes, manually/ by mechanical means including staking of pipes within 50 metres lead as per direction of Engineer-in-charge: above 40 mm nominal bore.	28.00	Metre	29.05	813.40
3/ 18.12.8	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. 80 mm dia nominal bore.	8.00	Meter.	458.15	3,665.20
4/ 18.12.6	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. 50 mm dia nominal bore.	62.00	Meter.	280.10	17,366.20
5/ 18.12.5	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. 40 mm dia nominal bore.	28.00	Meter.	219.60	6,148.80
6/ 18.12.3	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. 25 mm dia nominal bore.	75.00	Meter.	156.85	11,763.75
7/ 18.13.1	Making connection of G.I. distribution branch with G.I. main of following sized by providing and fixing tee, including cutting and threading the pipe etc. complete: 25 to 40 mm nominal bore.	5.00	Each	166.05	830.25
8/ 18.13.2	Making connection of G.I. distribution branch with G.I. main of following sized by providing and fixing tee, including cutting and threading the pipe etc. complete: 50 to 80 mm nominal bore.	4.00	Each	423.20	1,692.80
<b>TOTAL</b>				<b>Rs.</b>	<b>43,525.40</b>
			<b>Say</b>	<b>Rs.</b>	<b>43,525.00</b>

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote \_\_\_\_\_ % ( \_\_\_\_\_ ) above / below the estimated cost.

Our quoted offer amounts to Rs. \_\_\_\_\_ ( Rupees \_\_\_\_\_

\_\_\_\_\_ ) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



**Bharat cocking coal Limited**  
(A Subsidiary of Coal India Limited)  
**OFFICE OF THE GENERAL MANAGER**  
**CHANCH-VICTORIA AREA-XII**  
**P.O.-BARAKAR – 713324, DIST-BURDWAN ( W.B.)**  
**Phone : 06540-272126 ; FAX 0341-2520063**

**Annex-I**



1. Name of Work: **“Repairing & maint. Of 2 units ‘C’ type qtr at B.Mata colliery for shifting of CISF personal from B. Mata Barrack (Qtr. No C/type 7 & 8)”**

2. Name of Tenderer :

3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/56/1654

Date: 28.11.2011

5. Details of E.M.D. No:

Rs:

Date:

**BILL OF QUANTITY: (Sl. No. 8)**

SL.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 meters lead: of are 3 sq. metres and below.	3.00	Each	54.60	163.80
2/ 9.1.3	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position. Kiln seasoned and chemically treated Hollock wood.	0.11	Cum	31,339.40	3,447.33
3/ 9.53	Providing 40x5 mm flat iron hold fast 40 cm long including fixing to frame with 10 mm diameter bolts, nuts and wooden plugs and embeddings in cement concrete block 30x10x15cm 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size).	9.00	Each	61.50	553.50
4/ 17.23	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively.	2.00	Each	578.95	1,157.90
5/ 17.28.1.2	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. 40 mm dia.	2.00	Each	47.95	95.90
6/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	30.00	sqm	8.20	246.00
7/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	30.00	Sqm	67.65	2,029.50
8/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	617.80	Sqm	4.10	2,532.98
9/ 13.39.1	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats ) with a base coat of white washing with lime.	816.34	Sqm	9.30	7,591.96
10/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	178.18	Sqm	22.85	4,071.41
11/ 9.7.2	Panelling for paneled for paneled and glazed shutters 20 to 40 mm thick:Kiln seasoned and chemically treated Hollock wood.	7.71	Sqm	711.25	5,483.73
12/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	1.26	Cum	368.45	464.24
13/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	52.00	Sqm	143.75	7,475.00
<b>TOTAL</b>				<b>Rs.</b>	<b>35,313.25</b>
			<b>Say</b>	<b>Rs.</b>	<b>35,313.00</b>

Having gone through the Tender documents & elements of work in the bill of quantity :-

I/We quote Rs. /-

above / below the estimated



**Bharat cocking coal Limited**  
 (A Subsidiary of Coal India Limited)  
**OFFICE OF THE GENERAL MANAGER**  
**CHANCH-VICTORIA AREA-XII**  
**P.O.-BARAKAR – 713324, DIST-BURDWAN ( W.B.)**  
**Phone : 06540-272126 ; FAX 0341-2520063**



1. Name of Work: “Cleaning of drain, ash and garbages in project colony, NLOCP.”
2. Name of Tenderer:
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/56/1654

Date: 28.11.2011

5. Details of E.M.D. No:

Rs:

Date:

**BILL OF QUANTITY: (Sl. No. 9)**

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ A.R	Cleaning of Katch /pucca drain including disposal of exterminated material such as liquid mud, sludge etc up to 50 mter. Lead as drain by Engineer-in-charge.	84.13	Cum	108.09	9,093.61
2/ 1.1.3	Carriage of material by mechanical transport including loading, un loading and stacking. Lead up to 1 K.M. Earth	178.06	Cum	42.97	7,651.24
	<b>TOATAL</b>			<b>Rs.</b>	<b>16,744.24</b>
			<b>Say</b>	<b>Rs.</b>	<b>16,745.00</b>

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote \_\_\_\_\_% ( \_\_\_\_\_ ) above / below the estimated cost.

Our quoted offer amounts to Rs. \_\_\_\_\_ ( Rupees \_\_\_\_\_

\_\_\_\_\_ ) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



**Bharat cocking coal Limited**  
(A Subsidiary of Coal India Limited)  
**OFFICE OF THE GENERAL MANAGER**  
**CHANCH-VICTORIA AREA-XII**  
**P.O.-BARAKAR – 713324, DIST-BURDWAN ( W.B.)**  
**Phone : 06540-272126 ; FAX 0341-2520063**

**Annex-I**



1. Name of Work: **“White washing, colour washing, painting of 3 Nos. welfare center at Damagoria colliery.”**
2. Name of Tenderer:
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/56/1654

Date: 28.11.2011

5. Details of E.M.D. No:

Rs:

Date:

**BILL OF QUANTITY: (Sl. No. 10)**

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 14.42.1	White washing with lime to give an even shade: Old work (two or more coats).	541.83	Sqm	4.10	2,221.50
2/ 14.53.1	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: one or more coats on old work.	19.38	Sqm	25.85	500.97
3/ 13.66.1	Floor painting with floor enamel paint of approved brand and manufacture of required colour to give an even shade: two or more coats on new work.	17.84	Sqm	37.05	660.97
4/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: one or more coats on old work.	76.52	Sqm	22.85	1,748.48
5/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	20.00	Sqm	67.65	1,353.00
6/ 2.32	Clearing grass and removal of the rubbish up to distance of 50 m outside the periphery of the area cleared.	100.00	100 Sqm	135.65	135.65
7/ 15.56	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	10.00	sqm	8.20	82.00
<b>TOTAL</b>				<b>Rs</b>	<b>6,0702.57</b>
			<b>Say</b>	<b>Rs.</b>	<b>6,703.00</b>

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote \_\_\_\_\_% ( \_\_\_\_\_ ) above / below the estimated cost.

Our quoted offer amounts to Rs. \_\_\_\_\_ ( Rupees \_\_\_\_\_

\_\_\_\_\_ ) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



**Bharat cocking coal Limited**  
(A Subsidiary of Coal India Limited)  
**OFFICE OF THE GENERAL MANAGER**  
**CHANCH-VICTORIA AREA-XII**  
**P.O.-BARAKAR – 713324, DIST-BURDWAN ( W.B.)**  
**Phone : 06540-272126 ; FAX 0341-2520063**

**Annex-I**



1. Name of Work: **“Remaking of drain at CMWO colony Laikdih.”**
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/56/1654

Date: 28.11.2011

5. Details of E.M.D. No:

Rs:

Date:

**BILL OF QUANTITY: (Sl. No. 11)**

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ A.R	Cleaning of Katch /pucca drain including disposal of exterminated material such as liquid mud, sludge etc up to 50 mter. Lead as drain by Engineer-in-charge.	0.99	Cum	108.09	107.00
2/ 2.27	Supplying and filling in plinth with jamuna sand under floors including, watering, ramming consolidating and dressing complete.	0.32	Cum	301.50	96.48
3/ 4.1.8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level:1:4:8 (1 cement: 4 coarse sand: 8 graded stone aggregate 40 mm nominal size)	0.51	Cum	2,449.00	1,248.99
4/ 6.1.2	Brick work in F.P.S bricks of class designation 50 in foundation and plinth in: Cement mortar 1:6 (1 cement: 6 coarse sand).	0.78	Cum	2,007.00	1,565.46
5/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	1.53	Sqm	143.75	219.94
6/ 13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:4 (1 Cement: 4 fine sand).	16.29	Sqm	97.90	1,594.79
7/ 5.3	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:2 4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	0.35	Cum	3,673.85	1,285.85
8/ 5.9.3	Centering and shuttering including strutting, propping etc. and removal of form for: suspended floors, roofs, landing, balconies and access platform.	2.71	Sqm	187.35	507.72
9/ 5.22.3	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete . Cold twisted bars.	28.00	K.G.	42.70	1,195.60
10/ 6.12.2	Half brick masonry with F.P.S. brick of class designation in foundations and plinth in . cement mortar 1:4 (1 cement: 4 coarse sand).	5.02	Sqm	257.20	1,291.14
<b>TOTAL</b>				<b>Rs.</b>	<b>9,112.97</b>
			<b>Say</b>	<b>Rs.</b>	<b>9,113.00</b>

Having gone through the Tender documents & elements of work in the bill of quantity:-

I / we quote \_\_\_\_\_% ( \_\_\_\_\_ ) above / below the estimated cost.

Our quoted offer amounts to Rs. \_\_\_\_\_ (Rupees \_\_\_\_\_)

\_\_\_\_\_ ) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



**Bharat cocking coal Limited**  
 (A Subsidiary of Coal India Limited)  
**OFFICE OF THE GENERAL MANAGER**  
**CHANCH-VICTORIA AREA-XII**  
**P.O.-BARAKAR – 713324, DIST-BURDWAN ( W.B.)**  
**Phone : 06540-272126 ; FAX 0341-2520063**



1. Name of Work: **“Making one culvert on drain to connect PWD road to laikdih Durga Mandir.”**

2. Name of Tenderer :

3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/56/1654

Date: 28.11.2011

5. Details of E.M.D. No:

Rs:

Date:

**BILL OF QUANTITY: (Sl. No. 12)**

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 2.27	Supplying and filling in plinth with jamuna sand under floors including, watering, ramming consolidating and dressing complete.	0.31	Cum	301.50	93.47
2/ A.R.	Dry brick flat soling with bricks of CD 50.	4.09	Cum	111.09	454.36
3/ 4.1.8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level:1:4:8 (1 cement: 4 coarse sand: 8 graded stone aggregate 40 mm nominal size)	0.41	Cum	2,449.00	1,004.09
4/ 6.1.2	Brick work in F.P.S bricks of class designation 50 in foundation and plinth in: Cement mortar 1:6 (1 cement: 6 coarse sand).	2.65	Cum	2,007.00	5,318.55
5/ 13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:4 (1 Cement: 4 fine sand).	13.03	Sqm	97.90	1,275.64
6/ 5.3	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:2 4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	0.62	Cum	3,496.35	2,167.74
7/ 5.22.3	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete . Cold twisted bars.	75.00	K.G.	42.70	3,202.50
8/ 5.9.3	Centering and shuttering including strutting, propping etc. and removal of form for: suspended floors, roofs, landing, balconies and access platform.	3.61	Sqm	187.35	676.33
<b>TOTAL</b>				<b>Rs.</b>	<b>14,192.68</b>
			<b>Say</b>	<b>Rs.</b>	<b>14,193.00</b>

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote \_\_\_\_\_ % ( \_\_\_\_\_ ) above / below the estimated cost.

Our quoted offer amounts to Rs. \_\_\_\_\_ ( Rupees \_\_\_\_\_

\_\_\_\_\_ ) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer





**Bharat cocking coal Limited**  
(A Subsidiary of Coal India Limited)  
**OFFICE OF THE GENERAL MANAGER**  
**CHANCH-VICTORIA AREA-XII**  
**P.O.-BARAKAR – 713324, DIST-BURDWAN ( W.B.)**  
**Phone : 06540-272126 ; FAX 0341-2520063**

**Annex-I**



1. Name of Work: **“Re-construction of drain with cover slabs and barbed wire fencing with RCC post, back site of proposed transformer room of V. West colliery.”**
2. Name of Tenderer :
3. Address:
4. NIT No. : BCCL/XII/ACE/QTN/2011-12/56/1654 Date: 28.11.2011
5. Details of E.M.D. No: Rs: Date:

**BILL OF QUANTITY: (Sl. No. 13)**

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 2.6.1- 2.35	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth. 1.5m in width as well as 10sqm on plan) including disposal of excavated earth, lead up to 50m and lift up to 1.5m, disposed earth to be leveled and neatly dressed. All kinds of soil.	2.86	Cum	(101.85-13.85)= 88/-	251.68
2/ 4.1.8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level:1:4:8 (1 cement: 4 coarse sand: 8 graded stone aggregate 40 mm nominal size)	3.74	Cum	2,449.00	9,159.26
3/ 6.1.2	Brick work in F.P.S bricks of class designation 50 in foundation and plinth in: Cement mortar 1:6 (1 cement: 6 coarse sand).	2.25	Cum	2,007.00	4,515.75
4/ 13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix: 1:4 (1 Cement: 4 fine sand).	13.65	Sqm	97.90	1,336.33
5/ 11.3 A.R.	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete. 25 mm thick with 12.5 mm nominal size stone aggregate.	4.45	Sqm	143.75	639.68
6/ 5.12	Providing, hoisting and fixing up to floor five level precast reinforced cement concrete work in string courses, bands copings, bed plates, anchor blocks, plain window sills and the like including the cost of required centering, shuttering, finishing smooth with 6 mm thick cement plaster 1:3 (1 cement: 3 fine sand ) on exposed surfaces complete but excluding cost of reinforcement with 1:2:4 (1 cement : 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	0.71	Cum	4,880.15	3,464.90
7/ 5.22.3	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete . Cold twisted bars.	53.25	K.G.	42.70	2,273.77
8/ 16.15.1	Supplying at site: R.C.C. standards post/struts/rails/pales of mix 1:1.5:3 (1 cement: 1.5 coarse sand: 3 graded stone aggregate 12.5 nominal size) with wooden plugs of 6mm bar nibs wherever required as per direction of Engineer-in-charge including fixing (cost of earth works in excavation, concrete works in foundation to be paid separately).	0.67	Cum	12,473.10	8,356.97
9/ 2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kind of soil.	2.80	Cum	103.40	289.52

Contd.....P/2

<b>10/ 16.17.1</b>	Fencing with R.C.C. post placed at required distance, ambedded in cement concrete blocks, every 15 <sup>th</sup> post, last but one end post and corner post shall be strutted on both sides and end post one side only, provided with horizontal lines and two diagonals of barbed wire 9.38 kg per 100 metres (min) between the two posts fitted and fixed with G.I. staples on wooden plugs or G.I. binding wire tied to 6 mm bar nibs fixed while casting the post (cost of R.C.C posts, struts, earth work and concrete to be paid for separately) :- Payment to be made per meter cost of total length of barbed wire used. With G.I. barbed wire.	434.00	Meter	5.85	2,538.90
	<b>TOTAL</b>			<b>Rs.</b>	<b>32,826.76</b>
			<b>Say</b>	<b>Rs.</b>	<b>32,827.00</b>

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote \_\_\_\_\_ % ( \_\_\_\_\_ ) above / below the estimated cost.

Our quoted offer amounts to Rs. \_\_\_\_\_ ( Rupees \_\_\_\_\_

\_\_\_\_\_ ) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer



**Bharat cocking coal Limited**  
 (A Subsidiary of Coal India Limited)  
**OFFICE OF THE GENERAL MANAGER**  
**CHANCH-VICTORIA AREA-XII**  
**P.O.-BARAKAR – 713324, DIST-BURDWAN ( W.B.)**  
**Phone : 06540-272126 ; FAX 0341-2520063**



1. Name of Work: **“Renovation of kitchen shed at CISF Barrack Begunia.”**
2. Name of Tenderer:
3. Address:
4. NIT No. : BCCL/XII/ACE/QTN/2011-12/56/1654 Date: 28.11.2011
5. Details of E.M.D. No: Rs: Date:

**BILL OF QUANTITY: (Sl. No. 14)**

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.28.2	Dismantling roofing including ridges, hips valleys and gutters etc., and stacking the material with 50 metres lead of: Asbestos sheet.	31.21	Sqm	11.75	366.71
2/ 15.17.2	Dismantling steel work in single sections including dismembering and stacking within 50 meters lead in: Channels, angles, tees and flats.	254.01	Kg.	0.35	88.90
3/ 15.7.4	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 meter lead as per direction of Engineer-in-charge. In cement mortar	3.16	Cum	310.75	981.97
4/ 2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kind of soil.	7.42	Cum	103.40	767.22
5/ 4.1.8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level:1:4:8 (1 cement: 4 coarse sand: 8 graded stone aggregate 40 mm nominal size)	1.48	Cum	2,449.00	3,624.52
6/ 6.1.2	Brick work in F.P.S bricks of class designation 50 in foundation and plinth in: Cement mortar 1:6 (1 cement: 6 coarse sand).	4.94	Cum	2,007.00	9,914.58
7/ 6.4.2 (A.R.)	Brick work in F.P.S. bricks of class designation 50 in superstructure above plinth level up to floor V level in all shapes and sizes in : cement mortar 1:6 (1 cement : 6 coarse sand).	8.00	Cum	2,315.50	18,524.00
8/ A.R	Labour cost for steel work in single section.	254.01	Kg.	6.15	1,562.16
9/ 13.1.2	12 mm cement plaster of mix: 1:6 (1 Cement: 6 fine sand).	66.89	Sqm	67.65	4,525.10
10/ 12.10.1 SOR '02	Providing and fixing 6 mm thick A.C. Sheet roof as per directive of Engineer-in-charge.	47.37	Sqm	153.65	7,278.40
11/ 12.11	Extra for providing and fixing wind ties of 40x6 mm flat iron section.	18.28	Metre	73.65	1,346.32
12/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	1.50	Cum	368.45	552.67
13/ 11.3.1	Cement concrete flooring 1:2:4 (1 cement:2 coarse sand: 4 graded stone aggregate) finished with a floating coat of neat sement including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate.	39.46	Sqm	192.95	7,613.80
14/ 13.37.1	White washing with lime to give an even shade: New work (three or more coats)	66.89	Sqm	6.75	451.50
	<b>TOTAL</b>			<b>Rs.</b>	<b>57,597.85</b>
			<b>Say</b>	<b>Rs.</b>	<b>57,597.00</b>

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote \_\_\_\_\_ % ( \_\_\_\_\_ ) above / below the estimated cost.

Our quoted offer amounts to Rs. \_\_\_\_\_ (Rupees \_\_\_\_\_)

\_\_\_\_\_ ) including the above percentage

**FOR PAYMENT TO CONTRACTORS***(Note: To be submitted in Triplicate)***PROFORMA FOR COLLECTING PAYMENT THROUGH ELECTRONIC MODE INCLUDING ELECTRONIC FUND TRANSFER (EFT) & ELECTRONIC CLEARING SYSTEM (ECS)**

1	Vendor/ supplier/ contractor/ customer's name & address (with telephone number & Fax number)	
2	Particulars of Bank Account	
	a) Bank Name	
	b) Branch Name (Including RTGS Code)	
	Address	
	Telephone No. & Fax No.	
	c) 9 – Digit Code Number of the Bank & Branch (Appearing on the MICR Cheque issued on the bank) or 5 digit code number of SBI	
	d) Account Type (S.B. Account/ Current Account or Cash Credit with code 10/11/13)	
	e) Ledger No./ Ledger Folio No.	
	f) Account Number (Core Banking) & Style of Account (As appearing on the cheque Book)	

**3. DATE OF EFFECT:**

I hereby declare that the particulars given above are correct & complete. If the transaction is delayed or not effected at all for reasons of incomplete or incorrect information, I would not hold the user institution responsible. I have read the option invitation letter and agree to discharge responsibility expected of me as a participant under the scheme. Any bank charges levied by the bank of such e-transfer shall be borne by us.

Date: -

contractor

( \_\_\_\_\_ )  
Signature of customer/ vendor/ supplier/

Certified that the particulars furnished above are correct as per our records.

( \_\_\_\_\_ )  
Signature of the authorized officials from the Bank

**DECLARATION**

I, -----, Partner/Legal Attorney/ Accredited Representative of M/S -----  
-----, solemnly declare that :

1. We are submitting Tender for the Work -----  
----- against Tender  
Notice No.----- dt -----
2. None of the Partners of our firm is relative of employee of Bharat Coking Coal Ltd.
3. All information furnished by us in respect of fulfillment of eligibility criteria and qualification information of this Tender is complete, correct and true.
4. None of the partners of the Firm has either individually or collectively been involved in criminal offences.
5. I hereby declare that /our firm has not been banned or delisted by any Govt. or Quasi Govt. agencies or PSUs.
6. All documents/ credentials submitted along with this Tender are genuine, authentic, true and valid.
7. I/ We hereby agree and assure the management that provision of engagement of 25% PAPs will be followed as per contract.
8. If any information and document submitted is found to be false/ incorrect any time, department may cancel my Tender and action as deemed fit may be taken against us, including termination of the contract, forfeiture of all dues including Earnest Money and banning / delisting of our firm and all partners of the firm etc.

Signature of the Tenderer

Dated-----