

BHARAT COKING COAL LIMITED

(A Subsidiary of Coal India Limited)

Regd. Office : Koyla Bhawan

**OFFICE OF THE GENERAL MANAGER (CIVIL)
CIVIL ENGINEERING DEPARTMENT
KOYLA NAGAR (DHANBAD)**

1. Name of work : Emergent Roof Repair of Civil Engineering Department at Koyla Nagar, BCCL.
2. Name of contractor :

Address (with Pin Code) :
3. Quotation Ref. No. : BCCL/CED/TC/QTN-11/2011-12/3994-4019 dtd. 13.09.2011
4. Date of Receipt of Quotation : From 10.00 AM to 3.00 P.M. on 26.09.2011
5. Date of open of Quotation : AT 04.00 P.M. on 26.09.2011
6. Documents Issued
 - i) Quotation Notice : 2 (two) pages
 - ii) Bill of Quantity : 1 (one) page
7. Details of E.M.D. :

SIGNATURE OF ISSUING OFFICER



भारत कोकिंग कोल लिमिटेड

(कोल इंडिया लिमिटेड का एक अंग)

BHARAT COKING COAL LIMITED

(A Subsidiary of Coal India Limited)

Civil Engineering Department, Koyla Nagar, Dhanbad – 826 005 (JH) India.

Ref. No. : BCCL/CED/TC/QTN-11/2011-12/3994-4019

Date: 13.09.2011

QUOTATION NOTICE

Sealed Quotation on overall Percentage Rate basis are invited from the reputed contractors for the following work and the same will be received on **26.09.2011** from 10.00 AM to 3.00 P.M. in **Tender Box No. 20** kept at **C.I.S.F. Post, near Koyla Bhawan Gate, Koyla Nagar, BCCL, Dhanbad** and opened at **04.00 P.M. on 26.09.2011** in the Office of GM (Civil), Civil Engineering Department, BCCL, Koyla Nagar, Dhanbad in the presence of intending tenderers or their authorized representatives. B.O.Q. for the job can be obtained from the office of the GM (Civil), CED, Koyla Nagar during working hours from **19.09.2011 to 23.09.2011**. The Quotation is also available on Website <http://www.bccl.gov.in/> and can be downloaded. The other documents such as General terms & conditions and responsibility of the contractors, additional safety measures etc. also can be seen in the office of GM (Civil), Civil Engineering Department, Koyla Nagar on any working day which will be applicable to the contract. The details of works are given below:-

Name of work	Estimated cost	Earnest money	Time of completion
Emergent Roof Repair of Civil Engineering Department at Koyla Nagar, BCCL.	₹ 96,431.68	₹ 1,000.00	1 (one) month

No materials will be issued by the department for this work. The Quotation to be submitted in single Part. No tender without Earnest Money will be acceptable. Earnest Money to be submitted in form of cash or bank draft of Nationalized bank/ scheduled commercial bank approved by Reserve Bank of India in favour of Bharat Coking Coal Ltd., payable at Dhanbad.

The tenderers have to submit Permanent Account Number of Income Tax (PAN No.) & TIN No.

Chief Manager (Civil) TC

Distribution:-

- 1) CGM/GMs of all Areas of BCCL – for display in Notice Board.
- 2) G.M.(Civil), CED, Koyla Nagar.
- 3) Chief Manager (Civil) W/S, CED
- 4) Chief Manager (Civil) EC, CED
- 5) Sr. Manager (Finance), CED, Koyla Nagar.
- 6) Manager (Civil) TC, CED
- 7) Dy Manager (Finance), CED
- 8) Inspector I/c, CISF, Koyla Bhawan
- 9) Notice Board.
- 10) Concerned File
- 11) Tender Cell, CED

Security Deposit

4.1.1 Security Deposit shall consist of two parts;

- a) Performance Security to be submitted at award of work and
- b) Retention Money to be recovered from running bills.

The security deposit shall bear no interest.

4.1.2 Performance Security should be 5% of contract amount and should be submitted within 28 days of receipt of LOA by the successful bidders in any of the form given below

- a Bank Guarantee in the form given in the bid document
- Govt. Securities, FDR or any other form of deposit stipulated by the owner
- Demand Draft drawn in favour of Bharat Coking Coal Limited on any Scheduled Bank payable at its Branch at Dhanbad.

The Earnest Money/ Bid Security deposited in the form of Bank Guarantee shall be discharged when the Bidder has signed the Agreement and furnished the required Performance Security/ Security Deposit. The bid security deposited in the form of Demand draft/ cash shall be adjusted against the security deposit.

If performance security is provided by the successful bidders in the form of bank guarantee it shall be issued either -

- (a) at Bidder's option by a nationalized/ Scheduled Indian Bank or
- (b) by a foreign bank located in India and acceptable to the employer.
- (c) the validity of the Bank Guarantee shall be for a period of one year or ninety days beyond the period of contract, whichever is more.

Failure of the successful bidder to comply with the requirement as above shall constitute sufficient ground for cancellation of the award of work and forfeiture of the bid security.

4.2.1 All running on account bills shall be paid at 95% (ninety five percent) of work value. This 5% (five percent) deduction towards Retention Money will be the second part of security deposit.

4.2.2 . 5% Performance Security should be refunded within 14 days of the issue of defect liability certificate (taking over certificate with a list of defects). Retention Money should be refunded after issue of No Defect Certificate. Retention Money should be deducted at 5% from running bills.

4.3 The Bank Guarantee towards security deposit shall be acceptable only for values above Rs.50, 000/- and the Bank Guarantee shall also be valid for a minimum period of one year or ninety days beyond the period of contract, whichever is more.. Bank Guarantee is to be submitted in the format prescribed by the company. Bank Guarantee shall be irrevocable and will be from amongst the list of Banks (Scheduled Banks) provided in the bid document.

4.4 The Company shall be at liberty to deduct/appropriate from the security deposit such sums as are due and payable by the contractor to the company as may be determined in terms of the contract, and the amount appropriated from the security deposit shall have to be restored by further deduction from the contractors subsequent on account running bills, if any.

The refund of security deposit shall be subject to company's right to deduct/ appropriate its due against the contractor under this contract or under any other contract.

4.5 On completion of the entire work and issue of defect liability certificate (taking over certificate with a list of defects) by the Engineer-in-charge, one half of the security deposit remaining with the company shall be refunded. The other half shall be refunded to the contractor after issue of No Defect Certificate by the Engineer-in-Charge. on the expiry of Defect Liability Period of six months , subject to the following conditions:

a) Any defect/defects in the work, if detected after issue of defect liability certificate is/are rectified to the satisfaction of the Engineer-in-Charge within the said period.

b) In the case of building work or other work of similar nature, the refund shall be made on the expiry of the said six months period or at the end of one full monsoon period i.e. June to September, whichever is later in point of time and any defects such as leakages in roof, effloresces in walls, dampness, defects in drainage etc. should be rectified to the satisfaction of Engineer-in-Charge.

**Bill of Quantity for the Work of “Emergent Roof Repair of Civil Engineering
Department at Koyla Nagar, BCCL.”**

Sr. No.	Description of Item	unit	Quantity	Rate	Amount (₹)
1	Removal of Old tar felt	sqm	417.00	14.46	6029.82
2	Providing and laying four courses water proofing treatment with bitumen felt over roofs consisting of first and third courses of blown bitumen 85/25 or 90/15 conforming to IS : 702 applied hot @ 1.45 Kg per square metre of area for each course, second course of roofing felt type 3 grade-I (Hessian based self finished bitumen” felt) and fourth and final course of stone grit 6mm and down size or pea-sized gravel spread at 6 cubic diameter per square metre including preparation of surface but excluding grading complete with : Bitumen felt (hessian base) type 3 grade I conforming to IS : 1322.	sqm	417.00	184.80	77061.60
3	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	sqm	57.00	8.20	467.40
4	Grading roof for water proofing treatment with Cement concrete 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	cum	2.80	3314.95	9281.86
5	Painting top of roofs with bitumen of approved quality at 17kg per 10 sqm impregnated with a coat of coarse sand at 60 cum per 10 sqm including cleaning the slab surface with brushes and finally with a piece of cloth lightly soaked in kerosene oil complete : With residual type petroleum bitumen of penetration 80/100	sqm	57.00	63.00	3591.00
Total (₹)					96,431.68

Synopsis:-

I/ We Quote % (.....) Above/ Below
the Estimated Cost amounting to ₹
(Rupees)

Signature of Contractor

Name of Contractor
Seal & Date