

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Ltd)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII
P.O.-BARAKAR – 713324, DIST-BURDWAN (W.B.)
Phone : 06540-272126 ; FAX 0341-2520063

Ref. No. BCCL/XII/ACE/QTN/2011-12/ 19 /1305

Dates: 04.07.2011

QUOTATION NOTICE

Sealed Quotations on percentage rate basis are invited from the bonafide & experienced contractors for the following works:

Sl.No.	Name of the work	Estimated cost	Earnest Money	Time of completion
1.	Repair Maintenance of 1 (One) unit bungalow converted to CISF barrack at Victoria West colliery.	Rs. 76422.00	Rs. 765.00	30 days
2.	Making pump foundation at DBOCP mine.	Rs. 11440.00	Rs. 115.00	10 days
3.	Making 2(Two) nos. retaining wall at 10 west level of Brindabanpur seam .	Rs. 56791.00	Rs. 568.00	30 days
4.	Roof repairing of Victoria West colliery dispensary.	Rs. 52245.00	Rs. 523.00	15 days
5.	Demolishing of 7 units CMW type Qtr at Heslop pit under DOCP.	Rs. 29545.00	Rs. 296.00	20 days

Terms and conditions:

- Completed sealed **Quotations will be received on 14.07.2011 up to 3.00 P.M.** at the following places. Quotation may opt any one place to submit their quotation as per their convenience.
 - In the office of the General Manager, C.V. Area-XII, AT-Begunia, P.O –Barakar(W.B.)
 - At BCCL H.Q. i.e. C.I.S.F. post, near Koyala Bhawan gate, Koyala Nagar, Dhanbad.
 - Office of the ACE, CCWO, W.W.Z. Area, Saraidhela, Dhanbad.
 - Office of the ACE, CHD, Jagjiban Nagar, Dhanbad.
- Quotations will be opened on 16.07.2011 at 11.30 A.M.** in the office of the Area Civil Engineer, C.V. Area-XII, AT-Begunia, P.O –Barakar(W.B.).
- Specification of work shall be governed by DSR-2007 & C.P.W.D specification.
- Terms and conditions as per C.I.L. C.E. manual shall be applicable against the quotations submitted against this Quotation Notice.
- Completed sealed Quotations shall consist of (1) EMD in the shape of cash receipt obtained from the finance deptt. C.V. Area-XII or DD from any Scheduled/Nationalised Bank, (2) Experience certificate, (3) Copy of Pan card, (4) Copy of VAT/Sales Tax clearance certificate along with VAT/Sales Tax registration No.(TIN), (5) Declaration and (6) EFT (Electronic Fund Transfer) & ECS (Electronic Clearance System) as per the format issued along with the Tender paper and (7) BOQ along with quoted rate by the Tenderer.
- The quoted rate shall include all taxes and levies.
- Statutory deductions for Income Tax and Sales Tax shall be made as per Rules and notifications.
- The contractor has to abide by the Rules of Contract Labour Regulation & Abolition Act-.
- Validity of tender shall be 120 days from the date of opening of the tender.
- Interested parties can collect the BOQ and other related papers of the Quotation from the office of the Area Civil Engineer, C.V. Area-XII, AT-Begunia, P.O –Barakar(W.B.). **from 09.07.2011 to 13.07.2011 during** office hours except Sunday and Holiday. BOQ and other relevant pages (Declaration & EFT form) can be down loaded from BCCL website- <http://www.bccl.gov.in>
- No conditional tender shall be accepted.
- The contractors have to be acquainted with the site condition
- Unless otherwise mentioned, no material will be issued by the department.
- Successful tender has to deposit 5% Performance Security (including 1% EMD) and another 5% Security Deposit will be deducted from the Running Account/ Final Bill.
- The management of BCCL reserves right to reject any or all tender or split the work among two or more tenderers without assigning any reasons whatsoever.

Sd/
Area Civil Engineer
Chanch Victoria Area-XII

Copy to :-

- GM, Chanch Victoria Area-XII.
- GM (Civil), BCCL, Koyla Nagar.
- All CGM/GM of Areas/Projects under BCCL.
- Addl. GM, Chanch Victoria Area-XII.
- A.F.M., Chanch Victoria Area-XII.
- All P.O.s of Chanch Victoria Area-XII.
- Cashier, C.V. Area-XII
- Incharge,, CISF Post, Koyala Bhawan gate, Koyala Nagar,
- Assistant Commandant, CISF, C.V. Area-XII-with 2 copies of NIT for displaying on Notice Board.
- Builders Association of India, Central Akashkinaree Kanta, Katras Garh, Dhanbad-828113.
- ACE CCWO, W.W.Z Area saraidhela, Dhanbad.
- ACE CHD, jagiban Nagar, Dhanbad
- Notice Board.**

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Ltd)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII

1. Name of Work: **“Repair Maintenance of 1 (One) unit bungalow converted to CISF barrack at Victoria West colliery.”**

2. Name of Tenderer :

3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/19/1305

Date: 04.07.2011

5. Details of E.M.D. No:

Date:

BILL OF QUANTITY: (Sl. No. 1)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 10.1	Structural steel work in single section fixed with or without connecting plate including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	316.92	Kg.	42.15	13,358.17
2/ 14.2.1 14.2.2	Fixing chowkhats in existing opening including embedding chowkhats in floors or walls cutting masonry for holdfasts embedding hold fasts in cement concrete blocks with cement concrete 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) painting two coats of approved wood preservative to sides of chowkhats and making good the damages to walls and floors and required complete including disposal of rubbish to the dumping ground within 50 meters lead: i) Door chowkhats. ii) Window chowkhats.	4.00 1.00	Each Each	354.45 214.20	1,417.80 214.20
3/ 15.7.4	Demolishing brick work manually/ by mechanical means including stacking of serviceable materil and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar.	0.73	Cum	310.75	226.84
4/ 15.12.1	Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 meter lead: of area 3 sq. metres and below.	1.00	Each	54.60	54.60
5/ 6.13.2	Half brick masonry with F.P.S. bricks of class designation 50 in superstructure above plinth level up to floor V level. Cement Mortar 1:4 (1 Cement : 4 coarse sand).	11.40	Sqm.	273.45	3,117.33
6/ 9.119	Providing and fixing factory made P.V.C. door frame of size 50x47 mm with a wall thickness of 5 mm, made out of extruded 5mm rigid PVC foam sheet mitred at corners and joined with 2 Nos . of 150mm long brackets of 15x15 mm M.S. square tube, the vertical door profiles to be reinforced with 19x19 mm M.S. square tube of 19 gauge, EPDM rubber gasket weather seal to be provided through out the frame. The door frame to be fixed to the wall using M.S . screws of 65/100 mm size complete as per manufactures specification and direction of Engineer-in-charge.	9.75	Metre	353.10	3,442.72
7/ 9.118.1	providing and fixing to existing door frames. 24mm thick factory made PVC door shutters made of styles and rails of a UPVC hollow section of size 59x24 mm and wall thickness 2 mm +- 0.2.. mm with inbuilt edging on both sides. The styles and rails mitred and joined at the conrnrs by means of M.S. galvanized / plastic brackets of size 75x220 mm having wall thickness 1.0 mm and stainless steel screws. The styles of the shutter reinforced by inserting galvanized M.S. tube of size 20x20 mm and 1 mm +- 0.1. mm wall thickness. The lock rail made up of 'H' section, a UPVC hollow section of size 100x24 mm and 2 mm +- 0.2 mm wall thickness fixed to theshutter styles by means of plastic /galvanized M.S. 'U' cleats, the shutter frame filled with a UPVC multi-chambered single panel of size not then 620 mm, having over all thickness of 20mm and 1mm +- 0.1 mm wall thickness. The panels filled verticallya dn tie bar at tow places by inserting horizontally 6mm galvanized M.S rod and fastened with nuts and washers, complete as per manufacturer's specification and direction of Engineer-in-charge. (For W.C. and bathroom door shutter).	3.51	Sqm	2,190.50	7,688.65

Contd. P-3

8/ 9.100.2	Providing and fixing aluminium hanging floor door stopper ISI marked anodized (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete: 100 mm.	4.00	Each	35.30	141.20
9/ 9.97.2	Providing and fixing aluminium tower bolts ISI marked anodized (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade with necessary screws etc. complete: 250x10mm.	4.00	Each	62.20	248.80
10/ 1.8.1/3	Wiring to light /fan point	35.00	Each	264.00	8,448.00
11/ 2.21.1	Providing and fitting amn switch 32 Amps.	1.00	Each	768.00	768.00
12/ 14.5.1	Renewing glass panes, with putty and nails wherever necessary: Float glass panes of thickness 4 mm	0.20	Sqm	427.60	85.52
13/ 0114	Labour for cleaning of roof etc.	5.00	Each	135.25	676.25
14/ 14.42.1	White washing with lime to give an even shade : Old work (two or more coats).	866.52	Sqm	4.10	3,552.73
15/ 14.54.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give even shade: one or more coats on old work.	67.10	Sqm	22.85	1,533.23
16/ 13.39.1	Colour washing such as green, blue of buff to give an even shade: New work (two or more coats) with a base coat of white washing with lime.	150.00	Sqm	9.30	1,395.00
17/ 13.1.2	12 mm cement plaster of mix : 1:6 (1 Cement : 6 fine sand).	85.00	Sqm	67.65	5,750.25
18/ 17.13.1	Providing and fixing white vitreous china water closet squatting pan (Indian type). Long pattern W.C. pan of size 580 mm	2.00	Each	534.60	1,069.20
19/ 17.60.1. 2	Providing and fixing trap of self cleansing design with screwed down or hinged grating with or without vent arm complete, including cost of cutting and making good the walls and floors: sand cast iron S & S as per IS: 1729.	2.00	Each	442.10	884.20
20/ 17.35.1. 1	Providing and fixing soil, waste and vent pipes: sand cast iron S&S pipe as per IS: 1729.	10.00	Meter.	451.00	4,510.00
21/ M.R.	Cleaning of septic tank.	1.00	Each	1000.00	1000.00
22/ 6.1.2 (A.R)	Brick work with F.P. S bricks of class designation 50 in foundation and plinth in : cement mortar 1:6 (1 cement : 6 coarse sand).	1.17	Cum	2,007.00	2,348.19
23/ 5.12	Providing, hosting and fixing up to floor five level precast reinforced cement concrete work in string courses, bands, copings, bed plated, anchor blocks, plain window sills and the like including the cost of required centering, shuttering, finishing smooth with 6 mm thick cement plaster 1:3 (1 cement : 3 fine sand) on exposed surfaces complete but excluding cost of reinforcement with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).	0.31	Cum	4,880.15	1,512.84
24/ 5.22.3	Reinforcement for R.C.C work including straightening, cutting, bending, placing in position and binding all complete. Cold twisted bars.	25.00	Kg.	42.70	1,067.50
23/AR	Providing and fitting PVC pipe for external work a) 25 mm dia nominal bore b) 20 mm dia nominal bore c) 15 mm dia nominal bore.	30.00 20.00 15.00	Meter Meter Meter	101.02 83.88 64.03	3,030.60 1,677.60 960.45
24/ 18.46.3 18.46.2 18.46.1	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work). a) 25 mm dia nominal bore b) 20 mm dia nominal bore c) 15 mm dia nominal bore.	2.00 2.00 2.00	Meter Meter Meter	107.25 96.80 151.80	214.50 193.60 151.80
25/ 18.13.1	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete : 25 to 40 mm nominal bore.	1.00	Each	166.05	166.05

Contd. P-4

-P/4-

26/M.R.	Providing and fixing plastic bib cock of all	4.00	Each	20.00	80.00
27/ 6.12.2	Half brick masonry with F.P.S brick of class designation 50 in foundations and plinth in : cement mortar 1 : 4 (1 cement : 4 coarse sand).	12.00	Sqm.	257.25	3,087.00
28/ 13.7.2	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 Cement : 4 fine sand).	24.00	Sqm	97.90	2,349.60
	Total			Rs.	76,421.82
			Say	Rs.	76,422.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer

-4-

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Ltd)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII

1. Name of Work: “**Making pump foundation at DBOCP mine.**”

2. Name of Tenderer :

3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/ 19 /1305

Date: 04.07.2011

5. Details of E.M.D. No:

Date:

BILL OF QUANTITY: (Sl. No.-2)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 2.6.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30 cm in depth, 1.5 in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5m, disposed earth to be leveled and neatly dressed. All kinds of soil.	1.45	Cum	101.85	147.68
2/ 4.1.8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level:1:4:8 (1 cement: 4 coarse sand: 8 graded stone aggregate 40 mm nominal size).	0.48	Cum	2,449.00	1,175.52
3/ 6.4.1 (A.R)	Brick work with F.P.S bricks of class designation 50 in superstructure above plinth level up to floor V level in all shapes and sizes in cement mortar 1:4 (1 Cement: 4 coarse sand).	2.98	Cum	2,487.15	7,411.71
4/ 4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level: 1:2:4 (1 cement: 2 coarse sand: 4 graded stone aggregate 20 mm nominal size).	0.32	Cum	3,257.45	1,042.38
5/ 4.1.2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level: 1:1.5:4 (1 cement: 1.5coarse sand: 3 graded stone aggregate 20mm nominal size).	0.20	Cum	3,629.80	725.96
5/ 13.31.1	Pointing on brick work or brick flooring with cement mortar 1:3 (1 cement: 3 fine sand) Flush/ruled/struck of weswthered pointing.	4.58	Sqm	45.40	207.93
6/ 10.19	Providing and fixing M.S. round holding down bolts with nuts and washer plastes complete.	14.00	Kg.	52.05	728.70
	Total			Rs.	11,439.88
			Say	Rs.	11,440.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote ____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Ltd)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII

1. Name of Work: “Construction of two (2) nos. Retaining wall at Travelling road of 1 Level and 3rd dip of 2nd West Level of Begunia Project.”

2. Name of Tenderer :

3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/19 /1305

Date: 04.07.2011

5. Details of E.M.D. No:

Date:

BILL OF QUANTITY (Sl. No. 3)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1 / 2.7.3	Earth work in excavation by mechanical means(Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50 M and lift upto 1.5 M, disposed earth to be levelled and neatly dressed.---Hard rock(blasting prohibited).	4.82	Cum	325.25	1,567.70
2/ 2.7.1	Earth work in excavation by mechanical means(Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50 M and lift upto 1.5 M, disposed earth to be levelled and neatly dressed.---Ordinary rock.	5.60	Cum	152.60	854.56
3/ 6.1.1	Brick work with F.P.S. bricks of class designation 75 in foundation and plinth in: Cement mortar 1:4 (1 cement: 4 coarse sand).	4.82	Cum	2,293.40	11,054.19
4/ 6.4.1	Brick work with F.P.S. bricks of class designation 50 in superstructure above above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:4 (1 cement: 4 coarse sand)	14.39	Cum	2,309.65	33,235.86
5/ 4.2.3	Providing & laying cement concrete 1:2:4(1 cement: 2 coarse sand: 4 stone aggr. 20mm size) in retaining walls, return walls (any thickness) including attached pillars, columns, piers, abutments, pillars, posts, -- excluding the cost of centring, shuttering and finishing.	1.25	Cub	3,579.10	4,473.87
6/ 13.7.2	12 mm cement plaster of mix: 1:4 (1 cement: 4 fine sand).	40.35	Sqm	97.90	3,950.27
	Total (A)				55,136.45
	Add underground allowance @ 12% of 25% of (A)				(+) 1,654.09
	Gross Total			Rs.	56,790.54
				Say Rs.	56,791.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____

_____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Ltd)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII

1. Name of Work: **“Roof repairing of Victoria West colliery dispensary.”**
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/19 /1305
5. Details of E.M.D. No:

Date: 04.07.2011
Date:

BILL OF QUANTITY (Sl. No. 4)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ (BCCL SOR)	Removal of old tarfelt of all complete.	268.22	Sqm	1.85	498.88
2/ 22.14.3	Grading roof for water proofing treatment with cement mortar 1:4 (1 cement : 4 coarse sand).	0.50	Cum	4,357.65	2,178.82
3/ 22.8.1	Providing and laying four courses water proofing treatment with bitumen felt over roofs consisting of first and third courses of blown bitumen 85/25 or 90/15 conforming to IS : 702 applied hot @ 1.45 Kg per square metre of area for each course, second course of roofing felt type 3 grade-I (Hessian based self finished bitumen felt) and fourth and final course of stone grit 6 mm and down size or pea-sized gravel spread at 6 cubic diameter per square metre including preparation of surface but excluding grading complete with : Bitumen felt (hessian base) type 3 grade I conforming to IS : 1322.	268.22	Sqm	184.80	49,567.05
	TOTAL			Rs.	52,244.75
			Say	Rs.	52,245.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Ltd)
OFFICE OF THE GENERAL MANAGER
CHANCH-VICTORIA AREA-XII

1. Name of Work: “Demolishing of 7 units CMW type Qtr at Heslop pit under DOCP.”
2. Name of Tenderer :
3. Address:

4. NIT No. : BCCL/XII/ACE/QTN/2011-12/19/1305
5. Details of E.M.D. No:

Date: 04.07.2011
Date:

BILL OF QUANTITY (Sl. No. 5)

Sl.No.	Description of Item	Qty	Unit	Rate	Amount
1/ 15.28.2	Dismantling roofing including ridges, hips valleys and gutters etc., and staking the material within 50 metres lead of: Asbestos sheet	38.96	Sqm	11.75	457.78
2/ 15.7.1	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In mud mortar.	173.88	Cum	106.45	18,509.52
3/ 15.2.1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 meters lead as per direction of Engineer-in-charge. 1:3:6 or richer mix.	10.29	Cum	368.45	3,791.35
4/ 1.1.1	Carriage of building rubbish up to 1 K.M.	173.88	Cum	39.03	6,786.53
	Total			Rs.	29,545.53
			Say	Rs.	29,545.00

Having gone through the Tender documents & elements of work in the bill of quantity :-

I / we quote _____% (_____) above / below the estimated cost.

Our quoted offer amounts to Rs. _____ (Rupees _____) including the above percentage.

SIGNATURE OF ISSUING OFFICER

Signature & seal of Tenderer

FOR PAYMENT TO CONTRACTORS
Triplicate)*(Note: To be submitted in***PROFORMA FOR COLLECTING PAYMENT THROUGH ELECTRONIC MODE INCLUDING ELECTRONIC FUND TRANSFER (EFT) & ELECTRONIC CLEARING SYSTEM (ECS)**

1	Vendor/ supplier/ contractor/ customer's name & address (with telephone number & Fax number)	
2	Particulars of Bank Account	
	a) Bank Name	
	b) Branch Name (Including RTGS Code)	
	Address	
	Telephone No. & Fax No.	
	c) 9 – Digit Code Number of the Bank & Branch (Appearing on the MICR Cheque issued on the bank) or 5 digit code number of SBI	
	d) Account Type (S.B. Account/ Current Account or Cash Credit with code 10/11/13)	
	e) Ledger No./ Ledger Folio No.	
	f) Account Number (Core Banking) & Style of Account (As appearing on the cheque Book)	

3. DATE OF EFFECT:

I hereby declare that the particulars given above are correct & complete. If the transaction is delayed or not effected at all for reasons of incomplete or incorrect information, I would not hold the user institution responsible. I have read the option invitation letter and agree to discharge responsibility expected of me as a participant under the scheme. Any bank charges levied by the bank of such e-transfer shall be borne by us.

Date:-

contractor

(_____)
Signature of customer/ vendor/ supplier/

Certified that the particulars furnished above are correct as per our records.

the Bank

(_____)
Signature of the authorized officials from

DECLARATION

I, _____, Partner/Legal Attorney/ Accredited Representative of M/S _____

_____, solemnly declare that :

1. We are submitting Tender for the Work _____

_____ against Tender

Notice No. _____

dt _____

2. None of the Partners of our firm is relative of employee of Bharat Coking Coal Ltd.
3. All information furnished by us in respect of fulfillment of eligibility criteria and qualification information of this Tender is complete, correct and true.
4. None of the partners of the Firm has either individually or collectively been involved in criminal offences.
5. I hereby declare that /our firm has not been banned or delisted by any Govt. or Quasi Govt. agencies or PSUs.
6. All documents/ credentials submitted alongwith this Tender are genuine, authentic, true and valid.
7. If any information and document submitted is found to be false/ incorrect any time, department may cancel my Tender and action as deemed fit may be taken against us, including termination of the contract, forfeiture of all dues including Earnest Money and banning / delisting of our firm and all partners of the firm etc.

Signature of the Tenderer

Dated_____