

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Limited)
TOWN ADMN. DEPARTMENT KOYLA NAGAR
DHANBAD-826 005.

Ref.No.BCCL/TA/Chief Manager(C)/Tender-3/11-12/942

Dated 01.08.2011

NOTICE INVITING TENDER (N.I.T).

Sealed tender in two parts (part –I &II) on over all percentage rate above/below basis are Invited from, experienced and eligible contractors for the following work:-

Sl. No.	Name of work	Estimated cost (Rs.)	E.M.D. (Rs.)	Cost of tender paper(non refundable)	Time of completion
1	Maintenance of different qtrs at Koyla nagar	10062.62	101.00	100.00	7(seven) days
2	Repairing of tilted compound wall in between D/X/11-10 including roof repairing of D/X/11 & D/V/6 at Koyla nagar	48882.47	490.00	100.00	10(ten)days
3	Replacement of damaged frames,and shutter of doors, ventilators with renewing glass panes of ventilators at Koyla nagar hospital .	48197.46	485.00	100.00	10(ten)days
4	Provision of barbed wire fencing for plantation near shopping complex at Koyla nagar	44797.78	450.00	100.00	10(ten)days
5	Repair/maintenance including replacement of damaged wood work under shifting & emergency cases in qtr no. C2/X/40,D/X/5, B/II/200 &218 at Koyla nagar	47701.06	480.00	100.00	10(ten)days
6	Internal&External repair/maintenance of Gouri Shanker Hanuman Mandir near B type colony at Koyla nagar	33812.97	340.00	100.00	10(ten)days
7	Internal repair /maintenance work of quarters under shifting /emergency cases of sector-IX,IV, and XI at Koyla nagar	185320.79	1855.00	100.00	6(six)month
8	Repairing of plinth protection and drain in C2/VII type qtr block no, 13to18,19to 24 ,31 to 36,37 to 42,55to 60, 61 to 66,73to 78,91 to 96,97to 102 nine block at Koyla nagar	182129.10	1825.00	100.00	2(two) month
9	Repairing and maintenance of sewing centre at Koyla nagar	30132.60	302.00	100.00	7(seven) days

10	Need based maintenance work of water supply and sanitary system of sector-VII & VIII at Koyla Nagar	101083.32	1012.00	100.00	4(four) month
11	Need based maintenance work relating to Internal water supply, sanitation and sewerage system in sector-IX,V and XI at Koyla Nagar	182835.38	1830.00	100.00	6(six)month
12	Uprooting of unwanted trees/plants from exteriors of quarters of A type ,sector-I and D type , sector-III at Koyla nagar	107205.35	1075.00	100.00	3(three)month
13	Repairing of plinth protection and drain in D/VIII type quarters from 1 to 29(except-10 &24) at Koyla nagar	128305.95	1285.00	100.00	2(two)month
14	Providing and fixing chequired tiles and snowcem of children park and maintenance of CISF main check post at Koyla nagar	93447.39	935.00	100.00	1(one)month
15	Repairing of fallen boundary wall of D/IX/23 & C1/IV/25 at Koyla nagar	99429.46	995.00	100.00	1(one)month
16	Cleaning of drain of sector-D/IX,C1/IV,B/XI and some other drains near shopping complex & guest house at Koyla nagar	51899.58	520.00	100.00	15(fifteen) days
17	Miscellaneous repair/maintenance work in different quarters at Koyla nagar	47939.77	480.00	100.00	15(fifteen) days
18	Repair /maintenance of qtr.no.D/V/ 3&12 including replacement of damaged wood work under shifting & emergency cases at Koyla nagar	72724.90	730.00	100.00	15(fifteen) days
19	Repair/maintenance including replacement of damaged wood work under shifting & emergency cases in qtr.no.B/II/48 &72 and 86 at Koyla nagar	84722.97	850.00	100.00	15(fifteen) days
20	Miscellaneous repairs/maintenance work in guest house at Koyla nagar	99868.30	1000.00	100.00	15(fifteen) days
21	Emergency repairing of qtr no. A/114,194,229 of A type sector-I at Koyla nagar	37902.60	380.00	100.00	10(ten)days
22	Annual maintenance of Ambedkar chowk,Subhas Chowk ,martyr memorial chowk,road divider.Rajiv Gandhi chowk,painting of speed breakers& trees stems and some miscellaneous works at Koyla nagar	117134.73	1175.00	100.00	1(one)month

23	Repairing and maintenance of qtr of sector-VII & VIII under shifting and emergency cases at Koyla nagar	108148.18	1085.00	100.00	1(one)month
24	Annual maintenance of shri Shiv mandir,Durga Mandir,Hunuman Mandir, Sri Ram mandir,Maa Adya Kali mandir,near martyr memorial and Baba Sidhnath Mandir& Hunuman mandir at Koyla nagar	88778.13	890.00	100.00	15(fifteen) days
25	Annual maintenance of BCCL press on the occasion of Vishwakarma Puja painting white washing & snowcem of flag posts (KNTA,SBI,KNH,& 33KVA substatioin) on the occasion of Independence day and republic day at Koyla nagar	44293.34	445.00	100.00	10(ten)days
26	Internal/external repair/maintenance of Bhartiya vidya Mandir school at Koyla nagar	90334.87	905.00	100.00	15(fifteen) days
27	Renovation of septic tank near III type at Karmik Nagar	194648.36	1950.00	100.00	3(Three)month

Availability of tender documents from : 10.08.2011 to 13.08.2011

Tender documents will be issued on all working days during working hours except on Sundays & holidays. In the event of the specified date for submission/ opening of bids being declared a holiday the bids will be received/opened on the appointed time on the next working day. The tender document is also available on Website <http://www.bccl.gov.in>.and can be downloaded.

Time and date of receipt/opening of tender:

- The tenders will be received on 16.08.2011 from 10.00A.M to 3.00 P.M. in tender box.
- The tenders received will be opened on 17.08.2011 at 3.30 P.M.

Eligibility Criteria.

- The intending tenderers must have in its name as a prime contractor experience of having successfully completed similar works during last 7(seven) years ending last day of month, previous to the one in which bid application are invited should be either of the following
 - Three similar completed works each costing not less than the amount equal to 40% of the estimated cost
Or
 - Two similar completed works each costing not less than the amount equal to 50% of the estimated cost
Or
 - One similar completed work costing not less than the amount equal to 80% of the estimated cost

Similar work means:- construction/repair/maintenance of building for sl.no.1,6to9 12,13 and 17to19, For sl.no.3&5 wood work,for sl.no.4 steel work ,for sl.no.10&11 water supply and sanitation/sewerage system, for sl.14 tiles work, for sl.no.2 &15 brick work,and for sl.16 cleaning /sanitation work, for sl.no.27 construction/renovation of septic tank/brick work.

2. Average annual financial turn over of civil works during last three years ending 31st March of the previous financial year should be at least 30% of the estimated cost.

The intending tenderer must submit documentary evidence in support of (1) & (2) above in the form of certified copy of work order, completion certificate, payment certificates/ vouchers etc. indicating the period of work for which the payment has been made, duly signed by him/them.

Note:

- a) Provision under eligibility criteria 1 shall also include those similar works “while considering value completed works , full value of completed works be considered whether or not date of commencement is within the said seven years period,
 - b) As per eligibility criteria specified under Sl.No.1 Pre-qualification shall be done based on experience of successfully completed work and not on experience of work in progress.
- 3 The tender documents can be had from the office of the [Chief Manager \(Civil\)I/C, KNTA/JNTA, Koyla Nagar, Dhanbad](#) during the period mentioned above on deposition of requisite cost of tender paper in form of cash or bank draft of Nationalized bank/ schedule commercial bank approved by Reserve bank of India in favour of Bharat Coking Coal Ltd. Payable at Dhanbad.
 - 4 Completed sealed tender documents (part I & II) should be submitted at the same time.

Part-I shall consist of terms and conditions of the tender, additional terms & conditions if any, technical bid and credentials.

Part-II shall consist of tender documents as sold to be tenderers duly filled in for rates, amounts etc. i.e. price bid.

The earnest money deposit is to be submitted in a separate envelop super scribing “**Earnest money deposit**”. (Earnest money to be submitted in form cash or bank draft of nationalised bank/ schedule commercial bank approved by Reserve Bank of India in favour of BHARAT COKING COAL LIMITED payable at Dhanbad)

The bid shall be submitted in three separate envelopes.

Envelop-I should contain E.M.D. and the cost of tender document if down loaded from the website.

Envelop-II should contain Part-I of tender document.

Envelop-III should contain part-II i.e. Price Bid.

Thereafter all three envelopes should be submitted in one sealed envelope.

The tender will be received on 16.08.2011 from 10.00AM to 3.00 P.M., at

1. **C.I.S.F. post, near Koyla Bhawan gate, Koyla Nagar, BCCL, Dhanbad**
2. **Jaggiwan Nagar Town Administration Office.Dhanbad**
3. **Civil Engineering Department,Central Hospital,Dhanbad.**
- 4 **Koyla nagar Town Administration Office,Dhanbad..**

Tender will be opened at 3.30 P.M.on 17.08.2011 in presence of the intending tenderer or their authorized representative in the office of Chief Manager (Civil) I/C, KNTA/JNTA Koyla Nagar, Dhanbad. Only part-I will be opened on this date

The part-I will be opened only after receipt of EMD and in case of downloaded tender, the cost of tender document too.

The part-II will be opened only after: The department is satisfied that the criteria fixed are fulfilled i.e. on acceptance of part-I

- 5 The Earnest money to be deposited as per detail given in the tender documents.
- 6 Sales Tax clearance certificate copy shall be **attested by a Gazetted Officer** of the Govt. (Central or State) and TIN NO.
- 7 The tenderers have to submit permanent account No. (PAN) of Income Tax.
- 8 Conditional tenders will not be accepted.
- 9 Issuance of tender documents does not mean that the parties are considered qualified.
- 10 The experience as given in the eligibility criteria should be in the name and style in which tender is filled. The experience in the name of some other firm/company will not be considered for this purpose.
- 11 The validity of the tender will be 120 days from the date of opening of price bid or revised price bid if any.
- 12 The management of BCCL reserves right to reject any or all tender or split the work among two or more tenderers without assigning any reasons whatsoever.
- 13 Other details may be obtained from detailed tender notice/tender documents/website
[http:// www.bccl.gov.in.](http://www.bccl.gov.in.)
- 14 If tender document has been downloaded from the above mentioned website, the tenderers are required to deposit along with their tender, a Bank Draft of any Nationalized / Schedule commercial Bank payable at Dhanbad exclusively towards the cost of tender document for the amount indicated as above, in the envelope as stated at clause 3 of this NIT.
- 15 The contents of the tender documents available in our offices shall be deemed as authentic. The bidder will be required to submit an undertaking that they will accept the tender document as available in the website and their tender shall be rejected if any tampering is there in the tender document thus submitted.
16. Earnest Money will be refunded to the unsuccessful parties and bear no interest.
17. There will be no arbitration clause.
18. No tender will be issued or submitted by postal means.
19. The tenderers must ensure that submission of photo copies of documents submitted in tenders are legible.
20. The tenderer must submit an Affidavit as per format issued along with tender documents. Non submission will lead to cancellation of tender.
21. The tenderer must also give a declaration to be submitted along with Techno Commercial Bid that they have not been banned or delisted by any Govt./ Quasi Govt. agencies/PSU'S.
22. The KNTA management will not be responsible for any delay / difficulties / inaccessibility of downloading facility for any reason whatsoever. The downloading facilities shall be available during the period of sale of tender paper.

23. In case of any discrepancy between the tender documents downloaded for the web site and the master copy available in the office, the latter shall prevail and will be binding on the tenderers. No claim in the respect will be entertained.
24. The contract labour (Regulation & abolition) Act 1970 shall have to be strictly complied.
25. Power of attorney is required in case the tender is signed by an authorized representative of tenderer.
26. Tenderers must acquaint themselves fully with the site conditions, job requirements and scope of work before quoting their rates.
27. No subletting of the work is permissible.
28. Bidders are required to fill format of Electronic fund transfer in triplicate which is enclosed with the detailed tender document.

Chief Manager (Civil) I/C,KNTA/JNTA.

Distribution for wide publicity.

1. CVO, BCCL, Koyla Bhawan
2. Dy.GM(Admn.), Koyla Bhawan
3. GM(Civil), C.E.Deptt., Koyla Nagar.
4. GM(System),BCCL,HQ – soft copy will be sent separately for display this NIT in BCCL website The downloading facility should be available during the period of sale of tender document only..
5. All CGMs/GM's of Areas.
6. Sr. Manager(Pay), K.B.
7. Sr. Manager(C), KNTA/JNTA.
8. Chief Manager (Civil) Central Hospital, Dhanbad.
9. Inspector I/c, CISF, Koyla Bhawan
10. Sr. Manager(Security)HQ,KNTA
11. Notice board

PART - I

TECHNO COMMERCIAL BID

(To be submitted with Part-I envelope)

DETAILED TENDER NOTICE

1. Sealed tenders in prescribed forms and parts with the name of works superscribed as..as per NIT.....as per..... Tender Notice No, BCCL:TA/Chief Manager(civil)/c:TENDER:11-12:..... date.....) on each of the envelopes are invited from eligible and experienced contractors and will be received at C.I.S.F. post, near Koyla Bhawan gate, Koyla Nagar, BCCL, Dhanbad as well as in the Office of undersigned from 10.00am to 3.00 pm onAll tenders will be opened at 3.30 PM onin the presence of the attending tenderers or their authorised representatives who wish to be present .In case where the tender is in two parts, only Part-I, will be opened on the above day and time.

2 (a) Tenders should be submitted in the prescribed form in time. These forms together with the proposed contract document including specifications and tender drawings (if available) may be obtained from the above office during normal working hours on payment of Rs (non-refundable) (Rupees.....) only as Application Fee for each set. The payment may be made either in Cash or by Bank Draft drawn in favour of Bharat Coking Coal Limited on any Nationalised Bank Payable at Dhanbad. General specification and description of work is enclosed with the tender document.

2 (b) Any Bids received after the deadline prescribed at Clause 1 above due to any reasons whatsoever will not be accepted.

In the event of the specified date for the submission of bids being declared a holiday by the employer, the bids will be received upto the appointed time on the next working day.

2 (c) Tenders thus submitted shall consist of the following:

- i) Complete set of tender documents as sold, duly filled in and signed on all pages and at different places as required of the tender documents including Part I & Part II of the tenders as per the tender notice as applicable.
- ii) Valid Sales-tax Registration No. (TIN No.)
- iii). PAN (Permanent I. Tax Account Number)
- iii) Earnest money deposit (as specified hereafter)
- iv) Power of Attorney in the case the tender is signed by an authorised representative of the tenderer.
- v) Full name and address of the tenderer shall be written on the bottom left hand corner of the sealed covers.

2 (d) The tender document in which the tender is submitted by the tenderer shall become the property of the Company and the Company shall have no obligation to return the same to the tenderer.

2 (e) The tender shall be submitted in Two Envelope System with the first envelope containing credentials (duly authenticated by the bidder) in support of his qualifications in accordance with the eligibility criteria along with the EMD in a separate envelope and the second envelope containing the duly filled in Tender Document superscribing Envelope I , II and EMD on the cover.

Part II shall consist of tender documents as sold to the tenderers duly filling in rates, amounts etc. i.e. price bid.

The Earnest Money Deposit is to be submitted in a separate Envelope altogether; super-scribing "Earnest Money Deposit"; and not inside the envelope containing Part I or part II of the Bid.

2 :

The Part I & Part II should also be put into separate sealed envelopes superscribed as such. Thereafter all the three envelopes (four envelopes in case of Bidders using downloaded Bid document) should be submitted in a sealed envelope with appropriate superscription.

The date of opening of the 'Second Envelope or Part II of the tenders shall be communicated in due course after consideration of 'First Envelope or Part-I.

3. Each bidder shall submit only one bid for one package. A bidder who submits or participates in more than one bid (other than as sub-contractor or in case of alternatives that have been permitted or requested) will cause all the proposals with the bidders' participation to be disqualified.

4. No tender shall be considered unless accompanied by the said Earnest Money

5. The earnest money will be retained in the case of successful tenderer and refunded to the unsuccessful tenderer in due course and will not carry any interest. The earnest money deposited by the successful tenderer will be dealt with as provided elsewhere in the tender documents.

6. (a) Site Investigation Report: The contractor, in preparing the bid, shall rely on the site investigation report referred to in the bid document, supplemented by any information available to the bidder.

(b). Every tenderer is expected, before quoting his rates, to go through the requirements of materials/workmanship under specification/requirements and conditions of contract and to inspect the site/area of the proposed work.

The shall be written both in words and figures and the unit in the words and the amount against each item totalled. The rates for the work should be inclusive of all incidentals, over heads, all taxes, control's duties, leads, lifts, carriage, tools & plant etc. as required for execution and completion of the work.

It shall be deemed that the tenderer has visited the site/are and got fully acquainted with the working conditions and other prevalent conditions and fluctuations there to whether they actually visited the site/ are or not and have taken all the above factors into account while quoting his rates.

7 (a) Corrections where unavoidable, shall be made by crossing out and rewriting duly authenticated with full signature and date by the tenderer. Erasing or over-writing in the tender documents may disqualify the tender.

(b) The tender shall be submitted either in English or in Hindi.

(c) Cost of Bidding: The bidder shall bear all costs associated with the preparation and submission of his bid and the Employer will in no case be responsible and liable for those cost

8. The tenderer shall closely study all specification in detail, which govern the rates for which he is tendering.

9. The work should be completed within months from expiry of ten (10) days from the issue of letter or letter of acceptance of tender/work order or handing over the site, or handing over reasonable number of working drawings to the contractor or the period of mobilization allowed in the work order of starting the work in special circumstances whichever is latest.

: 3 :

10. On completion of the work all rubbish, debris, brick bats etc. shall be removed by the contractor(s) at his/their own expense and the site cleaned and handed over to the company and he/they shall intimate officially of having completed the work as per contract.

11. The Company does not bind itself to accept the lowest tender and reserves the right to reject any or all the tenders without assigning any reasons whatsoever and to split up the work between two or more tenderers or accept the tender in part and not in its entirety.

12. The tenderer(s) will indicate the equipment/machinery/ vehicles he/they is/are going to use on this job and also give adequate evidence of experience in doing similar works and financial capacity to complete the work in time.

13. The tenderer(s) should also state what technical/ supervisory personal he/they would be employing for supervising the work.

14 (a). Full information should be given by the tenderer in respect of following:

- | | |
|---------------------------|--|
| i) If an individual: | Full name.
Postal Address.
Place of Business. |
| ii) If proprietary firm: | Name of the Proprietor.
Full postal address of Firm/ Proprietors. |
| iii) If partnership firm: | Full name of partners.
Full postal addresses of the registered office of firm & the partners.
Registered partnership Deed. |

The bidders, who will download the tender documents from the website of the company, will be required to pay the cost of tender documents (Application Fee) by Bank Draft as per NIT at the time of submission of tenders.

The bidders will be required to submit an undertaking that they will accept the tender documents as available in the website and their tender shall be rejected if any tampering in the tender document is found to be done at the time of opening of tender.

The Bank Draft towards the cost of tender documents (Application Fee) and the undertaking of the tenderer as above shall be submitted in a separate envelope marked "Cost of Tender Documents and the Undertaking" and not with Part-I/ EMD.

In case of any discrepancy between the tender documents downloaded from the web site and the master copy available in the office, the latter shall prevail and will be binding on the tenderers. No claim on this account will be entertained.

(* **STRIKE OUT WHICHEVER IS NOT APPLICABLE AS PER THE ESTIMATED VALUE OF THE WORK**) 2 (f) Each bidder shall submit only one bid for one package. A bidder who submits or participates in more than one bid (other than as sub-contractor or in case of alternatives that have been permitted or requested) will cause all the proposals with the bidders' participation to be disqualified.

4 :

3. Earnest Money/ Bid Security @1% of the estimated cost (rounded off to nearest hundred rupees subject to maximum of Rs. 50 lakhs) is to be deposited in the form of irrevocable Bank Guarantee (from Scheduled Bank/ Branch acceptable to the owner) with validity 28 days beyond the validity of the Bid in the format given in the Bid Document in a separate envelope alongwith the tender. Certified Cheques and Demand Drafts will also be acceptable as Earnest Money/ Bid Security drawn in favour of Bharat Coking Coal Limited on any scheduled Bank payable at its branch at Dhanbad For works valued upto Rs. 5 lakhs the earnest money may be deposited in cash or in the aforesaid form. In case of earnest money deposit by cash, cash receipt is to be submitted in a separate envelope alongwith the tender. Earnest Money/ Bid Security of the unsuccessful bidder shall be refunded as promptly as possible after opening of Price Bid and finalisation of the tender and shall bear no interest.

In case of item rate tender a schedule of quantities is enclosed with the tender document. He should quote specific rate for each item in the schedule and the rates shall be in rupees and paise. The rates shall be written both in words and figures and the unit in the words and the amount against each item totaled. In the event of any discrepancy between the description in words and figures, the description in words will prevail. The rates for the work should be inclusive of all incidentals, overheads, all taxes, Octroi's, duties, leads, lifts, carriage, tools & plant etc. as required for execution and completion of the work. It shall be deemed that the tenderer has visited the site/area and got fully acquainted with the working conditions and other prevalent conditions and fluctuations thereto whether they actually visited the site/area or not and have taken all the above factors into account while quoting his rates.

9. Sales-tax clearance certificate for the last financial year or the last assessment whichever is later or proof of filing the returns for the previous financial year should accompany the tender.

10. The work should be completed within months from expiry of ten (10) days from the issue of letter or letter of acceptance of tender/work order or handing over the site, or handing over reasonable number of working drawings to the contractor or the period of mobilization allowed in the work order of starting the work in special circumstances whichever is latest.

11. On completion of the work all rubbish, debris, brick bats etc. shall be removed by the contractor(s) at his/their own expense and the site cleaned and handed over to the company and he/they shall intimate officially of having completed the work as per contract.

12. The Company does not bind itself to accept the lowest tender and reserves the right to reject any or all the tenders without assigning any reasons whatsoever and to split up the work between two or more tenderers or accept the tender in part and not in its entirety.

13. The tenderer(s) will indicate the equipment/machinery/ vehicles he/they is/are going to use on this job and also give adequate evidence of experience in doing similar works and financial capacity to complete the work in time.

14. The tenderer(s) should also state what technical/ supervisory personal he/they would be employing for supervising the work.

14 (a). Full information should be given by the tenderer in respect of following:

- | | |
|---------------------------|--|
| i) If an individual: | Full name.
Postal Address.
Place of Business. |
| ii) If proprietary firm: | Name of the Proprietor.
Full postal address of Firm/ Proprietors. |
| iii) If partnership firm: | Full name of partners.
Full postal addresses of the registered office of firm & the partners.
Registered partnership Deed. |

: 5 :

15 Change in Constitution of the Contracting Agency:

Prior approval in writing of the company shall be obtained before any change is made in the constitution of the contracting agency, otherwise it will be treated as a breach of Contract.

16. Canvassing in connection with the tenders in any shape or form is strictly prohibited and tenders submitted

by such tenderers who resort to canvassing shall be liable for rejection.

17 (a) Every Tenderer will have to submit a declaration in support of the authenticity of the credentials submitted by him along with the Tender in the form of an AFFIDAVIT as per the format provided at ANNEXURE VI.

(b) If a Tenderer deliberately provides wrong information or submits false credentials in support of his qualifications, the Company reserves the right to terminate/rescind the contract, forfeit the EMD and other dues of the contractor and to take any other action as may be deemed fit.*

(c) An intending tenderer, after obtaining tender documents on payment of Application Fee, having doubts as to the meaning of any part of the tender documents may submit to the official inviting tender a written request for interpretation or clarification thereof. Any interpretation or clarification of the tender documents by formal addendum if issued by the official inviting tender, shall be final and valid and binding on the company and the tenderers.

18. On receipt of letter for acceptance of the tender issued by the Company, the successful tenderer shall execute/accept contract agreement/work order in the company's prescribed form for the due fulfillment of the contract. Failure to enter into the required contract/accept the work order issued by the company within the specified period in the work order shall entail cancellation of letter of acceptance of tender/work order and forfeiture of the earnest money. The written contract/ work order to be entered into between the contractor and the company shall be the foundation of the rights of both the parties and the contract shall not be deemed to be executed until the contract/ work order is signed/ accepted by both the parties i.e. Contractor and the Company.

19(a) The validity period of the tenders shall be 4 (four) months from the date of opening of price bid or revised price bid, if any. The tenderer shall not, during the said period or within the period extended by mutual consent, revoke or cancel his tender or alter the tender or any terms/conditions thereof without consent in writing of the company. In case the tenderer violates to abide by this, the Company will be entitled to forfeit the Earnest Money and reject the tender.

(b) The Company reserves the right to postpone the date of receipt and opening of tenders or to cancel the tenders without assigning any reason whatsoever.

20. This detailed Tender Notice shall be deemed to be part of the Contract Agreement/Work Order.

21. The work shall be executed as per General terms & conditions of the contract prevailing in BCCL, the description of items in the BOQ and as per the instruction of the EIC.

22. No subletting of work as a whole by the contractor is permissible. Subletting of work in piece rated jobs is permissible with the prior approval of the department.

23. In case the contractor enters into any litigation, such action should have to be taken in a court of law with jurisdiction over the place where the subject work is to be executed.

24. Earnest Money:
- i) The earnest money for tenders should be 1% (one percent) of estimated value of work.
 - ii) Earnest money to be deposited in the form of irrevocable bank guarantees from scheduled bank/branch acceptable to the company with validity 26 days before the validity of the bid in the prescribed format. Certificate cheques and demand draft will also be acceptable as earnest money/bid security.
 - iii) However for work valued up to Rs.5.0 lakhs the earnest money may be deposited in cash or in the aforesaid from the earnest money/bid security shall bear no interest.
25. Forfeiture of earnest money :
- According to prevalent standard practice earnest money is paid by cash tenderers to enable the company to ensure that a tenderer does not refuse to execute the work after it has been awarded to him. In case where the tenderer fails to commence the work latest within one month of award of the work or within one month of handing over site, whichever is earlier, the earnest money shall be absolutely forfeited to company. In case where decisions has been taken to forfeit earnest money of the tenderer for valid reasons, it is necessary to issue request notice to defaulting contractor.
26. Refund of Earnest Money :
- The earnest money will be refunded to the unsuccessful bidders after finalization of the award or on rejection of his bid or at the expiry of the validity period of the tender (unless extended) whichever is earlier. The earnest money of the successful bidders will be retained by the department as part of the security deposit for due fulfilment of the contract and will not carry any interest.
27. **Security Deposit:**
- i) Security Deposit shall consist of two parts;
 - a) Performance Security to be submitted at award of work and
 - b) Retention Money to be recovered from running bills.
 - ii) The 1st part of the Security deposit including the earnest money already be deposited should be 5% of the contract value within 28 days of receipt of LOA by the successful bidders in any of the form given below
 - a Bank Guarantee in the prescribed form.
 - Govt. Securities, FDR or any other form of deposit stipulated by the company
 - Demand Draft drawn in favour of the company on any schedule bank.
- The Earnest Money/ Bid Security deposited in the form of Bank Guarantee shall be discharged when the Bidder has signed the Agreement and furnished the required Performance Security/ Security Deposit. The bid security deposited in the form of Demand draft/ cash shall be adjusted against the security deposit.
- iii) All running on account bills shall be paid at 95% (ninety five percent) of work value. This 5% (five percent) deduction towards Retention Money will be the second part of security deposit.
28. Refund of Security Deposit :
- The refund of security deposit shall be subject to company's right to deduct/ appropriate its due against the contractor under this contract or under any other contract.

On completion of the entire work and issue of defect liability certificate (taking over certificate with a list of defects) by the Engineer-in-charge, one half of the security deposit remaining with the company shall be refunded. The other half shall be refunded to the contractor after issue of No Defect Certificate by the Engineer-in-Charge. on the expiry of Defect Liability Period of six months , subject to the following conditions:

- a) Any defect/defects in the work, if detected after issue of defect liability certificate is/are rectified to the satisfaction of the Engineer-in-Charge within the said period.
- b) In the case of building work or other work of similar nature, the refund shall be made on the expiry of the said six months period or at the end of one full monsoon period i.e. June to September, whichever is later in point of time and any defects such as leakages in roof, effloresces in walls, dampness, defects in drainage etc. should be rectified to the satisfaction of Engineer-in-Charge.

29. Execution of agreement / Work Order :

As soon as possible after the acceptance of a tender and award of work the successful tenderer is called upon to furnish the required initial security deposit and to execute a formal agreement. Only work order is issued to the contractor for works valued upto Rs.5.0 lakhs and it is not necessary to execute agreement in such cases, standard documents only form part of the contract agreement. Important points of the correspondences with the contractor should be reflected in the work order / contract agreement.

30 The bidders would give a declaration that they have not been banned or delisted by any Govt. Or Quasi-Govt. Agencies or PSU's (As per format).

31. In price part the overall lowest tenderer shall be considered for award of the work being lowest in any part of the tender shall be of no consequences and such tenderers shall not have any claim for award of part work.

32. The credentials / documents submitted by the tenderer should be numbered serially and properly tagged.

33. Evaluation of tenders (Weightage)

Financial turn over and cost of completed works of previous works shall be given a weightage of 5% per year (average annual rate of inflation) to bring them at current price level, while evaluating the qualification requirement and bid assessment of the bidders.

The price bids of the tenderers will have no condition. The price bids which are incomplete and not submitted as per instructions given in the tender document will be rejected.

If the bid of the successful bidder is seriously unbalanced in relation to the estimate of the cost of work to be performed under the contract, the company may require the bidder to produce detailed price analysis for any or all items of the bill of quantities to demonstrate the internal consistency of these prices with the construction method and the schedule proposed. After evaluation of the price analysis, the company may require that the amount of the performance security/security deposit is increased at the expense of the successful bidder to a level sufficient to protect the company against financial loss in the event of default on the part of the successful bidder under the contract.

Letter of acceptance is an acceptance of offer by the company and it need not be accepted by the tenderer. But the tenderer should acknowledge the receipt of the order within 15 days of mailing of work order and any delay in acknowledging the receipt will be treated as a breach of contract and compensation for the loss caused by such breach will be declared by the company by lowering EMD/bid bond.

: 8 :

34. Banned or delisted contractors :

The bidders would give a declaration that they have not been banned or delisted by any Govt. Or Quasi-Govt. Agencies or PSU's. If a bidder has been banned or delisted by any Govt. Or Quasi Govt. Agencies or PSU's this fact must be clearly stated and it may not necessary be a cause for disqualification. If the declaration is not given, the bid will be rejected as non-responsive.

35. Discrepancies in contract documents & adjustments thereof.

The documents forming part of the contract are to be treated as mutually explanatory of one another and in as of discrepancy between schedule of quantity, the specifications and/ or drawing, the following order of preference shall be observed.

- a) Description in bill of quantities of work.
- b) Particular specification and special conditions, if any.
- c) Drawings
- d) General specifications.

Any error in description, quantity or rate in bill of quantities or any omission there from, shall not vitiate the contract or release the contractor from discharging his obligations, under the contract including execution of work according to drawings and specifications, forming part of the particular contract document.

36. Any difference detected in the tender/ tenders submitted resulting from :

- a) Discrepancy between description in words and figures, the rate which corresponds to the amount worked out by the contractor shall be taken as correct.
- b) Discrepancy in the amount quoted by the contractor due to calculation mistake of the unit rate and quantity, the unit rate shall be regarded as firm and amount corrected.
- c) Discrepancy in totalling or carry forward in the amount quoted by the contractor shall be corrected.
- d) When the amount of an item is not worked out by the contractor or it does not correspond with the rates written either in figures or words, then the rates quoted by the Contractor in words shall be taken as correct.

The tendered sum so corrected and altered shall be substituted for the sum originally tendered and considered for acceptance instead of the original sum quoted by the tenderer along with other tender/tenders. Rounding off to the nearest rupee should be done in the final summary of the amount instead of in totals of various sections of the offer.

Time is the essence of the contract and as such all works shall be complete within the time stipulated in the contract/work order.

37. If the contractor, without reasonable cause or valid reasons, commits default in commencing the work within the aforesaid time limit, the company shall without prejudice to any other right or remedy, be at liberty, by giving 15 days notice in writing to the contractor to commence the work, to forfeit the Earnest Money deposited by him and to rescind the Letter of Acceptance of Tender/Work Order.

38. COMPENSATION FOR DELAY :

If the contractor fails to maintain the required progress in terms of the agreed time and progress chart or to complete the work and clear the site on or before the contract or extended date of completion, he shall without prejudice to any other right or remedy available under the law to the company on account of such breach, pay as compensation (Liquidated Damages) @ half percent (1/2%) of the contract price per week of delay. The aggregate of such compensation/ compensations shall not exceed 10 (ten) percent of the total value as shown in the contract.

: 9 :

This will also apply to items or group of items for which separate period of completion has been specified. The amount of compensation may be adjusted or setoff against any sum payable to the contractor under this or any other contract with the company.

39. The company, if satisfied, that the works can be completed by the contractor within a reasonable time after the specified time of completion, may allow further extension of time at its discretion with or without the levy of L.D. In the event of extension granted being with L.D, the company will be entitled without prejudice to any other right or remedy available in that behalf, to recover from the contractor as agreed damages equivalent to half percent of the contract value of the works for each week or part of the week subject to a ceiling of 10% of the contract price.

40. The company, if not satisfied that the works can be completed by the contractor, and in the event of failure on the part of the contractor to complete work within further extension of time allowed as aforesaid, shall be entitled, without prejudice to any other right, or remedy available in that behalf, to rescind the contract.

41. **A HINDRANCE REGISTER** shall be maintained by both department and the contractor at site to record the various hindrances, as stated above, encountered during the course of execution.

Hindrance register will be signed by both the parties. The contractor may also record his observations in the Hindrance Register. In case the contractor has a different opinion for hindrance and a dispute arises then the matter would be referred to the EIC and or the next higher authority whose decision would be final & binding on the contractor & the decision to be communicated within 15 days.

The contractor shall request the company in writing for extension of time within 15 days of happening of such event causing delay stating also, the period for which extension is required. The company may, considering the genuinity of the request, give a reasonable extension of time for completion of the work. Such extension shall be communicated to the contractor in writing by the company through the Engineer In Charge within 1(one) month of the date of receipt of such request.

42. Provisional extension of time may also be granted by the Engineer In Charge during the course of execution, on written request for extension of time within 15(fifteen) days of happening of such events as stated above, reserving the company's right to impose/ waive penalty at the time of granting final extension of time as per contract agreement.

In case the contractor does not apply for grant of extension of time within 15(fifteen) days of the hindrance occurring in execution of the work and the department wants to continue with the work beyond the stipulated date of completion for reason of the work having been unavoidably hindered, the Engineer-in-charge can grant extension of time even in the absence of application from the contractor.

Such extension of time granted by the Engineer In Charge is valid provided the contractor accepts the same either expressly or implied by his actions before and subsequent to the date of completion. Such extension of time shall be without prejudice to Company's right to levy compensation under the relevant clause of the contract.

43. The contractor shall bear the cost of loading, transportation to site, unloading, storing under cover as required etc. as may be necessary for the use and keeping the materials in good condition.

44. The contractor shall arrange necessary water for the work and his own establishment. However, if available and feasible the company may arrange water at one point near the work site for which recovery @ 1% of the contract value of work done will be made from the contractor's bills.

45. The company, through the Engineer In Charge, shall have full powers to reject any materials or work due to a defect therein for not conforming to the required specification, or for materials not being of the required quality and standard or for reasons of poor workmanship or for not being in accordance with the sample approved by him. The contractor shall forthwith remedy the defect/replace the materials at his expense and no further work shall be done pending such rectification/replacement of materials, if so instructed by the Engineer In Charge.

46. The Engineer In Charge shall be entitled to have tests carried out for any materials, according to the standard practice followed for such tests, other than those for which satisfactory proof has already been furnished by the contractor who shall provide at his expense all facilities which the Engineer In Charge may require for the purpose.

47. The cost of any other tests, if so required by the Engineer In Charge, shall be borne by the contractor only, if the test shows the workmanship or materials not to be in accordance with the provision of the contract or the instruction of Engineer In Charge, but otherwise by the company.

Extra items of work executed will be paid on specific written authorisation of CGM (Civil)/ GM(C)/ CE(C) of the company or Staff Officer (Civil) of the Area provided that the value of such extra items of work when added together is not more than 10% of the contract value and the total gross payment including excess quantity does not exceed the contract value.

48. Balance amount on account of excess quantity and extra items of work executed shall be paid after the deviation estimate / revised estimate regularising the extra items and excess quantities of work is sanctioned by the competent authority of the company with the concurrence of the Finance Department of the company.

The contractors are required to execute all works satisfactorily and according to the specifications laid down in the contract/ work order. If certain items of work, executed by the contractor, are below specifications, the contractor should re-do them according to the specifications and instructions of EIC and if the contractor fails to rectify the defect within the time and in the manner specified by the EIC, the work shall be got re-done or rectified by the department at the risk and cost of the contractor. Engineer In Charge may accept such work of below specifications provided the department is satisfied with the quality of such works and the strength/ structural safety of such works. In that case Engineer In Charge shall make such deductions for the difference in value, as in his opinion is reasonable and is approved by the accepting authority of the company i.e. CGM(C)/ GM(C)/ CE(C) of the company in this case or any other officer nominated by CGM(C)/ GM(C)/ CE(C) for the purpose.

49. **Termination, Cancellation, Suspension and Foreclosure of Contract**

The company shall, in addition to other remedial steps to be taken as provided in the conditions of contract be entitled to cancel the contract in full or in part, if the contractor :-

a) makes default in proceeding with the works with due diligence and continues to do so even after a notice in writing from the Engineer In Charge, then on the expiry of the period as specified in the notice

Or

b) commits default/breach in complying with any of the terms and conditions of the contract and does not remedy it or fails to take effective steps for the remedy to the satisfaction of the Engineer In Charge, then on the expiry of the period as may be specified by the Engineer In Charge in a notice in writing.

Or

c) obtains a contract with the company as a result of ring tendering or other non-bonafide methods of competitive tendering

Or

e) shall offer or give or agree to give any person in the service of the company or to any other person on his behalf any gift or consideration of any kind as an inducement or reward for act/acts of favour in relation to the obtaining or execution of this or any other contract for his company.

Or

f) fails to complete the work or items of work with individual dates of completion, on or before the date/dates of completion or as extended by the company, then on the expiry of the period as may be specified by the Engineer In Charge in a notice in writing.

Or

f) transfers, sublets, assigns the entire work or any portion thereof without the prior approval in writing from the Engineer In Charge. The Engineer In Charge may by giving a written notice, cancel the whole contract or portion of it in default.

50. Additional Responsibilities of the Contractor(s).

The contractor/contractors shall employ only competent, skilful and orderly men to do the work. The Engineer-In-Charge shall have the right to ask the contractor/contractors to remove from the work site any men of the contractor/contractors who in his opinion is undesirable and the contractor/contractors will have to remove him within 3 (three) hours of such orders.

The contractor shall maintain all records as per the provision made in the various statutes including contract Labour (Regulation & Abolition) Act, 1970 and the contract labour (Regulation & Abolition) central rules 1971 minimum wages at workmen compensation Act etc. And latest amendment thereof. Such records maintained by the contractor shall be opened for inspection by the Engineer-In-Charge or by the nominated representatives of the Principal employer.

The contractor/contractors shall provide facilities for the sanitary necessities of all persons employed on the work shall be constructed and maintained in the number, manner and place approved or ordered or by the Engineer-In-Charge. The contractor/contractor shall vigorously prohibit committing of nuisance at any other place. Cost of all works under this item shall be covered by the contractor/contractors tendered rates.

The contractor/contractors shall furnish to the Engineer-In-Charge or his authorized representative with work report from time to time regarding the contractor/contractors organization and the progress made by him/them in the execution of the work as per the contract.

51. All taxes, whether local municipal provincial or central etc. And cess, royalties etc. Are payable or may become payable during the entire periods of contract shall be to the contract/contractors account and shall be deemed to have been included in the tender for the work to be executed by him/her.

The contractor/contractors shall make his/heir own arrangement for all materials, tools, staff and labourer required for the contract, which shall include cost of lead lift, loading, unloading, railway freight recruiting expenses and any other charges for the completion of the work to entire satisfaction of the company.

The contractor/contractors shall make their own arrangement for carriage of all materials to the work site at his/their own cost.

52. The work shall not be sublet to any other party, unless approved by Engineer-In-charge in writing.

53. The contractor/contractors shall not pay less than the minimum wages to the labourers engaged by him/them as per minimum wages Act or such other legislation or award to the minimum wages fixed by the respective State Govt. And the Central Govt. As may be in force.

The contractor shall at all times during the tenure of the contract indemnify the company against all claims, damages or compensation under the provision of the workmen's compensation act and shall take insurance policy covering all risk, claims, damages or compensation payable under the workmen's compensation act or under any other law retaining thereto.

54. On receipt of letter of acceptance of tender/work order the contractor shall forthwith register and obtain license from the competent authority under the contract labour (Regulation & abolition) act 1970 the contract labour (Regulation & abolition) central rules, 1971 and submit certified copies of the same to the Engineer-In-Charge and the Principal employer.

55. The contractor shall be registered with the concerned State Govt. And the Central Govt. In respect of Sales Tax Act and the certificate having details of Registration No. Period of validity etc. Should be submitted with the tender documents.

56. Defects Liability Period:

In addition to the defects to be rectified by the contractor as per terms of the contract/work order, the contractor shall be responsible to make good and remedy at his own expense the defects mentioned here under within such period as may be stipulated by the Engineer-In-charge in writing.

a) Any defect/defects in the work detected by the Engineer-In-Charge within a period of 6 (six) months from the date of issue of defect liability certificate/completion certificate.

b) In the case of building works or other works of similar nature any defect in the work detected by the Engineer-In-Charge within a period of 6 (six) months from the date of issue of defect liability certificate/completion certificate or before the expiry of one full monsoon period i.e. June, to October whichever is later in point of time.

57. A programme shall be drawn by the contractor and the Engineer In Charge for carrying out the defects by the contractor detected within the defect liability period and if the contractor fails to adhere to this programme, the Engineer In Charge shall be at liberty to procure proper materials and carry out the rectifications in any manner considered advisable under the circumstances and the cost of such procurement of materials and rectification work shall be chargeable to the contractor and recoverable from any of the pending dues of the contractors.

The defect liability period can be extended by the company on getting request from the contractor only for valid reasons.

There will be no defect liability period for works like Grass Cutting, Jungle Cutting, Surface Dressing & any other work of similar nature to be decided by the Engineer in Charge.

58. It is incumbent upon the contractor to avoid litigation and disputes during the course of execution. However, if such disputes take place between the contractor and the department, effort shall be made first to settle the disputes at the company level.

The contractor should make request in writing to the Engineer-in-charge for settlement of such disputes/ claims within 30 (thirty) days of arising of the cause of dispute/ claim failing which no disputes/ claims of the contractor shall be entertained by the company.

59. If differences still persist, the settlement of the dispute with Govt. Agencies shall be dealt with as per the Guidelines issued by the Ministry of Finance, Govt. of India in this regard. In case of parties other than Govt. Agencies, the redressal of the dispute may be sought in the Court of Law.

60. Safety measure : The contractor shall make all adequate arrangements for the safety of the workmen at his own cost during execution or work.

61. COMPLIANCE OF LABOUR LAWS :

The contractor/contractors shall not pay less than the minimum wages to the labourers engaged by him/them as per minimum wages act or such other legislation or award to the minimum wages fixed by the respective State Govt. and the Central Govt. as may be in force.

The contractor shall at all times during the tenure of the contract indemnify the company against all claims, damages or compensation under the provision of the workmen's compensation act and shall take insurance policy covering all risk, claims, damages or compensation payable under the workmen's compensation act or under any other law retaining thereto.

62. We have read the tender document and understood all provisions and specification in totally. All terms and conditions are acceptable to us. We do not have any terms and conditions of.

63. The terms and conditions as mentioned in the tender document are only indicative for any other matter not mentioned in this tender. Quotation documents the guidelines of CIVIL ENGINEERING MANUAL OF COAL INDIA LIMITED shall be referred.

Chief .Manager(C)/I/C,KNTA/JNTA

Signature of the tender as taken
of acceptance.

Seal.

INSTRUCTION TO THE BIDDERS :

1. The bidders are supposed to visit and examine the site of work, at their own cost and risk, and obtain all information that may be necessary for participating in the tender and entering into contract.
2. The bidders are advised to study this document in detail and understand all provisions.
3. Place of deposit of tender document at C.I.S.F post near Koyla Bhawan gate, Koyla Nagar, BCCL Dhanbad as well as in the office of undersigned.
4. On opening of part-I of the tenders, the following shall only be checked for deciding eligibility for opening of price bids (Part-II)

Works value up to Rs.5.00 lakhs :

1. Earnest money deposit in the form of Demand Draft on nationalised bank / scheduled bank acceptable to the company in favour of BCCL.
2. Photo copy of permanent Income Tax Account Number (PAN).
3. Particulars of Registration with appropriate Sales Taxes authorities with its validity.
4. Affidavit regarding genuineness of the papers submitted and information furnished duly authenticated by Notary as per format given.
5. The proprietor or attorney holder / authorised signatory in case of partnership firm only should sign the tender document.
6. The bidders would give a declaration that they have not been banned or delisted by any Govt. or Quasi-Govt. Agencies or PSU's.
7. Proof of experience as per NIT completion certificate / copy of final bill only.

Process for evaluation of tenders :

1. Tender document shall be issued to intending bidder on request and production of cost of tender document as stipulated in NIT.
2. Tenders shall be submitted either in single part or in two parts as stipulated NIT in the tender box placed in the office of the Chief Manager (Civil)/c, KNTA/JNTA or as specified in NIT within the scheduled date and time.
3. Part-I of the tenders will be opened in presence of attending bidders by duly constituted committee. The Part-II (Price bid) of all the bidders shall be sealed in a separate cover which would be kept in safe custody.
4. Part-I of the tenders shall be evaluated on scrutiny of Papers/documents submitted by the tenderers along with the tenders in terms of eligibility criteria as mentioned in the NIT/tender document/instruction of bidders of NIT. The bidders who fail to fulfil eligibility criteria shall not be entitled for opening of their price bid.
5. Part-II (Price bid) of those bidders who fulfil the eligibility criteria shall be opened only, on scheduled date and time with intimation to the eligible bidders. Tenders submitted shall be the property of the company, un-opened price bids of the company shall have no obligation to return the same to the tenderer.
6. The overall lowest tenderer shall be considered for award of the work. Being lowest in any part of the tender shall be of no consequence and such tenders shall not have any claim for award of part work.
7. After observing the above formalities TCR would be processed as the case may be as per the guide line of CIVIL ENGINEERING MANUAL.

DECLARATION

I / we _____ hereby declare that our firm
(Name of the firm & address) _____

Have not been banned or delisted by any State Government or Central Government or Quasi
Government Agencies or Public Sector Undertakings.

Signature of the Bidder
& Seal of firm

PROFORMA FOR AFFIDAVIT TO BE SUBMITTED BY THE TENDERER

Non Judicial Stamp Paper.

AFFIDAVIT

I, -----, Partner/Legal Attorney/ Accredited Representative of M/S -----
-----, solemnly declare that :

1. We are submitting Tender for the Work -----
----- against Tender Notice No.---
----- dt -----
2. None of partners of our firm is relative of employee of BCCL.
3. All information furnished by us in respect of fulfillment of eligibility criteria and qualification information of this Tender is complete, correct and true.
4. All documents/ credentials submitted along with this Tender are genuine, authentic, true and valid.
5. If any information and document submitted is found to be false/ incorrect any time, department may cancel my Tender and action as deemed fit may be taken against us, including termination of the contract, forfeiture of all dues including Earnest Money and banning / delisting of our firm and all partners of the firm etc.
6. None of the partners of the firm has either individually are collectively been involved in criminal offences.

Signature of the Tenderer

Dated-----

Seal of Notary

**PROFORMA FOR COLLECTING PAYMENT THROUGH ELECTRONIC MODE INCLUDING ELECTRONIC FUND
TRANSFER (EFT) &ELECRONIC CLEARING SYSTEM (ECS)**

1	Vender/supplier /contractor /customer 's name and address(with telephone number & Fax number)	
2	Particulars of bank account	
	a) Bank name	
	b) Branch name (including RTGS CODE)	
	Address	
	Telephone & Fax no.	
	c) 9- Digit code number of Bank & branch (Appearing on the MICR cheque issued on bank) or 5 units code number of S.B.I.	
	d)Accounts type (S.B. Account /current Account or Cash credit with code 10/11/13)	
	e) Ledger no,/ Ledger folio no.	
	f)Account number (Core banking &style of account) (As appearing on the cheque book)	

3 DATE OF EFFECT:-

I hereby declare that the particulars given above are correct & complete. If the transaction is delayed or not effected at all for reasons of incomplete or incorrect information. I would not hold the user institution responsible. I have read the option invitation letter and agree to discharge responsibility expected of me as a participant under the scheme. Any bank charges levied by the bank of such e- transfer shall be borne by us.

()
Signature of customer/ vender/supplier/contractor

Certified that the particulars furnished above are correct as per our records.

()
Signature of the authorized officials from the bank.

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyna nagar/Jagjiwan nagar-Town Administration
Dhanbad.

Name of work:- repairing and maintenance of different qtrs at Koyna nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/ 942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED
(A Subsidiary of coal India Limited)
Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II

(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- repairing and maintenance of different qtrs at Koyla nagar

Name of contractor:-

Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 17.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of repairing and maintenance of different qtrs at Koyla nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	White washing with lime to give an even shade Old work (two or more coats)	sqm	1020.73	4.10	4184.99
2	Distempering with dry distemper of approved brand and manufacturers (one or more coat)and of required shade on old work to give an even shade	sqm	275.16	12.35	3398.22
3	Colour washinhg such as green ,blue or buff to give an even shade Old work (two or more coats)with lime	sqm	509.12	4.87	2479.41
				Total	10062.62

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration

Dhanbad.

Name of work:- Repairing of tilted compound wall between D//X/11 & 10 including roof repairing of D/X/11 and D/V/6 at Koyla nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED
(A Subsidiary of coal India Limited)
Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II

(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- for the work of repairing of tilted compound wall between D//X/11 & 10
including roof repairing of D/X/11 and D/V/6 at Koyla nagar

Name of contractor:-

Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of repairing of tilted compound wall between D//X/11 & 10 including roof repairing of D/X/11 and D/V/6 at Koyla nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	Dismantling brick work manually by mechanical means including stacking serviceable material and disposal of unserviceable material within 50m lead as per direction of Engineer In Charge in cemen mortar	cum	10.70	310.75	3325.02
2	Removing mortar from bricks and cleaning bricks including stacking within a lead of 50m(stacks of cleaned bricks shall be measured) from brick work in cement mortar	1000nos	2115.00	998.80	2112.46
3	Earth work in excavation by mechanical means (hydraulic excavater) manual means in foundation trenches or drains (not exceeding 1;5m depth or 10sqm on plan)including dressing of sides and ramming of bottoms lift upto 1.5m including getting out the excavated soil and disposal of surplus excavated soil as directed within a lead of 50m all kind of soil	cum	1.42	103.40	146.83
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering 1:4:8(1cement: 4coarse sand:8graded stone aggregate 40mm nominal size.	cum	0.20	2449.00	489.80
5	Brick work with F,P.S brick of class designation 50 in foundation and plinth in. 1:6(1cement : 6 course sand)	cum	6.03	2007.00	12644.10
6	Brick work with FPS bricks of class designation 50 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:6(1 cement :6coarse sand	cum	4.62	2315.50	10697.61
7	Brick work 7cm thick with FPS bricks of class designation 50 in cement mortar 1:3(1cement:3 coarse sand)	sqm	5.33	206.10	1098.51
8	12mm thick cement plaster of mix 1:6(1cement : 6 course sand)	sqm	89.00	72.70	6470.30
9	Colour washinhg such as green ,blue or buff to give an even shade				

	Old work (two or more coats)with lime	sqm	89.00	4.87	827.70
10	Deduction of using old /available bricks	1000nos	2115.00	2195.14	-4642.72
11	Grading roof for water proofing treatment with Cement concrete 1;2:4(1 c ment :2 coarse sand 4 graded stone aggregate 20mm nominal size	cum	4.74	3314.95	15712.86
				Total	48882.47

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration

Dhanbad.

Name of work:-Replacment of damaged frames,shutter,doors Ventilators,with renewing glass panes of ventilators at Koyla nagar hospital.

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/ 942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED
(A Subsidiary of coal India Limited)
Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II

(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:-Replacment of damaged frames,shutter,doors Ventilators,with renewing glass panes
of ventilators at Koyla nagar hospital

Name of contractor:-

Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of replacment of damaged frames,shutter,doors Ventilators,with renewing glass panes of ventilators at Koyla nagar hospital.

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	Dismantling door windows and clerestory wondows (steel or wood)shutter including chowkhats , architrave holdfasts etc complete and stacking within 50metres lead of area 3 sq metres and below	each	2.00	54.60	109.20
2	Taking out doors windows and clerestory window shutters (steel or wood)including stacking within 50metres lead of area 3 sq metres and below	each	2.00	21.40	42.80
3	Providing wood work in frames of door windows clerestory window and other frames wrought framed and fixed in position Sal wood	cum	0.0084	30511.95	256.30
4	Providing and fixing factory made PVC door frame of size 50x47mm with a wall thickness of 5mm , made out of extruded 5mm rigid PVC foam sheet mitred at corners and joined with 2nos of 150mm long brackets of 15x15mm M.S sequire tube , the vertical door profiles tobe reinforced with 19x19mm M.S squire tube of 19 guage .EPDM rubber gasket weather seal to be provided through out the frame . The door frame to be fixed to the wall using M.S screws of 65/100mm size complete as per manufacturers specification and direction of Engineer In Charge	metre	10.40	353.10	3672.24
5	Providing and fixing to existing door frames 30mm thick factory made panel PVC door shutter consisting of frame made out of M.S tubes of 19guage thickness and size 19mm x19mm for styles and 15x15mm for top and bottoms rail , MS frame shall have a coat of steel primers of approved make and manufacturere , M.S frame covered with 5mm thickheat moulded PVC C channel of size 30mm thickness 70mm width out of which 50mm shalll be flate and 20mm shall be tapered in 45degree angle on either side forming styles and 5mm thick 95mm wide PVC sheetout of which 75mm shall be flate and 20mm shall be tapered in 45degree				

	on the inner side to form top and bottom rail and 115mm wide PVC sheet out of which 75mm shall be flate and 20mm shall be tapered on both sides form lock rail. Top and bottom and lock rails shall be provided either side of the pannel 10mm thick 20mm wide cross PVC sheet be provided s gap insert for top rail and bottom rail panelling of 5mm thick both side PVC sheet to fitted in M.S frame welded /sealed to styles rails with 7mm thick 15mm wide PVC sheet beading on inner side and joined together with salvent cement adhesive and addl.5mm thick PVC strip of 20mm width is to be stuck on the interior side fo C chanel using PVC salvent adhesive etc complete	sqm	3.47	2109.95	7321.53
6	Providing and fixing ISI marked flush door shutters confirming to IS:2202(Part-I)decorative type core of block board construction with frame of Ist class hard wood and well matched leak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters: 30mm thick including ISI marked stainless steel butts hinges with necessary screws .	sqm	4.83	1415.45	6836.62
	25mm thick (for cup board)including ISI marked nickel plated bright finished M.S plano hinges IS:3818 marked with necessary screws.	sqm	0.72	1317.65	948.71
7	Providing and fixing 40x5mm flat iron hold fast 20cm long and embedding in cement concrete 1:3:6 etc.	each	16.00	39.94	639.04
8	Providing and fixing IS:3564 marked aluminium extruded section body tubular type universal dydraulic door closer with double speed adjustment with necessary accessories and screws etc complete .	each	2.00	911.10	1822.20
9	12mm thick cement plaster of mix 1:6(1cement:6 fine sand)	sqm	5.00	67.65	338.25
10	Providing and fixing alumunium sliding door bolt I.S.I marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with nuts and screws etc complete 300x16mm	each	5.00	158.50	792.50
11	Providing and fixing alumunium tower bolt ISI;marked anodised (anodised coating not less than grade AC 10 as per IS:1868) transperent or dyed to required colour or shade with necessary screws etc complete 150x10mm	each	8.00	42.75	342.00

	200x10mm	each	8.00	62.20	497.60
12	Providing and fixing and finishing alumunium handle I.S.I marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc complete 100mm	each	12.00	35.30	423.60
13	Providing and fixing 32mm thick fully glazed ventilator shutter of gamhar wood with 4cm thick glass panes as per direction of Engineer Incharge complete job.	sqm	1.27	2249.03	2856.27
14	Renewing lass panes with wooden fillets wherever necessary Float glass panes of thickness 4mm	sqm	41.12	498.55	20500.38
15	Applying priming coat with ready mixed pink or grey primer of approved brand and manufacture on wood work ((hard and soft wood)	sqm	15.38	16.55	254.54
16	Painting with sythetic enamel paint of approved brand and manufacturers required colour to give an even shade Two or more coat on new work	sqm	15.38	35.35	543.68
				Total	48197.46

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration

Dhanbad.

Name of work:- provision of barbed wire fencing for plantation near shopping complex at Koyla nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/942

dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED
(A Subsidiary of coal India Limited)
Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II

(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- provision of barbed wire fencing for plantation near shopping complex at Koyla nagar

Name of contractor:-

Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)/C/Tender/2011-12/942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of provision of barbed wire fencing for plantation near shopping complex at Koyla nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	Earth work in excavation by mechanical means (Hydraulic excavation) material over areas (exceeding 30cm depth 1.5m in width as well as 10sqm on plan) including disposal of excavated earth lead up to 50m and lift upto 1.5m disposal earth to be levelled and neatly dressed Ordinary rock	Cum	70.00	152.60	10682.00
2	Earth work in foundation trenches or drains not exceeding 1.5m in width or 10sqm on plan including dressing of sides and ramming of bottoms lift up to 1.5 m including getting out the excavated soil and disposal of surplus excavated soils as directed within in lead of 50m Ordinary rock	Cum	7.60	162.65	1236.14
3	Supplying at site angle iron post & strut of required size including bottom to be spilt and bent at right angle in opposite direction for 10cm length and drilling holes upto 10mm dia etc complete.	kg	247.20	43.35	10716.12
4	Fencing with angle iron post placed at required distance embedded in cement concret blocks ever 15th post last but one end post and corner post shall be struted on both sides and end post on one side only and provided with horzental lines and two diagonals interwoven with horizontal wires , of barbed wire 9.38kgper 100m(minimum) between the two posts fitted and fixed with G.I staples , turn buckles etc complete (cost of posts , struts earth work and concrete work to be paid for seperataly)payment to be made per metre cost of total length of barbed wire used With G.I barbed wire	metre	666.49	8.45	5631.84
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering 1:3:6(1cement: 3 coarse sand:6 graded stone aggregate				

	40mm nominal size)	cum	5.49	2713.05	14894.64
6	Painting with synthetic enamel paint of approved brand and manufacturers required colour to give an even shade				
	Two or more coat on new work	sqm	7.13	35.35	252.03
7	Edging with bricks laid dry length wise including excavation				
	refilling consolidated with hard packing and spreading neatly				
	Surplus earth within a lead of 50m.				
	F.P.S bricks	metre	100.00	13.85	1385.00
					0.00
				Total	44797.78

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration

Dhanbad.

Name of work:- Repair/maintenance including replacement of damaged wood work under shifting & emergency cases in qtr no. C2/X/40,D/X/5, B/II/200 &218 at Koyla nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/942

dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED
(A Subsidiary of coal India Limited)
Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II

(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- Repair/maintenance including replacement of damaged wood work under shifting & emergency cases in qtr no. C2/X/40,D/X/5, B/II/200 &218 at Koyla nagar

Name of contractor:-

Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of repair and maintenance including replaceemnt of damaged wood work under shifting &emergency cases in qtrno. C2/X/40,D/X/5,B/II/200&218 at Koyla Nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	Providing wood work in frames of door windows clerestory window and other frames wrought framed and fixed position sal wood	cum	0.04	30511.95	1220.48
2	Providing and fixing 40x5mm flat iron hold fast 20cm long and embedding in cement concrete(1:3:6) etc	each	4.00	48.36	193.44
3	Providing and fixing 32mm thick gamhar wood 2/3 panelled and 1/3 glazed using 4mm thick glass panel complete job as per direction of Engineer Incharge	sqm	5.00	2218.66	11093.30
4	Providing and fixing ISI marked flush door shutters to IS:2202(Part-I)non decorative type core of block board construction with frame of Ist class hard wood well matched commercial 3 ply veneering with verical grains or cross bands and face veneers on both faces of shutters: 30mm thick including ISI marked stainless steel butts hinges with necessary screws .	sqm	1.36	904.40	1229.98
5	Providing and fixing fly proof 24SWG wire gauge wiremesh breading 20x12mm complete job as per direction of Engineer Incharge.	sqm	0.90	407.08	366.37
6	Providing and fixing flat pressed 3 layer particle board medium density exterior grade(Grade I)or graded wood particle board IS:3087marked to frame , backing or studding with screws etc , complete (frames backing or studing to be separatly 18mm thick	sqm	9.20	418.40	3849.28
7	12mm thick cement plaster finished with a floating of neat cement of mix 1:4(1cement: 4 fine sand)	sqm	2.40	97.90	234.96
8	Repair to plaster of thickness 12mm to 20mm in patchs of area 2.5sqr metre and under including cutting in patch in proper shape and raking out joints and preparing and plastering the surface of the walls complete including diposal of rubbish to dumping gound wihtin 50metre lead Cement mortar 1:4(1cement :4 coarse sand)	sqm	25.00	120.70	3017.50

9	Easy adjustment of doors,windows, shutters including necessary repair all type of doors,windows,shuttes including taking out and refitting the same in position all complete work as per direction of engineer incharge				
	Doors	each	1.00	168.52	168.52
	Wondows/shutter	each	1.00	81.05	81.05
10	Providing and laying ceramic glazed floor tiles 300x300mm (thickness to be specified bythe manufacture) of Ist quality confirming to IS:15622 of approved make in colours such as white ,Ivory,Grey fume, Red brown, laid on 20mm thick cement mortar 1:4 including pointing the joints with white cement and matching pigment etc complete	sqm	5.20	598.65	3064.88
11	Providing and fixing white vitrous china water closet squatting pan (Indian type) Long pattern W.C pan of size 580mm	each	1.00	534.60	534.60
12	Providing and fixing white vitreous china wash basin including making all connection but excluding the cost of fittings Flat back wash basin of size 550x400mm	each	1.00	596.20	596.20
13	Providing and fixing 15mm C.P. pillar cock complete asper direction of Engineer Incharge	each	4.00	357.15	1428.60
14	Proviidng and fixing uplasticised PVC connection pipe with brass unions 45cm length 15mm nominal bore	each	3.00	44.75	134.25
15	Providing and fixing PVC low level flushing cistern with manually controlled device (Handle lever) confirming to IS:7231 with all fittings and fixture complete. 10 letre capacity -white	each	1.00	709.75	709.75
16	Providing and fixing waste pipe for sink on wash basin including PVC waste fittings complete 32mm dia	each	2.00	42.15	84.30
17	Providing and fixing PTMT towel rail complete with brackets fixed to wooden cleats with C.P brass screws with concealed fitting arrangement of approved quality and colour 600mm long towel rail with total of 645mm,width 78mm and effective height of 88mm weighting not less than 190gms	each	1.00	329.50	329.50
18	Providing and fixing C.P brass shower rose with 15 or 20 mm inlet 100mm diameter	each	2.00	40.40	80.80

19	Providing and fixing brass stop cock of approved quality 15mm nominal bore	each	1.00	191.70	191.70
20	Providing and fixing G.I. pipes complete with G.I fittings and clamps including cutting and making good the wall etc.(Internal work) 15mm dia	metre	3.75	105.85	396.94
21	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6mm thick hard board backing Oval shape 450x350mm (outer dimension)	each	1.00	504.00	504.00
22	White washing with lime to give an even shade Old work (two or more coats)	sqm	657.00	4.10	2693.70
23	Colour washing such as green ,blue or buff to give an even shade Old work (two or more coats)with lime	sqm	370.00	4.87	1801.90
24	Distempering with dry distemper of approved brand and manufacturers (one or more coat)and of required shade on old work to give an even shade	sqm	525.00	12.35	6483.75
25	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc.complete.	sqm	370.00	3.20	1184.00
26	Removing dry or oil bound distemper, water proofing cement paint and the like scraping ,sand papering and preparing the surface smooth including necessary repairs to scratches etc complete	sqm	308.20	4.25	1309.85
27	Applying primer with whiting	sqm	308.20	3.68	1134.17
28	Cleaning mosaic marble/concrete floor using acid serf,soda etc.complete.	sqm	178.00	7.83	1393.74
29	Dismantling door windows and clerestory windows (steel or wood)shutter including chowkhats , architrave holdfasts etc complete and stacking within 50metres lead of area 3 sq metres and below	each	1.00	54.60	54.60
30	Taking out doors windows and clerestory window shutters (steel or wood)including stacking within 50metres lead of area 3 sq metres and below	each	6.00	21.40	128.40
31	Painting with sythetic enamel paint of approved brand and manufacturers required colour to give an even				

	shade				
	two or more coat on new work over and under coat of suitable shade with ordinary paint of approved brand and manufacturer	sqm	34.00	51.30	1744.20
32	Providing and fixing alumunium sliding door bolt I.S.I marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with nuts and screws etc complete				
	250x16mm	each	1.00	134.10	134.10
33	Providing and fixing alumunium tower bolt ISI;marked anodised (anodised coating not less than grade AC 10 as per IS:1868) transperent or dyed to required colour or shade with necessary screws etc complete				
	150x10mm	each	3.00	42.75	128.25
				Total	47701.06

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration

Dhanbad.

Name of work:- Internal & External repair/maintenance of Gouri Shanker Hanuman Mandir near B type colony at Koyla nagar

Place of work:-

Tender notice no and date:- BCCL/TA/CM(C)I/C/Tender/11-12/942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED
(A Subsidiary of coal India Limited)
Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II

(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- Internal & External repair/maintenance of Gouri Shanker Hanuman Mandir near B type colony at Koyla nagar

Name of contractor:-

Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of Internal /external repair and maintenance of GuariShanker Hanuman Mandir near B type colony at Koyla nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	Distempering with oil bound washable distemper of approved brand and manufacturer to give even shade old work one or more coat	sqm	530.00	14.90	7897.00
2	Finishing wall with water proofing cement paint of required shade Old work(one or more coats applied @ 2.20kg/10sqm) over priming coat of primer applied @ 0.80kg/10sqm complete including coat of priming coat	sqm	535.00	27.95	14953.25
3	Painting with sythetic enamel paint of approved brand and manufachure of required colour to give even shade old work one or more coat	sqm	159.00	22.85	3633.15
4	Removing dry or oil bound distemper, waterr proofing cement paint and the like scraping ,sand papering and preparing the surface smooth including necessary repairs to scratches etc complete	sqm	649.00	4.25	2758.25
5	Applying one coat of cement primer of approved brand manufacture on wall surface Cement primer	sqm	114.00	17.20	1960.80
6	Finishing wall with acylic smooth exteriorpaint of required shade old work one or more coat	sqm	54.00	22.80	1231.20
7	Repair to plaster of thickness 12mm to 20mm in patchs of area 2.5sqr metre and under including cutting in patch in proper shape and raking out joints and preparing and plastering the surface of the walls complete including diposal of rubbish to dumping gound wihtin 50metre lead Cement mortar 1:4(1cement :4 coarse sand)	sqm	5.00	120.70	603.50
8	Dry brick flat soling with class of designation 50 bricks asper direction of Engineer Incharge	sqm	3.00	137.54	412.62
9	Pointing on brick work or brick flooring with cement mortar 1:3(1cement:3 fine sand) Flush /Ruled /struck or weatherd pointing	sqm	8.00	45.40	363.20

Total 33812.97

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration

Dhanbad.

Name of work:- Internal repair /maintenance work of quarters under shifting /emergency cases of sector-IX,IV,
and XI at Koyla nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED
(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II
(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- Internal repair /maintenance work of quarters under shifting /emergency cases of sector-IX,IV,
and XI at Koyla nagar

Name of contractor:-
Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of Internal repair/maintenance work of quarters under shifting /emergency cases of sector-IX,IV, and XI at Koyla Nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	White washing with lime to give an even shade Old work (two or more coats)	sqm	3712.33	4.10	15220.55
2	Colour washinhg such as green ,blue or buff to give an even shade New work (two or more coats)with base coat of whiting	sqm	2012.12	9.10	18310.29
3	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scretches etc. complete.	sqm	2012.12	3.20	6438.78
4	Distempering with dry distemper of approved brand and manufacturers (one or more coat)and of required shade on old work to give an even shade	sqm	3393.34	12.35	41907.74
5	Removing dry or oil bound distemper, waterr proofing cement paint and the like scraping ,sand papering and preparing the surface smooth including necessary repairs to scratches etc complete	sqm	3393.34	4.25	14421.69
6	Providing wood work in frames of door windows clerestory window and other frames wrought framed and fixed in position Sal wood	cum	0.288	30511.95	8787.44
7	Providing and fixing 40x5mm flat iron hold fast 20cm long and embedding in cement concrete 1:3:6 etc.	each	32.00	39.94	1278.08
8	Providing and fixing 30mm thick fully panneled gamhar wood shutter including M.S hinges as per direction of Engineer Incharge.	sqm	3.34	2351.21	7853.04
9	Providing and fixing in wall lining flat pressed three layer(media density) particle board or graded wood prelaminated one side decorative lamination on other side balancing lamination Grade I type II IS:12823 marked including priming coat on unexposed surface with necessary fixing arrangement and screws etc complete 18mm thick	sqm	6.52	418.40	2727.96
10	Providing and fixing 32mm thick gamhar wood 2/3 panelled and 1/3 glazed using 4mm thick glass panel complete job as per direction of Engineer Incharge	sqm	2.59	2218.66	5746.33
11	Providing and fixing 32mm thick fully glazed ventilator				

	shutter of gamhar wood with 4cm thick glass panes as per direction of Engineer Incharge complete job.	sqm	3.76	2249.03	8456.35
12	Dismantling door windows and clerestory wondows (steel or wood)shutter including chowkhats , architrave holdfasts etc complete and stacking within 50metres lead				
	of area 3 sq metres and below	each	16.00	54.60	873.60
13	Taking out doors windows and clerestory window shutters (steel or wood)including stacking within 50metres lead				
	of area 3 sq metres and below	each	2.00	21.40	42.80
14	Providing and fixing factory made PVC door frame of size 50x47mm with a wall thickness of 5mm , made out of extruded 5mm rigid PVC foam sheet mitred at corners and joined with 2nos of 150mm long brackets of 15x15mm M.S sequire tube , the vertical door profiles tobe reinforced with 19x19mm M.S squire tube of 19 guage .EPDM rubber gasket weather seal to be provided through out the frame . The door frame to be fixed to the wall using M.S screws of 65/100mm size complete as per manufacturers specification and direction of Engineer In Charge	metre	45.23	353.10	15970.71
15	Providing and fixing to existing door frames 30mm thick factory made panel PVC door shutter consisting of frame made out of M.S tubes of 19guage thickness and size 19mm x19mm for styles and 15x15mm for top and bottoms rail , MS frame shall have a coat of steel primers of approved make and manufacturere , M.S frame covered with 5mm thickheat moulded PVC C channel of size 30mm thickness 70mm width out of which 50mm shalll be flate and 20mm shall be tapered in 45degree angle on either side forming styles and 5mm thick 95mm wide PVC sheetout of which 75mm shall be flate and 20mm shall be tapered in 45degree on the inner side to form top and bottom rail and 115mm wide PVC sheet out of which 75mm shall be flate and 20mm shall be tapered on both sides form lock rail. Top and bottom and lock rails shall be provided either side of the pannel 10mm thick 20mm wide cross PVC sheet be provided s gap insert for top rail and bottom rail panelling of 5mm thick both side PVC sheet to fitted in M.S frame welded /sealed to styles rails with 7mm thick 15mm wide PVC sheet beading on inner side and joined				

	together with solvent cement adhesive and addl.5mm thick PVC strip of 20mm width is to be stuck on the interior side of C channel using PVC solvent adhesive etc complete	sqm	12.95	2109.95	27323.85
16	Providing and fixing and finishing aluminium handle I.S.I marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc complete 100mm	each	10.00	35.30	353.00
17	Providing and fixing aluminium tower bolt ISI;marked anodised (anodised coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc complete 150x10mm	each	10.00	42.75	427.50
18	Providing and fixing aluminium sliding door bolt I.S.I marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with nuts and screws etc complete 250x16mm	each	5.00	134.10	670.50
19	Renewing glass panes with wooden fillets wherever necessary . Float glass panes of thickness 4mm	sqm	5.00	498.55	2492.75
20	Repair to plaster of thickness 12mm to 20mm in patches of area 2.5sqm metre and under including cutting in patch in proper shape and raking out joints and preparing and plastering the surface of the walls complete including disposal of rubbish to dumping ground within 50metre lead cement mortar 1:4(1cement :4 fine sand)	sqm	35.00	114.35	4002.25
21	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade Two or more coats on new work. over and under coat of suitable shade with ordinary paint of approved brand and manufacture	sqm	39.29	51.30	2015.56
					0.00
				Total	185320.79

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration
Dhanbad.

Name of work:- Repairing of plinth protection and drain in C2/VII type qtr block no, 13to18,19to 24 ,31 to 36,37 to 42,55to 60,61to 66,73to 78,91to 96,97to 102 nine block at Koyla nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II

(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- Repairing of plinth protection and drain in C2/VII type qtr block no, 13to18,19to 24 ,31 to 36,37
to 42,55to 60,61to 66,73to 78,91to 96,97to 102 nine block at Koyla nagar

Name of contractor:-
Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of repairing of plinth protection and drain in C2/VII type qtr of Block 13-18,19-24,31-36, 37-42,55-60,73-78,91-96,97-102 at Koyla nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	Cement concrete flooring 1:2:4 finished with a floating coat of neat cement including cement slurry but excluding the cost of nosing of steps etc complete 40mm thick with 20mm nominal size stone aggregate	sqm	790.00	192.95	152430.50
2	12mm cement plaster 1:3(1cement:3coarse sand) finished with a floating coat of neat cement.	sqm	216.00	112.80	24364.80
3	foundation and plinth in. 1:6(1cement : 6 coarse sand)	cum	2.2	2007.00	4415.40
4	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dunning ground within 50metre lead.	sqm	112.00	8.20	918.40
				Total	182129.10

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration
Dhanbad.

Name of work:- Repairing and maintenance of sewing centre at Koyla nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED
(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II
(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- Repairing and maintenance of sewing centre at Koyla nagar

Name of contractor:-
Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of Repairing and maintenance of sewing centre at Koyla nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	Removing dry or oil bound distemper, waterr proofing cement paint and the like scraping ,sand papering and preparing the surface smooth including necessary repairs to scratches etc complete	sqm	263.51	4.25	1119.92
2	Applying one coat of cement primer of approved brand manufacture on wall surface Cement primer	sqm	263.51	17.20	4532.37
3	Distempering with oil bound washable distemper of Approved brand and manufacture to give an even shade New work (two or more coats) over and including priming coat with cement primer.	sqm	263.51	41.55	10948.84
4	Painting with sythetic enamel paint of approved brand and manufachure of required colour to give even shade old work one or more coat	sqm	50.57	22.85	1155.52
5	Floor painting with floor enamel paint of approved brand and manufacture to give an even shade Two or more coats on new work	sqm	26.72	37.05	989.98
6	Finishing wallswith premium Acylic smooth exterior paint with sillcone additives of required shade Old work(one or more coats applied @0.83ltr/10sqm	sqm	40.21	46.60	1873.79
7	Finishing wall with water proofing cement paint of required shade Old work(one or more coats applied @ 2.20kg/10sqm) over priming coat of primer applied @ 0.80kg/10sqm complete including coat of priming coat	sqm	329.85	27.95	9219.31
8	Clearing jungle excluding uprooting of root,vegetation grass,bush trees and supply of girth up to 30cm measured of height of 1m above gound level and removal of rubbish up to 50m out side peripharyof the area cleared.	100sqm	150.99	193.97	292.88
					30132.60

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration

Dhanbad.

Name of work:- Need based maintenance work of water supply and sanitary system of sector-VII & VIII at Koyla Nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/ 942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II

(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- Need based maintenance work of water supply and sanitary system of sector-VII & VIII at
Koyla Nagar

Name of contractor:-
Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/ 942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q

for the work of Need based maintenance work of water supply and sanitary system of sector
VII & VIII at Koyla Nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	Providing and fixing G.I. pipes complete with G.I fittings and clamps including cutting and making good the wall etc.(Internal work) 15mm dia	metre	30.00	105.85	3175.50
	20mm dia	metre	15.00	133.85	2007.75
	25mm dia	metre	15.00	179.65	2694.75
2	Providing and fixing brass bib cock of approved quality 15mm nominal bore	each	30.00	191.70	5751.00
3	Providing and fixing brass stop cock of approved quality 15mm nominal bore	each	15.00	191.70	2875.50
4	Providing and fixing C.P brass pillar cock of approved quality 15mm nominal bore	each	15.00	131.10	1966.50
5	Providing and fixing uplasticised PVC connection pipe with brass unions 45cm length 15mm nominal bore	each	20.00	44.75	895.00
6	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6mm thick hard board backing Rectangular shape 453x357mm	each	6.00	465.10	2790.60
7	Providing and fixing white vitrous china water closet squatting pan (indian type) Orissa pattern W.C pan size 580x440mm	each	10.00	1010.85	10108.50
8	Providing and fixing white vitrous china pedestal type (European type wash down type)water closet pan	each	3.00	841.25	2523.75
9	Dismantling w.c pan(Indian /european type)and making the place clear to fix by new pan (Indian / european type)in position including taking out the debris within a lead of 50metre lead.	each	13.00	79.59	1034.67
10	Providing and fixing trap of self cleaning design with screwed down or hinged grating with or without vent arm complete including cost of cutting and making good the walls and floors Sand cast iron S&S as per IS:1729 100mm inlet and 100mm outlet	each	10.00	442.10	4421.00
	100mm inlet and 75mm outlet	each	10.00	375.90	3759.00

11	Providing and fixing solid plastic seat with lid for pedestal type W.C pan complete White solid plastic seat with lid	each	5.00	334.95	1674.75
12	Providing and fixing soil waste, and vent pips 100mm dia	metre	15.00	451.00	6765.00
	75mm dia	metre	6.00	395.45	2372.70
13	Providing and fixing plain bed of required degree 100mm Sand cost iron S&S pipe as per IS:1729	each	10.00	222.45	2224.50
	Providing and fixing plain bed of required degree 75mm dia				0.00
	Sand cost iron S&S pipe as per IS:1729	each	10.00	175.15	1751.50
14	Providing and fixing bend of required degree with access door, insertion rubber washer 3mm thick bolt and nut complete 100mm Sand cost iron S&S pipe as per IS:1729	each	10.00	255.00	2550.00
	Providing and fixing bend of required degree with access door, insertion rubber washer 3mm thick bolt and nut complete 75mm dia				
	Sand cost iron S&S pipe as per IS:1729	each	5.00	210.00	1050.00
15	Providing and fixing single equal plain junction of required degree 100x100x100mm Sand cost iron S&S pipe as per IS:1729	each	5.00	323.50	1617.50
	75x75x75mm Sand cost iron S&S pipe as per IS:1729	each	5.00	250.65	1253.25
16	Providing and fixing PVC low level flushing cistern with manually controlled device (Handle lever) confirming to IS:7231 with all fittings and fixture complete. 10 litre capacity -white	each	10.00	709.75	7097.50
17	Cement concrete flooring 1:2:4(1cement:2 coarse sand :4graded stone aggregate)finished with a floating coat of neat cement including cement slurry , but excluding the cost of nosing of steps etc compete 40mm thick with 20mm nominal size stone aggregate	sqm	7.00	192.95	1350.65
18	Providing and fixing C.P brass shower rose with 15 or 20 mm inlet 100mm diameter	each	15.00	40.40	606.00
19	Providing and fixing gun metal valve with C.I wheel				

	of approved quality with swrewed end) 25mm nominal bore	each	4.00	285.50	1142.00
20	Providing and fixing 100mm sand cst iron grating for gully trap	each	15.00	16.45	246.75
21	Providing and fixing wash basin with C.I brackets 15,mm C.P brass piller taps 32mm C.P brass waste of standerd partern including painting of fittings and brackes cutting and making good the walls wherever required . white vitreous china flat backwash basin size 550x400mm with single 15mm C.P brass pillar tap	each	8.00	1044.90	8359.20
22	Providing and fixing kitchen sink with C.i brackets C.P brass chain with rubber plug, 40mm C.P brass waste complete including painting and fittings and brackets cutting and making good the walls wherever required.(white glazed fire clay kitchen sink of size 600x450x250mm	each	3.00	1793.35	5380.05
23	Providing and fixing waste pipe for sink on wash basin including PVC waste fittings complete semi rigid pipe 32mm dia	each	12.00	42.15	505.60
	40mm dia	each	5.00	47.95	239.75
24	Providing and fixing C.P brass waste complete 32mm dia	each	12.00	60.72	728.64
	40mm dia	each	5.00	67.04	335.20
25	Providing and fixing drain board with C.I brackets including painting of brackets cutting and making good the walls wherever requir 600x450x25mm	each	3.00	638.60	1915.80
26	Providing and fixing bracket for wash basin /sink including taking out bracket and fixing new one etc	each	3.00	246.32	738.96
27	Providing and fixing G.I union in G.I pipe including cutting and threading the pipe making loang screws etc complete(New work) 15mm nominal bore	each	6.00	75.90	455.40
	20mm nominal bore	each	3.00	96.80	290.40
	25mm nominal bore	each	3.00	107.25	321.75
28	Cutting chases in brick masonary walls for following diameter sand cast iron/centrifugally cast (spun) iron pipes and making good the same with cement concrete 1:3:6(1cement:3coarse sand:6 graded stone aggregate12.5mm nominal size)including necessary plaster and pointing in cement mortar				

	1:4(1cement:4 coarse sand)				
	100mm dia	metre	15.00	152.45	2286.75
	75mm dia	metre	6.00	108.85	653.10
29	Providing and fixing 600x120x5mm glass shelf wutg edges round of supported on anodised alumunium angle frame with C.P brass brackets and guard rail complete fixed with 40mm long screws rawl plugs etc complete				0.00
		each	8.00	216.70	1733.60
30	Dismantling of flushing cistern of any size including stacking of useful materials near the site and disposal of unserviceable materials within 50 metre lead .				
		each	10.00	43.35	1433.50
				Total	101083.32

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration

Dhanbad.

Name of work:- Uprooting of unwanted trees/plants from exteriors of quarters of A type ,sector-I and D type , sector-III at Koyla nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/ 942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II

(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- Uprooting of unwanted trees/plants from exteriors of quarters of A type ,sector-I and D type ,
sector-III at Koyla nagar

Name of contractor:-
Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/ 942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of Uprooting unwanted trees/plants form the exterior of quarters of A type sector-I and D type sector-III at Koyla nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	Felling trees rooted on wall surface of the building of the girth measured at a height of 15cm from the surface including cutting of branches if required removing th e roots after cutting walls and filling the same with cement concrete 1:2:4(1 cement :2coarse sand:4 graded stone aggregate 20mm nominal size)including finishing the same etc. (height of the wall upto 10m) dia of the tree 7.5cm	each	1043.00	90.60	94495.80
2	Dismantling brick work manually by mechanical means including stacking serviceable material and disposal of unserviceable material within 50m lead as per direction of Engineer In Charge in cemen mortar	cum	4.00	310.75	1243.00
3	Brick work with FPS bricks of class designation 50 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:6(1 cement :6coarse sand	cum	4.00	2315.50	9262.00
4	12mm thick cement plaster of mix 1:6(1cement : 6 course sand)	sqm	21.30	72.70	1548.51
5	Finishin wall with water proofing cement paint of required shade New work(two or more coats applied @ 3.84kg/10sqm	sqm	21.30	30.80	656.04
				Total	107205.35

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration

Dhanbad.

Name of work:- Need based maintenance work relating to Internal water supply, sanitation and sewerage system in sector-IX,V and XI at Koyla Nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II

(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- Need based maintenance work relating to Internal water supply, sanitation and sewerage system in sector-IX,V and XI at Koyla Nagar

Name of contractor:-
Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/ 942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

0.00

B.O.Q for the work of need based maintenance work relating to Internal water supply, sanitation, and sewerage system in sector-IX, IV, and XI at Koyla nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	Providing and fixing G.I. pipes complete with G.I fittings and clamps including cutting and making good the wall etc.(Internal work)				
	15mm dia	metre	15.00	105.85	1587.75
	20mm dia	metre	10.00	133.85	1338.50
	25mm dia	metre	12.00	179.65	2155.80
2	Providing and fixing brass bib cock of approved quality				
	15mm nominal bore	each	25.00	191.70	4792.50
3	Providing and fixing brass stop cock of approved quality				
	15mm nominal bore	each	10.00	191.70	1917.00
4	Providing and fixing C.P.pillar cock etc of approved quality.				
	15mm dia	each	10.00	357.15	3571.50
5	Providing and fixing white vitrous china water closet squatting pan (indian type)				
	Lang pattern W.C pan of size 580mm	each	6.00	534.60	3207.60
6	Providing and fixing water closet squatting pan (Indian type)with 100mm iron cast P & S trap 10litre low level white PVC flushing cistern with manually controlled device (handle cover)confirming to IS:7231 with all fittings and fixtures complete including cutting and making good the wall and floors wherever required				
	Orrisa pattern WC pan size 550x440mm with intergral type foot rest	each	2.00	2304.65	4609.30
7	Providing and fixing white vitrous china pedestal type (european type /wash down type) water closet pan.	each	2.00	841.25	1682.50
8	Dismantling w.c pan(Indian /european type)and making the place clear to fix by new pan (Indian / european type)in position including taking out the debris within a lead of 50metre lead.	each	6.00	79.45	476.70
9	Providing and fixing a pair of white vitrous of china foot rest of standerd pattern for squatting pan water closet .				
	250x130x30mm	each	6.00	111.70	670.20

10	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6mm thick hard board backing Oval shape 450x350mm (outer dimension)	each	10.00	504.00	5040.00
11	Providing and fixing wash basin with C.I brackets 15,mm C.P brass pillar taps 32mm C.P brass waste of standard pattern including painting of fittings and brackets cutting and making good the walls wherever required . 550x400mm	each	8.00	1176.10	9408.80
12	Providing and fixing kitchen sink with C.I brackets C.P brass chain with rubber plug, 40mm C.P brass waste complete including painting and fittings and brackets cutting and making good the walls wherever required.(white glazed fire clay kitchen sink of size 600x450x250mm	each	2.00	1793.35	3586.70
13	Providing and fixing gun metal valve with C.I wheel of approved quality with screwed end) 25mm nominal bore	each	3.00	285.50	856.50
14	Providing and fixing bracket for wash basin /sink including taking out bracket and fixing new one etc	each	12.00	246.32	2955.84
15	Providing and fixing PVC low level flushing cistern with manually controlled device (Handle lever) conforming to IS:7231 with all fittings and fixture complete. 10 litre capacity -white	each	8.00	709.75	5678.00
16	Providing and fixing 1st quality ceramic glazed tiles wall conforming to IS:15622(thickness to be specified by the manufacture) of approved make in all colours shades except burgundy ,brown ,green ,black of any size as approved by Engineer In charge in skirting risers of steps and dados over 12mm thick bed of cement mortar 1:3 and jointing with grey cement slurry /@3.3kg per sqm including pointing in white cement mixed with pigment to match the shade complete	sqm	30	556.60	16698.00
17	Providing and laying polished vitrified floor tiles in different sizes (thickness to be specified by the manufacturer)with water absorption, s less than 0.08%and conforming to IS: 15622 of approved make in all colours and shades , laid on 20mm thick cement mortar 1:4(1 cement: 4 coarse sand)including grouting the joints with white cement and matching				

	pigments etc complete . Size of tiles 60x60cm Deduct for not using 20mm thick cement mortar 1:4(1 cement:4 coarse sand) bedding in laying of floor tiles.	sqm	20.00	957.10	19142.00
18	Dismantling old G.I pipes etc 15 to 25mm as per direction of Engineer Incharge	metre	37.00	8.43	311.91
19	Dismantling old tiles laid in cm etc as per direction of Engineer Incharge	sqm	30.00	48.67	1460.10
20	Dismantling floor tiles in cm etc as per direction of Engineer Incharge	sqm	20.00	11.72	234.40
21	Cleaning of sewerline of dia 100 to 150mm by manual means using iron bamboo plats etc complete as per direction of Engineer Incharge	mtrr	1500.00	21.56	32340.00
22	Cleaning of septic tank of size 15.00x4.00m and liquid depth upto 1.5m and down manually by taking out right soil waste,sludges and rubbish like all in or under foul position,including pumping out water as required lead up to 50metre.	each	10.00	3670.00	36700.00
23	Cleaning of manholes including dewatering and taking out sludges ,soils,waste and debris etc complete.	each	200	51.36	10272.00
24	Cleaning of gully trap including dewatering and taking out sludges ,soils,waste and debris etc	each	200.00	24.39	4878.00
25	Dismantling 150mm & down S.W pipe etc complete as per direction of Engineer Incharge	metre	15.00	14.74	221.10
26	Earth work in excavation by mechanical means (hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1;5m depth or 10sqm on plan)including dressing of sides and ramming of bottoms lift upto 1.5m including getting out the excavated soil and disposal of surplus excavated soil as directed within a lead of 50m all kind of soil	cum	2.70	103.40	279.18
27	Providing and laying cement concrete 1:5:10(1cement:5 coarse sand:10 graded stone aggregate 40mm nominal size) upto haunches of S.W pipes including bed concrete as per standerd design. 150mm dia S.W pipes	metre	15.00	255.10	3826.50
28	12mm thick cement plaster finished with a floating of neat cement of mix 1:4(1cement: 4 fine sand)	sqm	30.00	97.90	2937.00

Total 182835.38

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration

Dhanbad.

Name of work:-Repairing of plinth protection and drain in D/VIII type quarters from 1 to 29(except-10 &24)
at Koyla nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/ 942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II

(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:-Repairing of plinth protection and drain in D/VIII type quarters from 1 to 29(except-10 &24)
at Koyla nagar

Name of contractor:-
Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of Repairing of plinth protection and drain of D/VIII type qtr no. 1 to 29(except -10&24) at Koyla Nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	Cement concrete flooring 1:2:4 finished with a floating coat of neat cement including cement slurry but excluding the cost of nosing of steps etc complete 40mm thick with 20mm nominal size stone aggregate	sqm	597.00	192.95	115191.15
2	12mm cement plaster 1:3(1cement:3coarse sand) finished with a floating coat of neat cement.	sqm	91.80	112.80	10355.04
3	foundation and plinth in. 1:6(1cement : 6 coarse sand)	cum	1.00	2007.00	2007.00
4	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50metre lead.	sqm	91.80	8.20	752.76
Total					128305.95

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration

Dhanbad.

Name of work:- Providing and fixing chequered tiles and snowcem of children park and maintenance of CISF main check post at Koyla nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/ 942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED
(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II
(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- Providing and fixing chequired tiles and snowcem of children park and maintenance of
CISF main check post at Koyla nagar

Name of contractor:-
Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/ 942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of chequered tiles snowcem of children park and maintenance of CISF main check post at Koyla nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	Chequered precast cement concrete tiles 22mm thick in footpath & courtyard jointed with neat cement slurry mixed with pigment to match the shade of tiles including rubbing and cleaning etc complete on 20mm thick bed of cement mortar 1:4(1 cement:4 coarse sand) dark shade using ordinary cement	sqm	152.69	454.60	69412.87
2	Finishing wall with acrylic smooth paint of required shade Old work(two or more coat applied @ 1.67 Ltr/10sqm) on existing cement paint surface .	sqm	608.08	36.30	22073.30
3	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade Two or more coats on new work.	sqm	55.48	35.35	1961.21
				Total	93447.39

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration
Dhanbad.

Name of work:- Repairing of fallen down boundary wall of D/IX/23 & C1/IV/25 at Koyla nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/ 942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II

(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- Repairing of fallen down boundary wall of D/IX/23 & C1/IV/25 at Koyla nagar

Name of contractor:-
Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/ 942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of repairing of fallen down boundary wall of D/IX/23 & C2/IV/25 at Koyla nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	Earth work in excavation by mechanical means (hydraulic excavater) manual means in foundation trenches or drains (not exceeding 1;5m depth or 10sqm on plan)including dressing of sides and ramming of bottoms lift upto 1.5m including getting out the excavated soil and disposal of surplus excavated soil as directed within a lead of 50m all kind of soil	cum	18.00	103.40	1861.20
2	Supplying and filling in plinth with Jamuna sand under floors including watering , ramming consolidating and dressing complete	cum	1.20	301.50	361.80
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering 1:4:8(1cement:4 fine sand:8grade stone aggregate 40mm nominal size) All work up to plinth level	cum	2.40	2296.15	5510.76
4	Brick work with F,P.S brick of class designation 50 in foundation and plinth in. 1:6(1cement : 6 course sand)	cum	22.56	2007.00	45277.92
5	Brick work with FPS bricks of class designation 50 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:6(1 cement :6coarse sand	cum	11.53	2315.50	26697.71
6	Brick work 7cm thick with F.PS brick of class designation 50 in cement mortar 1:3(1 cement: 3coarse sand) in superstructure.	sqm	11.04	206.09	2275.23
7	Providing and laying in position cement concrete in retaining walls, return walls (any thickness)including attached pilasters columns , piers, abutments, pillars, posts, struts , buttresses , string or lacing courses ,parapet coping bed, blocks anchor, blocks plain window sills fillets etc up to floor five level excluding the cost of centering shuttering and finishing 1:2:4(1cement: 2courses sand:4 graded stone aggregate 20mm nominal size	cum	0.55	3579.10	1968.50
8	12mm thick cement plaster of mix				

	1:6(1cement : 6 course sand)	sqm	157.20	67.65	10634.58
9	Finishin wall with water proofing cement paint of required shade				
	New work(two or more coats applied @ 3.84kg/10sqm	sqm	157.20	30.80	4841.76
				Total	99429.46

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration

Dhanbad.

Name of work:- Cleaning of drain of sector-D/IX,C1/IV, B/XI and some other drains near shopping complex & guest house at Koyla nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/ 942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10..08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED
(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II
(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- Cleaning of drain of sector-D/IX,C1/IV,B/XI and some other drains near shopping complex & guest house at Koyla nagar

Name of contractor:-
Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of cleaning of drain of sector-D/IX,C1/IV,B/XI and others drains near shopping complex & guest house at Koyla nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	Cleaning of drain ,excavated loose soil,lequid mud taking out debrices etc all along colony,road side incuding disposal of same within a lead of 50metre as per direction of Engineer Incharge.	cum	450	75.80	34110.00
2	Carriage of material by mechanical transport including loading unloading and stacking sludge etc complete	cum	414.00	42.97	17789.58
				Total	51899.58

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration

Dhanbad.

Name of work:-Miscellaneous repair/maintenance work in different quarters at Koyla nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II

(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:-Miscellaneous repair/maintenance work in different quarters at Koyla nagar

Name of contractor:-
Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of repair/maintenance work in different quartrs at Koyla nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	Providing and fixing flat pressed 3 layer particle board medium density exterior grade(Grade I)or graded wood particle board IS:3087marked to frame , backing or studding with screws etc , complete (frames backing or studing to be separatly 12mm thick	sqm	25.16	364.95	9182.14
2	Providing and fixing 30mm thick gamhar wood wire gauge shutter etc as per direction of Engineer Incharge	sqm	1.28	1397.65	1788.99
3	Providing and laying ceramic glazed floor tiles 300x300mm (thickness to be specified bythe manufacture) of Ist quality confirming to IS:15622 of approved make in colours such as white ,Ivory,Grey fume, Red brown, laid on 20mm thick cement mortar 1:4 including pointing the joints with white cement and matching pigment etc complete	sqm	9.83	630.80	6200.76
4	Providing and fixing Ist quality ceramic glazed tiles wall confirming to IS:15622(thickness to be specified by the manufacture) of approved make in all colours shades except burgundy ,bottle ,green ,black of any size as approved by Engineer In charge in skirting risers of steps and dados over 12mm thick bed of cement mortar 1:3 and jointing with grey cement slurry /@3.3kg per sqm including pointing in white cement mixed with pigment to match the shade complete	sqm	12.38	556.60	6890.71
5	Dismantling wall tiles laid in cement mortar in adhesive cutting/ranking old plaster in good shape and cleaning the surface including disposal of unserviceable materials rubbish to the dumping ground within 50m lead .	sqm	12.38	48.67	602.53
6	Providing and fixing 15mm dia C.P.Brass stop cock (concealed)of approved make.etc complete as per direction of engineer Incharge	each	2.00	1195.98	2391.96
7	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6mm thick hard board backing Oval shape 450x350mm (outer dimention)	each	2.00	504.00	1008.00
8	Providing and fixing white vitrous china padestal				

	type (european type /wash down type) water closet pan.	each	1.00	841.25	841.25
9	Extra for using coloured pedestal type W.C pan (european) type (european type)low level cistern of same coloured instead of white vitrous china w.c.pan and cistern.	each	1.00	876.95	876.95
10	Providing and fixing white vitrous china water closet squatting pan (Indian type) Long pattern W.C pan of size 580mm	each	1.00	534.60	534.60
11	Providing and fixing C.P brass shower rose with 15 or 20 mm inlet 150mm diameter	each	2.00	55.80	111.60
12	Providing and fixing brass stop cock of approved quality 15mm nominal bore	each	4.00	191.70	766.80
13	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade Two or more coats on new work. over and under coat of suitable shade with ordinary paint of approved brand and manufacture	sqm	3.08	51.30	158.00
14	Brick work with FPS bricks of class designation 50 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:6(1 cement :6coarse sand	cum	4.23	2315.50	9774.56
15	Finishing wall with water proofing cement paint of required shade Old work(one or more coats applied @2.20kg/sqm) over priming coat of primer applied @ 0.80lter/10s sqm complete including cost of priming coat .	sqm	48.95	27.95	1367.31
16	Half brick masnory with FPS bricks of class of class of designation 50superstructure above in plinth level upto floor V level Cement mortar 1:4(1 cement :4coarse sand	sqm	10.27	289.58	2973.97
17	12mm thick cement plaster of mix 1:6(1cement : 6 course sand)	sqm	1.37	67.65	92.68
18	12mm thick cement plaster finished with a floating of neat cement of mix 1:4(1cement: 4 fine sand)	sqm	7.31	97.90	715.65
19	Cement concrete flooring 1:2:4(1cmnt:2 coarse sand :4graded stone aggregate)finished with a floating coat of neat cement including cement slurry , but excluding the cost of nosing of steps etc compete 40mm thick with 20mm nominal size stone aggregate	sqm	8.61	192.95	1661.30

Total 47939.77

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration

Dhanbad.

Name of work:- Repair /maintenance of qtr.no.D/V/ 3&12 including replacement of damaged wood work under shifting & emergency cases at Koyla nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyna nagar/Jaggiwan nagar - Town Administration ,
Dhanbad.

PART- II

(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- Repair /maintenance of qtr.no.D/V/ 3&12 including replacement of damaged wood work under shifting & emergency cases at Koyna nagar

Name of contractor:-
Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of repair/maintenance of qtr no. D/V/3&12 including replacment of damaged wood work under shifting & emergency cases at Koyla nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	White washing with lime to give an even shade Old work (two or more coats)	sqm	315.00	4.10	1291.50
2	Colour washinhg such as green ,blue or buff to give an even shade Old work (two or more coats)with lime	sqm	575.00	4.87	2800.25
3	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scretches etc.complete.	sqm	575.00	3.20	1840.00
4	Distempering with dry distemper of approved brand and manufacturers (one or more coat)and of required shade on old work to give an even shade	sqm	866.00	12.35	10695.10
5	Removing dry or oil bound distemper, waterr proofing cement paint and the like scraping ,sand papering and preparing the surface smooth including necessary repairs to scratches etc complete	sqm	866.00	4.25	3680.50
6	Applying primer with whiting	sqm	866.00	3.68	3186.88
7	Cleaning of mosaic/marble/concrete flooring using acid surf & soda etc complete as per direction of engineer incharge.	sqm	356	7.83	2787.48
8	Providing wood work in frames of door windows clerestory window and other frames wrought framed and fixed in position Sal wood	cum	0.4	30511.95	12204.78
9	Providing and fixing 40x5mm flat iron hold fast 20cm long and embedding in cement concrete 1:3:6 etc.	each	46.00	48.36	2224.56
10	Providing and fixing ISI marked flush door shutters to IS:2202(Part-I)non decorative type core of block board construction with frame of Ist class hard wood well matched commercial 3 ply veneering with verical grains or cross bands and face veneers on both faces of shutters: 25mm thick (for cupboard)including ISI marked nickel plated bright finished M.S plano hinges with necessary screws.	sqm	2.73	853.05	2328.83
11	Providing and fixing ISI marked flush door shutters to IS:2202(Part-I)non decorative type core of block board construction with frame of Ist class hard wood				

	well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters: 30mm thick including ISI marked stainless steel butts hinges with necessary screws .	sqm	1.70	904.40	1537.48
12	Providing and fixing 30mm thick fully paneled gamhar wood shutter including M.S hinges as per direction of Engineer Incharge.	sqm	1.72	2351.21	4044.08
13	Providing and fixing 32mm thick fully glazed ventilator shutter of gamhar wood with 4cm thick glass panes as per direction of Engineer Incharge complete job.	sqm	0.67	2249.03	1506.85
14	Providing and fixing flat pressed 3 layer particle board medium density exterior grade(Grade I)or graded wood particle board IS:3087marked to frame , backing or studding with screws etc , complete (frames backing or studing to be separately 18mm thick	sqm	8.81	418.40	3686.10
15	Providing and fixing and finishing alumunium handle I.S.I marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc complete 100mm	each	8.00	35.30	282.40
16	Providing and fixing alumunium tower bolt ISI;marked anodised (anodised coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc complete 150x10mm	each	6.00	42.75	256.50
	200x10mm	each	4.00	62.20	248.80
17	Providing and fixing oxidised M.S hasp and staple (safety type) confirming to IS:363 with necessary screws etc complete 90mm	each	2.00	8.85	17.70
18	Providing and fixing M.S.hooks & eyes 150mm long as per direction of Engineer Incharge.	each	4.00	13.52	54.08
19	Easy adjustment of doors, windows, shutters including necessary repair all type of doors, windows, shutters including taking out and refitting the same in position all complete work as per direction of engineer incharge Doors	each	4.00	168.52	674.08
	Windows/shutter	each	11.00	81.05	891.55
20	Half brick masonry with FPS bricks of class of class of designation 50superstructure above in				

	plinth level upto floor V level				
	Cement mortar 1:4(1 cement :4coarse sand	sqm	5.00	289.68	1448.40
21	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering				
	1:2:4(1cement :2coarse sand:4 graded stone aggregate 20mm nominal size)				
	All work up to plinth level	cum	0.03	3257.45	97.72
22	Providing and laying ceramic glazed floor tiles 300x300mm (thickness to be specified bythe manufacture) of Ist quality confirming to IS:15622 of approved make in colours such as white ,Ivory,Grey fume, Red brown, laid on 20mm thick cement mortar 1:4 including pointing the joints with white cement and matching pigment etc complete	sqm	3.12	589.40	1838.93
23	Providing and fixing PVC low level flushing cistern with manually controlled device (Handle lever) confirming to IS:7231 with all fittings and fixture complete.				
	10 litre capacity -white	each	3.00	709.75	2129.25
24	Providing and fixing white vitrous china water closet squatting pan (Indian type)				
	Orissa pattern W.C pan of size 580x440mm	each	1.00	1010.85	1010.85
25	Providing and fixing C.P brass shower rose with 15 or 20 mm inlet				
	100mm diameter	each	3.00	40.40	121.20
26	Providing and fixing C.P brass pillar cock approved quality.				
	15mm dia	each	3.00	357.15	1071.45
27	Providing and fixing 32mm C.P waste for wash basin etc as per direction of Engineer Incharge	each	1.00	60.72	60.72
28	Providing and fixing waste pipe for sink on wash basin including PVC waste fittings complete				
	semi rigid pipe				
	32mm dia	each	1.00	46.80	46.80
29	Providing and fixing brass bib cock of approved quality				
	15mm nominal bore	each	4.00	191.70	766.80
30	Providing and fixing brass stop cock of approved quality				
	15mm nominal bore	each	6.00	191.70	1150.20
31	Proviidng and fixing uplasticised PVC connection pipe with brass unions 45cm length				

	15mm nominal bore	each	6.00	44.75	268.50
32	Providing and fixing white vitreous china wash basin including making all connection but excluding the cost of fittings				
	Flat back wash basin of size 550x400mm	each	1.00	596.20	596.20
33	Providing and fixing 600x450mm bevelled edge mirror of superior glass (of approved quality)complete with 6mm thick hard board gound fixed to wooden cleats with C.P brass screws and washer s complete				
	Rectanglar shape 453x357mm	each	1.00	493.65	493.65
34	Providing and fixing 600x120x5mm glass shelf wutg edges round of supported on anodised alumunium angle frame with C.P brass brackets and guard rail complete fixed with 40mm long screws rawl plugs etc complete				
		each	1.00	216.70	216.70
35	Providing and fixing chlorinated polyvinyl chloride (CPVC) pipes having thermal stability for hot & cold water supply including CPVC plain and brass threaded fittings this includes jointing of pipes & fittings with one step CPVC solvent cement trenching refilling & testing of joints complete as per direction of Engineer in Charge				
	15mm nominal outer dia pipes	mrtre	3.70	97.95	362.41
36	Dismantling door windows and clerestory wondows (steel or wood)shutter including chowkhats , architrave holdfasts etc complete and stacking within 50metres lead				
	of area 3 sq metres and below	each	10.00	54.60	546.00
37	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade				
	Two or more coats on new work.				
	over and under coat of suitable shade with ordinary paint of approved brand and manufacture	sqm	56.00	51.30	2872.80
38	12mm thick cement plaster of mix				
	1:6(1cement : 6 course sand)	sqm	20.50	67.65	1386.82
				Total	72724.90

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration

Dhanbad.

Name of work:- Repair/maintenance including replacement of damaged wood work under shifting & emergency cases in qtr.no.B/II/48 &72 and 86 at Koyla nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/ 942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II

(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- Repair/maintenance including replacement of damaged wood work under shifting
& emergency cases in qtr.no.B/II/48 &72 and 86 at Koyla nagar

Name of contractor:-
Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of repair/maintenance including replacement of damaged wood work under shifting & emergency cases in Qtr.no. B/II/48&72 and 86 at Koyla nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	Providing wood work in frames of door windows clerestory window and other frames wrought framed and fixed in position Sal wood	cum	0.17	30511.95	5187.03
2	Providing and fixing 40x5mm flat iron hold fast 20cm long and embedding in cement concrete 1:3:6 etc.	each	38.00	48.36	1837.68
3	Providing and fixing 30mm thick fully paneled gamhar wood shutter including M.S hinges as per direction of Engineer Incharge.	sqm	3.27	2351.21	7688.46
4	Providing and fixing ISI marked flush door shutters to IS:2202(Part-I)non decorative type core of block board construction with frame of Ist class hard wood well matched commercial 3 ply veneering with verical grains or cross bands and face veneers on both faces of shutters: 25mm thick (for cupboard)including ISI marked nickel plated bright finished M.S plano hinges with necessary screws.	sqm	5.35	853.05	4563.82
5	Providing and fixing 30mm thick gamhar wood wire gauge shutter etc as per direction of Engineer Incharge	sqm	7.7	1397.65	10761.90
6	Providing and fixing fly proof 24SWG wire gauge wiremesh breading 20x12mm complete job as per direction of Engineer Incharge.	sqm	7.60	407.08	3093.81
7	Providing and fixing 32mm thick fully glazed ventilator shutter of gamhar wood with 4cm thick glass panes as per direction of Engineer Incharge complete job.	sqm	0.57	2249.03	1281.95
8	Providing and fixing 32mm thick gamhar wood 2/3 panelled and 1/3 glazed using 4mm thick glass panel complete job as per direction of Engineer Incharge	sqm	8.83	2218.66	19590.77
9	Providing and fixing flat pressed 3 layer particle board medium density exterior grade(Grade I)or graded wood particle board IS:3087marked to frame , backing or studding with screws etc , complete (frames backing or studing to be separatly 18mm thick	sqm	4.61	418.40	1928.82
10	Dismantling door windows and clerestory wondows (steel or wood)shutter including chowkhats , architrave holdfasts etc complete and stacking within 50metres				

	lead				
	of area 3 sq metres and below	each	8.00	54.60	436.80
11	Taking out doors windows and clerestory window shutters (steel or wood)including stacking within 50metres lead				
	of area 3 sq metres and below	each	15.00	21.40	321.00
12	Providing and fixing oxidised M.S hasp and staple (safety type) confirming to IS:363 with necessary screws etc complete				
	90mm	each	3.00	8.85	26.55
13	Providing and fixing ISI marked oxidised M.S handles confirming to IS;4992 with necessary screws etc complete				
	75mm	each	14.00	5.45	76.30
14	Providing and fixing ISI marked oxidised M.S handles confirming to IS;4992 with necessary screws etc complete				
	100mm	each	2.00	7.75	15.50
15	Providing and fixing ISI marked oxidised M.S tower bolt black finished (barral type) with necessary screws etc complete				
	150x10mm	each	8.00	23.40	187.20
16	Providing and fixing ISI marked oxidised M.S sliding door bolt with nuts and screws etc complete				
	250x10mm	each	1.00	69.65	69.65
17	Providing and fixing factory made PVC door frame of size 50x47mm with a wall thickness of 5mm , made out of extruded 5mm rigid PVC foam sheet mitred at corners and joined with 2nos of 150mm long brackets of 15x15mm M.S sequire tube , the vertical door profiles tobe reinforced with 19x19mm M.S squire tube of 19 guage .EPDM rubber gasket weather seal to be provided through out the frame . The door frame to be fixed to the wall using M.S screws of 65/100mm size complete as per manufacturers specification and direction of Engineer In Charge	metre	5.03	353.10	1776.09
18	Providing and fixing to existing door frames 30mm thick factory made panel PVC door shutter consisting of frame made out of M.S tubes of 19guage thickness and size 19mm x19mm for styles and 15x15mm for top and bottoms rail , MS frame shall have a coat of steel primers of approved make and manufacturere ,				

	M.S frame covered with 5mm thick heat moulded PVC C channel of size 30mm thickness 70mm width out of which 50mm shall be flat and 20mm shall be tapered in 45 degree angle on either side forming styles and 5mm thick 95mm wide PVC sheet out of which 75mm shall be flat and 20mm shall be tapered in 45 degree on the inner side to form top and bottom rail and 115mm wide PVC sheet out of which 75mm shall be flat and 20mm shall be tapered on both sides form lock rail. Top and bottom and lock rails shall be provided either side of the panel 10mm thick 20mm wide cross PVC sheet be provided a gap insert for top rail and bottom rail panelling of 5mm thick both side PVC sheet to fitted in M.S frame welded /sealed to styles rails with 7mm thick 15mm wide PVC sheet beading on inner side and joined together with solvent cement adhesive and addl. 5mm thick PVC strip of 20mm width is to be stuck on the interior side of C channel using PVC solvent adhesive etc complete	sqm	1.40	2109.95	2953.93
19	Brick work with FPS bricks of class designation 50 in superstructure above plinth level up to floor V level in all shapes and sizes in				
	Cement mortar 1:6 (1 cement : 6 coarse sand)	cum	0.90	2315.50	2083.95
20	Repair to plaster of thickness 12mm to 20mm in patches of area 2.5sqm and under including cutting in patch in proper shape and raking out joints and preparing and plastering the surface of the walls complete including disposal of rubbish to dumping ground within 50metre lead				
	Cement mortar 1:4 (1 cement : 4 coarse sand)	sqm	5.00	120.70	603.50
21	Grading roof for water proofing treatment with Cement concrete 1:2:4 (1 cement : 2 coarse sand 4 graded stone aggregate 20mm nominal size)	cum	2.15	3314.95	7127.14
22	12mm thick cement plaster of mix 1:4 (1 cement : 4 coarse sand)	sqm	11.10	82.55	916.31
23	Fixed to opening / wooden frames with rawl plugs screws etc	kg	15.30	64.40	985.32
24	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade Two or more coats on new work. over and under coat of suitable shade with ordinary paint of approved brand and manufacture	sqm	97.00	51.30	4976.10
25	Easy adjustment of doors, windows, shutters including				

	necessary repair all type of doors,windows,shuttes including taking out and refitting the same in position all complete work as per direction of engineer incharge				
	Doors	each	6.00	168.52	1011.12
	Wondows/shutter	each	8.00	81.05	648.40
26	White washing with lime to give an even shade Old work (two or more coats)	sqm	540.00	4.10	2214.00
27	Colour washinhg such as green ,blue or buff to give an even shade Old work (two or more coats)with lime	sqm	78.30	4.87	381.32
28	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scretches etc.complete.	sqm	618.30	3.20	1978.56
				Total	84722.97

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost
as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration

Dhanbad.

Name of work:- Miscellaneous repairs/maintenance work in guest house at Koyla nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/ 942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II

(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- Miscellaneous repairs/maintenance work in guest house at Koyla nagar

Name of contractor:-
Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of miscellaneous repair /maintenance work in guest house at Koyla nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	Providing and laying polished vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption, less than 0.08% and confirming to IS: 15622 of approved make in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand) including grouting the joints with white cement and matching pigments etc complete. Size of tiles 60x60cm	sqm	3.63	966.35	3507.85
2	Providing and fixing Ist quality ceramic glazed tiles wall confirming to IS: 15622 (thickness to be specified by the manufacture) of approved make in all colours shades except burgundy, bottle, green, black of any size as approved by Engineer In charge in skirting risers of steps and dados over 12mm thick bed of cement mortar 1:3 and jointing with grey cement slurry /@ 3.3kg per sqm including pointing in white cement mixed with pigment to match the shade complete	sqm	2.00	556.60	1113.20
3	Providing and fixing coloured wash basin with basin mixture and other all materials/fittings as per direction of Engineer Incharge	each	3.00	7507.13	22521.39
4	Providing and fixing wall mixture with telephonic shower etc all complete as per direction of engineer incharge	each	1.00	4872.20	4872.20
5	Providing and fixing health faucet C.P brass etc all complete as per direction of Engineer Incharge.	each	1.00	1029.66	1029.66
6	Providing and fixing 200mm dia C.P brass head shower rose sequire with 15/20mm inlet as per direction of Engineer Incharge.	each	9.00	2372.96	21356.64
7	Providing and fixing 450mm long shower rose etc complete as per direction of Engineer Incharge	each	5.00	1826.75	9133.75
8	Providing and fixing coloured european commode with 10 litre low level PVC flushing cistern with all fittings etc complete	set	2.00	4688.91	9377.82
9	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6mm thick hard board backing				

	Oval shape 450x350mm (outer dimension)	each	2.00	504.00	1008.00
10	Providing and supplying 500mm fancy glass shelf with all fittings etc complete as per direction of engineer Incharge	each	6.00	543.37	3260.22
11	Providing and fixing C.P brass shower rose with 15 or 20 mm inlet 100mm diameter	each	1.00	40.40	40.40
12	Providing and fixing C.P.brass bib cock of approved quality confirming to IS:8931 15mm nominal bore	each	1.00	313.10	313.10
13	Dismantling cement concrete manually by mechanical means including disposal of materials within 50metre lead as per direction of Engineer In charge 1:3:6 or richer mix	cum	2.60	368.45	957.97
14	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering 1:2:4(1cement :2coarse sand:4 graded stone aggregate 20mm nominal size) All work up to plinth level	cum	1.95	3257.45	6352.03
15	Chequered precast cement concrete tiles 22mm thick in footpath & courtyard jointed with neat cement slurry mixed with pigment to match the shade of tiles including rubbing and cleaning etc complete on 20mm thick bed of cement mortar 1:4(1 cement:4 coarse sand) dark shade using ordinary cement	sqm	25.99	454.60	11815.05
16	Finishing wall with water proofing cement paint of required shade Old work(one or more coats applied @2.20kg/sqm) over priming coat of primer applied @ 0.80lter/10s sqm complete including cost of priming coat .	sqm	114.82	27.95	3209.02
				Total	99868.30

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration

Dhanbad.

Name of work:- Emergency repairing of qtr no. A/114,194,229 of A type sector-I at Koyla nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/ 942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED
(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II
(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- Emergency repairing of qtr no. A/114,194,229 of A type sector-I at Koyla nagar

Name of contractor:-
Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of emergency repairing of qtrs A/114,194 & 229 of A type sector-I Koyla nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	Repair to plaster of thickness 12mm to 20mm in patches of area 2.5sqm metre and under including cutting in patch in proper shape and raking out joints and preparing and plastering the surface of the walls complete including disposal of rubbish to dumping ground within 50metre lead Cement mortar 1:4(1cement :4 coarse sand)	sqm	24.50	120.70	2957.15
2	Repairing of damaged balconies slab, chhajja, parapet etc by providing 15mm cement plaster (1:0.5:2) with 10mm stone chipping applying cement slurry on the under layer with 12mm to 20mm thick cement plaster 1:4 in chhajja, balcony, pillar, columns, parapet soffits etc upto height 10m above ground level including double scaffolding system bracing, Runners, connecting with building wherever required with special safety features for workmen etc all complete as per direction of Engineer Incharge.	sqm	3.10	405.80	1257.98
3	Brick work with FPS bricks of class designation 75 in superstructure above plinth level up to floor V level in all shapes and size in Cement mortar 1:4(1 cement :4coarse sand)	cum	0.18	2487.15	447.68
4	White washing with lime to give an even shade Old work (two or more coats)	sqm	318.50	4.10	1305.85
5	Colour washing such as green, blue or buff to give an even shade Old work (two or more coats) with lime	sqm	48.00	4.87	233.76
6	Providing and fixing factory made PVC door frame of size 50x47mm with a wall thickness of 5mm, made out of extruded 5mm rigid PVC foam sheet mitred at corners and joined with 2nos of 150mm long brackets of 15x15mm M.S square tube, the vertical door profiles to be reinforced with 19x19mm M.S square tube of 19 gauge. EPDM rubber gasket weather seal to be provided				

	through out the frame . The door frame to be fixed to the wall using M.S screws of 65/100mm size complete as per manufacturers specification and direction of Engineer In Charge	metre	10.10	353.10	3566.31
7	Providing and fixing to existing door frames 30mm thick factory made panel PVC door shutter consisting of frame made out of M.S tubes of 19 gauge thickness and size 19mm x19mm for styles and 15x15mm for top and bottoms rail , MS frame shall have a coat of steel primers of approved make and manufacture , M.S frame covered with 5mm thick heat moulded PVC C channel of size 30mm thickness 70mm width out of which 50mm shall be flat and 20mm shall be tapered in 45 degree angle on either side forming styles and 5mm thick 95mm wide PVC sheet out of which 75mm shall be flat and 20mm shall be tapered in 45 degree on the inner side to form top and bottom rail and 115mm wide PVC sheet out of which 75mm shall be flat and 20mm shall be tapered on both sides form lock rail. Top and bottom and lock rails shall be provided either side of the panel 10mm thick 20mm wide cross PVC sheet be provided s gap insert for top rail and bottom rail panelling of 5mm thick both side PVC sheet to fitted in M.S frame welded /sealed to styles rails with 7mm thick 15mm wide PVC sheet beading on inner side and joined together with solvent cement adhesive and addl.5mm thick PVC strip of 20mm width is to be stuck on the interior side fo C channel using PVC solvent adhesive etc complete	sqm	3.15	2109.95	6646.34
8	Providing wood work in frames of door windows clerestory window and other frames wrought framed and fixed in position Sal wood	cum	0.067	30511.95	2044.30
9	Providing and fixing 30mm thick fully paneled gamhar wood shutter including M.S hinges as per direction of Engineer Incharge.	sqm	3.35	2351.21	7876.55
10	Providing and fixing 30mm thick gamhar wood wire gauge shutter etc as per direction of Engineer Incharge	sqm	1.7	1397.65	2376.01
11	Providing and fixing 32mm thick gamhar wood 2/3 panelled and 1/3 glazed using 4mm thick glass panel complete job as per direction of Engineer Incharge	sqm	1.70	2218.66	3771.72
12	Providing and fixing ISI marked flush door shutters to IS:2202(Part-I)non decorative type core of block board construction with frame of Ist class hard wood				

	well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters: 35mm thick including ISI marked stainless steel butt hinges with necessary screws.	sqm	1.67	929.95	1553.01
13	Providing and fixing 40x5mm flat iron hold fast 20cm long and embedding in cement concrete 1:3:6 etc.	each	4.00	39.94	159.76
14	Providing and fixing aluminium sliding door bolt I.S.I marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with nuts and screws etc complete 250x16mm	each	3.00	134.10	402.30
15	Providing and fixing aluminium tower bolt ISI;marked anodised (anodised coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc complete 200x10mm	each	10.00	52.00	520.00
	150x10mm	each	8.00	32.15	257.20
16	Providing and fixing and finishing aluminium handle I.S.I marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc complete 100mm	each	10.00	35.30	353.00
	75mm	each	4.00	28.35	113.40
17	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade Two or more coats on new work. over and under coat of suitable shade with ordinary paint of approved brand and manufacture	sqm	22.75	51.30	1167.06
18	Dismantling door windows and clerestory windows (steel or wood) shutter including chowkhats , architrave holdfasts etc complete and stacking within 50metres lead of area 3 sq metres and below	each	4.00	54.60	218.40
19	Taking out doors windows and clerestory window shutters (steel or wood) including stacking within 50metres lead of area 3 sq metres and below	each	3.00	21.40	64.20
20	Providing and fixing fly proof 24SWG wire gauge wiremesh breasting 20x12mm complete job as per direction of Engineer Incharge.	sqm	1.50	407.08	610.62

Total 37902.60

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration

Dhanbad.

Name of work:- Annual maintenance of Ambedkar chowk,Subhas Chowk,martyr chowk,road divider.Rajiv Gandhi chowk,painting of spread breakers& trees stems and some miscellaneous works at Koyla nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/ 942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II

(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- Annual maintenance of Ambedkar chowk,Subhas Chowk,martyr chowk,road divider.Rajiv Gandhi chowk,painting of spread breakers& trees stems and some miscellaneous works at Koyla nagar

Name of contractor:-
Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of Annual maintenance of Ambedkar chowk,Subhas chowk,Martyr chowk, road divider Rajiv Gandhi chowk,painting of speed breaker and tree stems and some misc.works at Koyla nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	Painting with sythetic enamel paint of approved brand and manufachure of required colour to give even shade old work one or more coat	sqm	2767.18	22.85	63230.06
2	Finishing wall with water proofing cement paint of required shade Old work(one or more coats applied @2.20kg/sqm) over priming coat of primer applied @ 0.80lter/10s sqm complete including cost of priming coat .	sqm	841.85	27.95	23529.71
3	Finishing wall with acrylic smooth paint of required shade Old work(two or more coat applied @ 1.67 Ltr/10sqm) on existing cement paint surface .	sqm	570.98	36.30	20726.57
4	White washing with lime to give an even shade Old work (two or more coats)	sqm	2228.41	4.10	9136.48
5	Painting with alumunium paint of approved brand and manufacturere to give an even shade one or more coat on old work	sqm	28.05	18.25	511.90
				Total	117134.73

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration

Dhanbad.

Name of work:- Repairing and maintenance of qtr of sector-VII & VIII under shifting and emergency cases at Koyla nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED
(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II
(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- Repairing and maintenance of qtr of sector-VII & VIII under shifting and emergency cases at Koyla nagar

Name of contractor:-
Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of repairing and maintenance of qtr of sector-VII & VIII under shifting and emergency cases at Koyla nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	White washing with lime to give an even shade Old work (two or more coats)	sqm	1713.00	4.10	7023.30
2	Colour washinhg such as green ,blue or buff to give an even shade Old work (two or more coats)with lime	sqm	877.00	4.87	4270.99
3	Distempering with dry distemper of approved brand and manufacturers (one or more coat)and of required shade on old work to give an even shade	sqm	1783.00	12.35	22020.05
4	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scretches etc.complete.	sqm	877.00	3.20	2806.40
5	Removing dry or oil bound distemper, waterr proofing cement paint and the like scraping ,sand papering and preparing the surface smooth including necessary repairs to scratches etc complete	sqm	535.00	4.25	2273.75
6	Repair to plaster of thickness 12mm to 20mm in patchs of area 2.5sqr metre and under including cutting in patch in proper shape and raking out joints and preparing and plastering the surface of the walls complete including diposal of rubbish to dumping gound wihtin 50metre lead Cement mortar 1:4(1cement :4 coarse sand)	sqm	12.00	120.70	1448.40
7	Providing and fixing white vitrous china water closet squatting pan (Indian type) Orissa pattern W.C pan of size 580x440mm	each	4.00	1010.85	4043.40
8	Providing and fixing white vitrous china padestal type (european type /wash down type) water closet pan.	each	2.00	841.25	1682.50
9	Providing and fixing trap of self cleaning design with screwed down or hinged grating with or without vent arm complete including cost of cutting and making good the walls and floors Sand cast iron S&S as per IS:1729 100mm inlet and 100mm outlet	each	4.00	442.10	1768.40
10	Providing and fixing PVC low level flushing cistern with manually controlled device (Handle lever)				

	confirming to IS:7231 with all fittings and fixture complete.				
	10 litre capacity -white	each	4.00	709.75	2839.00
11	Providing and fixing solid plastic seat with lid for pedestal type W.C pan complete				
	Black solid plastic seat with lid	each	2.00	305.90	611.80
12	Providing and fixing wash basin with C.I brackets 15,mm C.P brass piller taps 32mm C.P brass waste of standerd partern including painting of fittings and brackes cutting and making good the walls wherever required .				
	white vitreous china flat backwash basin size 550x400mm with single 15mm C.P brass pillar tap	each	2.00	1044.90	2089.80
13	Providing and fixing waste pipe for sink on wash basin including PVC waste fittings complete semi rigid pipe				
	Flixible pipe 32mm dia	each	4.00	46.80	187.20
14	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6mm thick hard board backing Rectangular shape 453x357mm	each	2.00	465.10	930.20
15	Providing and fixing brass bib cock of approved quality				
	15mm nominal bore	each	6.00	191.70	1150.20
16	Providing and fixing brass stop cock of approved quality				
	15mm nominal bore	each	3.00	191.70	575.10
17	Providing and fixing C.P.brass approved quality as per direction of Engineer Incharge				
	15mm dia	each	4.00	131.10	524.40
18	Providing and fixing fly proof 24SWG wire gauge wiremesh breading 20x12mm complete job as per direction of Engineer Incharge.	sqm	6.15	407.08	2503.54
19	Providing wood work in frames of door windows clerestory window and other frames wrought framed and fixed in position				
	Sal wood	cum	0.155	30511.95	4729.35
20	Providing and fixing 40x5mm flat iron hold fast 20cm long and embedding in cement concrete 1:3:6 etc.	each	20.00	39.94	798.80
21	Providing and fixing 30mm thick fully panneled gamhar wood shutter including M.S hinges as per direction of Engineer Incharge.	sqm	3.40	2351.21	7994.11

22	Providing and fixing 32mm thick gamhar wood 2/3 panelled and 1/3 glazed using 4mm thick glass panel complete job as per direction of Engineer Incharge	sqm	2.70	2218.66	5990.38
23	Providing and fixing 30mm thick gamhar wood wire gauge shutter etc as per direction of Engineer Incharge	sqm	3.4	1397.65	4752.00
24	Providing and fixing 32mm thick fully glazed ventilator shutter of gamhar wood with 4cm thick glass panes as per direction of Engineer Incharge complete job.	sqm	4.65	2249.03	10457.98
25	Providing and fixing ISI marked flush door shutters to IS:2202(Part-I)non decorative type core of block board construction with frame of Ist class hard wood well matched commercial 3 ply veneering with verical grains or cross bands and face veneers on both faces of shutters: 35mm thick including ISI marked stainless steel butt hinges with necessary screws.	sqm	3.40	929.95	3161.83
26	Providing and fixing ISI marked flush door shutters to IS:2202(Part-I)non decorative type core of block board construction with frame of Ist class hard wood well matched commercial 3 ply veneering with verical grains or cross bands and face veneers on both faces of shutters: 25mm thick (for cup board) including ISI marked nickel plated bright finished M.S plono hinges with necessary screws .	sqm	5.20	853.05	4435.86
27	Dismantling door windows and clerestory wondows (steel or wood)shutter including chowkhats , architrave holdfasts etc complete and stacking within 50metres lead of area 3 sq metres and below	each	4.00	54.60	218.40
28	Taking out doors windows and clerestory window shutters (steel or wood)including stacking within 50metres lead of area 3 sq metres and below	each	11.00	21.40	235.40
29	Providing and fixing alumunium sliding door bolt I.S.I marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with nuts and screws etc complete 250x16mm	each	4.00	134.10	536.40
30	Providing and fixing alumunium tower bolt ISI;marked anodised (anodised coating not less than grade AC 10 as per IS:1868) transparent or dyed to required				

	colour or shade with necessary screws etc complete 150x10mm	each	18.00	42.75	769.50
31	Providing and fixing and finishing alumunium handle I.S.I marked anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade with necessary screws etc complete 100mm	each	10.00	35.30	353.00
	75mm	each	8.00	28.35	226.80
32	Cement concrete flooring 1:2:4 finished with a floating coat of neat cement including cement slurry but excluding the cost of nosing of steps etc complete 40mm thick with 20mm nominal size stone aggregate	sqm	2.00	192.95	385.90
33	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade Two or more coats on new work. over and under coat of suitable shade with ordinary paint of approved brand and manufacture	sqm	46.60	51.30	2390.58
34	Supply and applying one coe primer on wall surface as per direction of engineer Incharge	sqm	535.00	3.67	1963.45
				Total	108148.18

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost
as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration

Dhanbad.

Name of work:- Annual maintenance of shri Shiv mandir,Durga Mandir,Hunuman Mandir,
Sri Ram mandir,Maa Adya Kali mandir,near martyr and Baba Sidhnath Mandir& Hunuman mandir
at Koyla nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/ 942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II

(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- Annual maintenance of shri Shiv mandir,Durga Mandir,Hunuman Mandir,
Sri Ram mandir,Maa Adya Kali mandir,near martyr and Baba Sidhnath Mandir& Hunuman mandir
at Koyla nagar

Name of contractor:-
Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of Annual repair/maintenance of Sri Shiv Mandir,Durga Mandir,Hanuman Mandir, SriRam

Mandir,Maa Adya Kali Mandir, near martyr and Baba Sidhnath mandir,& Hanuman Mandir at Koyla nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	Finishing wall with water proofing cement paint of required shade Old work(one or more coats applied @2.20kg/sqm) over priming coat of primer applied @ 0.80lter/10s sqm complete including cost of priming coat .	sqm	1546.91	27.95	43236.13
2	Wall painting with plastic emulsoin paint of approved brand manufacture of required colour to give an even shade (one or more coat old work)	sqm	71.99	25.85	1860.94
3	Distempering with oil bound washable distemper of approved brand and manufacturere to give even shade old work one or more coat	sqm	744.21	14.90	11088.73
4	Painting with sythetic enamel paint of approved brand and manufachure of required colour to give even shade old work one or more coat	sqm	612.14	22.85	13987.40
5	French spirit polishing one more coat old work One or more coats on old work	sqm	33.64	38.40	1291.77
6	White washing with lime to give an even shade Old work (two or more coats)	sqm	49.73	4.10	203.89
7	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scretches etc.complete.	sqm	816.20	3.20	2611.84
8	Applying one coat of cement primer of approved brand and manufacture on wall surface Cement primer	sqm	816.20	17.20	14038.64
9	Providing and applying plaster of paris putty of 2mm thickness over plastered surface to prepare the surface even and smooth complete.	sqm	9.72	47.20	458.78
				Total	88778.13

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration

Dhanbad.

Name of work:- Annual maintenance of BCCL press on the occasion of Vishwakarma Puja painting white washing & snowcem of flag posts (KNTA,SBI,KNH,& 33KVA substatioin) on t he occasion of Independence day and republic day at Koyla nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/ 942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED
(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II
(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- Annual maintenance of BCCL press on the occasion of Vishwakarma
Puja painting white washing & snowcem of flag posts (KNTA,SBI,KNH,& 33KVA substatioin)
on the occasion of Independence day and republic day at Koyla nagar

Name of contractor:-
Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/ 942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of Annual maintenance of BCCL press on the occasion of vishwkarma Puja, painting white washing, and snowcem of flag posts (KNTA, SBI, KNH, & 33 KVA substation) on the occasion of Independence and Republic day at Koyla nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	White washing with lime to give an even shade Old work (two or more coats)	sqm	310.45	4.10	1272.85
2	Finishing wall with water proofing cement paint of required shade Old work (one or more coats applied @ 2.20kg/sqm) over priming coat of primer applied @ 0.80lter/10s sqm complete including cost of priming coat .	sqm	683.48	27.95	19103.27
3	Painting with sythetic enamel paint of approved brand and manufacture of required colour to give even shade old work one or more coat	sqm	594.49	22.85	13584.10
4	Distempering with dry distemper of approved brand and manufacturers (one or more coat)and of required shade on old work to give an even shade	sqm	836.69	12.35	10333.13
					0.00
				Total	44293.34

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration

Dhanbad.

Name of work:- Internal/external repair/maintenance of Bhartiya vidya Mandir school at Koyla nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II

(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- Internal/external repair/maintenance of Bhartiya vidya Mandir school at Koyla nagar

Name of contractor:-
Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of Internal/external repair/maintenance of Bhartiya Vidya Mandir school at Koyla nagar

Sl.No	Description of work	Unit	quantity	Rate	Amount
1	2	3	4	5	6
1	Removing dry or oil bound distemper, waterr proofing cement paint and the like scraping ,sand papering and preparing the surface smooth including necessary repairs to scratches etc complete	sqm	432.86	4.25	1839.65
2	Distempeing oil bound washable distemper of approved brand and manufacturer to give an even shade New work(two or more coat)over and including priming coat with cement primer	sqm	432.86	41.55	17985.33
3	Colour washing such as green ,blue or buff to give an even shade New work(two or more coats)with a base coat of whitening	sqm	287.09	9.10	2612.52
4	White washing with lime to give an even shade Old work (two or more coats)	sqm	808.30	4.10	3314.03
5	Painting with sythetic enamel paint of approved brand and manufachure of required colour to give even shade old work one or more coat	sqm	392.90	22.85	8977.76
6	French spirit polishing one more coat old work One or more coats on old work	sqm	5.46	38.40	209.66
7	Finishing wall with water proofing cement paint of required shade Old work(one or more coats applied @2.20kg/sqm) over priming coat of primer applied @ 0.80lter/10s sqm complete including cost of priming coat .	sqm	1534.70	27.95	42894.85
8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering 1:2:4(1cement :2coarse sand:4 graded stone aggregate 20mm nominal size) All work up to plinth level	cum	3.54	3257.45	11531.37
9	Repair to plaster of thickness 12mm to 20mm in patchs of area 2.5sqr metre and under including cutting in patch in proper shape and raking out joints and preparing and plastering the surface of the walls complete including diposal of rubbish to dumping gound wihtin 50metre lead cement mortar 1:4(1cement :4 fine sand)	sqm	8.48	114.35	969.69

Total 90334.87

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar-Town Administration

Dhanbad.

Name of work:- renovation of septic tank near III type at Karmik nagar

Place of work:-

Tender notice no and date:-BCCL/TA/CM(C)I/C/Tender/11-12/ 942 dated 01.08.2011

Date and time of submission of tender:- from 10.00AM to 3.00PM on 16.08.2011

Date and time of opening tender:- at 3.30PM on 17.08.2011

Date of issue of tender document:- from 10.08.2011 to 13.08.2011

Name of tenderer:-

Receipt no./date/Amount

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

(A Subsidiary of coal India Limited)

Koyla nagar/Jagjiwan nagar - Town Administration ,
Dhanbad.

PART- II

(TO BE SUBMITTED IN SEPARATE ENVELOPE)

Name of work:- renovation of septic tank near III type at Karmik nagar

Name of contractor:-
Address

N.I.T.reference :-BCCL/TA/Chief Manager(Civil)I/C/Tender/2011-12/ 942 dated 01.08.2011

Date of receipt of tender :- from 10.00am to 3.00pm on 16.08.2011

Date of opening of part-II :- To be communicated later

Documents issued to Tenderers:- Bill of quantity no(pages.....)

SIGNATURE OF ISSUING OFFICER

BHARAT COKING COAL LIMITED

B.O.Q for the work of renovation of septic tank near III type at Karmik nagar

Sl.No	Description of work	quantity	Unit	Rate	Amount
1	2	3	4	5	6
1	Dismantling RCC work manually by mechanical means including stacking of steel bars and disposal of unserviceable material within 50metre lead as per direction of engineer incharge.	7.32	cum	537.55	3934.86
2	Dismantling brick work manually by mechanical means including stacking serviceable material and disposal of unserviceable material within 50m lead as per direction of Engineer In Charge in cemen mortar	6.17	cum	310.75	1917.32
3	Cleaning of septic tank of size 15.00x4.00mm and liqued depth upto 1.5m and down manually by taking out right sub waste,sludge and rubbish like all in under found pushion including pumping out water as required lead upto 50m as per direction of Engineer In Charge	1.00	each	3834.70	3834.70
4	Brick work with F,P.S brick of class designation 50 in foundation and plinth in. 1:6(1cement : 6 course sand)	10.28	cum	2006.99	20631.85
5	12mm thick cement plaster finished with a floating coat of neat cement of mix 1:4(1cement: 4fine sand)	36.00	cum	97.90	3524.40
6	Reinforcement of cement conctret work in beam suspended floors roofs , having slope upto 15"landing balconies shelves chhaja lintels bands plain window sills straircases and spiral stair cases upto floor five level excluding the cost of centering and shuttering finishing and reinforcement with 1:2:4(1 cement :2coarses sand 4graded stone aggregate 20mm nominal size	7.17	cum	3673.85	26341.50
7	Providing and hoisting up to floor five level precast reinforced cement concrete in shelves including setting in cement mortar 1:3(1cement:3coarses sand) cost of required centering shuttering and finishing with neat cement punning on exposed surfaces but excluding the cost of reinforcement with 1:2:4(1 cement :2 coarses sand 4graded stone aggregate 20mm nominal size)	0.12	cum	6840.10	820.81

8	Reinforcement of RCC work including straightening cutting bending placing in position and binding all complete Cold twisted bars	841.00	kg	42.70	35910.70
9	Centering and shuttering including strutting ,propping etc and removal of form work for: suspended floors roofs , having slope upto	67.80	sqm	187.35	12702.33
10	Constructing brick masonry manhole in cement mortar 1:4 RCC top slab with 1:2:4 mix (1 cement :2coarse : 4 graded stone aggregate 20mm nominal size)foundation concrete 1:4:8 and inside (1 cement:4 coarse sand:8graded stone 40mm nominal size)inside plastering 12mm thick with cement plaster 1:3(1cement:3coarse sand)finished with floating coat of neat cement and making channels in cement concrete 1:2:4(1cement:2coarse sand :4graded stone aggregate 20mm nominal size)finished with a floating coat of neat cement complete as per standard design. Inside size 120x90cm and 90cm deep including C.I cover with frame (heavy duty) 560mm internal diameter total weight of cover and frame to be not less than 208kg (weight of cover 108 kg and weight of frame 100kg.				0.00
		4.00	each	15582.10	62328.40
11	Providing and laying and jointing glazed stoneware pipes grade A with stiff mixture of cement concrete mortar in the proportion of 1:1 including testing of joints etc complete 150mm dia	30.50	metre	151.65	4625.32
12	Providing and laying cement concrete 1:5:10(1cement 5coarse sand:10graded stone aggregate 40mm nominal size) up to haunches of S.W pipes including bed concrete as per standard design. 100mm diameter S.W pipe Providing and laying cement concrete 1:5:10(1cement 5coarse sand:10graded stone aggregate 40mm nominal size) up to haunches of S.W pipes including bed concrete as per standard design. 150mm diameter S.W pipe	30.50	metre	255.10	7780.55
13	Excavating trenches of required width for pipes cables etc including excavation for sockets and dressing of sides ramming of bottoms depth upto 1..50m including getting out the excavated soil and then returning the soil as required in layers not exceeding 20cm in depth including consolidating each deposited layer by ramming watering etc and disposing of surplus excavated soil				

	as directed within a lead of 50m				
	Pipes cables etc exceeding 80mm dia but not exceeding 300mm dia	30.50	metre	115.05	3509.02
14	Earth work in excavation by mechanical means (hydraulic excavater) manual means in foundation trenches or drains (not exceeding 1;5m depth or 10sqm on plan)including dressing of sides and ramming of bottoms lift upto 1.5m including getting out the excavated soil and disposal of surplus excavated soil as directed within a lead of 50m all kind of soil	12.74	cum	103.40	1317.31
15	Reinforcement of cement concretet work in beam suspended floors roofs , having slope upto 15"landing balconies shelves chhaja lintels bands plain window sills straircases and spiral stair cases upto floor five level excluding the cost of centering and shuttering finishing and reinforcement with 1:2:4(1 cement :2coarases sand 4graded stone aggregate 20mm nominal size stair cases upto floor five level excluding the cost of centering and shuttering finishing and reinforcement with 1:2:4(1 cement :2coarases sand 4graded stone aggregate 20mm nominal size	1.10	cum	3673.85	4041.23
		1.10	cum	3673.85	4041.23
16	Centering and shuttering including strutting ,propping etc and removal of form work for: Lintals beams, plinth girders ,bressmers and cantilevers	8.78	sqm	162.65	1428.05
				Total	192837.41

Chief Manager(Civil)KNTA/JNTA

I/we/am/are ready to execute the work on(in ward)..... above/below the estimated cost as above,

Signature of tenderer)

