



**BHARAT COKING COAL LIMITED**  
(A Subsidiary of Coal India Limited)

**Bhuli Town Administration**

**Bhuli : Dhanbad- 828104**  
PHONE NO. 0326-2340420, 2340341

Ref.No.BCCL/BTA/Bhuli/2011/203

Dated -21/10//2011.

**QUOTATION NOTICE.**

:- Sealed Quotation on Percentage Rate Above or Below basis are invited from the reputed contractors for the following works and the same will be received from **11.00 A.M. to 3.00 P.M. on 27.10. 2011** and opened on **12.00 Noon on 28.10 2011** at the office of the Area Manager ,BTA in the presence of intending tenderers or their authorized representatives. B.O.Q. for the job can be obtained from the office of the Area Manager ,BTA during working hours **ON 24.10..2011**. The Quotation is also available on Website <http://bccl.gov.in> and can be downloaded. The other documents such as General terms & conditions and responsibility of the contractors, additional safety measures etc. also can be seen at the office of A.M.(BTA),Bhuli Town Admn.,Bhuli on Any working day which will be applicable to the contract . The details of works are given below

Sl.No	Name of work	Est.Cost.Rs.	Earnest Money Rs.	Time of completion
1.	RENOVATION OF BROKEN STAIR CASE SYSTEM IN QTR.NOS. D/XB/ 66 TO 70 AT D BLOCK,BHULI.	47,754.00	478/-	1 MONTH.

No materials will be issued by the department for this work. The quotation to be submitted in single part. No tender without Earnest Money will be accepted. The Draft of Earnest Money will be after the date of quotation.

The tenderers have to submit Permanent Account Number of Income Tax (PAN NO.) & Tin No.

**DISTRIBUTION:**

1.GM© CED K.NAGAR 2. CHIEF MANAGER © CED K.NAGAR  
3. G.M.(ADMN) K.BHAWAN 4.FM(BTA) 5. G.M.(SYSTEM)K.BHAWAN 6.I/C CISF  
KOYLA BHAWAN 7 S.E.(C) BTA 8.CASHIER,BTA 9.NOTICE BOARD,BTA.

Dy.CE(C), BTA



**BHARAT COKING COAL LIMITED**  
(A Subsidiary of Coal India Limited)

**Bhuli Town Administration**

**Bhuli : Dhanbad- 828104**  
PHONE NO. 0326-2340420, 2340341

**BILL OF QUANTITY FOR THE WORK OF RENOVATION OF BROEN STAIR CASE SYSTEM IN  
QTR.NO.D/XB/66 TO 70 AT D BLOCK,BHULI.**

SL .NO	ITEM	QTY/UNIT	RATE RS.	AMOUNT RS.
1.	Dismantling of RCC work I & removing of surplus materials. From site.	0.50 cum	537.55/cum	268.77
2.	Dismantling brick work in cement mortar.	1.0 cum	310.75/cum	310.75.
3.	Earth work in cluding in foundation.	4,0 cum	103.40/cum	434.28
4.	P & Laying cement concrete 1:4:8 in foundation.	0.70 cum	2296.15	1607.30
5.	Brick work with C.D. 50 brick in cement mortar 1:6 in F & plinth.	3.25 cum	2007.00	6522,75
6.	Brick work with C D 50 brick in cement mortar 1:6 in S.Str.	12.54 cum	2205.05	27651.32
7.	Half brick work with cD – 50 brick in cement motar 1:4 in S.Str.	15.0 sqm	258.03	3870.45
8.	12mm th. Cement plaster 1:4	61.0 sqm	77.55	4730.55
9.	Laying neat cement punning.	11.0 sqm.	21.40	235.40
10.	12mm th. Cement plaster. (1:6) .	18.0 sqm	67.65	1217.70
1.1	12mm th. Cement plaster 1:4 + Neat ce,ment punning.	8.0 sqm	70.90	783.20
12..	White washing on old work.	18.0 sqm.	6.75	121.50

TOTAL RS. 47754.00