

BHARAT COKING COAL LIMITED

SIJUA AREA.

Ref. No : GM/SA/Plg./2103/2011

Dated : 02.07.2011

NOTICE INVITING TENDER

Sealed Tenders on percentage rate basis in two parts (Part-I & Part-II) are hereby invited from experienced and eligible contractors for the following work :-

Sl. No.	Name of work & Location	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender paper (in Rs.)	Time of Completion
1.	Construction of 3 Nos. ventilation stoppings and repairing of 8 nos. of old ventilation stoppings at MAP 3 seam Tetulmari.	1,03,681.50	1037.00	100.00	Two Months
2.	Construction of 5 Nos. ventilation stoppings and repairing of one ventilation stoppings at Dev. Dist. Of 2 seam bott. at PST-2, Tetulmari.	98,892.58	989.00	100.00	Two Months
3.	Construction of 3 Nos. ventilation stoppings at IV seam (top) at 7/8 incline Mudidih.	52,714.25	527.00	100.00	One Month

The Tender will be received separately in two sealed covers in Part-I and Part –II on 18.07.2011 from 10:00 a.m. to 3:00 p.m. in Tender Box kept at :-

- i) Office of the undersigned.
 - ii) Office of CISF, Post Sijua Area.
 - iii) Office of CISF Post, near Koyla Bhawan gate, Koyla Nagar, Dhanbad.
- [1] (a) Part –I i.e. Technical/Commercial Bid should contain the proof of credentials, earnest money deposit, Sale Tax Clearance Certificate/VAT & PAN. The Part –I will be opened on 22.07.2011 at 3:30 P.M. in the presence of the tenders or their authorized representatives.
- (b) Part –II i.e. Price Bid, containing the Tender Documents issued to the tenderers rate will be furnished in figure and words will be opened by the Tender Committee only on acceptance of the Part –I Bid.
- [2] The Tender paper can be had from the office of the undersigned on written request on any working day from 12.07.2011 to 14.07.2011 on payment of requisite cost as indicate above to be deposited in cash with associate finance at Sijua Area.

ELIGIBILITY CRITERIA :

The intending tenderers must have in the name, experience and having successfully completed similar works during last (Seven) years ending, last day of month previous to the one in which Bid Application are invited i.e. eligibility period should be other of the following :-

- (a) Three similar completed works each costing not less than the amount equal to 40% of the estimated cost.

OR

- (b) Two similar completed work each costing not less than amount equal to 50% of the estimated cost.

OR

- (c) One similar completed work costing not less than the amount equal to 80% of the estimated cost.

Contd...pg/2

N.B : Similar completed works means civil construction works successfully completed in underground mine.

- 3) The tenderers must have average annual financial turn over civil works during last three years ending 31st March of previous financial year i.e. in 2008-09, 2009-10 & 2010-11 should be least 30% of the estimated cost.
- 4) Rate to be quoted in % above/below of the estimated cost both in figure and words in BCCL prescribed forms issued to tenderers.
- 5) The contractor have to acquainted with the side condition.
- 6) All Taxes as applicable will be born by the Contractor.
- 7) The tenderers have to submit their name of Bank, name of Branch & Bank A/c number.
- 8) The Earnest Money to be deposited in cash with associated finance at Sijua Area or in the form of Demand Draft only in favour of Bharat Coking Coal Ltd., DHANBAD, Earnest Money bears no interest and may be refund only to the unsuccessful tenderers in due course on completion of formalities.
- 9) Tenderers have to fully acquaint and satisfy themselves with the NIT & side conditions, drawing, estimates etc. before submitting their tenders.
- 10) All other terms and conditions of general NIT Rules of BCCL and/or other authorities/statutory bodies as applicable from time to time.
- 11) Validity of Tender shall be 120 days from the date of opening of the Price Bid or revised Bid if any.
- 12) The management of BCCL reserves the right to reject any or all the tenderers without assigning any reasons what-so-ever or to split up and distribute the work amongst the tenderers.
- 13) No material shall be issued by the department.
- 14) No Tender will be issued or submitted by postal means.
- 15) Issuance of Tender Documents does not mean that the party is considered qualified.
- 16) Conditional Tenders will not be accepted.
- 17) In case of any injury/accident it will be the responsibility of the Contractor to pay all legal dues their workers.

**Area Manager (Plg.)
Sijua Area**

c.c.to : All CGM/GMs Area- I to 12, Block-II, E/Jharia & W/Jharia.

c.c.to : A.G.M / A.F.M., Sijua Area.

c.c.to : A.M. (System), Sijua Area – along with soft copy and forwarding letter for uploading in BCCL's website.

c.c.to : Project Officers, all units of Sijua Area.

c.c.to : Inspector CISF, Koyla Bhawan.

c.c.to : Notice Board. Sijua Area.

Bill of Quantity for the work of “Construction of 3 Nos. ventilation stoppings and repairing of 8 nos. of old ventilation stoppings at MAP 3 seam Tetulmari.”

Sl. No.	Particulars of the work	Unit of Qnty.	Quantity	Rate	Amount (in Rs.)
1	Recess cutting in coal.	cum	13.70	152.60	2090.62
2	Brick work in s/s.	cum	36.91	2137.96	78903.55
3	12mm thick plaster.	cum	158.39	67.65	10715.08
4	Loading unloading				
a)	Bricks	nos.	17786.00	408.61	7267.59
b)	Sand	cum	9.750	218.93	2134.36
c)	Cement	bag	27.50	93.46	2570.15
				Total (Rs.)	1,03,681.50

Bill of Quantity for the work of “Construction of 5 Nos. ventilation stoppings and repairing of one ventilation stoppings at Dev. Dist. Of 2 seam bott. at PST-2, Tetulmari.”

Sl. No.	Particulars of the work	Unit of Qnty.	Quantity	Rate	Amount (in Rs.)
1	Recess cutting in coal.	cum	18.875	152.60	2880.32
2	Brick work in s/s.	cum	37.982	2314.55	87911.23
3	12mm thick plaster.	cum	107.950	67.65	7302.81
4	White washing two coats	sqm	107.950	6.75	728.66
5	Loading unloading	cum	37.982	11.05	419.70
6	Carriage of materials	cum	37.982	3.35	127.23
7	Supply of Labour	Nos.	45.000	138.45	6230.25
				Total (Rs.)	98,892.58

Bill of Quantity for the work of “Construction of 3 Nos. ventilation stoppings at IV seam (top) at 7/8 incline Mudidih.”

Sl. No.	Particulars of the work	Unit of Qnty.	Quantity	Rate	Amount (in Rs.)
1	Recess cutting in coal.	Cum	7.16	152.60	1092.61
2	Brick work in p&f.	Cum	8.620	2008.13	16596.17
3	Brick work in s/s.	Cum	12.20	2316.65	28263.13
4	12mm thick plaster.	Cum	75.60	67.65	5114.34
5	Cleaning of site.	Cum	9.45	33.35	317.04
6	Loading unloading				
a)	Bricks	nos.	10311	79.53	820.03
b)	Sand	Cum	10.95	42.61	466.57
c)	Cement	Bag	40.00	1.23	49.36
				Total (Rs.)	52,714.25