

Bharat Coking Coal Limited
Chanch Victoria Area.

Ref.No.E&M/XII/BCCL/NIT/11-12/ 373

Date:- 12.6.11
13

Notice Inviting Tender

Sealed tenders are invited from experienced and bonafide Contractor / Agency for the under noted work. The tender should be submitted in two part, that is, Part I Containing Tech-Commercial bid and Part-II Containing Price bid, Part- I and Part-II envelope must be super-scribed and sealed. Sealed Part I & Part II envelope must be sealed in a third envelope.

Tenders must reach the office of the undersigned latest by 12.7.11 upto 1.00 P.M. and Tech-Commercial bid will be opened on the same day at 3.00 P.M.

Sl No.	Description of work.	Tender cost(Rs)	Estimated cost(Rs)	Earnest money(Rs)	Time of completion
--------	----------------------	-----------------	--------------------	-------------------	--------------------

	Renovation of existing 3 phase 350 Volts overhead line from Area Guest House to Dishargarh (Incl. colony under Begunia project.	Rs.114/-	Rs.3,72,050/-	Rs.3,720/-	25 days
--	---	----------	---------------	------------	---------

(Non-refundable)

(Tender issue upto 11.7.11

Terms & Conditions:-

1. Tender paper can be obtained from the office of the undersigned on any working day on production of money Receipt for the Cost of Tender paper (Non-refundable).
2. Earnest money as mentioned above should be deposited either in the form of Bank draft drawn in favour of BCCL,A-XII, payable at Barakar or may be deposited in Cash with Finance Dept., upto 1.00 P.M. on week days and money receipt in original is to be submitted alongwith the offer, without E. Money no tender will be accepted.

3. Other Requirements :-

- (a) PAN CARD (ZEROX) (b) VAT (Upto date)(c) E.Money Receipt(in original)
- (d) Time of completion(e) Validity of Tender should be 120 days from the date of opening of price bid (f) Guarantee period minimum six months
- (g) Valid Contractor Licence with Supervisory certification for power line jobs applicable, (H.T/L.T as applicable)..(h) Service registration copy(i) Deed of Partnership, Residential proof and proof of commencement of business.(j) All documents should be self attested with date & seals.
- (k) Bank A/c detail alongwith IFSC/RTGS CODE Bank name, Branch
- CSB A/c no and A/c Type to be submitted along with quotation.

Contd.-page-2-

(K) Desirable Experience Credential.

The intending tenders must have in his name and experience and having successfully completed **Electrical** work in BCCL or any other public sector undertaking or Govt. firm during last 7 yrs ending last day of the month previous to the one in which bid application are invited, should be either of the following :-

- i) Three similar completed work each costing not less than the amount equal to 40% of the estimated cost. Or.
 - ii) " TWO" similar completed works each costing not less than the amount equal to 50% of the estimated cost. Or
 - iii) One similar completed work costing not less than the amount equal to 80% of the Estimated cost.
4. 10% Security money including earnest money will be deducted from the final bill till completion of Guarantee period.
 5. Please send authorised representative for Tender paper collection etc.
 6. Management reserves the right to accept or reject the tender or part there of without assigning any reason whatsoever.
 7. Quotation must be needly Typed

Area Manager (E&M)
C/V Area.

Area Manager (E & M)
CV Area-XII. BCCL
Bavakar

Distribution:-

1. P.M.(Adm.), C.V. Area for display in Notice Board.
2. All A.M.(E&M), A-I to XI.
3. All Colly. Eng. (T&T), C/V Area.
4. Addl.G.M., C/V Area.
5. A.F.M., C/V Area.
6. Cashier, C.V. Area, for cost paper/E.Money.
7. Tender File.
8. C.G.M. (E&M), BCCL, H/Q Koyla Bhawan, Dhanbad
9. The G.M. System/publication, BCCL HQ, Koyla Bhawan for uploading in Company's website/newspaper publication.
10. Chief Vigilance officer, BCCL H.Q. Koyla Bhawan, Dhanbad.

Office of the General Manager
Bharat Cooking Coal Limited
(A Subsidiary of Coal India Limited)
Chanach Victoria Area-XII.

TENDER PAPER

NIT No. E&M/XII/BCCL/NIT/11-12/373 Date 22/23.06.2011.

Name of Work :- Renovation of existing 3 phase 550 volts Overhead line from
Area Guest House to Dishergarh Colony under Begunia Project.

Sl.No.	Description of Job.	Quantity.	Rate(Rs.)	Amount(Rs)
01.	Erection of Pole by earth cutting & refilling etc. Pole up to 11 meter but not exceeding 13 meter (Pole supply by BCCL) and erection of 8 meter long PCC Pole including transportation from Colliery store to working site.	11 Nos.		
02.	Supply of cement , sand & stone chips for cement 3 coarse sand, 6 graded nominal size stone chips 1.5 cum in each Pole.	11 Nos.		
03.	Supply & erection of 19/20 mm dia stay set by earth cutting with cement concreting with supply of cement, stone chips, sand including stay wire, stay insulator complete set.	24 Nos.		
04.	Supply ,fabrication ,erection & painting of Iron materials such as cross arms, cradle guard bracket, as suitable size clamp, nuts, bolts washer etc.	770 Kg.		
05.	Supply & erection of shackle insulator 75 x 90 mm dia with GI hardware.	72 Nos.		
06.	Erection ,laying & stringing of ACSR conductor 3 ph. 1 neutral(ACSR DOG) sag as per rule including binding.	1306 Kg.		
07.	Dismantling of ACSR Rabbit conductor, cross arms, MS bracket ,GI wire etc.	1560 Kg.		
08.	Supply & erection of earth wire by 7/16 SWG GI wire for continuous running earth.	1100 meter.		
			Total	

Cont. Page No. 02

[Signature]
22/6/11
Area Manager (E & M)
Area-XII BCCL
Barakpur

Signature of
Contractor with
Seal & date.

Office of the General Manager
Bharat Cooking Coal Limited
(A Subsidiary of Coal India Limited)
Chanach Victoria Area-XII.

TENDER PAPER

Page No.02

Sl.No.	Description of Job. B/F	Quantity.	Rate(Rs.)	Amount(Rs.)
09.	Supply & erection of cradle guard wire with 8 SWG GI wire for road & domestic colony .	350 meter.		
10.	Supply & erection of 550 volt grade Lighting arresstor complete with termination.	02 Nos.		
11.	Making earth pit by earth cutting with refilling by charcoal, salt, bentonyte soil etc. as per IE rule.	06 Nos.		
12.	Supply & erection of Pole mounting kit for cable termination.	04 Nos.		
13.	Supply & erection of 550 volt grade 3 phase , 4 Pole 200 Amps capacity main switch with cable connection.	02 Nos.		
14.	Testing & commissioning of over head line after completion of entire job including trimming the branches of tree etc.	LS.		
15.	Painting of 11 meter long steel tubular Pole by one coat of primer & two coat of Al. paint after necessary rubbing & cleaning the surface of the Pole.	11 Nos.		
16.	Dismantling & transportation dismantled Pole from site to colliery store.	11 Nos.		
			Grand Total	

(Rupees :-
.....)

Issuing authority
Area Manager(E&M)
C.V.Area-XII,BCCL

23/6/11
Area Manager (E & M)
C.V. Area-XII BCCL
Barakur

Signature of
Contractor with
Seal & date.