

**Office of the General Manager  
Bharat Coking Coal Limited  
(A subsidiary Of Coal India Limited)  
Chanch Victoria Area-XII**

Ref.No.:E&M/XII/BCCL/NIT/11-12/ 707

Date: 19-08-11

**Notice Inviting Tender**

Sealed Tenders are invited from Licensed , Experienced and Bonafide Electrical contractors in Two Parts i.e. Technical Bid as Part-I and Price Bid as Part-II. Both Part of the Bid has to be wax sealed separately and should be wax sealed in a third envelope super scribing the nature of bid in each envelope and the bids for the reference as above to be submitted.

The sealed bids must has to reach in the office of the undersigned on or before 06 - 09 - 11 up to 1 P.M. in the Tender Box. No tender will be accepted after the date and time. Only the Technical Bids will be opened on the same day at 4 P.M. in presence of the intending bidders.

Sl. No.	Name Of Work	Estimated Cost Rs.	Tender Cost Rs.	Earnest Money Rs.	Time of Completion
1.	Erection of 440 Volt O/H Line From NLOCP New Sub-Stn. to JOCP Project Colony Under Laikdih Colliery.	3.10 Lacs	114/- Inc. VAT (Non-Refundable)	3,105/- (Refundable)	30 days only.

**Terms & Conditions :-**

1. Tender Paper can be obtained from the office of the undersigned on any working day except Sunday and holidays from 26-08-11 to 05-09-11 on production of tender cost cash money receipt issued by the Cashier, Finance Department, BCCL C/V Area-XII or demand draft of any nationalized bank in favour of BCCL, Area-XII ( Payable at Barakar ). No Tender Paper will be issued on 06-09-11. Earnest Money can also be deposited / submitted in the similar manner and no cash Earnest Money will be accepted on 06-09-11. Original cash receipt for Earnest Money is to be deposited with the technical bid. Without Earnest Money no Tender will be accepted and is to be treated as cancelled. Tender documents can also be downloaded from our company's website [www.bccl.cmpdi.co.in](http://www.bccl.cmpdi.co.in) but cost of the tender document is to be submitted along with bid document by Bank Draft.
2. The technical bid is to be incorporated with valid Electrical Contractors License Of the respective State Jurisdiction for the Site of Work, Supervisory License For O/H Lines , VAT registration, Pan Card, Service Tax Registration, No Relation Certificate ( Declaration of No Relative Employees Working in BCCL ), Past experiences, Deed of partnership / proprietorship, Letter of Credit From Banks, List of Tools and Plants ,Company's Profile , and Earnest Money.
3. **Technical Parameters** ; The intending Bidders must have in their name having successfully completed the similar nature of work in Government /Public Sector Undertaking in last 7 years ending with the last day of the month previous to the one in which bid applications are invited should be as follows :-

contd. on pg.- 2

**Office of the General Manager  
Bharat Coking Coal Limited  
(A subsidiary Of Coal India Limited)  
Chanch Victoria Area-XII**

- (i) Three similar completed works each costing not less than the amount equal to 40% of the estimated cost. Or
- (ii) Two similar completed works each costing not less than the amount equal to 50% of the estimated cost. Or
- (iii) One similar completed work costing not less than the amount equal to 80% of the estimated cost.

**SIMILAR NATURE OF WORK MEANS :- COMMISSIONING / INSTALLATION  
OF 1.1 KV GRADE OVERHEAD LINE WORKS.**

- 4. 10% security money including the Earnest Money will be withheld for a defect liability/guarantee period of six months from the date of handing over.
- 5. The offer of the intending bidders should be valid for 120 days.
- 6. All taxes/levies will be applied/charged upon bidders as per company's rule.
- 7. All safety wears, tools and tackles has to be provided to the workmen is the sole responsibility of the intending bidder.
- 8. The Tender Paper will be issued to authorized signatories of the firm only and in any case no unauthorized agents will be entertained.
- 9. Management reserves the right either to accept or reject the entire tender or part thereof/split up the work without assigning any reason whatsoever.

**Area Manager,E&M  
BCCL, C/V Area-XII.**

**Distribution :-**

- 1. Notice Board, BCCL, C/V Area-XII for display.
- 2. All CGM/GM/AM (E & M) – Area - I to Area – XII.
- 3. AFM, AGM & Cashier, BCCL, C/V Area-XII.
- 4. CGM (E & M), BCCL HQ, Koyla Bhawan, Dhanbad.
- 5. Chief Vigilance Officer, BCCL HQ, Koyla Bhawan, Dhanbad.
- 6. The General Manager ,System/Publication, BCCL HQ, Koyla Bhawan, Dhanbad.  
(For Uploading in Company's website/Newspaper Publication)
- 7. All Colliery Engineer (E & M), BCCL, C/V Area-XII.
- 8. Tender File.

Name Of Work :- Erection of 440 Volt O/H Line From NLOCP New Sub-Station to JOCP Project Colony Under Laikdih.

NIT Ref.No.: E&M / XII / BCCL / NIT / 11-12 / 707 dtd.19-08-2011.

<u>Sl.No.</u>	<u>Description of Job</u>	<u>Quantity</u>	<u>Unit Rate(Rs.)</u>	<u>Amount (Rs.)</u>
01.	Erection of pole Tubular/PCC above 10 Mtrs but not exceeding 12 Mtrs incl. Pole Pit digging & Cement Concreting as reqd.(Pole BCCL Supply)	14 Nos	Each	
02.	Supply of cement, sand and stone chips for cement concreting 1:3:6(1 Cement, 3 Coarse Sand, 6 Graded Stone Chips aggregate 40 mm nominal size)1.5cum	14 Nos	Each	
03.	Supply & Erection of Galv. Stay Set with Earth digging as reqd. with 19/20 mm dia x 1.8 mtrs. long stay rod, anchor plate of size 45 cm x 45 cm x 7.5 mm thick thimbles comp. incl. supply of cement, sand, stone chips for its concreting with G.I. stay wire, Stay/Guy Insulator etc.	20 Nos.	Each	
04.	Supply, Fabrication, Erection & Painting from red oxide of iron and steel materials such as cross arms bracing, various sizes of clamps incl. suitable size nut, bolts, washer etc.	750 Kgs.	Kg	
05.	Supply & Erection of Earth continuous earth wire from 7/16 SWG/8 No.G.I. wire for earth continuity.	800 Mtrs..	Mtr	
06.	Laying & Stringing of AAAC/ACSR Rabbit / Weasel Conductors with Sag. Incl. jump ring and binding etc.( Conductor BCCL Supply) Erection =651 Kgs		Kg	
07.	Supplying & Erection of 1.1 KV Pin / Shackle insulator comp. with large steel head G.I. pin, nuts, washers, etc. as reqd.	72 Nos.	Each	
08.	Transportation of poles & Conductors From the Stores to W/Site as reqd.	14 Nos	Each	

<u>Sl.No.</u>	<u>Description of Job</u>	<u>Quantity</u>	<u>Unit Rate(Rs.)</u>	<u>Amount (Rs.)</u>
09.	Supplying & Erection of 3 pcs Non-Linear resistor type lightning arrestor suitable for 3 wire, 1.1 KV O/H Lines with rated voltage .12 KV (rms) with a nominal discharge current rating of .5 KA and comp. with Galv. Clamping arrangement, G.I. bolts, Nuts, Washers, as reqd.	2 Set	Each	
10.	Ear thing as per I.E. rule with earth cutting and refilling by supplying salt, charcoal, and sand G.I. Perforated pipe of 50 mm dia 3 Mtrs. long with earth electrode duly welded at the bottom.	4 Nos	Each	
11.	Making of cradle guard by cross lacing of 8 No. G.I. wire at the sections form pole to pole as reqd for safety.( For Road / House / Pond Crossing)	200 Mtrs	Mtr	
12.	a) Dismantling of old PCC/Tubular /MS Rail poles at location embedded in cement concrete.	9 Nos	Each	
	b)Dismantling of O/H Lines comprising aluminum conductor G.I. wires, Cross Arms, Insulators etc.	500 Kg.	Kg	
	c) Handling of wires including making coils and transporting the same by hand Pulling cart.	L.S.		
	Check Survey, pit making, making approach Road & OBR cleaning, Tree cutting, Corridor Cleaning for the O/H line.	L.S.		
Total				Rs.
Add Service Tax @ 4.12% on Total				Rs.
Grand Total				Rs.

Amount In Words Rupees

Issuing Authority  
Dy.G.M.(E&M)  
BCCL,C/V Area-XII

Signature of the Contractor  
With Date And Seal