



## BHARAT COKING COAL LIMITED

(A Subsidiary of Coal India Limited)  
Office of the General Manager, Katras Area  
P.O. Sijua Distt. Dhanbad.

Ref. No. BCCL/GM/IV/Civil/ Quotation/11-12/4457

Dated: 08.11.2011

### QUOTATION NOTICE

Sealed QUOTATION is invited in percentage rate above/below basis in single part from experienced and bonafide resourceful civil contractors for the following civil works :-

<u>Sl. No.</u>	<u>Nature of Job &amp; location</u>	<u>Estimated Cost</u>	<u>Earnest Money</u>	<u>Time of Completion</u>
1	Repairing 5 units quarters at E.S.Section of Salanpur Colliery under Katras Area.	₹43,108.31	₹431/-	15 Days
2	Repair maintenance of 3 units quarters at Latail Dhowra under Salanpur Colliery.	₹25,116.17	₹251/-	15 Days
3	Repair maintenance of 5 units quarters at 8 no. colony of Salanpur Colliery.	₹40,346.89	₹403/-	15 Days
4	Construction of pump foundation at 10 & 8A seam (3nos.) at KCC under Katras Area.	₹31,038.63	₹310/-	15 Days

### Date and time of receipt/opening of Quotation

- a) The quotation will be received on **29.11.2011** from 10.00A.M. to 3.00 P.M. in tender box kept at
- Office of Asstt.Commandant,CISF. Camp,Angarpathra
  - CISF Post, near Koyala Bhawan gate,Koyala Nagar, BCCL,Dhanbad in Box marked Katras Area.
  - CISF Post, Sijua Area V in tender box marked Katras Area,
  - CISF Post, Govindpur Area-III in tender box marked Katras Area,.
- b) The quotations received will be opened on **01.12.2011** at 4.00 P.M. in the office of the Area Civil Engineer, Katras Area.

All the materials and equipments required for this work will be responsibility of the contractors.

Contractors have to abide by the Labour regulation /abolition Act. Govt. of India adopted by BCCL time to time.

contd...pg2

Conditional quotations will be out-right rejected.

Late or delayed quotations will not be accepted.

Quotations will not be considered by postal means.

Bill of Quantity and site conditions or the other documents such as general terms & conditions, general specifications and credentials, responsibility of the contractors, additional safety measures etc. can be seen at the office of the undersigned which will be applicable to the contract. Bill of quantity also can be seen in the company website [www.bccl.gov.in](http://www.bccl.gov.in) during time period.

Requisite Earnest Money is to be deposited in cash with the Cashier/ Dy.Manager (Finance)/Sr. F.O., Katras Area or A/c Payee Demand Draft by local nationalized bank in favour of BHARAT COKING COAL LIMITED payable at Dhanbad and proper money receipt should be enclosed with the quotations.

Income Tax clearance certificate /PAN.No. & VAT is to be submitted.

BCCL Management reserves its right to reject any or all of the quotations received or to split up and distribute the work between two or more contractors for which no reasons will be given what so ever.

Area Civil Engineer  
Katras Area-IV

Copy to :-

- 1) General Manager, Katras Area,
- 2) G.M.(Civil), BCCL. Koyla Nagar,Dhanbad,
- 3) General Manager (Admn.), BCCL. Koyla Bhawan,
- 4) Sr.E.S. to C.V.O., Koyla Bhawan, BCCL.,
- 5) All Area CGM/GM's Areas & Projects of BCCL.
- 6) Addl.G.M./SO(Mining)/AFM/APM/AM(Plg.)/AM(Safety)/PM(Admn.),Katras Area
- 7) All Project Officer's, Collys. Of Katras Area.
- 8) All SE(Civil), under Katras Area
- 9) Sr.F.O./Cashier, Katras Area
- 10) Notice Board, Katras Area
- 11) LEO®, Katrasgarh.
- 12) The Secretary, Chhatabad Malkera Adarsh Shramik Sahayog Samiti Ltd.,  
5 No. Chhatabad, At- Malkera Road, P.O. Katrasgarh, Dhanbad.
- 13) Asstt. Commandant,CISF Camp Angarpathra- with a request to depute Security personnel during the time period of receiving of tender near tender box and sealing the box at the time mentioned in NIT.
- 14) Commandant, CISF In-charge, Koyla Bhawwan BCCL Dhanbad -for necessary arrangement at his end.
- 15) Inspector Incharge,CISF Post, Govindpur Area-III.
- 16) Inspector Incharge,CISF Post, Sijua Area-V.
- 17) Manager(System), EDP,BCCL, Katras Area –along with a copy of NIT & BOQ.+ a C.D. against the above mentioned works for publication of the same in company website.
- 18) Tender File.

**Bill of Quantity for Repairing 5 units quarters at E.S.Section  
of Salanpur Colliery under Katras Area.**

Sl. No.	Item	Unit	Quantity	Rate	Amount
1	12mm cement plaster of mix: 1:6 (1cement : 6fine sand).	sqm	151.39	67.65	10241.53
2	Brick work with FPS bricks of class designation 50 in foundation and plinth using cement mortar 1:6 (1cement : 6coarse sand).	cum	3.83	2007.00	7686.81
3	25mm thick cement concrete flooring with 1:2:4 et.c	sqm	109.50	141.11	15451.54
4	Steel work in riveted, bolted or welded in built up sections, trusses and framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	kg	80.00	46.35	3708.00
5	6mm cement plaster of mix 1:3 (1cement : 3 fine sand).	sqm	30.90	62.15	1920.43
6	White washing with lime to give an even shade: Old work (two or more coats).	sqm	1000.00	4.10	4100.00
<b>Total (₹)</b>					<b>43,108.31</b>

**Bill of Quantity for Repair maintenance of 3 units quarters at**  
**Latail Dhowra under Salanpur Colliery.**

Sl. No.	Item	Unit	Quantity	Rate	Amount
1	12mm cement plaster of mix: 1:6 (1cement : 6fine sand).	sqm	153.16	67.65	10361.27
2	Providing and fixing A.C. sheet roofing.	sqm	15.00	279.84	4197.60
3	25mm thick cement concrete flooring with 1:2:4 et.c	sqm	30.00	141.11	4233.30
4	Brick work with FPS bricks of class designation 50 in foundation and plinth using cement mortar 1:6 (1cement : 6coarse sand).	cum	1.50	2007.00	3010.50
5	12mm cement plaster finished with a floating coat of neat cement of mix: 1:4 (1cement : 4fine sand).	sqm	15.00	97.90	1468.50
6	White washing with lime to give an even shade: Old work (two or more coats).	sqm	450.00	4.10	1845.00
<b>Total (₹)</b>					<b>25,116.17</b>

**Bill of Quantity for Repair maintenance of 5 units quarters at**  
**8 no. colony of Salanpur Colliery.**

Sl. No.	Item	Unit	Quantity	Rate	Amount
1	12mm cement plaster of mix: 1:6 (1cement : 6fine sand).	sqm	288.10	67.65	19489.96
2	25mm thick cement concrete flooring with 1:2:4 et.c	sqm	87.10	141.11	12290.68
3	6mm cement plaster of mix 1:3 (1cement : 3 fine sand).	sqm	25.00	62.15	1553.75
4	Dismantling old plaster or skirting including raking out the joints and cleaning the surface for plaster and disposal of rubbish to the dumping ground within 50 metres lead.	sqm	150.00	8.20	1230.00
5	White washing with lime to give an even shade: Old work (two or more coats).	sqm	225.00	4.10	922.50
6	Colour washing with lime to give an even shade: Old work (two or more coats).	sqm	1000.00	4.86	4860.00
<b>Total (₹)</b>					<b>40,346.89</b>

**Bill of Quantity for Construction of pump foundation at 10 &  
8A seam (3nos.) at KCC under Katras Area.**

Sl. No.	Item	Unit	Quantity	Rate	Amount
1	Recess cutting in floor.	cum	4.00	149.85	599.40
2	Brick work with FPS bricks of class designation 50 in foundation and plinth using cement mortar 1:6 (1cement : 6coarse sand).	cum	11.37	2007.00	22819.59
3	Providing and laying cement concrete of specified grade excluding the cost of centering and shuttering in all works up to plinth level : 1:2:4 (1cement : 2coarse sand : 4graded stone aggregates 20 mm nominal size).	cum	1.87	3257.45	6091.43
4	12mm cement plaster finished with a floating coat of neat cement of mix: 1:4 (1cement : 4fine sand).	sqm	15.61	97.90	1528.21
<b>Total (₹)</b>					<b>31,038.63</b>