BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Limited)
Office of the General Manager : Barora Area
Excavation Department
P.O. Nawagarh,Dist.DHANBAD-828306

Ref no: GM/BA/AM(Excvn)/NIT/11-12/ 5885 Dated: 11/12.01.2012

NOTICE INVITING TENDER

Sealed tenders in 2 bid system (Techno-commercial & price bid) are invited from experienced contractors/repairers for undertaking the following repair job of Barora Area, BCCL.

Sl no	Description of job	Estimated value of tender (Rs.)	Earnest money (1% of estimated value) (Rs.)	Last date & time for submission of tender	Date & time of opening of tender	Work completion period	Minimum Warranty/ Guarantee
1.	Repairing of Dipper Body with Door Assly. of BE-195 (10 M^3)Shovel, Sl.No.140763, BCCL No.S-87 of Muraidih OCP.	2,56,433=00	2565=00	08.02.12 up to 3.00 p.m.	08.02.12 at 4.30 p.m.	30 days from issue of work order or handing over of job for repair whichever is later	2000 hrs or 12 months from the date of completion & handing over of the work whichever is later.

Tender paper & Tender document will be issued from 01.02.12 to 07.02.12 during office hours from the Office of the Area Manager (Excvn), Barora Area, BCCL upon submission of DD for Rs.250.00(Rs Two hundred Fifty) payable to Bharat Coking Coal Limited payable at Dhanbad or by deposition of cash at Cash Section of Barora Area. The rest of the details like terms & conditions are in the Tender Document. Sealed tenders are to be submitted in the tender box placed in the Office of the Area Manager (Excvn), Barora Area. Tenderers must submit their Bank A/c. details in prescribed format which will be issued alongwith tender document. Failure to submit the same by the bidder, his offer may be liable to be rejected. The sale of tenders shall be stopped one day prior to the last day of submission of tender. The tenderers may inspect the item for repair at Muraidih OCP on any working day during working hours prior to submission of tenders.

SCOPE OF WORK:

(1) Removal of all worn out stiffner plate of complete assy. (2) Gauging of all crack portion. (3) Dismantling of all worn out damaged bushing & removal of bulged materials. (4) Welding of front wall with heel area crack portion. (5) Welding of side wall and upper wall crack portion. (6) Strengthening of Dipper Body by welding with 30 mm stiffener plate in two layer. (7) Strengthening of Heel with bore up to thickness 6 inch, jointing by welding . (8) Rebuilding and strengthening of Dipper Body lip area with tooth point lock portion (9) Welding / machining / grinding and new bush fitting (16 nos). (10) Door Assy crack portion welding. (11) Strengthening of Door Assy both side (front & rear) with 25 mm thick plate welding. (12) Welding & strengthening of Latch keeper base and guide system repairing by welding.

Note: Job has to be done at site (Muraidih OCP) and only electric supply will be provided by BCCL.

Area Manager (Excvn)
Barora Area, BCCL

Copy to:

(1) GM / AGM / AFM, Barora Area. (2) G.M.(Excvn), Koyla Bhawan. (3) Sr. Manager (System), Regional Stores, Barora Area—For publication of tender on web site as per laid down procedure. (4) Notice Board-Barora Area. (5) Notice Board, All Areas of BCCL.