

Bharat Coking Coal Limited
Sijua Area

Ref.No. GM/SA/Civil/ 2993 /2011

Dated 26/27.08.2011

Quotation Notice

Sealed quotation will be received in % age rate above/below basis in contractors their letter pad from BCCL, experience and bonafide resourceful civil contractors.

Sl. No.	Name of work & location	Estimated cost	Earnest money	time of completion
1.	Extension of drain at 40 dhowrah Ekra Basdeoopur colliery.	Rs.11,661=02	Rs.117=00	15 days
2.	Repairing Raiganj tiles roof of veranda and other misc. Work of Mudidih dispensary.	Rs.17,391=94	Rs.174=00	-do-
3.	Supply of good earth at PST 2 & O seam rehabilitation site Tetulmari colliery.	Rs.11,100=77	Rs.111=00	-do-
4.	P/F G.I. pipe near Bank of India bore hole to CB4 bungalow & Chandour basti at Tetulmari colliery.	Rs.19,385=80	Rs.194=00	-do-
5.	Strengthening of foundation of crusher Machine,heightening boundary wall & repairing drain at Lobotary of L.C.P.	Rs,26,061=53	Rs.261=00	One month
6.	Laying drinking water pipe line from main pipe to Somari Muhalla at Loyabad Coke Plant.	Rs.19,290=16	Rs.193=00	15 days
7.	Providing & fixing PVC pipe Qtr.No. 661 to 672& 673 to 684 at Nichitpur township.	Rs.16,455=80	Rs.165=00	-do-
8.	Rep./maint. of pipe line around C type flat at Loyabad colliery.	Rs.10,971=00	Rs.110=00	-do-

Contd.....p/2.....

9. Providing PVC pipe3 line for drinking water supply for the Qtr. of Amruddin Mia & others working at Loyabad resident of L.C.P.	Rs.16,931=45	Rs.169=00	-do-
10. Letter & writing for quarter nos.519 units of Pootki colony at Loyabad colliery.	Rs.24,289=99	Rs.243=00	-do-
11. Rep./maint. of pipe line (pit water) at Sweeper colony,Kankanee No.3 under Loyabad colliery.	Rs.25,583=35	Rs.256=00	-do-
12. Cleaning ash/drain and repairing of drain from worker's colony near durga mandir at Loyabad.	Rs.18,173=61	Rs.182=00	-do-
13. Cleaning & repairing of colony drain near B.R.A. School at Loyabad colliery.	Rs.11,037=27	Rs.110=00	-do-
14. maint. of pipe line for Qtr. of D.. Tiwari & Pramod Chouhan 2" at Loyabad colliery.	Rs.10,017=45	Rs.100=00	- do-
15. Repair/maint. pit water pipe line at Loyabad 6no. Shramik colony at Loyabad colliery.	Rs.11,586=10	Rs.116=00	-do-
16. Repairing of damaged brick work ,R.C.C. slab, plaster & other misc. Work around office of Mudidih colliery.	Rs.22,112=41	Rs.221=00	-do-

Availability of quotation documents

from 02.09.2011 to 06.09.2011

Tender documents will be issued on all working days during working hours except on Sundays & holidays in the event of the specified date for submission/opening of bids being declared a holiday the bids will be received/opened on the appointed time on the next working day. The tender document is also available on website <http://www.bccl.gov.in>.

Time and date of receipt/opening of quotation

- a) The quotation will be received on 08.09.2011 from 10.00 A.M. to 03.00 P.M. in Tender Box kept at:

Contd...p/3....

- i) CISF Post ,Sijua Area Office campus.
 - ii) CISF Post near Koyla Bhawan gate,Koyla Nagar,BCCL,Dhanbad.
 - iii) Office of the Asstt. Commandant CISF Camp, Angarpathra, katras Area.
 - iv) Office of the Asstt. Commandant CISF Camp, Kusunda Area Office.
- b) The quotation received will be opened on 10.09.2011 at 11.00 A.M. in the Office of Addl.General Manager,Sijua Area.
 - c) The quotation paper/documents can be obtained during normal office hours during the period mentioned above on production of application requested issued of quotation.
 - d) Completed sealed tender documents (Part-I & Part-II) should be submitted at the same time.

Part-I shall consist of terms and conditions of the tender, additional terms and conditions if any, Technical bid and credentials.

Part – II shall consist of quotation documents as issued to the quotationers duly filled in for rates, amounts etc. i.e. price bid.

The Earnest money deposit is to be submitted in a separate Envelope superscribing”

Earnest Money Deposit” (Earnest money to be submitted in form of cash or bank draft of Nationalized bank/scheduled commercial bank approved by Reserve Bank of India in favour of Bharat Coking Coal Limited payable at Dhanbad).

The bid shall be submitted in three separate Envelopes

Envelope-I should contain EMD and the tender document if downloaded from website & sealed.

Envelope-II should contain Part-I of sales tax/VAT clearance certificate & PAN No. and sealed.

Envelope-III should contain Part-II i.e. Price Bid & sealed.

Thereafter, all the three sealed envelopes should be submitted in one sealed envelope .

All the papers of each envelope should be serially numbered. If tender documents downloaded from website, it should be marked on the top of envelope as “DOWNLOADED DOCUMENTS”

TERMS & CONDITION:

1. The management of BCCL reserve the right to accept or reject any or all the quotations or split up work between the quotationers without assigning any reason what-so-ever.
2. The responsibility for procurement of all materials required for the work shall be with the contractors.
3. Conditional/incomplete quotation shall be out right rejected.
4. The validity of the quotations shall be 4(four) months from the date of opening of price bid or revised offer which ever is later.
5. Quotation without earnest money shall be out right rejected.
6. All other terms & conditions is as per general NIT rule of BCCL.
7. In case of any injury /accident it will be the responsibility of the contractor to pay legal dues their workers.

Contd...p/4.....

: 4 :

8. The tenders are advised to submit their Bank A/C No. Name of Bank & Name of Branch.
9. Contractors have to abide by the labour regulation/abolition Act. Govt. Of India adopted by BCCL.

Area Civil Engineer
Sijua Area

Cc to : E.S. to E.D.(Vig.),BCCL,Koyla Bhawan

Cc to: G.M.(Civil) Koyla Bhawan

Cc to: G.M.(Welfare)Koyla Bhawan

Cc to: G.M.(System),with a request to display this NIT in BCCL website.

The downloading facility should be available during the period of sale of
Tender document only.

Cc to: G.M.,Sijua Area

Cc to: A.G.M., -do-

Cc to: A.F.M. -do-

Cc to: PM(Admn.),Sijua Area

Cc to: All CGM/GMs Area-I to Area-12,Block-II,E/Jharia & W/Jharia.

Cc to: All Project Officer,Sijua Area.

Cc to: Civil Tender Notice Board kept at CISF Office,Sijua Area..

Cc to: Inspector I/C. CISF,Koyla Bhawan.

Cc to: Asstt.Commandant,CISF,Sijua Area/CISF Camp Angarpathra ,Katras Area IV.

Cc to: Dy,Commandant,CISF Kusunda Area Office Area VI.

Cc to: The Secretary Chhatabad Malkera Adarsh Shramik Sahyog Samiti Ltd.Chhatabad
Katrasgarh,Dhanbad.

Cc to: Builders Association of India,Central Akashkinaree Kanta Garh,Dhanbad-828113.

Cc to: Builders Association of india,316 LIG Housing Colony,Dhanbaad.

BHARAT COKING COAL LIMITED
SIJUA AREA

1. Name of work : _____
2. Name of agency : _____
3. Cost of tender paper : Rs. _____
4. Details of earnest money : Rs. _____

Signature of Tenderer

Area Civil Engineer
Sijua Area

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal india Limited)
SIJUA AREA—V.

The following details have to furnished by the tenderer while submitting the tender.

1. Name of the tender :
2. Whether individual partnership company :
3. Postal address of the company/proprietor

together with telephone no. etc.
4. In respect of partnership or limited company the name to the other partners, director together with their address.
5. List of other firms partnership doing business in BCCL where in the above firm/partners/directors are connected with.
6. Whether proprietor partner director are connected with an employee working in BCCL. If so the details for the employee, designation and place³ of working etc.
7. Any contract being carried on an BCCL. If the above firm/proprietor ship/limited in this own name if so the details of the contract bring executed.
8. Details of sales tax registration number if any.
9. Whether the proprietor/partnership firm/company is an income tax assessment has been deducted (income tax clearance certificate should be enclosed)

Failure to fill up these data will automatic rejection of the tender. The tender papers without any other these information will not be considered. This will from the part of the agreement also.

Sig. of the tenderer

Area Civil Engineer

Sijua Area

Bill of quantity for extension of drain
at 40 dhowra Ekra,Basdeopur colliery.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	Earth work excavation	5.18 Cu.M.	Rs.103=40	Rs. 535=61
2.	P.C.C.(1:4:8)	0.93 Cu.M.	Rs.2449=00	Rs. 2,277=57
3.	Brick work with C.M.(1:6) in F&P	2.55 Cu.M.	Rs.2007=00	Rs. 5,117=85
4.	12mm thick cement plaster (1:4) with punning	38.10 Sq.M.	Rs.97=90	Rs. 3,729=99

				Rs.11,661=02

Bill of quantity for repairing Raniganj tiles roof of Veranda
and other misc. Work of Mudidih dispensary.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	Cement painting (1:3) R/tiles roof	335.00 Sq.M.	Rs.24=90	Rs. 8,341=50
2.	Cement washing	335.00 Sq.M.	Rs. 2=80	Rs. 938=00
3.	Brick work with C.M. (1:6) in superstructure	2.00 Cu.M.	Rs.2137=76	Rs. 4,275=92
4.	12mm thick cement plaster(1:6)	11.71 Sq.M.	Rs.67=65	Rs. 792=18
5.	12mm thick cement plaster(1:4) with punning	5.00 Sq.M.	Rs.97=90	Rs. 489=50
6.	25mm thick P.S. flooring(1:2:4)	8.00 Sq.M.	Rs.102=83	Rs. 822=64
7.	P/fixing 4mm thick ply wood	3.00 Sq.M.	Rs.577=40	Rs. 1,732=20

				Rs.17,391=94

Bill of quantity for supply of road earth at PST 2 &
O seam rehabilitation site Tetulmari colliery.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	Supply of good earth cutting	56.68 Cu.M.	Rs.101=85	Rs. 5,772=85
2.	Transporting up 8 K.M.	56.68 Cu.M.	Rs.94=00	Rs. 5,327=92

				Rs.11,100=77

Bill of quantity for P/F G.I. pipe near Bank of india bore hole to
CB4 bungalow & Chandor basti at Tetulmari colliery.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	P/F/F G.I. pipe with G.I. fitting 25mm	72.00 Mtr.	Rs.156=85	Rs.11,233=20
	50mm	18.00 Mtr.	Rs.280=10	Rs. 5,041=80
2.	P/F 50mm dia flange	2 pairs	Rs.140=00	Rs. 280=00
3.	P/F 25mm dia union	6 Nos.	Rs.180=55	Rs. 1,083=30
4.	Dismantling G.I. pipe	90.00 Mtr.	Rs.18=75	Rs. 1,687=50

				Rs.19,385=80

Bill of quatity for strengthening of foundation of crusher machine,
heightening boundary wall & repairing drain at Laboratory of L.C.P.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	Brick work with C.M. (1:6) in foundation & plinth	9.71 Cu.M.	Rs.2007=00	Rs.19,487=97
2.	12mm thick cement plaster(1:6)	35.59 Sq.M.	Rs.67=65	Rs. 2,407=66
3.	12mm thick cement plaster (1:4) with punning	24.39 Sq.M.	Rs.97=90	Rs. 2,387=78
4.	White washing two coats	100.00 Sq.M.	Rs. 4=10	Rs. 410=00
5.	P.C.C.(1:2:4)	0.42 Cu.M.	Rs.3257=45	Rs. 1,368=12

				Rs.26,061=53

Bill of quantity for laying drinking pit water pipe line
from main pipe to somari Muhalla at Loyabad Coke pant.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	Providing & fixing P.V.C. 25mm dia pipe	76.25 Mtr.	Rs.179=85	Rs.13,713=5
2.	P/fixing G.I. union 25mm.	5 Nos.	Rs.180=55	Rs. 902=75
3.	Making connection from			
	a) G.I.main 50mm	1 No.	Rs.423=20	Rs. 423=20
	b) G.I. main 25mm	5 Nos.	Rs.166=05	Rs. 830=25
4.	P/fixing 15mm G.I. pipe for stand post	5.00 Mtr.	Rs.94=05	Rs. 470=25
5.	brick work with cement mortar (1:6) in F&P	0.35 Cu.M.	Rs.2007=00	Rs. 702=45
6.	Brick flat soling	7.49 Sq.M.	Rs.20=94	Rs. 155=58
7.	12mm thick cement plaster (1:4) with punning	21.37 Sq.M.	Rs.97=90	Rs. 2,092=12

				Rs. 19,290=16

Bill of quantity for providing & fixing P.V.C. pipe
Qtr.No.661 to 672 & 673 to 684 at Nichitpur township

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	P/laying P.V.C. pipe of dia 25mm	153.00 Mtr.	Rs.62=00	Rs. 9,486=00
2.	Earth work excavation	25.00 Mtr.	Rs.101=83	Rs. 2,545=75
3.	P/fixing 25mm socket	45 Nos.	Rs.35=25	Rs. 1,586=25
4.	P/fixing 25mm G.I. union	5 Nos.	Rs.107=25	Rs. 536=25
5.	Making connection	1 No.	Rs.166=05	Rs. 166=05
6.	P/F Sluice valve			
	3"	1 No.	Rs.1850=00	Rs. 1,850=00
	1"	1 No.	Rs. 285=50	Rs. 285=50

				Rs.16,455=80

Bill of quantity for rep. /maint. of pipe line
around C type flat at Loyabad colliery .

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	Dismantling G.I. pipe of dia 50mm	90.00 Mtr.	Rs.29=05	Rs. 2,614=50
2.	Labour charge for cleaning 50m m dia pipe.	90.00 Mtr.	Rs.37=45	Rs. 3,370=50
3.	P/laying PVC pipe of dia 25mm	12.00 Mtr.	Rs.179=85	Rs. 2,158=20
4.	P/fixing 50mm G.I. union socket	6 Nos.	Rs.335=50	Rs. 2,013=00
5.	Earth work excavation over	3.00 Cu.M.	Rs.101=85	Rs. 814=80

				Rs.10,971=00

Bill of quantity for providing P.V.C. pipe line for drinking water supply for
the Qtr. of Amruddi Mia & others working at Loyabad resident of L.C.P.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	25mm of P.V.C. pipe line	90.00 Mtr.	Rs.179=85	Rs.16,186=50
2.	P/F 25mm dia union	3 Nos.	Rs.107=25	Rs. 321=80
3.	Making connection	1 No.	Rs.423=20	Rs. 423=20

				Rs.16,931=45

Bill of quantity for letter & writing for quarter os.519 units
of Pootki colony at Loyabad colliery.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	Wall painting one coat	36.17 Sq.M.	Rs.25=95	Rs. 934=99
2.	Lettering & writting 2595 nos.	25950 nos.	Rs. 0=90	Rs.23,355=00

				Rs.24,289=99

Bill of quantity for rep./maint. of pipe line(pit water)
at Sweeper colony,kankanee No.3 under Loyabad colliery.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	Dismantling 50mm G.I. pipe	150.00 Mtr.	Rs.29=05	Rs. 4,357=50
2.	Labour charge for fixing 50m G.I. pipe cleaning	150.00 Mtr.	Rs.37=45	Rs. 5,617=50
3.	P/fixing G.I. pipe 50mm dia	42.00 Mtr.	Rs.280=10	Rs.11,764=2
4.	Making connectiong from G.I. main 3 Nos.		Rs.423=20	Rs. 1,269=60
5.	P/fixing G.I. union of dia 50mm	4 Nos.	Rs.333=50	Rs. 1,334=00
6.	P/fixing 15mm G.I. pipe	6.00 Mtr.	Rs.94=05	Rs. 564=30
7.	Labour engaged for cleaning 50mm pipe	5 nos.	Rs.135=25	Rs. 676=25

				Rs.25,583=35

Bill of quantity for cleaning ash/drain and repairing of drain
from worker,s colony neaar Durga mandir at Loyabad.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	Cleaning of muck from drain	14.10 Cu.M.	Rs.64=16	Rs. 904=65
2.	12mm thick cement plaster (1:4) with punning.	100.00 Sq.M.	Rs.97=90	Rs. 9,826=22
3.	Transporting of mech within 1 k.m. lead.	61.00 Cu.M.	Rs.42=97	Rs. 2,621=17
4.	Cleaning of Ash/earth	47.34	Rs.101=85	Rs. 4,821=57

				Rs.18,173=61

Bill of quantity for cleaning & repairing of colony drain
near B.R.A. School at Loyabad colliery.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	Cleaning of meck from drai n	7.08 Cu.M.	Rs.64=16	Rs. 454=25
2.	Brick work with C.M. (1:6) in F&P	0.74 Cu.M.	Rs.2007=00	Rs. 1,485=18
3.	12mm thick cement plaster(1:4)	92.93 Sq.M.	Rs.97=90	Rs. 9,097=84

				Rs.11,037=27

Bill of quantity for maintenance of pipe line for Qtr.
of D.N. Tiwari & Pramod Chouhan 2" at Loyabad colliery.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	Dismantling G.I. pipe 25mm dia	88.00 Mtr.	Rs.24=90	Rs. 2,191=20
2.	Laying G.I. pipe of 25mm dia after cleaning pipe.	52.00 Mtr.	Rs.31=50	Rs. 1,638=00
3.	Providing & laying G.I. pipe	36.00Mtr.	Rs.156=85	Rs. 5,646=60
4.	P/fixing G.I. union	3 Nos.	Rs.180=55	Rs. 541=65

				Rs.10,017=45

Bill of quantity for repair/maint. pit water pipe line
at Loyabad 6 no. Shramik colony at Loyabad colliery.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	Dismantling old pipe of dia 50mm	140.00 Mtr.	Rs.29=05	Rs. 4,067=00
2.	Labour charge for laying G.I. pipe of dia 50mm	140.00 Mtr.	Rs.37=45	Rs. 5,243=00
3.	Making connection from G.I. main	3 Nos.	Rs.423=20	Rs. 1,209=60
4.	P/fixing G.I. union of dia 50mm	3 Nos.	Rs.335=50	Rs. 1,006=50

				Rs.11,586=10

Bill of quantity for repairing of damaged brick work,R.C.C.
slab,plaster & other misce. Work around office of Mudidih colliery.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	B/work in F&P(1:6)	0.78 Cu.M.	Rs.2007=00	Rs. 1,565=46
2.	12mm c/plaster in (1:6)	14.80 Sq.M.	Rs.67=65	Rs. 1,001=22
3.	12mm c/plaster with punning	77.00 Sq.M.	Rs.97=90	Rs. 7,540=25
4.	P/L cement concrete(1:2:4)	2.14 Cu.M.	Rs.3257=45	Rs. 6,970=94
5.	R.C.C.(1:2:4) in precast slab	0.48 Cu.M.	Rs.42=70	Rs. 2,343=48
6.	Reinforcement for R.C.C. slab	41.00 Kg.	Rs.4882=28	Rs. 2,343=48
7.	25mm P.S. flooring in (1:2:4)	10.68 Sq.M.	Rs.86=05	Rs. 919=01

				Rs.22,112=41