

BHARAT COKING COAL LTD.
OFFICE OF THE GENERAL MANAGER

(A subsidiary of Coal India Limited)

Chanch Victoria Area-XII

Ref.No. : E&M/XII/BCCL/NIT/11-12/838

Date: 8/9/2011

Notice Inviting Tender

Sealed tenders are invited from Licensed, Experienced and bonafide Electrical contractors in two part i.e.,- Technical Bid as Part-I and Price bid as Part-II. Both Part of the Bid has to be wax sealed separately and should be wax sealed in a third envelope super scribing the nature of bid in each envelope and the bids for the reference as above to be submitted.

The sealed bids must has to reach in the office of the undersigned on or before 07/10/11 up to 1 P.M. in the Tender box. No. tender will not be accepted after the date and time. Only the Technical Bids will be opened on the same day at 4:00 P.M. in presence of the intending bidders.

Sl. No.	Name of work	Estimated Cost Rs.	Tender Cost Rs.	Earnest Money Rs.	Time of Completion
1.	Erection of new 440 Volt, O/H line from V.Colly. New qtrs. To Babu para of V.Colly. under DBOCP	2.69 lacs.	114/- inc.vat (Non- refundable) (Refundable)	2,700/-	20Days.

Terms & Conditions:-

1. Tender Paper can be obtained from the office of the undersigned on any working day except Sunday and holidays from 26/09/2011 to 6/10/2011. On production of tender cost cash money receipt issued by the Cashier Finance Department, BCCL C/V Area-XII or demand draft drawn of any nationalized Bank in favor of BCCL, Area-XII (payable at Barakar). No tender paper will be issued on 07/10/2011. Earnest money can also be deposited/ submitted in the similar manner and no cash Earnest money will be accepted on 07/10/2011. Original cash receipt for Earnest Money is to be deposited with the Technical Bid. Without earnest money no tender will be accepted and is to be treated as cancelled. Tender documents can also be downloaded from our company's website www.bccl.gov.in but cost of tender document is to be submitted along with bid document by Bank draft.

2. The technical Bid is to be incorporate with valid Electrical Contractors license, Supervisory License for 11KV Lines, VAT Registration, PAN Card, Service Tax Registration, Past Experiences, Deed of partnership/proprietorship, Letter of credit from bank, list of tools and plants, Company's Profile and Earnest Money. None submission of these documents may result in rejection of the submitted bids.

Contd. On pg.- 2

3. Technical Parameters:- The intending bidders must have in their name having successfully completed the similar nature of work in Government/Public sector undertaking in last 7 years ending with the last day of the month previous to the one in which bid application are invited, should be as following:-

- (i) Three similar completed works each costing not less than the amount equal to 40% of the estimated cost. Or
- (ii) Two similar completed works each costing not less than the amount equal to 50% of the estimated cost. Or
- (iii) One similar completed works each costing not less than the amount equal to 80% of the estimated cost.

Similar Nature of work Means:- Commissioning /Installation of 1.1 KV grade Overhead Line works.

- 4. 10% security money including the Earnest Money will be withheld for a defect liability/guarantee period of six months from the date of handing over.
- 5. The offer of intending bidders should be valid for 120 days.
- 6. All taxes/levies will be applied/charged upon bidders as per Company's rule.
- 7. All safety wears, tools and tackles has to be provided to the workmen is to sole responsibility of the intending bidder.
- 8. The tender paper will be issued to authorized signatories of the firm only and in any case no unauthorized agents will be entertained.
- 9. Managements reserves the right either to accept or reject the entire tender paper or part there off/split up the work without assigning any reasons whatsoever.

**Area Manager(E&M)
BCCL;C/V Area-XII,**

Distribution:-

- 1. Notice Board, BCCL C/V Area -XII for display.
- 2. All CGM/GM/AM (E&M) – Area- I to Area- XII.
- 3. AFM, AGM and Cashier, BCCL, C/V Area-XII.
- 4. CGM (E&M), BCCL HQ, Koyla Bhawan, Dhanbad.
- 5. Chief Vigilance Officer, BCCL HQ, Koyla Bhawan, Dhanbad.
- 6. The General Manager System/Publication, BCCL HQ, Koyla Bhawan, Dhanbad (for website and newspaper publication)
- 7. All Colliery Engineer (E&M), BCCL, C/V Area- XII.
- 8. Tender file.

BHARAT COKING COAL LIMITED
Chanch Victoria Area-XII
Tender Paper

Ref No. E&M/XII/BCCL/NIT/11-12/ 838

Date: 8/9/2011

Name of work:-Erection of new 440 V. O/H line from V.Colly. new qtrs. to Babu para of V.Colly under DOCP.

<u>Sl.No.</u>	<u>Description of Job</u>	<u>Qty.</u>	<u>Rate</u>	<u>Amount</u>
1.	Erection of steel tubelor PCC pole of length exceeding 10m but not exceeding 12m in cement concrete 1:3:6(1 cement, 3 Coarse Sand, 6 graded stone aggregate 40 mm Nominal size) foundation including Excavation and refilling etc. as reqd. Pole BCCL supply.	5 Nos		
2.	Supply of cement sand and stone chips for cement concreting (1:3:6) aggregate 40 mm nominal size. 1.5 cum.	5 Nos		
3.	Supply and erection of Stay Set complete (Galv.) with 19/20 mm dia X 1.8 m long stay Rod, Anchor plate of size 45 cm X 45 cm X 7.5 mm, thimble, Stay clamps, bow tightener 7 X 4.00 mm dia G.I. Stay wire and strain Insulator etc. in cement concrete 1:3:6 foundation Including excavation and refilling etc. As required.	10 Nos		
4.	Supply & erection of 100 mm X 110 mm Shackle insulator with G.I. Bolts, nuts, and Straips etc.,	28 Nos		
5.	Supply & erection of 100 mm X 80 mm Pin insulator complete with G.I. Spindle, And nuts etc. as reqd.,	18 Nos		
6.	Supply, fabrication & erection after painting From Red Oxide of Iron & Steel materials such as cross arms, bracings, M.S. Channel for heightening, Brackets, Clamps, Nut & Bolts etc. as required.	425 Kg.		

Cont. Page-2

7. Supply and erection of continuous earth wire 7/16 SWG /8 SWG G.I. wire for earth continuity incl. binding.	500 Mtrs.
8. Erection of ACSR conductor of 7/3.35mm dia mm AAAC conductor 7/1.96 mm to 7/3.10 mm dia incl. Binding etc. as reqd.	425 Kgs.
9. Transportation of PCC pole upto 8.0 mtrs. Long from Work shop to work site.	10 Nos.
10. Pit making & tree cutting along the over Head line.	L.S.
11. Earthing as per I.E.Rule.	2 Nos.
13. Supply of ACSR Rabbit conductor.	600 Mtrs.
14. Dismantling of pole.	10 Nos.
15.Dismantling of old conductor ACSR cond. earth wire bracket nut, bolt insulator comp. set	450 Kgs.
16. Transporting of dismantle materials.	L.S.

Add :- 4.12% Service Tax

Rs.

Rs.

Total Rs.

(Rupees _____ only.)

Area Manager (E&M)
C/V area- XII,

Signature of contractor.
Seal and date.