

BHARAT COKING COAL LTD.
OFFICE OF THE GENERAL MANAGER

(A subsidiary of Coal India Limited)

Chanch Victoria Area-XII

Ref.No. : E&M/XII/BCCL/NIT/11-12/ 900

Date: 20/9/2011

Notice Inviting Tender

Sealed tenders are invited from Licensed, Experienced and bonafide Electrical contractors in two part i.e.,- Technical Bid as Part-I and Price bid as Part-II. Both Part of the Bid has to be wax sealed separately and should be wax sealed in a third envelope super scribing the nature of bid in each envelope and the bids for the reference as above to be submitted.

The sealed bids must has to reach in the office of the undersigned on or before 11/10/11 up to 1 P.M. in the Tender box. No. tender will not be accepted after the date and time. Only the Technical Bids will be opened on the same day at 4:00 P.M. in presence of the intending bidders.

Sl. No.	Name of work	Estimated Cost Rs.	Tender Cost Rs.	Earnest Money Rs.	Time of Completion
1.	Installation of 11 KV O/H Line from DBOCP S/Stn. to susil sub-stn. along the new diverted road under DBOCP.	3.41 lacs.	114/- inc.vat (Non- refundable) (Refundable)	3,410/-	30Days.

Terms & Conditions:-

1. Tender Paper can be obtained from the office of the undersigned on any working day except Sunday and holidays from 30/9/2011 to 10/10/2011. on production of tender cost cash money receipt issued by the Cashier Finance Department, BCCL C/V Area-XII or demand draft drawn of any nationalized Bank in favor of BCCL, Area-XII (payable at Barakar). No tender paper will be issued on 11/10/2011. Earnest money can also be deposited/ submitted in the similar manner and no cash Earnest money will be accepted on 11/10/2011. Original cash receipt for Earnest Money is to be deposited with the Technical Bid. Without earnest money no tender will be accepted and is to be treated as cancelled. Tender documents can also be downloaded from our company's website www.bccl.gov.in but cost of tender document is to be submitted along with bid document by Bank draft.

2. The technical Bid is to be incorporate with valid Electrical Contractors license, Supervisory License for 11KV Lines, VAT Registration, PAN Card, Service Tax Registration, Past Experiences, Deed of partnership/proprietorship, Letter of credit from bank, list of tools and plants, Company's Profile and Earnest Money. None submission of these documents may result in rejection of the submitted bids.

Contd. On pg.- 2

3. Technical Parameters:- The intending bidders must have in their name having successfully completed the similar nature of work in Government/Public sector undertaking in last 7 years ending with the last day of the month previous to the one in which bid application are invited, should be as following:-

- (i) Three similar completed works each costing not less than the amount equal to 40% of the estimated cost Or
- (ii) Two similar completed works each costing not less than the amount equal to 50% of the estimated cost. Or
- (iii) One similar completed works each costing not less than the amount equal to 80% of the estimated cost.

Similar Nature of work Means:- Commissioning /Installation of 11 KV grade Overhead Line works.

- 4. 10% security money including the Earnest Money will be withheld for a defect liability/guarantee period of six months from the date of handing over.
- 5. The offer of intending bidders should be valid for 120 days.
- 6. All taxes/levies will be applied/charged upon bidders as per Company's rule.
- 7. All safety wears, tools and tackles has to be provided to the workmen is to sole responsibility of the intending bidder.
- 8. The tender paper will be issued to authorized signatories of the firm only and in any case no unauthorized agents will be entertained.
- 9. Managements reserves the right either to accept or reject the entire tender paper or part there off/split up the work without assigning any reasons whatsoever.

**Area Manager(E&M)
BCCL;C/V Area-XII,**

Distribution:-

- 1. Notice Board, BCCL C/V Area -XII for display.
- 2. All CGM/GM/AM (E&M) – Area- I to Area- XII.
- 3. AFM, AGM and Cashier, BCCL, C/V Area-XII.
- 4. CGM (E&M), BCCL HQ, Koyla Bhawan, Dhanbad.
- 5. Chief Vigilance Officer, BCCL HQ, Koyla Bhawan, Dhanbad.
- 6. The General Manager System/Publication, BCCL HQ, Koyla Bhawan, Dhanbad (for website and newspaper publication)
- 7. All Colliery Engineer (E&M), BCCL, C/V Area- XII.
- 8. Tender file.

BHARAT COKING COAL LIMITED
Chanach Victoria Area-XII
Tender Paper

Ref:- E&M/XII/BCCL/NIT/11-12/900

Date.20/9/2011

Name of work:-Installation of 11 KV O/H line from DBOCP S/S to Sushil S/Stn along the new diverted road under DBOCP

<u>Sl.No.</u>	<u>Description of Job</u>	<u>Qty.</u>	<u>Rate</u>	<u>Amount</u>
1.	Erection of steel tubelor PCC pole of length exceeding 10m but not exceeding 12m in cement concrete 1:3:6foundation including Excavation and refilling etc. (Pole BCCL Supply)	14 Nos		
2.	Supply of cement sand and stone chips for concreting mixtures for pole foundation 1:3:6(1 Cement : 3 coarse : 6 graded Stone aggregate 40mm nominal size. (1.5 cum. for each pole foundation)	14 Nos		
3.	Transportation of poles from store/godown To site incl. handling, loading & unloading etc.	14 Nos		
4.	Supply and erection of Galvanised Stay Set complete with 19/20 mm dia X 1.8 m long stay Rod, Anchor plate of size 45 cm X 45 cm X 7.5 mm thick, thimble, Stay Turn buckle (20mm X 600mm) 7 X 4.00 mm dia G.I. Stay wire and 11 KV strain Insulator etc in cement concrete 1:3:6foundation including excavation and refilling etc. As required	38 Nos		
5.	Supplying & erection of 11KV Grade Disc insulators for 11 KV O/H line with G.I. Insulator fittings, ball and socket type and complete with G.I. Strain Clamps, bolts, nuts, washers, etc. as reqd.	30 Nos		
6.	Supplying & Erection of 11 KV Pin Insulator comp. with large steel head G.I. Pin Nuts, & Washers etc. as reqd.	48 Nos		

7. Supply & Erection of 6 Nos G.I. Wire/
7/16 SWG Wire for earth continuity. 228 Kgs.

8. Supply, fabrication, painting and erection
of MS Steel structures such brackets, Pole
top, cross Bracing, Cross arms, Ties, M.S. Clamps
of various shape and size incl. Nut, Bolts &
Washers as required. 750 Kg.

9. Erection of ACSR Conductors up to 7/3.35 mm
Diameter and above incl. binding of insulator
etc. as reqd. 1382 Kgs.

10. Check Survey, Pit making tree & Corridor
cleaning for 11 KV O/H line . L.S.

11. Making of Earth Pits by supplying 50mm
Dia G.I. Pipe 3 Mtrs. Long with Earth Electrode
duly welded at the bottom of the pipe incl.
pit digging & refilling by supplying Salt,
Sand & charcoal/ Bentonite Clay. 4 Nos

Total Rs. _____
Add :- Service Tax 4.12% - Rs. _____

Grand Total Rs. _____

Area Manager (E & M)
C/V Area – XII. BCCL

Signature of contractor
Seal & date