

BHARAT COKING COAL LIMITED

(A Subsidiary of Coal India Limited)

Office of the General Manager, Katras Area

P.O. Sijua, Distt. Dhanbad.

Ref. No. BCCL/GM/IV/Civil/Quotation//2011-12/ 2332

Dated: 03.08.2011.

QUOTATION NOTICE

Sealed **QUOTATION** is invited in percentage rate above/below basis in **single part** from BCCL experienced and bonafide resourceful civil contractors for the following civil works:-

| Sl. No. | Nature of Job & Location | Estimated Cost | Earnest Money | Cost of Tender Paper | Time of Completion |
|---------|---|----------------|---------------|----------------------|--------------------|
| 1. | Repair and maintenance of quarter No.EK/NAP/6 (Qtr.no.3) at Angarpathra Colliery under Katras Area. | Rs.20,724.06 | Rs.208/- | Nil/- | 20 Days. |
| 2. | Repairing & maintenance work of quarter of Sri Gopal Singh, Foreman at Ramkanali Colliery under Katras Area. | Rs.15,478.42 | Rs.155/- | Nil. | 15 Days. |
| 3. | Repair/ Maintenance of quarter No.,Block No.A/20 NHS/Qtr. No.7 at check post 'B' of Ramkanali Colliery under Katras Area. | Rs.18,855.32 | Rs.190/- | Nil. | 15 Days. |
| 4. | Repair & Maintenance of Qtr.No.EK/NAP-6/21 at Angarpathra Colliery under Katras Area. | Rs.11,703.26 | Rs.117/- | Nil. | 10 Days. |
| 5. | Repair of Compound wall in Qtr.No. 98 of Tilatand Township under Katras Area. | Rs.9,746.57 | Rs.98/- | Nil. | 10 days |
| 6. | Repair of pipe line & change the valve near pump room at T.B. ward,Regional Hospital Tilatand under Katras Area. | Rs.11,079.80 | Rs.111/- | Nil. | 10 days. |
| 7. | Repair and Maintenance of Qtr.No.181 at Tilatand Township under Katras Area. | Rs.4,837.70 | Rs.50/- | Nil. | 10 days. |
| 8. | Repair of One room and closing of Verandah of Area Laboratory at Angarpathra under Katras Area. | Rs.9,986.20 | Rs.100/- | Nil. | 10 days. |
| 9. | Repair & Maintenance of Qtr.No.1 Adarsh Colony at Ramkanali Colliery under Katras Area. | Rs.12,684.00 | Rs.127/- | Nil. | 10 days. |
| 10. | Repair & Maintenance work in the Quarter No.261 at Adarsh Colony, Angarpathra under Katras Area. | Rs.16,148.57 | Rs.162/- | Nil. | 10 days. |

Date and time of receipt/opening of Quotation :-

a) The quotation will be received on

17.08.2011 from **10.00A.M.** to **3.00 P.M.** in a tender box kept at:-

i) Office of Asstt.Commandant,CISF. Camp,Angarpathra.

Cont.d..P/2.

ii) CISF Post, near Koyala Bhawan gate, Koyala Nagar, BCCL, Dhanbad in Box marked Katras Area
iii) CISF Post, Sijua Area V in tender box marked Katras Area,

iv) CISF Post, Govindpur Area-III in tender box marked Katras Area,.

b) The quotations received will be opened on **19.08.2011** at **4.00 P.M.** in the office of the Area Civil Engineer, Katras Area.

All the materials and equipments required for this work will be responsibility of the contractor.

Contractors have to abide by the Labour regulations/abolitions Act. Govt. of India adopted by BCCL from time to time.

Conditional quotations will be out right rejected.

Late or delayed quotations will not be accepted.

Quotations will not be considered by postal means.

Bill of Quantity and site conditions or the other documents such as general terms & conditions, general Specifications and credentials responsibility of the contractors, additional safety measures etc. can be seen at the office of the undersigned which will be applicable to be contract. Bill of quantity also can be seen in the company website www.bccl.gov.in during time period.

Requisite Earnest Money is to be deposited in cash with the Cashier/Dy. Manager (Finance)/Sr.F.O., Katras Area or A/c. payee Demand Draft by local nationalized bank in favour of BHARAT COKING COAL LIMITED payable at Dhanbad and proper money receipt should be enclosed with the quotations. Income Tax clearance certificate /PAN.No. & VAT is to be submitted.

BCCL Management reserves its right to reject any or all of the quotations received or to split up and distribute the work between two or more contractors for which no reasons will be given what so ever.

Area Civil Engineer,
Katras Area.IV.

Copy to:-

1. General Manager, Katras Area,
2. G.M.(Civil), BCCL. Koyla Nagar, Dhanbad,
3. General Manager (Admn.), BCCL. Koyla Bhawan,
4. Sr.E.S. to C.V.O., Koyla Bhawan, BCCL.,
- 5 All Area CGM/GM's Areas & Projects of BCCL.
6. Addl.G.M./SO(Mining)/AFM/APM/AM(Plg.)/AM(Safety)/PM(Admn.), Katras Area,
- 7 All Project Officer's, Collys. Of Katras Area,
- 8 All SE(Civil), under Katras Area,
9. Sr.F.O./Cashier, Katras Area,
10. Notice Board, Katras Area,
11. LEO, Katrasgarh,
12. The Secretary, Chhatabad Malkera Adarsh Shramik Sahayog Samiti Ltd.,
5 No. Chhatabad, At- Malkera Road, P.O. Katrasgarh, Dhanbad.
13. Asstt. Commandant, CISF Camp Angarpathra- with a request to depute Security personnel during the time period of receiving of tender near tender box and sealing the box at the time mentioned in NIT.
14. Commandant, CISF In-charge, Koyla Bhawan BCCL Dhanbad -for necessary arrangement at his end.
15. Inspector Incharge, CISF Post, Govindpur Area-III,
- 16) Inspector Incharge, CISF Post, Sijua Area-V.
- 17) Manager(System), EDP, BCCL, Katras Area –along with a copy of NIT & BOQ.+ a C.D. against the above mentioned works for publication of the same in company website.
18. Tender File.

**Bill of Quantity for Repair and maintenance of quarter No.EK/NAP/6
(Qtr.No.3) at Angarpathra Colliery under Katras Area. (Sl.No.1).**

| Sl. No. | Item | Quantity | Unit | Rate | Amount |
|---------|--|------------|--------------------|--------|------------------|
| 1. | Half brick work in cement mortar 1:4 in F & P. complete job. | 3.60 m2 | /m2. | 257.23 | 926.02 |
| 2. | 12mm.thick cement plaster 1:6 all complete. | 108.00 m2. | /m2. | 67.65 | 7306.20 |
| 3. | 12mm.thick cement plaster 1:4 with punning all complete job. | 15.00 m2 | /m2 | 97.90 | 1468.50 |
| 4. | 6mm. thick cement plaster 1;3 in ceiling complete job. | 11.15 m2 | /m2 | 62.15 | 692.97 |
| 5. | 25mm.thick cement concrete flooring 1:2:4 all complete job. | 60.65 m2 | /m2 | 141.11 | 8558.32 |
| 6. | White washing two coats all complete. | 15.00 m2 | /m2 | 4.10 | 615.00 |
| 7. | Colour washing two coats all complete. | 75.00 m2 | /m2 | 3.85 | 288.75 |
| 8. | Painting two coats all complete | 38.00 m2 | /m2 | 22.85 | 868.30 |
| | | | Total (Rs.) | | 20,724.06 |

Bill of Quantity for Repairing & Maintenance work in the quarter of Sri Gopal Singh, Foreman at Ramkanali Colliewry under Katras Area. (Sl.No.2).

| Sl. No. | Item | Quantity | Unit | Rate | Amount |
|---------|---|------------|--------------------|---------|------------------|
| 1. | Brick work in cement mortar 1:6 in F & P. all complete. | 1.27 m3 | /m3 | 2007.00 | 2,546.89 |
| 2. | Half brick work in cement mortar 1:4 in F & P. etc.complete. | 1.53 m2 | /m2 | 389.35 | 595.70 |
| 3. | 12mm thick cement plaster with 1:6 c.m. etc. complete. | 30.00 m2 | /m2 | 67.65 | 2029.50 |
| 4. | 12mm.thick cement plaster 1:4 with punning all complete. | 5.00 m2 | /m2 | 97.90 | 489.50 |
| 5. | 25mm.thick cement concrete 1:2:4 in flooring etc.complete. | 11.00 m2 | /m2 | 141.11 | 1552.21 |
| 6. | White washing two coats all complete. | 130.00 m2 | /m2. | 4.10 | 533.00 |
| 7. | Distemparing two coats all complete. | 210.00 m2. | /m2. | 14.90 | 3129.00 |
| 8. | Colour washing with lime (two or more coats) etc.complete. | 186.15 m2 | /m2 | 3.85 | 716.67 |
| 9. | Painting two coats with synthetic enamel paint etc. complete. | 86.00 m2 | /m2 | 22.85 | 1965.10 |
| 10. | Providing steel door all complete. | 32.00 Kg. | /kg. | 48.95 | 1566.40 |
| 11. | Fixing of door all complete. | 1 No. | Each.354.45 | | 354.45 |
| | | | Total:(Rs.) | | 15,478.42 |

Bill of Quantity for Repair & Maintenance of quarter No./Block No. A/20
NHS/Qtr.No.7 at check post 'B' of Ramkanali Colliery under Katras Area.
(Sl.No.3.)

| Sl. No. | Item | Quantity | Unit | Rate | Amount |
|---------|---|----------------|------------------------------|--------------------------------|--------------------------------|
| 1. | 12mm. thick cement plaster 1:6 all complete job. | 50.00 m2 | /m2 | 67.65 | 3,382.50 |
| 2. | 6mm. thick cement plaster 1:3 all complete | 9.85 m2 | /m2 | 62.15 | 612.17 |
| 3. | 12mm. thick cement plaster 1:4 with punning all complete. | 9.00 m2 | /m2 | 97.90 | 881.10 |
| 4. | 25mm.thick cement concrete flooring 1:2:4 all complete. | 45.00 m2 | /m2 | 141.11 | 6349.55 |
| 5. | Half brick work in cement mortar 1:4 in F & P. all complete. | 3.25 m2 | /m2 | 289.00 | 939.25 |
| 6. | Brick work in cement mortar 1:6 in Superstructure all complete. | 0.90 m3 | /m3 | 2007.00 | 1806.30 |
| 7. | Providing steel door/window all complete. | 50.00 Kg. | /Kg. | 48.95 | 2447.50 |
| 8. | Fixing of door/window all complete. a) Door b) Window | 1 No. 1 No. | Each. Each. | 354.45 214.20 | 354.45 214.20 |
| 9. | White washing two coats all complete. | 150.00 m2 | /m2 | 4.10 | 615.00 |
| 10. | Color washing two coats all complete. | 100.00 m2 | /m2 | 3.85 | 385.00 |
| 11. | Painting two coats with synthetic enamel paints all complete. | 38.00 m2 | /m2 | 22.85 | 868.30 |
| | | | | Total:. | Rs.18,855.32 |

Bill of Quantity for Repair & Maintenance of Quarter No. EK/NAP-6/21 at Angarpathra colliery under Katras Area.(Sl.No.4)

| Sl.No. | Item. | Quantity. | Unit./ | Rate | Amount |
|--------|---|-----------|--------------------|--------|------------------|
| 1. | 12mm.thick cement plaster 1:6 all complete. | 50.00 m2 | /m2 | 67.65 | 3382.50 |
| 2. | 12mm.thick cement plaster 1:4 with punning all complete. | 3.00 m2 | /m2 | 97.90 | 293.70 |
| 3. | 6mm.thick cement plaster 1:3 all complete. | 8.00 m2 | /m2 | 62.15 | 497.20 |
| 4. | 25mm.thick cement concrete flooring 1:2:4 all complete. | 38.00 m2 | /m2 | 141.11 | 5362.18 |
| 5. | Providing steel door all complete. | 36.00 Kg. | /Kg. | 46.35 | 1668.60 |
| 6. | Fixing of door all complete. | 1 No. | Each. | 354.45 | 354.45 |
| 7. | Painting two coats with synthetic enamel paint etc. complete job. | 4.35 m2 | /m2 | 33.25 | 144.63 |
| | | | | | |
| | | | Total (Rs.) | | 11,703.26 |
| | | | | | |

Repair of compound wall in Quarter No.98 of Tilatand Township under Katras Area. (Sl.No. 5)

| Sl. No. | Item | Quantity | Unit | Rate | Amount |
|---------|--|-----------|-------------------|---------|-----------------|
| 1. | Brick work in Superstructure 1:6 (1 cement: 6 Fine sand) with bricks of class 50 complete job. | 3.41 m3 | /m3 | 2197.00 | 7,491.77 |
| 2. | Steel work in Built up section etc. complete job. | 41.00 Kg. | /Kg. | 46.35 | 1900.35 |
| 3. | Fixing of Door | 1 No. | Each | 354.45 | 354.45 |
| | | | Total: Rs. | | 9,746.57 |
| | | | | | |
| | | | | | |

Bill of Quantity for Repair of pipe line & change the valve near pump room at T.B.ward, Regional Hospital Tilatand under Katras Area. (Sl.No.6)

| Sl. No. | Item | Quantity | Unit | Rate | Amount |
|---------|---|----------|--------------------|---------|------------------|
| 1. | Providing, Fixing G.I. pipe complete with G.I. fittings as per instruction of E/Inc. complete job. a) 65mm. nominal bore | 6.00 M. | /mtr. | 356.15 | 2136.90 |
| 2. | Providing/Fixing union 65mm.dia. | 1.00 No. | Each. | 528.30 | 528.30 |
| 3. | Providing, Fixing Gate valve 80mm.dia. | 2 Nos. | Each. | 3600.00 | 7200.00 |
| 4. | Providing ,Fixing Union 80mm.dia. | 2 Nos. | Each. | 607.30 | 1214.60 |
| | | | Total (Rs.) | | 11,079.80 |
| | | | | | |

Bill of Quantity for Repair & Maintenance of Quarter No.181 at Tilatand Township under Katras Area. (Sl.No.7)

| Sl. No. | Item | Quantity | Unit | Rate | Amount |
|---------|--|------------|--------------------|--------|-----------------|
| 1. | White wash old work complete job. | 174.00 M2. | /m2. | 4.10 | 713.40 |
| 2. | Painting two coats with synthetic enamel paint all complete. | 50.00 m2 | /m2 | 22.85 | 1142.50 |
| 3. | Steel work in built up section etc.complete. | 41.00 Kg. | /Kg. | 46.35 | 1900.35 |
| 4. | Fixing of door | 1 No. | Each. | 354.45 | 354.45 |
| 5. | 12mm.thick cement plaster (1:6) | 10.00 m2 | /m2 | 72.70 | 727.00 |
| | | | Total (Rs.) | | 4,837.70 |
| | | | | | |

Bill of Quantity for Repair of One Room and closing of Verandah of Area Laboratory at Angarpathra under Katras Area. (Sl.No.8)

| Sl. No. | Item | Quantity | Unit | Rate | Amount |
|---------|---|-----------|--------------------|---------|----------------|
| 1. | Brick work with bricks of class-50 in Superstructure (1:6) 1 cement: 6 coarse sand etc. complete job. | 3.50 m3 | /m3. | 2137.95 | 7482.82 |
| 2. | 12mm.thick cement plaster (1:6) | 26.00 m2 | /m2 | 72.70 | 1890.20 |
| 3. | White washing old work . | 100.00 m2 | /m2 | 4.10 | 410.00 |
| 4. | 25mm thick P.S. flooring 1:2:4 Cement concrete all complete | 1.00 m3 | M3 | 141.11 | 141.11 |
| 5. | 6mm thick cement plaster (1:3) 1 cement : 3 fine sand etc complete in ceiling | 1.00m2 | /m2 | 62.15 | 62.15 |
| | | | Total (Rs.) | | 9986.20 |

Bill of Quantity for Repair & Maintenance of Qtr No. 1, at Adarsh Colony, Ramkanali Colliery under Katras Area. (Sl.No.9).

| Sl. No. | Item | Quantity | Unit | Rate | Amount |
|---------|---|-----------|--------------------|--------|-----------------|
| 1. | 25 mm thick cement concrete flooring 1:2:4 etc complete | 37.61 m2 | /m2 | 141.11 | 5307.14 |
| 2. | 12 mm thick cement plaster 1:6 all completer | 27.22 m2 | /m2 | 67.65 | 1841.47 |
| 3. | steel structural work welded in single section for M.S. Door etc complete | 80.00 Kg | Kg | 46.35 | 3708.00 |
| 4. | White washing 2 coats with lime etc complete | 160.00 m2 | /m2 | 4.10 | 656.00 |
| 5. | Colour washing with lime all complete | 50.00 m2 | /m2 | 4.86 | 243.00 |
| 6. | Painting with synthetic enamel paint etc complete | 29.00 m2 | /m2 | 22.85 | 662.65 |
| 7. | Dismantling old plaster etc complete | 32.41 m2 | /m2 | 8.20 | 265.76 |
| | | | Total (Rs.) | | 12683.98 |
| | | | Say Rs. | | 12684.00 |

**Bill of Quantity for Repair & Maintenance of Qtr No. 261, at Adarsh Colony,
Angarpathra Colliery under Katras Area. (Sl.No.10).**

| Sl. No. | Item | Quantity | Unit | Rate | Amount |
|---------|--|-----------|------------------|--------|------------------|
| 1. | White wash old work | 267.00 m2 | /m2 | 4.10 | 1094.70 |
| 2. | Colour wash old work | 100.00 m2 | /m2 | 3.85 | 385.00 |
| 3. | 12 mm thick cement plaster 1:6 | 32.00 m2 | /m2 | 72.70 | 2326.40 |
| 4. | 25 mm thick P.S. flooring (1:2:4) all complete | 27.00 m2 | /m2 | 141.11 | 3809.97 |
| 5. | Steel work in built up section | 82.00 kg | Kg | 46.35 | 3800.70 |
| 6. | Fixing of door | 2 Nos | Each | 354.45 | 708.90 |
| 7. | Half brick work (1:4) in F&P all complete | 5.00 m2 | /m2 | 257.00 | 1285.00 |
| 8 | 12mm thick cement plaster 1:4 with punning | 17.00 m2 | /m2 | 97.90 | 1664.30 |
| 9 | Painting old work with synthetic enamel paint & etc complete | 47.00 m2 | /m2 | 22.85 | 1073.95 |
| | | | Total Rs. | | 16,148.57 |