

BHARAT COKING COAL LIMITED

(A Subsidiary of Coal India Limited)

Office of the General Manager, Katras Area

P.O. Sijua, Distt. Dhanbad.

Ref. No. BCCL/GM/IV/Civil/Quotation//2011-12/ 3246 Dated: 19.09.2011.

QUOTATION NOTICE

Sealed **QUOTATION** is invited in percentage rate above/below basis in **single part** from Experienced and bonafide resourceful civil contractors for the following civil works:-

Sl. No.	Nature of Job & Location	Estimated Cost	Earnest Money	Cost of Tender Paper	Time of Completion
1.	Repair & Maintenance of office Building, Tool rooms at 6 pit of Gaslitand Colliery under Katras Area.	Rs.46,568.08	Rs.466/-	Nil/-	20 Days.
2.	Repairing Roof of Survey section with Bitumen painting and repairing of False Ceiling in Survey section,patch repairing, White washing, Colour washing of office of the Project Officer at Katras Choitudih Colliery under Katras Area.	Rs.40,890.17	Rs.410/-	Nil.	15 Days.
3.	Maintenance of Community Centre (Shiv Mandir,) Kali Mandir near office at Angarpathra Colliery under Katras Area.	Rs.22,081.62	Rs.221/-	Nil.	15 Days.
4.	Maintenance of 'C' Type Bungalow occupied by Sri Sanjay Singh,ACM of Ramkanali Colliery & residing at Katras Choitudih Colliery under Katras Area.	Rs.12,702.00	Rs.128/-	Nil.	10 Days.
5.	Repair /Maintenance of Qtr.No./Block No.AE/10,Qtr.No.10 at Angarpathra Colliery under Katras Area.	Rs.11,873.30	Rs.120/-	Nil.	10 days
6.	Repairing of Quarter No.H/AP/10 X at Angarpathra Colliery under Katras Area.	Rs.9,555.17	Rs.96/-	Nil.	10 days.

Date and time of receipt/opening of Quotation :-

a) The quotation will be received on

11.10.2011 from 10.00A.M. to 3.00 P.M. in a tender box kept at:-

i) **Office of** Asstt.Commandant,CISF. Camp,Angarpathra.

ii)CISF Post, near Koyala Bhawan gate,Koyala Nagar, BCCL,Dhanbad in Box marked Katras Area,

iii) CISF Post,Sijua Area V in tender box marked Katras Area,

iv) CISF Post,Govindpur Area-III in tender box marked Katras Area,.

Cont'd...p/2,

The quotations received will be opened **on 13.10.2011 at 4.00 P.M. in the office of the Area Civil Engineer, Katras Area.**

All the materials and equipments required for this work will be responsibility of the contractor.

Contractors have to abide by the Labour regulations/abolitions Act. Govt. of India adopted by BCCL from time to time.

Conditional quotations will be out right rejecte4ed.

Late or delayed quotations will not be accepted.

Quotations will not be considered by postal means.

Bill of Quantity and site conditions or the other documents such as general terms & conditions, general Specifications and credentials responsibility of the contractors, additional safety measures etc. can be seen at the office of the undersigned which will be applicable to be contract. Bill of quantity also can be seen in the company website www.bccl.gov.in during time period.

Requisite Earnest Money is to be deposited in cash with the Cashier/Dy.Manager(Finance)/Sr.F.O., Katras Area or A/c. payee Demand Draft by local nationalized bank in favour of BHARAT COKING COAL LIMITED payable at Dhanbad and proper money receipt should be enclosed with the quotations.

Income Tax clearance certificate /PAN.No. & VAT is to be submitted.

BCCL Management reserves its right to reject any or all of the quotations received or to split up and distribute the work between two or more contractors for which no reasons will be given what so ever.

Area Civil Engineer,
Katras Area.IV.

Copy to:-

1. General Manager, Katras Area,
2. G.M.(Civil), BCCL. Koyla Nagar,Dhanbad,
3. General Manager (Admn.), BCCL. Koyla Bhawan,
4. Sr.E.S. to C.V.O., Koyla Bhawan, BCCL.,
- 5 All Area CGM/GM's Areas & Projects of BCCL.
6. Addl.G.M./SO(Mining)/AFM/APM/AM(Plg.)/AM(Safety)/PM(Admn.),Katras Area,
- 7 All Project Officer's, Collys. Of Katras Area,
- 8 All SE(Civil), under Katras Area,
9. Sr.F.O./Cashier, Katras Area,
10. Notice Board, Katras Area,
11. LEO©, Katrasgarh,
12. The Secretary, Chhatabad Malkera Adarsh Shramik Sahayog Samiti Ltd.,
5 No. Chhatabad, At- Malkera Road, P.O. Katrasgarh, Dhanbad.
- 13.Asstt. Commandant,CISF Camp Angarpathra- with a request to depute Security personnel during the time period of receiving of tender near tender box and sealing the box at the time mentioned in NIT.
- 14.Commandant, CISF In-charge, Koyla Bhawwan BCCL Dhanbad -for necessary arrangement at his end.
15. Inspector Incharge,CISF Post, Govindpur Area-III,
- 16) Inspector Incharge,CISF Post, Sijua Area-V.
- 17) Manager(System), EDP,BCCL, Katras Area –along with a copy of NIT & BOQ.+ a C.D. against the above mentioned works for publication of the same in company website.
18. Tender File.

Bill of Quantity for Repair & Maintenance of office Building, Tool rooms at 6 pit of Gaslitand Colliery under Katras Area.

(Sl.No.1)

Sl. No.	Item	Quantity	Unit	Rate	Amount
1.	Dismantling cement plaster all complete.	102.144 m2	/m2	8.20	837.58
2.	12mm.thick cement plaster 1:6 complete job.	102.144m2	/m2	67.60	6910.04
3.	6mm. thick cement plaster 1:4 in Ceiling all complete	50.00m2	/m2	62.50	3125.00
4.	12mm. thick cement plaster 1:4 with a floating coat of neat cement punning all. complete	10.00 m2	/m2	97.90	979.00
5.	Dismantling A.C. Sheet roofing	27.385 m2	/m2	11.75	321.97
6.	Labour charge for A.C. Sheet roofing	13.450 m2	/m2	14.39	193.54
7.	P/F/F. A.C. Sheet roofing	13.935 m2	/m2	153.65	2141.11
8.	25mm.thick 1:2:4 flooring all complete.	50.233 m2	/m2	86.05	4322.54
9.	PCC 1:2:4 in floor	1.566 m3	/m3	3257.45	5101.16
10.	Dismantling brick work in c.m.	2.00 m3	/m3	310.76	621.50
11.	Kiln brick work in c.m.1:6 in Superstructure.all complete.	4.322 m3	/m3	2315.50	10,007.59
12.	Dismantling door/window	6 nos.	Each.	54.60	327.60
13.	Jamming door	3 nos.	Each.	345.45	1063.35
14.	Jamming window	3 nos.	Each.	214.20	642.60
15.	White washing two coats all complete	347.92 m2	/m2	4.10	1423.48
16.	Color washing two coats all complete.	181.141 m2	/m2	3.85	697.39
17.	Painting two coats with synthetic enamel paint all complete.	53.520 m2	/m2	22.85	1222.93
18.	Grading on roof 1:2:4 all complete.	2.00 m3	/m3	3314.95	6629.90
			Total (Rs.)		46,568.08

Bill of Quantity for Repairing Roof of Survey section with Bitumen painting and repairing of False Ceiling in Survey section, patch repairing, White washing, Colour washing of office of the Project Officer at Katras Choitudih Colliery under Katras Area. **(Sl.No.2).**

Sl. No.	Item	Quantity	Unit	Rate	Amount
1.	Bitumen painting all complete.	215.00 m2	/m2	15.00	3225.00
2.	12mm.thick cement plaster 1:6 complete job.	72.50m2	/m2	67.65	4904.62
3.	White washing all complete	377.00m2.	/m2	4.10	1545.70
4.	Color washing to coats all complete	198.88 m2	/m2	3.85	765.68
5.	P/F. frame for False Ceiling	0.50 m3	/m3	30511.95	15255.97
6.	P/F. insulated board 12mm in ceiling	48.79 m2	/m2	311.40	15193.20
				Total (Rs.)	40.890.17

Bill of Quantity for Maintenance of Community Centre (Shiv Mandir,) Kali Mandir near office at Angarpathra Colliery under Katras Area.

(Sl.No.3)

Sl. No.	Item	Quantity	Unit	Rate	Amount
1.	White washing all complete	407.60 m2	/m2	4.10	1671.16
2.	Color washing two coats all complete.	657.75m2	/m2	6.75	4439.81
3.	Providing water proofing cement paint (snowcem) one or more coats all complete.	399.91m2.	/m2	10.75	4299.03
4.	Distempering with oil bound distemper two coats all complete	387.75 m2	/m2	14.90	5777.47
5.	Painting with synthetic enamel Paint one or more coats all complete.	141.09 m2	/m2	22.85	3223.90
6.	12mm.thick cement plaster 1:6 all complete.	25.00 m2	/m2	67.65	1691.25
7.	12mm.thick cement plaster 1:4 with punning all complete.	10.00 m2	/m2	97.90	979.00
			Total (Rs.)		22,081.62

Bill of Quantity for Maintenance of 'C' Type Bungalow occupied by Sri Sanjay Singh,ACM of Ramkanali Colliery & residing at Katras Choitudih Colliery under Katras Area..

(Sl.No.4)

Sl. No.	Item	Quantity	Unit	Rate	Amount
1.	Distempering with oil bound distemper two coats all complete	252.50 m2	/m2	14.90	3762.25
2.	Painting with synthetic enamel Paint one or more coats all complete.	120.00m2	/m2	22.85	2742.00
3.	Precast RCC slab(1:2:4) all complete.	0.05 m3	/m3	4880.15	244.00
4.	Providing steel Reinforcement all complete.	4.00 Kg.	/kg.	42.70	170.80
5.	Providing wash basin (550x450) all complete	1 No.	Each	1044.90	1044.90
6.	Half Brick work in c.m.1:4 all complete.	2.23 m2	/m2	257.22	573.60
7.	12mm.thick cement plaster 1:4 with punning all complete.	16.72 m2	/m2	97.90	1636.88
8.	P/F. Shower all complete	2 Nos.	Each.	101.95	203.90
9.	P/F. Bib cock all complete.	8 Nos.	Each	120.85	966.80
10.	12mm.thick C.P. 1:6 all complete.	15.00 m2	/m2	67.65	1014.75
11.	Providing Glass panes	0.80 m2	/m2	427.60	342.08
			Total (Rs.)		12,702.00

Bill of Quantity for Repair /Maintenance of Qtr.No./Block No.AE/10,Qtr.No.10 at Angarpathra Colliery under Katras Area.

(Sl.No.5)

Sl. No.	Item	Quantity	Unit	Rate	Amount
1.	12mm.thick C.P. 1:6 all complete.	80.00 m2	/m2	67.65	5412.00
2.	12mm.thick cement plaster 1:4 with punning all complete.	5.00 m2	/m2	97.90	489.50
3.	25mmn.thick cement concrete flooring 1:2:4 all complete.	15.00m2	/m2	141.11	2116.65
4.	Providing steel door all complete.	36.00 kg	/kg.	48.95	1762.20
5.	Fixing of steel door	1 No.	Each.	354.45	354.45
6.	Color washing two coats all complete.	75.00 m2	/m2	3.85	288.75
7.	White washing two coats all complete.	160.00 m2	/m2	4.10	650.00
8.	Painting with synthetic enamel Paint one or more coats all complete..	35.00 m2	/m2	22.85	799.75
			Total (Rs.)		11,873.30

Bill of Quantity for Repairing of Quarter No.H/AP/10 X at Angarpathra Colliery under Katras Area.
(Sl.No.6)

Sl. No.	Item	Quantity	Unit	Rate	Amount
1.	White washing two coats all complete.	368.00 m2	/m2	4.10	1508.80
2.	Painting with synthetic enamel Paint one or more coats all complete..	28.00 m2	/m2	22.85	639.80
3.	25mmn.thick cement concrete flooring 1:2:4 all complete.	12.00m2	/m2	141.11	1693.32
4.	12mm.thick C.P. 1:6 all complete.	26.00m2	/m2.	72.70	1890.20
5.	Brick work in c.m. 1:6 in Superstructure all complete.	1.00 m3	/m3.	2137.95	2137.95
6.	P/F. A.C. sheet roofing all completer.	6.00 m2	/m2	280.85	1685.10
			Total (Rs.)		9,555.17

