



BHARAT COKING COAL LIMITED

(A Subsidiary of Coal India Limited)
Office of the General Manager, Katras Area
P.O. Sijua Distt. Dhanbad.

Ref. No. BCCL/GM/IV/Civil/ Quotation/11-12/3725

Dated: 10/11.10.2011

QUOTATION NOTICE

Sealed QUOTATION is invited in percentage rate above/below basis in single part from experienced and bonafide resourceful civil contractors for the following civil works :-

<u>Sl. No.</u>	<u>Nature of Job & location</u>	<u>Estimated Cost</u>	<u>Earnest Money</u>	<u>Time of Completion</u>
1	Renovation of guest room at Katras Thana under Katras Area.	₹9,979.78	₹100/-	10 Days
2	Roof repairing for seepage of water at Katras Thana Office under Katras Area.	₹9,924.10	₹100/-	10 Days
3	Repair and maintenance of Shiv Mandir of Katras Thana under Katras Area.	₹9,575.60	₹96/-	10 Days
4	Repair and maintenance of club of Katras Thana under Katras Area.	₹9,583.25	₹96/-	10 Days

Date and time of receipt/opening of Quotation

- a) The quotation will be received on **25.10.2011** from 10.00A.M. to 3.00 P.M. in tender box kept at
- Office of Asstt.Commandant,CISF. Camp,Angarpathra
 - CISF Post, near Koyala Bhawan gate,Koyala Nagar, BCCL,Dhanbad in Box marked Katras Area.
 - CISF Post, Sijua Area V in tender box marked Katras Area,
 - CISF Post, Govindpur Area-III in tender box marked Katras Area,.
- b) The quotations received will be opened on **28.10.2011** at 4.00 P.M. in the office of the Area Civil Engineer, Katras Area.

All the materials and equipments required for this work will be responsibility of the contractors.

Contractors have to abide by the Labour regulation /abolition Act. Govt. of India adopted by BCCL time to time.

Conditional quotations will be out-right rejected.

Late or delayed quotations will not be accepted.

Quotations will not be considered by postal means.

contd...pg2

Bill of Quantity and site conditions or the other documents such as general terms & conditions, general specifications and credentials, responsibility of the contractors, additional safety measures etc. can be seen at the office of the undersigned which will be applicable to the contract. Bill of quantity also can be seen in the company website www.bccl.gov.in during time period.

Requisite Earnest Money is to be deposited in cash with the Cashier/ Dy.Manager (Finance)/Sr. F.O., Katras Area or A/c Payee Demand Draft by local nationalized bank in favour of BHARAT COKING COAL LIMITED payable at Dhanbad and proper money receipt should be enclosed with the quotations.

Income Tax clearance certificate /PAN.No. & VAT is to be submitted.

BCCL Management reserves its right to reject any or all of the quotations received or to split up and distribute the work between two or more contractors for which no reasons will be given what so ever.

Area Civil Engineer
Katras Area-IV

Copy to :-

- 1) General Manager, Katras Area,
- 2) G.M.(Civil), BCCL. Koyla Nagar,Dhanbad,
- 3) General Manager (Admn.), BCCL. Koyla Bhawan,
- 4) Sr.E.S. to C.V.O., Koyla Bhawan, BCCL.,
- 5) All Area CGM/GM's Areas & Projects of BCCL.
- 6) Addl.G.M./SO(Mining)/AFM/APM/AM(Plg.)/AM(Safety)/PM(Admn.),,Katras Area
- 7) All Project Officer's, Collys. Of Katras Area.
- 8) All SE(Civil), under Katras Area
- 9) Sr.F.O./Cashier, Katras Area
- 10) Notice Board, Katras Area
- 11) LEO®, Katrasgarh.
- 12) The Secretary, Chhatabad Malkera Adarsh Shramik Sahayog Samiti Ltd.,
5 No. Chhatabad, At- Malkera Road, P.O. Katrasgarh, Dhanbad.
- 13) Asstt. Commandant,CISF Camp Angarpathra- with a request to depute Security personnel during the time period of receiving of tender near tender box and sealing the box at the time mentioned in NIT.
- 14) Commandant, CISF In-charge, Koyla Bhawwan BCCL Dhanbad -for necessary arrangement at his end.
- 15) Inspector Incharge,CISF Post, Govindpur Area-III.
- 16) Inspector Incharge,CISF Post, Sijua Area-V.
- 17) Manager(System), EDP,BCCL, Katras Area –along with a copy of NIT & BOQ.+ a C.D. against the above mentioned works for publication of the same in company website.
- 18) Tender File.

Bill of Quantity for Renovation of guest room at Katras Thana
under Katras Area.

Sl. No.	Item	Quantity	Unit	Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means foundation trenches, drain not exceeding 1.5 m in width as well as 10 sqm on plan including dressing of sides and ramming of bottom, lift up to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed within a lead of 50 m. (All kinds of soils).	cum	1.17	103.40	120.97
2	Providing and laying cement concrete of specified grade excluding the cost of centering and shuttering in all works up to plinth level : 1:4:8 (1cement : 4coarse sand : 8graded stone aggregates 40 mm nominal size).	cum	1.26	2449.00	3085.74
3	Brick work with FPS bricks of class designation 50 in foundation and plinth using cement mortar 1:6 (1cement : 6coarse sand).	cum	0.58	2007.00	1164.06
4	Half brick masonry with FPS bricks of class designation 50 in foundation and plinth in cement mortar 1:4 (1cement : 4coarse sand).	sqm	8.00	288.45	2305.80
5	Brick work with FPS bricks of class designation 50 in superstructure using cement mortar 1:6 (1cement : 6coarse sand).	cum	0.30	2137.95	641.38

6	Cement concrete flooring 1:2:4 (1cement : 2coarse sand : 4graded stone aggregates) finished with a floating coat of neat cement including cement slurry but excluding the cost of nosing of steps etc. complete: 40 mm thick with 20 mm nominal size stone aggregates.	sqm	13.23	192.95	2552.72
7	12mm cement plaster of mix: 1:6 (1cement : 6coarse sand).	sqm	1.50	72.70	109.09
Total (₹)					9,979.78

Bill of Quantity for Roof repairing for seepage of water at Katras
Thana Office under Katras Area.

Sl. No.	Item	Quantity	Unit	Rate	Amount
1	Cement washing with sand cow dung and water proofing compound.	cum	334.00	19.88	6639.92
2	12mm cement plaster of mix: 1:4 (1cement : 4coarse sand).	sqm	24.00	82.55	1981.20
3	Providing and laying cement concrete of specified grade excluding the cost of centering and shuttering in all works up to plinth level : 1:2:4 (1cement : 2coarse sand : 4graded stone aggregates 20 mm nominal size).	cum	0.40	3257.45	1302.98
Total (₹)					9,924.10

**Bill of Quantity for Repair and maintenance of Shiv Mandir of
Katras Thana under Katras Area.**

Sl. No.	Item	Quantity	Unit	Rate	Amount
1	Grading roof for water proofing treatment with: Cement concrete 1:2:4 (1cement : 2coarse sand : 4graded stone aggregate 20 mm nominal size)	cum	2.00	3314.95	6629.90
2	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: One or more coats on old work.	sqm	31.00	22.85	708.35
3	Distempering with dry distemper of approved brand and manufacture (one or more coats) and of required shade on old work to give an even shade.	sqm	156.00	12.35	1926.60
4	6mm cement plaster of mix 1:3 (1cement : 3 fine sand).	sqm	5.00	62.15	310.75
Total (₹)					9,575.60

Bill of Quantity for Repair and maintenance of club of Katras
Thana under Katras Area.

Sl. No.	Item	Quantity	Unit	Rate	Amount
1	12mm cement plaster of mix: 1:6 (1cement : 6coarse sand).	sqm	16.00	72.70	1163.20
2	6mm cement plaster of mix 1:3 (1cement : 3 fine sand).	sqm	15.00	62.15	932.25
3	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: One or more coats on old work.	sqm	30.00	22.85	685.50
4	White washing with lime to give an even shade: Old work (two or more coats).	sqm	109.00	4.10	446.90
5	Grading roof for water proofing treatment with: Cement concrete 1:2:4 (1cement : 2coarse sand : 4graded stone aggregate 20 mm nominal size)	cum	1.59	3314.95	5270.77
6	Colour washing with lime to give an even shade: Old work (two or more coats).	sqm	78.00	4.86	379.08
7	25mm thick p.s. flooring (1:2:4).	sqm	5.00	141.11	705.55
Total (₹)					9,583.25