

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Limited)
Office of the General Manager, Katras Area
P.O. Sijua, Distt. Dhanbad.

Ref. No. BCCL/GM/IV/Civil/Quotation//2011-12/ **3936**

Dated: 20.10.2011.

QUOTATION NOTICE

Sealed **QUOTATION** is invited in percentage rate above/below basis in **single part** from experienced and bonafide resourceful civil contractors for the following civil works:-

Sl. No.	Nature of Job & Location	Estimated Cost	Earnest Money	Cost of Tender Paper	Time of Completion
1.	Providing,fitting,fixing 25 Nos. steel doors and windows at Ramkanali Colliery under Katras Area.	Rs.44,913.75	Rs.450/-	Nil/-	15 Days.
2.	Fixing of barbed wire and board replacement of RCC precast slab of mainhole at Coal Dump colony under Katras Area.	Rs.8,462.29	Rs.85.00	Nil.	10 Days.
3.	Extension of pit water pipe line from KCC more to Shiv Mandir near workers colony,KCC under Katras Area.	Rs.11,727.30	Rs.118.00	Nil.	10 Days.
4.	Laying pipe line from KCC to CISF Camp & Qtr.of Anil Singh & Subhash Pandey at KCC under katra Arera.	Rs.13,035.80	Rs.131.00	Nil.	10 Days.
5.	Renewing pit water pipe line from Filter plant to Yule pit for workers quarters at KCC under Katras Area.	Rs.,19,577.90	Rs.196.00	Nil.	10 Days.
6.	Repair & Maintenance in the Qtr.,of Sri N.C. Mukherjee at Ramkanali under Katras Area.	Rs.15,097.13	Rs.151.00	Nil.	10 Days.

ate and time of receipt/opening of Quotation :-

a) The quotation will be received on

04.11.2011 from 10.00A.M. to 3.00 P.M. in a tender box kept at:-

i) Office of Asstt.Commandant,CISF. Camp,Angarpathra.

ii)CISF Post, near Koyala Bhawan gate,Koyala Nagar, BCCL,Dhanbad in Box marked Katras Area.

iii) CISF Post,Sijua Area V in tender box marked Katras Area,

iv) CISF Post,Govindpur Area-III in tender box marked Katras Area,.

b) The quotations received will be opened **on 07.11.2011 at 4.00 P.M. in the office of the Area Civil Engineer, Katras Area.**

All the materials and equipments required for this work will be responsibility of the contractor.

Contractors have to abide by the Labour regulations/abolitions Act. Govt. of India adopted by BCCLfrom time to time.

Cont.d..P/2.

Conditional quotations will be out right rejected.

Late or delayed quotations will not be accepted.

Quotations will not be considered by postal means.

Bill of Quantity and site conditions or the other documents such as general terms & conditions, general Specifications and credentials responsibility of the contractors, additional safety measures etc. can be seen at the office of the undersigned which will be applicable to be contract. Bill of quantity also can be seen in the company website www.bccl.gov.in during time period.

Requisite Earnest Money is to be deposited in cash with the Cashier/Dy.Manager(Finance)/Sr.F.O., Katras Area or A/c. payee Demand Draft by local nationalized bank in favour of BHARAT COKING COAL LIMITED payable at Dhanbad and proper money receipt should be enclosed with the quotations. Income Tax clearance certificate /PAN.No. & VAT is to be submitted.

BCCL Management reserves its right to reject any or all of the quotations received or to split up and distribute the work between two or more contractors for which no reasons will be given what so ever.

Area Civil Engineer,
Katras Area.IV.

Copy to:-

1. General Manager, Katras Area,
2. G.M.(Civil), BCCL. Koyla Nagar,Dhanbad,
3. General Manager (Admn.), BCCL. Koyla Bhawan,
4. Sr.E.S. to C.V.O., Koyla Bhawan, BCCL.,
- 5 All Area CGM/GM's Areas & Projects of BCCL.
6. Addl.G.M./SO(Mining)/AFM/APM/AM(Plg.)/AM(Safety)/PM(Admn.),Katras Area,
- 7 All Project Officer's, Collys. Of Katras Area,
- 8 All Sr.Managerr(Civil), under Katras Area,
9. Sr.F.O./Cashier, Katras Area,
10. Notice Board, Katras Area,
11. LEO©, Katrasgarh,
12. The Secretary, Chhatabad Malkera Adarsh Shramik Sahayog Samiti Ltd.,
5 No. Chhatabad, At- Malkera Road, P.O. Katrasgarh, Dhanbad.
- 13.Asstt. Commandant,CISF Camp Angarpathra- with a request to depute Security personnel during the time period of receiving of tender near tender box and sealing the box at the time mentioned in NIT.
- 14.Commandant, CISF In-charge, Koyla Bhawwan BCCL Dhanbad -for necessary arrangement at his end.
15. Inspector Incharge,CISF Post, Govindpur Area-III,
- 16) Inspector Incharge,CISF Post, Sijua Area-V.
- 17) Manager(System), EDP,BCCL, Katras Area –along with a copy of NIT & BOQ.+ a C.D. against the above mentioned work for publication of the same in company website.
18. Tender File.

Bill of Quantity for Providing,fitting,fixing 25 Nos. steel doors and windows at Ramkanali Colliery under Katras Area.

(Sl.No.1).

Sl. No.	Item	Quantity	Unit	Rate	Amount
1.	Dismantling door/window all complete.	25 Nos.	Each.	54.60	1365.00
2.	Providing steel door/window /structural steel work all complete.	705.00 kg.	/kg.	46.35	32676.75
3.	Fixing of door/window all complete a) Door b) B) Window	18 Nos. 7 Nos.	Each. Each.	354.45 214.20	6380.10 1499.40
4.	Providing two coat with synthetic enamel paint all complete.	90.00 m2	/m2	33.25	2992.50
			Total (Rs.)		44,913.75

Bill of Quantity for Fixing of barbed wire and board replacement of RCC precast slab of mainhole at Coal Dump colony under Katras Area.

(Sl.No.2).

Sl. No.	Item	Quantity	Unit	Rate	Amount
1.	Earth work in excavation	0.67 m3	/m3	103.40	69.27
2.	Providing, laying PCC 1:3:6 all complete.	0.67 m3	/m3.	2713.05	1817.78
3.	Providing two or more coats with synthetic enamel paint all complete.	5.00 m2	/m2.	51.30	256.50
4.	Steel work in single section all complete.	30.15 kg.	/kg.	42.15	1290.82
5.	Lettering with black japan paint of approved brand and manufacture. 2x131	262 Nos.	Each.	0.90	235.80
6.	Precast RCC Slab 1:2:4	0.50m3	/m3	6002.80	3061.42
7.	Reinforcement for RCC work all complete.	41.00 kg,	/kg.	42.70	1750.70
			Total (Rs.)		8,462.29

Bill of Quantity for Extension of pit water pipe line from KCC more to Shiv Mandir near workers colony,KCC under Katras Area.

(Sl.No.3).

Sl. No.	Item	Quantity	Unit	Rate	Amount
1.	Providing and laying G.I. Pipe 25mm.dia.	60 m	/m	156.85	9411.00
2.	Labour charge for laying pipe line etc.	60 m	/m.	35.00	2101.80
3.	Providing/fitting/fixing G.I. Union 25mm.dia. all complete.	2 Nos.	Each.	107.25	214.50
			Total (Rs.)		11,727.30

Bill of Quantity for Laying pipe line from KCC to CISF Camp & Qtr.of Anil Singh & Subhash Pandey at KCC under Katras Area..
(Sl.No.4).

Sl. No.	Item	Quantity	Unit	Rate	Amount
1.	Providing and laying G.I. Pipe 25mm.dia.	80 m	/m	156.85	12548.00
2.	Providing/fitting/fixing G.I. Union 25mm.dia. all complete.	3 Nos.	Each.	107.25	321.75
3.	Making connection all complete.	1 No.	Each.	166.05	166.05
			Total (Rs.)		13,035.80

Bill of Quantity for Renewing pit water pipe line from Filterr plant to Yule pit for worker's quarters at KCC under Katras Area..
(Sl.No.5).

Sl. No.	Item	Quantity	Unit	Rate	Amount
1.	Providing and laying G.I. Pipe 50mm.dia.	30 m	/m	280.10	8403.00
2.	P/F/ G.I pipe 25mm.dia.	60 mtr.	/mtr.	156.85	9411.00
3.	Providing/fitting/fixing G.I. Union 50mm.dia. all complete.	2 Nos.	Each.	235.60	471.20
4.	Providing/fitting/fixing G.I. Union 25 mm.dia. all complete.	4 Nos.	Each.	107.25	429.00
5.	P/F/ Gate valve 50mm.dia.	1 No.	Each.	578.20	578.20
6.	P/F/ Gate Valve 25mm.dia.	1 No.	Each.	285.50	285.50
			Total (Rs.)		19,577.90

**Bill of Quantity for Repair & Maintenance in the qtr. of Sri N.C. Mukherjee,
at Ramkanali Colliery under Katras Area.
(Sl.No.6).**

Sl. No.	Item	Quantity	Unit	Rate	Amount
1.	White wash old work.	130.00 m2	/m2	4.10	533.00
2.	Colour wash old work.	80 m2	/m2	3.85	308.00
3.	12mm thick C.P. 1:6. all complete.	35.00 m2.	/m2	72.70	2544.50
4.	12mm.thick C.P. 1:4 with punning all complete.	12.00 m2	/m2	97.90	1174.80
5.	25mm.thick P.S. Flooring 1:2:4 all complete.	25 m2	/m2	141.11	3527.75
6.	Steel work in built up/ single section all complete..	41.00 Kg.	/kg.	46.35	1900.35
7.	Fixing of door	1 No.	Each.	354.45	354.45
8.	P/F. precast RCC slab 1:2:4	0.35 m3	/m3	6002.80	2100.98
9.	Brick work 1:6 in F & P. all complete.	1.00 m3	/m3	2007.00	2007.00
10.	P/F. W.C.Pan	1 No.	Each.	534.60	534.60
11.	P/F. Foot rest	1 pair	Each pair	111.70	111.70
			Total (Rs.)		15,097.13