

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal India Limited)
Office of the General Manager, Katras Area
P.O. Sijua, Distt. Dhanbad.

Ref. No. BCCL/GM/IV/Civil/Quotation//2011-12/ **4022**

Dated: 24.10.2011.

QUOTATION NOTICE

Sealed **QUOTATION** is invited in percentage rate above/below basis in **single part** from experienced and bonafide resourceful civil contractors for the following civil works:-

Sl. No.	Nature of Job & Location	Estimated Cost	Earnest Money	Cost of Tender Paper	Time of Completion
1.	Water Supply pipe line works at 8 No. Colony of Salanpur Colliery under Katras Area.	Rs.29,127.50	Rs.292/-	Nil/-	15 Days.
2.	Repair/Maintenance of Area Sub-Station Building situated at 2 No.pit of KCC under Katras Area.IV.	Rs.42,433.43	Rs.425/-	Nil	15 Days.
3.	Repair/Maintenance of 'C' type Qtr.No.C/29 at Angarpathra Colliery under Katras Area.	Rs.18,232.75	Rs.183/-	Mil.	15 Days.
4.	Repair/Maintenance work of Qtr.No.CZ/JK/40,Qtr.No.7 of Sri Shankar Beldar at Angarpathra Colliery under Katras Area.	Rs.10,344.39	Rs.105/-	Nil.	10 Days.
5.	Repairing of Qtr.No.2, Block No.A-1 at Angarpathra Colliery under Katras Area.	Rs.3,939.75	Rs.40/-	Nil.	7 Days.
6.	Repair & Maintenance in the Qtr.No.7AC/AP/10 at Angarpathra Colliery under Katras Area.	Rs.9,947.47	Rs.100/-	Nil.	10 Days.

Date and time of receipt/opening of Quotation :-

a) The quotation will be received on

14.11.2011 from 10.00A.M. to 3.00 P.M. in a tender box kept at:-

i) Office of Asstt.Commandant,CISF. Camp,Angarpathra.

ii)CISF Post, near Koyala Bhawan gate,Koyala Nagar, BCCL,Dhanbad in Box marked Katras Area.

iii) CISF Post,Sijua Area V in tender box marked Katras Area,

iv) CISF Post,Govindpur Area-III in tender box marked Katras Area,.

b) The quotations received will be opened **on 16.11.2011 at 4.00 P.M. in the office of the Area Civil Engineer, Katras Area.**

All the materials and equipments required for this work will be responsibility of the contractor.

Contractors have to abide by the Labour regulations/abolitions Act. Govt. of India adopted by BCCLfrom time to time.

Cont.d..P/2.

Conditional quotations will be out right rejecte4ed.

Late or delayed quotations will not be accepted.

Quotations will not be considered by postal means.

Bill of Quantity and site conditions or the other documents such as general terms & conditions, general Specifications and credentials responsibility of the contractors, additional safety measures etc. can be seen at the office of the undersigned which will be applicable to be contract. Bill of quantity also can be seen in the company website www.bccl.gov.in during time period.

Requisite Earnest Money is to be deposited in cash with the Cashier/Dy.Manager(Finance)/Sr.F.O., Katras Area or A/c. payee Demand Draft by local nationalized bank in favour of BHARAT COKING COAL LIMITED payable at Dhanbad and proper money receipt should be enclosed with the quotations. Income Tax clearance certificate /PAN.No. & VAT is to be submitted.

BCCL Management reserves its right to reject any or all of the quotations received or to split up and distribute the work between two or more contractors for which no reasons will be given what so ever.

Area Civil Engineer,
Katras Area.IV.

Copy to:-

1. General Manager, Katras Area,
2. G.M.(Civil), BCCL. Koyla Nagar,Dhanbad,
3. General Manager (Admn.), BCCL. Koyla Bhawan,
4. Sr.E.S. to C.V.O., Koyla Bhawan, BCCL.,
- 5 All Area CGM/GM's Areas & Projects of BCCL.
6. Addl.G.M./SO(Mining)/AFM/APM/AM(Plg.)/AM(Safety)/PM(Admn.),,Katras Area,
- 7 All Project Officer's, Collys. Of Katras Area,
- 8 All Sr.Managerr(Civil), under Katras Area,
9. Sr.F.O./Cashier, Katras Area,
10. Notice Board, Katras Area,
11. LEO©, Katrasgarh,
12. The Secretary, Chhatabad Malkera Adarsh Shramik Sahayog Samiti Ltd.,
5 No. Chhatabad, At- Malkera Road, P.O. Katrasgarh, Dhanbad.
- 13.Asstt. Commandant,CISF Camp Angarpathra- with a request to depute Security personnel during the time period of receiving of tender near tender box and sealing the box at the time mentioned in NIT.
- 14.Commandant, CISF In-charge, Koyla Bhawwan BCCL Dhanbad -for necessary arrangement at his end.
15. Inspector Incharge,CISF Post, Govindpur Area-III,
- 16) Inspector Incharge,CISF Post, Sijua Area-V.
- 17) Manager(System), EDP,BCCL, Katras Area –along with a copy of NIT & BOQ.+ a C.D. against the above mentioned work for publication of the same in company website.
18. Tender File.

Bill of Quantity for Water Supply pipe line works at 8 No. Colony of Salanpur Colliery under Katras Area. (Sl.No.1).

Sl. No.	Item	Quantity	Unit	Rate	Amount
1.	Providing/Fitting G.I. pipe 50mm.dia. nominal bore	90.00 m.	/m	280.10	25,209.00
2.	P/F. G. I. Union 50mm.dia.	5 Nos.	Each.	335.50	1677.50
3.	P/F. G.I. pipe 15mm.dia. nominal bore	15 m.	/m.	94.05	1410.75
4.	Making Connection	50 Nos.	Each.	166.05	830.25
				Total:Rs.	29,127.50

Bill of Quantity for Repair/Maintenance of Area Sub-Station Building situated at 2 No. pit of KC Colliery under Katras Area. (Sl.No.2).

Sl. No.	Item	Quantity	Unit	Rate	Amount
1.	Grading roof with cement concrete 1:2:4	2.974 m3.	/m3	3257.45	9687.65
2.	Bitumen painting on roof	660.00 m2.	/m2	15.00	9900.00
3.	6mm.thick Ceiling plaster 1:3	33.28 m2	/m2.	62.15	2068.35
4.	Earth work excavation in foundation etc. complete.	2.09 M3	/M3	103.40	216.10
5.	Bick work in c.m. 1:6 in F & P. complete.with class 50 bricks	2.09 m3	/m3	2007.00	4194.63
6.	Brick work in c.m. 1:6 in Superstructure class-50 bricks all complete.	3.70 m3	/m3	2137.96	7910.45
7.	12mm.thick cement plaster 1:6 all complete	125.00 m2	/m2	67.65	8456.25
				Total:Rs.	42,433.43

Bill of Quantity for Repair/Maintenance of 'C' type Qtr.No. C/29 at Angarpathra Colliery under Katras Area. (Sl.No.3).

Sl. No.	Item	Quantity	Unit	Rate	Amount
1.	Distempering with oil bound distemper old work	304.00 m2.	/m2	14.90	4529.60
2.	Removing old oil bound distemper	92.00 m2	/m2	4.25	391.00
3.	Applying one coat of cement paint	92.00 m2.	/m2.	17.20	1582.40
4.	Painting with synthetic enamel paint old work	98.17 m2	/m2.	22.85	2243.18
5.	Steel work in built up section	30 kg.	/kg.	46.35	1390.50
6.	Fixing of Window	1 No.	Each.	214.20	214.20
7.	12mm.thick cement plaster 1:6	21.00 m2	/m2	72.70	1526.70
8.	6mm.thick cement plaster 1:3 in Ceiling	5.00 m2	/m2	62.15	310.75
9.	Providing,laying PCC 1:2:4 c.mix.	0.33 m3	/m3	3257.45	1074.95
10.	Renewing Glass panes	0.74 m2	/m2	427.60	316.92
11.	P/F. alluminium sliding door bolt 300x16mm.	1 No.	Each.	158.50	258.50
12.	P/F. PVC low leveling flushing cistern complete.	1 No.	Each.	709.75	709.75
13.	P/F. Mirror	2 No.	Each.	493.65	989.30
14.	P/F. Brass bib cock 15mm.dia.	3 Nos.	Each.	191.70	575.10
15.	P/F/F. Glass shelf	1 No.	Each.	218.80	218.80
16.	P/F. Wash Basin complete job.	1 No.	Each.	1776.10	1776.10
17.	White wash old work	55.00 m2	/m2	4.10	225.50
				Total:Rs.	18,232.75

Bill of Quantity for Repair/Maintenance work of Qtr.No.CZ/JK/40,Qtr.No.7 of Sri Shankar Beldar at Angarpathra Colliery under Katras Area. (Sl.No.4).

Sl. No.	Item	Quantity	Unit	Rate	Amount
1.	White wash two coats all complete	104.00 m2.	/m2	4.10	426.40
2.	Color wash two coats all complete	53.00 m2.	/m2	6.75	357.75
3.	Painting two coats all complete	17.40 m2	/m2.	22.85	397.59
4.	12mm.thick cement plaster 1:6 all complete	20.00 M2	/M2	67.65	1353.00
5.	12mm.thick cement plaster 1:4 with punning all complete	5.00 m2	/m2	97.90	1489.50
6.	25mm.thick cement concrete flooring 1:2:4 all complete.	30.00 m2	/m2	141.11	4233.30
7.	Providing A.C. sheet roofing all complete	13.00 m2	/m2	237.45	3086.85
				Total:Rs.	10,344.39

Bill of Quantity for Repair of Qtr.No.2, ,Block No.A-1 at Angarpathra Colliery under Katras Area. (Sl.No.5).

Sl. No.	Item	Quantity	Unit	Rate	Amount
1.	P/F/ RCC slab 1:2:4 all complete.	0.14 m3.	/m3	6002.80	840.39
2.	Reinforcement for RCC work	12.00 Kg.	/kg.	42.70	512.40
3.	Demolishing RCC slab	0.14 m3	/m3.	537.55	75.25
4.	White wash two coats old work all complete	129.00 M2	/M2	4.10	528.90
5.	Providing A.C. sheet roofing all complete	2.78 m2	/m2	294.95	819.96
6.	Half brick work 1:4 c.m.all complete.	1.87 m2	/m2	245.00	458.15
7.	12mm.thick cement plaster 1:4 with punning all complete.	2.00 m2	/m2	97.90	195.80
8.	12mm.thick cement plaster 1:6 all complete	7.00 m2	/m2	72.70	508.90
				Total:Rs.	3,939.75

Bill of Quantity for Repair /Maintenance work in the Qtr.No.7AC/AP/10 at Angarpathra Colliery under Katras Area. (Sl.No.6).

Sl. No.	Item	Quantity	Unit	Rate	Amount
1.	White wash two coats all complete	140.00 m2.	/m2	4.10	574.00
2.	Color wash two coats all complete	80.00 m2.	/m2	3.85	308.00
3.	12mm.thick cement plaster 1:6 all complete	41.00 m2	/m2	72.70	2973.73
3.	Painting two coats all complete	35.00 m2	/m2.	22.85	799.75
4.	Structural steel work in built up section	41.00 kg.	/kg.	46.35	1900.35
5.	Fixing of door	1 No.	Each.	354.45	354.45
6.	25mm.thick cement concrete flooring 1:2:4 all complete.	18.00 m2	/m2	141.11	2539.99
7.	6mm. thick cement plaster 1:3 in ceiling all complete	8.00 m2	/m2	62.15	497.20
				Total:Rs.	9947.47

