



## BHARAT COKING COAL LIMITED

(A Subsidiary of Coal India Limited)

Office of the General Manager, Katras Area

P.O. Sijua Distt. Dhanbad.

Ref. No. BCCL/GM/IV/Civil/ Quotation/11-12/5687

Dated: 04.10.2011

### **QUOTATION NOTICE**

Sealed QUOTATION is invited in percentage rate above/below basis in single part from experienced and bonafide resourceful civil contractors for the following civil works :-

<u>Sl. No.</u>	<u>Nature of Job &amp; location</u>	<u>Estimated Cost</u>	<u>Earnest Money</u>	<u>Time of Completion</u>
1	Drain cleaning at 8 no. colony, Latail Dhowra, New Lakarka and selected Govindpur Colony of Salanpur Colliery under Katras Area.	₹25,569.76	₹256/-	10 Days
2	Ash cleaning at different places at Hirak Colony at Salanpur Colliery under Katras Area.	₹19,844.60	₹199/-	10 Days
3	Ash cleaning at N.Lakarka, 8 no. Colony, Latail Dhowra and Selected Govindpur Colony under Katras Area.	₹34,778.68	₹348/-	10 Days
4	Drain cleaning at Hirak Colony of Salanpur Colliery under Katras Area.	₹14,646.97	₹147/-	10 Days
5	Repair of fallen part of Monsoon drain no. 2 at Salanpur Colliery under Katras Area.	₹48,502.57	₹485/-	15 Days

### **Date and time of receipt/opening of Quotation**

- The quotation will be received on **21.10.2011** from 10.00A.M. to 3.00 P.M. in tender box kept at
  - Office of Asstt.Commandant,CISF. Camp,Angarpathra
  - CISF Post, near Koyala Bhawan gate,Koyala Nagar, BCCL,Dhanbad in Box marked Katras Area.
  - CISF Post, Sijua Area V in tender box marked Katras Area,
  - CISF Post, Govindpur Area-III in tender box marked Katras Area.,
- The quotations received will be opened on **24.10.2011** at 4.00 P.M. in the office of the Area Civil Engineer, Katras Area.

All the materials and equipments required for this work will be responsibility of the contractors.

Contractors have to abide by the Labour regulation /abolition Act. Govt. of India adopted by BCCL time to time.

contd...pg2

Conditional quotations will be out-right rejected.  
Late or delayed quotations will not be accepted.  
Quotations will not be considered by postal means.

Bill of Quantity and site conditions or the other documents such as general terms & conditions, general specifications and credentials, responsibility of the contractors, additional safety measures etc. can be seen at the office of the undersigned which will be applicable to the contract. Bill of quantity also can be seen in the company website [www.bccl.gov.in](http://www.bccl.gov.in) during time period.

Requisite Earnest Money is to be deposited in cash with the Cashier/ Dy.Manager (Finance)/Sr. F.O., Katras Area or A/c Payee Demand Draft by local nationalized bank in favour of BHARAT COKING COAL LIMITED payable at Dhanbad and proper money receipt should be enclosed with the quotations.

Income Tax clearance certificate /PAN.No. & VAT is to be submitted.

BCCL Management reserves its right to reject any or all of the quotations received or to split up and distribute the work between two or more contractors for which no reasons will be given what so ever.

Area Civil Engineer  
Katras Area-IV

Copy to :-

- 1) General Manager, Katras Area,
- 2) G.M.(Civil), BCCL. Koyla Nagar,Dhanbad,
- 3) General Manager (Admn.), BCCL. Koyla Bhawan,
- 4) Sr.E.S. to C.V.O., Koyla Bhawan, BCCL.,
- 5) All Area CGM/GM's Areas & Projects of BCCL.
- 6) Addl.G.M./SO(Mining)/AFM/APM/AM(Plg.)/AM(Safety)/PM(Admn.),,Katras Area
- 7) All Project Officer's, Colls. Of Katras Area.
- 8) All SE(Civil), under Katras Area
- 9) Sr.F.O./Cashier, Katras Area
- 10) Notice Board, Katras Area
- 11) LEO©, Katrasgarh.
- 12) The Secretary, Chhatabad Malkera Adarsh Shramik Sahayog Samiti Ltd.,  
5 No. Chhatabad, At- Malkera Road, P.O. Katrasgarh, Dhanbad.
- 13) Asstt. Commandant,CISF Camp Angarpathra- with a request to depute Security personnel during the time period of receiving of tender near tender box and sealing the box at the time mentioned in NIT.
- 14) Commandant, CISF In-charge, Koyla Bhawwan BCCL Dhanbad -for necessary arrangement at his end.
- 15) Inspector Incharge,CISF Post, Govindpur Area-III.
- 16) Inspector Incharge,CISF Post, Sijua Area-V.
- 17) Manager(System), EDP,BCCL, Katras Area –along with a copy of NIT & BOQ.+ a C.D. against the above mentioned works for publication of the same in company website.
- 18) Tender File.

**Bill of Quantity for Drain cleaning at 8 no. colony, Latail  
Dhowra, New Lakarka and selected Govindpur Colony of  
Salanpur Colliery under Katras Area.**

Sl. No.	Item	Quantity	Unit	Rate	Amount
1	Cleaning ash, garbage, sludge, muck, mud etc. in drain.	cum	168.90	108.42	18312.13
2	Carriage of garbage sludge upto 1km lead.	cum	168.90	42.97	7257.63
<b>Total (₹)</b>					<b>25,569.76</b>

**Bill of Quantity for Ash cleaning at different places at Hirak  
Cololny at Salanpur Colliery under Katras Area.**

Sl. No.	Item	Quantity	Unit	Rate	Amount
1	Cleaning cutting ash, garbage, etc.	cum	156.80	83.59	13106.91
2	Carriage of ash upto 1km lead.	cum	156.80	42.97	6737.69
<b>Total (₹)</b>					<b>19,844.60</b>

**Bill of Quantity for Ash cleaning at N.Lakarka, 8 no. Colony,  
Latail Dhowra and Selected Govindpur Colony under Katras  
Area.**

Sl. No.	Item	Quantity	Unit	Rate	Amount
1	Cutting ash / garbage for cleaning.	cum	274.80	83.59	22970.53
2	Carriage of ash upto 1km lead.	cum	274.80	42.97	11808.15
<b>Total (₹)</b>					<b>34,778.68</b>

**Bill of Quantity for Drain cleaning at Hirak Colony of Salanpur**  
**Colliery under Katras Area.**

Sl. No.	Item	Quantity	Unit	Rate	Amount
1	Cleaning drain do-do-complete.	cum	96.75	108.42	10489.63
2	Carriage of garbage sludge etc. 1km lead.	cum	96.75	42.97	4157.34
<b>Total (₹)</b>					<b>14,646.97</b>

**Bill of Quantity for Repair of fallen part of Monsoon drain no. 2**  
**at Salanpur Colliery under Katras Area.**

Sl. No.	Item	Quantity	Unit	Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means foundation trenches, drain not exceeding 1.5 m in width as well as 10 sqm on plan including dressing of sides and ramming of bottom, lift up to 1.5 m including getting out the excavated soil and disposal of surplus excavated soil as directed within a lead of 50 m. (All kinds of soils).	cum	36.22	103.40	3745.14
2	Providing and laying cement concrete of specified grade excluding the cost of centering and shuttering in all works up to plinth level : 1:4:8 (1cement : 4 fine sand : 8graded stone aggregates 40 mm nominal size).	cum	3.98	2296.15	9138.67
3	Quarry boulder masonry work with cm (1:6).	cum	19.77	1290.08	25504.88
4	Providing and laying cement concrete of specified grade excluding the cost of centering and shuttering in all works up to plinth level : 1:2:4 (1cement : 2coarse sand : 4graded stone aggregates 20 mm nominal size).	cum	1.63	3257.45	5309.64
5	Pointing on stone work with cement mortar 1:3 (1cement : 3fine sand): Flush / Ruled pointing.	sqm	48.32	62.50	3020.00
6	Carriage of quarry boulder upto 2 km lead.	cum	19.77	90.25	1784.24
<b>Total (₹)</b>					<b>48,502.57</b>