

Bharat Coking Coal Limited
Sijua Area

Ref.No.GM/SA/Civil/ 2575 /2011

Dated 01/02.08.2011

Quotation Notice

Sealed quotations will be received in % age rate above/below basis in contractors their letter pad from BCCL, experience and bonafide resourceful civil contractors.

Sl.	Name of work	Estimated cost	Earnest money	Time of completion
1.	Sanitary fitting work for the bungalow of Addl.G.M. at Sijua Area.	Rs.24,048=76	Rs.240=00	15 days
2.	Damaged changing, pit water/drinking water pipe quarter of Ruth Parween (Metro) at R.H.Loyabad.	Rs.19,382=25	Rs.194=00	- do -
3.	Renovation of drain and heightening wall in the workshop at Sendra Bansjora colliery.	Rs.23,047=33	Rs.230=00	-do-
4.	Repair & maintenance of staff Re-creation club under Sijua Area.	Rs.25,196=67	Rs.252=00	-do-
5.	Making retaining wall for storage of water in Ekra jore near Ekra patch at Bansdeopour colliery.	Rs.29,691=37	Rs.297=00	-do-
6.	Supply of good earth at PST 2 & O seam rehabilitation site Tetulmari colliery.	Rs.27,753=00	Rs.278=00	-do-
7.	Making survey pittar at NOCP patch I and II for survey control Nichitpur.	Rs.12,317=01	Rs.123=00	-do-
8.	Making viow point(Challa) setting stone corner of Hole road and spreading lime at NOCP for Safety Inspection.	Rs.14,021=50	Rs.140=00	-do-
9.	Dismantling of Hutment on edge of OCP drain cuttings cleaning near Banarshi pond at Tetulmari colliery.	Rs.12,623=17	Rs.126=00	-do-

contd...p/2.....

10. Dismantling of shad from

Bansjora O.C.P.

Rs.16,774=65

Rs.168=00

-do-

Availability of quotation documents from 08.08.2011 to 12.08.2011

Quotation documents can be obtained on all working days during working hours except on Sundays & Holidays. In the event of the specified date for submission/opening of bids being declared a holiday the bids will be received/ opened on the appointed time on the next working day.

Time and date of receipt/opening of quotation:

- a) The quotation will be received on 17.08.2011 from 10.00 A.M. to 03.00 P.M. in Tender Box kept at :
- I) CISF Post Sijua Area Office campus.
 - II) CISF Post near gate Koyla Bhawan, BCCL, Dhanbad.
 - III) Office of the Asst. Commandant CISF Camp, Angarpathra Katras Area IV.
 - IV) Office of the Dy. Commandant CISF Camp, Kusunda Area VI.
- b) The quotation received will be opened on 19.08.2011 at 11.00 A.M. in the office of the Addl. General Manager, Sijua Area.
- c) The quotation documents can be obtained during normal office hours during the period mentioned above on production of application request issued of quotation.
- d) Completed sealed quotation documents (Part I & II) should be submitted at the same time.

Part-I shall consist of sales tax/VAT clearance certificate & PAN No.

Part-II shall consist of quotation documents as issued to the quotationers duly

filled in for rates, amounts etc. i.e. price bid.

The earnest money deposited is to be submitted in a spate Envelope superscribing "Earnest money deposit" (Earnest money to be submitted in form of cash or Bank draft of Nationalized Bank/scheduled commercial bank approved by Reserve Bank of India in favour of Bharat Coking Coal Ltd. payable at Dhanbad).

The bids shall be submitted in three separate envelopes.

Envelope – I should contain E.M.D.

Envelope-II should contain sales tax/VAT clearance certificate & PAN No.

Envelope-III should contain price bid.

Thereafter, all the three envelopes should be submitted in one sealed envelope.

Terms & conditions:

1. The management of BCCL reserves right to reject any or all quotations or split the work between the quotationers without assigning any reasons whatsoever.
2. The responsibility for procurement of all materials required for the work shall be with the contractors.
3. Conditional/incomplete quotation shall be outright rejected.

Contd...p/3....

4. The validity of the quotations shall be 4(four) months from the date of opening of price bid or revised offer whichever is later.
5. Quotation without earnest money shall be out right rejected.
6. All other terms & conditions is as per general NIT rule of BCCL.
7. In case of any injury/accident it will be the responsibility of the Contractor to pay all legal dues their workers.
8. The tenderers are advice to submit their Bank A/C No. Name of Bank & Name of Branch.
9. Contractors have to abided by the Labour regulation/abolition Act. Govt. of India adopted by BCCL.

Area Civil Engineer
Sijua Area.

E.S. to E.D.(Vig.),BCCL,Koyla Bhawan

Cc to: G.M.(Civil) Koyla Bhawan

Cc to: G.M.(Welfare)Koyla Bhawan

Cc to: G.M.(System),with a request to display this NIT in BCCL website.

The downloading facility should be available during the period of sale of
Tender document only.

Cc to: G.M.,Sijua Area

Cc to: A.G.M., -do-

Cc to: A.F.M. -do-

Cc to: PM(Admn.),Sijua Area

Cc to: All CGM/GMs Area-I to Area-12,Block-II,E/Jharia & W/Jharia.

Cc to: All Project Officer,Sijua Area.

Cc to: Civil Tender Notice Board kept at CISF Office,Sijua Area..

Cc to: Inspector I/C. CISF,Koyla Bhawan.

Cc to: Asstt.Commandant,CISF,Sijua Area/CISF Camp Angarpathra ,Katras Area IV.

Cc to: Dy,Commandant,CISF Kusunda Area Office Area VI.

Cc to: The Secretary Chhatabad Malkera Adarsh Shramik Sahyog Samiti Ltd.Chhattabad
Katrasgarh,Dhanbad.

Cc to: Builders Association of India,Central Akashkinaree Kanta Garh,Dhanbad-828113.

Cc to: Builders Association of india,316 LIG Housing Colony,Dhanbaad.

BHARAT COKING COAL LIMITED
SIJUA AREA

1. Name of work : _____
2. Name of agency : _____
3. Cost of tender paper : Rs. _____
4. Details of earnest money : Rs. _____

Signature of Tenderer

Area Civil Engineer
Sijua Area

BHARAT COKING COAL LIMITED
(A Subsidiary of Coal india Limited)
SIJUA AREA—V.

The following details have to furnished by the tenderer while submitting the tender.

1. Name of the tender :
2. Whether individual partnership company :
3. Postal address of the company/proprietor
together with telephone no. etc.
4. In respect of partnership or limited company the
name to the other partners, director together with
their address.
5. List of other firms partnership doing business in
BCCL where in the above firm/partners/directors
are connected with.
6. Whether proprietor partner director are connected
with an employee working in BCCL. If so the details
for the employee, designation and place³ of working etc.
7. Any contract being carried on an BCCL. If the above
firm/proprietor ship/limited in this own name if so the
details of the contract bring executed.
8. Details of sales tax registration number if any.
9. Whether the proprietor/partnership firm/company is
an income tax assessment has been deducted
(income tax clearance certificate should be enclosed)

Failure to fill up these data will automatic rejection of the tender. The tender papers without any other these information will not be considered. This will from the part of the agreement also.

Sig. of the tenderer

Area Civil Engineer
Sijua Area

Bill of quantity for sanitary fitting work for
the bungalow of Addl.G.M. at Sijua Area.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	P/F/F 100mm dia PVC rain water pipe	9.00 Mtr.	Rs.163=40	Rs. 1,470=60
2.	P/F/F 25mm dia PVC pipe	106.00 Mtr.	Rs.179=85	Rs.19,064=10
3.	P/F/F 25mm dia gate valve	1 No.	Rs.285=50	Rs. 285=50
4.	P/F/F 15mm dia PVC pipe	28.00 Mtr.	Rs.100=17	Rs.2,804=76
5.	P/F/F bib cock 15mm dia	4 Nos.	Rs.240=00	Rs. 960=00
6.	Making connection 10mm	1 No.	Rs.423=90	Rs. 423=90

				Rs.24,048=76

Bill of quantity for damaged changing, pit water/drinking
water pipe quarter of Rush Parween(Metro) at R.H.Loyabad.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	Dismantling damaged 25mm dia pipe	91.00 Mtr.	Rs.24=90	Rs.2,265=90
2.	P/F/F PVC 25mm dia	91.00 Mtr.	Rs.179=95	Rs.16,366=35
3.	P/F/F/ 25mm socket G.I. pipe	30.00 Mtr.	Rs.25=00	Rs. 750=00

				Rs,19,382=25

Bill of quantity for renovation of drain and heightening
wall in the workshop at Sendra Bansjora colliery.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	Earth cutting in foundation	11.15 Cu.M.	Rs.103=40	Rs. 1,152=91
2.	P.C.C. (1:4:8) in foundation	1.59 Cu.M.	Rs.2449=00	Rs.3,893=91
3.	C/B/W in foundation (1:6)	4.77 Cu.M.	Rs.2007=00	Rs. 9,573=39
4.	12mm thick cement plaster(1:4) with punning	42.00 Sq.M.	Rs.97=90	Rs.4,111=80
5.	Cleaning scrapping in workshop	6 Nos.	Rs.135=25	Rs. 811=50
6.	C/B/W in superstructure(1:6)	1.28 Cu.M.	Rs.2314=55	Rs.2,962=62
7.	12mm thick cement plaster(1:6)	8.00 Sq.M.	Rs.67=65	Rs. 541=20

				Rs.23,047=33

Bill of quantity for the repair & maintenance
of Staff Re-creation club under Sijua Area.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	Dismantling old plaster	80.00 Sq.M.	Rs. 8=20	Rs. 656=00
2.	12mm cement plaster(1:6)	30.00 Sq.M.	Rs.67=65	Rs. 2,029=50
3.	25mm P.S. flooring(1:2:4)	55.00 Sq.M.	Rs.102=83	Rs. 5,655=65
4.	Oil bond distemper	120.00 Sq.M.	Rs.14=90	Rs.1,788=00
5.	Painting	25.00 Sq.M.	Rs.22=85	Rs. 571=25
6.	Dedo paint	20.00 Sq.M.	Rs.18=80	Rs. 376=00
7.	w/washing two coats	60.00 Sq.M.	Rs. 4=10	Rs. 246=00
8.	C/Washing two coats	200.00 Sq.M.	Rs. 3=85	Rs. 770=00
9.	P/F sal wood choukhat	0.107 Cu.M.	Rs.30511=95	Rs. 3,264=77
10.	P/F M.S. hold bolt	14 Nos.	Rs.61=50	Rs. 861=00
11.	P/F door shutter	3.96 Sq.M.	Rs.899=70	Rs. 3,562=81
12.	P/F M.S. grill	27.71 kg.	Rs.64=40	Rs.1,784=52
13.	P/F M.S.al drop	2 Nos.	Rs.79=60	Rs. 159=20
14.	P/F hand band clip 12mm	11.15 Sq.M.	Rs.311=40	Rs. 3,472=11

				Rs.25,196=67

Bill of quantity for making retaining wall for storage of
water in ekra jore near Ekra patch at Bansdeopur colliery.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	Dismantling P.C.C. (1:3:6)	1.32 Cu.M.	Rs.368=45	Rs. 486=35
2.	Brick work with C.M.(1:6)	10.00 Cu.M.	Rs.2007=00	Rs.21,274=20
3.	12mm thick cement plaster(1:4) with punning	53.06 Sq.M.	Rs.97=90	Rs. 5,194=57
4.	P.C.C.(1:2:4) on top	0.84 Cu.M.	Rs.3257=45	Rs.2,736=25

				Rs.29,691=37

Bill of quantity for supply of good earth of PST2
& O seam rehabilitation site Tetulmari colliery.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	Earth cutting	141.72 Cu.M.	Rs.101=83	Rs.14,431=34
2.	Transporting up 8 k.m.	141.72 Cu.M.	Rs.94=00	Rs.13,321=68

				Rs.27,753=00

Bill of quatity for making survey pittar at NOCP
patch I and II for survey control Nichitpur.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	Earth work excavation	4.73 Cu.M.	Rs.101=15	Rs. 478=43
2.	Cement brick work(1:6)	3.74 Cu.M.	Rs.2007=00	Rs.7,506=18
3.	P.C.C.(1:2:4)	1.33 Cu.M.	Rs.3257=00	Rs.4,332=40

				Rs.12,317=01

Bill of quantity for making view point (Challa) setting stone
corner of Hole road and spreading lime at NOCP for Safety Inspection.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	Providing bamboo	20 Nos.	Rs.115=00	Rs.2,300=00
2.	Providing bichali	170.00 kg.	Rs. 6=50	Rs.1,105=00
3.	Rashi	1.00 kg.	Rs.40=00	Rs. 40=00
4.	Nail	½ kg.	Rs.60=00	Rs. 30=00
5.	Filling of challa	20 nos.	Rs.135=25	Rs.2,705=00
6.	Setting stone for side of Hole road	18 Nos.	Rs.135=25	Rs.2,434=50
7.	Spreading of lime	23 Nos.	Rs.135=25	Rs.3,110=75
8.	Providing of lime	18 bags	Rs.90=00	Rs.1,620=00
9.	Cleaning of jungle	5 Nos.	Rs.135=25	Rs. 676=25

				Rs.14,021=50

Bill of quantity for dismantling of hutment on edge of OCP drain
cuttings cleaning near Banarshi pond at Tetulmari colliery.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	Earth work excavation for drain	19.12 Cu.M.	Rs.101=85	Rs.1,977=37
2.	Cleaning of drain	10 labours	Rs.135=25	Rs.1,352=50
3.	Dismantling of brick work	16.00 Cu.M.	Rs.310=75	Rs.4,972=00
4.	Transporting of brick	5000 Nos.	Rs.105=42	Rs. 527=40
5.	Dismantling of naria tile,bamboo rola	25 nos.	Rs.135=25	Rs.3,381=25
6.	Transporting of naria bamboo rola rabish etc.	15.00 Cu.M.	Rs.29=53	Rs. 442=95

				Rs.12,623=17

Bill of quantity for dismantling of
shed from Bansjora O.C.P.

<u>Sl.No.</u>	<u>Description</u>	<u>Quantity</u>	<u>Rate</u>	<u>Amount</u>
1.	Dismantling C.G.I. sheet	461.71 Sq.M.	Rs.24=70	Rs.11,404=23
2.	Dismantling steel structural work	6318.149 kg.	Rs. 0=85	Rs.5,370=42

				Rs.16,774=65